

TABLE OF CONTENT

TABLE	OF CONTENT	
LIST OF	FIGURES	
LIST OF	TABLES	IV
ACRON	IYMS AND ABBREVIATIONS	VI
EXECU ⁻	TIVE SUMMARY	VII
0.1	OBJECTIVES	VII
0.2	COMPONENTS AND MAIN ACTIVITIES	VII
0.3	PROJECT ACTIVITIES IN THE SAVELUGU NAKPANZOO RICE VALLEY	
0.4	ANALYSIS OF ALTERNATIVE PROJECT OPTIONS	
0.5	INSTITUTIONAL AND LEGAL FRAMEWORK FOR IMPLEMENTATION OF THE PROJECT	
0.6	BRIEF DESCRIPTION OF THE PROJECT LOCATION IN SAVELUGU MUNICIPALITY	
	POTENTIAL MODERATE AND MAJOR IMPACTS	
0.7		
0.8	PUBLIC CONSULTATIONS	
0.9	ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN	XXXVII
0.10	ENVIRONMENTAL MONITORING	LII
0.11	INSTITUTIONAL CAPACITY TO IMPLEMENT ESMP	LVIII
0.12	GRIEVANCE REDRESS MECHANISM	LIX
0.13	ESMP IMPLEMENTATION BUDGET	LX
0.14	DECOMMISSIONING	LXII
0.15	CONCLUSION	LXIII
1.0	INTRODUCTION	1
1.1	BACKGROUND OF THE PROJECT	1
1.2	Purpose of the ESIA	2
1.3	METHODOLOGY FOR THE ASSESSMENT PROCESS	2
1.4	THE ESIA REPORT CONTENT AND STRUCTURE	3
2.0	PROJECT DESCRIPTION	4
2.1	Project Location	4
2.2	PROJECT COMPONENTS	7
2.3	Project Activities	10
3.0	ANALYSIS OF ALTERNATIVES	13
4.0	POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK	19
4.1	NATIONAL POLICIES AND PLANS	19
4.2	National Legal Framework	

4.2.1	Agriculture Sector Legislation and Related Requirements	26
4.2.2	Local Governance and Planning Requirements	26
4.2.3	National Labour, Environmental Quality, Health, Safety and Social Guidelines	28
4.3	NATIONAL INSTITUTIONAL FRAMEWORK	31
4.4	International Policies and Conventions	34
4.4.1	African Development Bank Operational Safeguards	34
4.4.2	International Conventions	39
5.0 EN	IVIRONMENTAL AND SOCIAL BASELINE CONDITIONS	41
5.1	SAVELUGU MUNICIPAL BASELINE CONDITIONS	41
5.1.1	Physical Environment	41
5.1.2	Biological Environment	53
5.1.3	Socio-economic Environment	55
5.2	CHARACTERISTICS OF THE PROJECT SITE (NAKPANZOO VALLEY)	58
5.2.1	Air Quality	59
5.2.2	Ambient Noise	65
5.2.3	Water Resources	67
5.2.4	Soils	67
5.2.5	Biodiversity	70
5.2.6	Socio-economic Environment – Project site (Nankpazoo Community)	79
6.0 ST	AKEHOLDER CONSULTATIONS	83
6.1	OBJECTIVES OF THE CONSULTATIONS	83
6.2	STAKEHOLDERS CONSULTED AND CONCERNS RAISED	
6.3	PUBLIC DISCLOSURE	
6.4	GRIEVANCE REDRESS MECHANISM	
	DTENTIAL ENVIRONMENTAL AND SOCIAL ISSUES AND IMPACTS	
7.1	IMPACT ASSESSMENT	
7.1.1		
7.1.2	Evaluation and Interpretation of Impacts	
7.1.3	- 3	
7.2	POTENTIAL ENVIRONMENTAL RISKS AND SOCIAL ISSUES	
7.3	Project Area of Influence (AoI)	
7.3.1		
7.3.2		
7.4	COMMUNITY INFLUENCE AND VULNERABLE GROUPS	
7.5	INSTITUTIONAL INFLUENCE	
7.6	POTENTIAL POSITIVE IMPACTS	106
7.6.1		
7.6.2	Increased commerce and boost to local economy	106
7.6.3	·····,	
7.6.4	Adoption of good agricultural practices	107
7.6.5	Technology transfer	107
7.7	MODERATE AND MAJOR NEGATIVE IMPACTS	107
771	Preparatory Phase: Moderate and Major adverse impacts	111

	7.7.2	Construction Phase: Moderate and major adverse impacts	114
	7.7.3	Operation Phase: Moderate and Major adverse impacts	120
	7.7.4	Decommissioning Phase: Moderate and major adverse impacts and specific measures	127
	7.7.5	Cumulative Negative Impacts of the Project	129
8.0	МІТ	IGATION MEASURES	131
8		ECOMMENDED MITIGATION MEASURES FOR IDENTIFIED IMPACTS	
9.0	EN۱	/IRONMENTAL AND SOCIAL MANAGEMENT PLAN	147
ç).1 E	SMP IMPLEMENTATION	163
	9.1.1	Institutional Arrangement and Responsibilities	163
ç).2 N	MONITORING AND REPORTING	164
ç).3 A	NNUAL E&S COMPLIANCE AUDITS OF THE PROJECT AND COST	165
ç).4 N	IEEDS ASSESSMENT OF THE IMPLEMENTING INSTITUTIONS	171
	9.4.1	Key Institutions	171
	9.4.2	Institutional Roles, Capacity Gaps and Recommendation	171
	9.4.3	Capacity Building Approach and Training Needs	173
	9.4.4	Environmental and Social Monitoring Approaches	174
	9.4.5	Technical and Operational Capacity	174
	9.4.6	Coordination and Accountability	174
ç).5 E	SMP ESTIMATED IMPLEMENTATION BUDGET	175
10.	n DEC	OMMISSIONING	170
		RE-DECOMMISSIONING ASSESSMENT	
]		DECOMMISSIONING PHASE ACTIVITIES	
	10.2.1	4.7	
	10.2.2		
]	.0.3 P	OST-DECOMMISSIONING ASSESSMENT	179
11.	o cor	NCLUSION	180
12.0) BIB	LIOGRAPHY	181
40		WENTS	400
13.) ANI	NEXES	182
LIS	T OF FIG	GURES	
		AAP OF GHANA SHOWING THE BENEFICIARY DISTRICTS INCLUDING SAVELUGU	
		OCATION MAP OF SAVELUGU MUNICIPAL SHOWING THE NAKPANZOO VALLEY	
		JNIMODAL RAINFALL REGIME OF NORTHERN GHANA, REPRESENTED BY TAMALE, 1960–2010	
		MEAN ANNUAL RAINFALL TOTAL AND STANDARD DEVIATION FOR NORTHERN GHANA.	
		AVERAGE MONTHLY RAINFALL	
		AVERAGE MONTHLY MINIMUM AND MAXIMUM TEMPERATURE	
		AVERAGE MONTHLY RELATIVE HUMIDITY	
		AVERAGE TOTAL SUNSHINE HOURS	
Figi	JRE 5-7 : <i>A</i>	VERAGE MONTHLY WIND SPEED	46

	4/
FIGURE 5-9: ELEVATION MAP OF THE SAVELUGU MUNICIPAL	48
FIGURE 5-10: DRAINAGE MAP OF THE SAVELUGU MUNICIPAL	49
FIGURE 5-11: SOIL MAP OF THE SAVELUGU MUNICIPAL	51
FIGURE 5-12: GEOLOGY MAP OF THE SAVELUGU MUNICIPAL	52
FIGURE 5-13: VEGETATION MAP OF THE SAVELUGU MUNICIPAL	54
FIGURE 5-14: GRAPH SHOWING COMPLIANCE AND OR EXCEEDANCE OF PARTICULATES TO GSA/WHO STANDARDS	62
FIGURE 5-15: GRAPHS OF GASES MONITORED AT THE VALLEY AND FULANI HAMLETS	64
FIGURE 5-16: NIGHT TIME AMBIENT NOISE LEVELS MEASURED AT THE VALLEY AND ITS NEAREST SENSITIVE RECEPTOR	67
FIGURE 5-17: AGE RANGE OF RESPONDENTS	79
FIGURE 5-18: A PIE CHART SHOWING DISABILITY STATUS OF HOUSEHOLDS	80
FIGURE 5-19: SECONDARY SOURCE OF INCOME FOR RESPONDENTS	81
FIGURE 6-1: PROCEDURE FOR GRIEVANCE REDRESS	96
FIGURE 7-1: EIA PROCESS	98
FIGURE 7-2: MITIGATION HIERARCHY	104
LIST OF TABLES	
Table 2-1: Project Beneficiaries	
Table 2-2: Proposed Rice Valleys for Development	
Table 3-1: Analysis of Alternative Project Options	
Table 4-1: National Policies and Plans	
Table 4-2: National Legal Framework	
Table 4-3: Agriculture Sector Legislation and Related Requirements	
Table 4-4: Local Governance and Planning Requirements	
TABLE 4-5: NATIONAL LABOUR, ENVIRONMENTAL QUALITY, HEALTH, SAFETY AND SOCIAL GUIDELINES	
Table 4-6: National Institutional Framework	31
Table 4-7: Operational Safeguards of AFDB	35
TABLE 4-8: INTERNATIONAL POLICIES AND FRAMEWORK	39
TABLE 5-1: ENVIRONMENT AND HEALTH PROTECTION- REQUIREMENTS FOR AMBIENT AIR QUALITY AND POINT SOURCES/STACK	
EMISSIONS (GS 1236:2019).	
TABLE 5-2: CHEMICAL AND PHYSICAL ANALYSIS OF SOIL SAMPLES	69
TABLE 5-3: COORDINATES OF SAMPLING LOCATIONS AND ASSOCIATED VEGETATION TYPES	
Table 5-4: Star Rating system	71
TABLE 5-5: IUCN RED LIST CATEGORIES	71
TABLE 5-6: SAMPLE PROFILES AND SPECIES COMPOSITION OF NAKPANZOO VALLEY	72
TABLE 5-7: FLORISTIC ANALYSIS OF NAKPANZOO VALLEY	73
TABLE 5-8: LIFE FORM COMPOSITION OF THE FLORA	74
TABLE 5-9: ECOLOGICAL GUILDS OF THE FLORA	
TABLE 5-10: IUCN RED LIST STATUS COMPOSITION OF THE FLORA	74
TABLE 5-11: FAUNA OF THE PROJECT AREA	76
TABLE 6-1: DETAILS OF STAKEHOLDERS IDENTIFIED AND CONSULTED.	85
TABLE 6-2: COMPOSITION OF GRIEVANCE REDRESS COMMITTEES / STRUCTURES	94
TABLE 6-3: GRM IMPLEMENTATION BUDGET SUMMARY	97

Table 7-1: Impact Characteristics	99
Table 7-2: Sensitivity Criteria	101
Table 7-3 : Impact Significance	103
Table 7-4: Impact significance definitions	103
TABLE 7-5: PREPARATORY PHASE POTENTIAL ADVERSE IMPACTS	111
Table 7-6: Construction Phase Potential Adverse Impacts	114
Table 7-7: Operation Phase Potential Adverse Impacts	120
Table 7-8: Decommissioning Phase Potential Adverse Impacts	127
Table 7-9: Cumulative Impact Assessment Matrix E	RROR! BOOKMARK NOT DEFINED.
Table 8-1: Proposed Mitigation and Management Measures for Identified Impacts	132
Table 8-2: Beneficial Impacts of the Project	146
Table 9-1: Environmental and Social Management Plan	148
Table 9-2: Roles and Responsibilities of Key Actors	163
Table 9-3: Environmental and Social Monitoring Plan	166
Table 9-4: Institutional Roles, Capacity Gaps and Recommendations	
Table 9-5: Estimated budget to implement ESMP	175
LIST OF PLATES	
PLATE 5-1: THE NANKPAZOO VALLEY	59
PLATE 5-2: ARA N-FRM SETUP FOR PM $_{2.5}$ and PM $_{10}$ sampling at the proposed Nakpanzoo i	RICE VALLEY60
PLATE 5-3: ARA N-FRM SETUP FOR PM $_{2.5}$ and PM $_{10}$ sampling at the nearest sensitive received	PTOR (FULANI HAMLETS) 60
PLATE 5-4: GASES MONITORING AT THE PROPOSED NANKPAZOO VALLEY	63
PLATE 5-5: GASES MONITORING AT THE NEAREST SENSITIVE RECEPTOR (FULANI HAMLETS)	63
PLATE 5-6: AMBIENT NOISE MONITORING AT THE PROPOSED NAKPANZOO RICE VALLEY	65
PLATE 5-7: AMBIENT NOISE MONITORING AT THE NEAREST SENSITIVE RECEPTOR (HAMLETS)	66
PLATE 5-8: NAKPANZOO VALLEY — FARMLAND (HARVESTED RICE FIELD) WITH ISOLATED TREES	70

ACRONYMS AND ABBREVIATIONS

AEZ Agro-Ecological Zones
AfDB African Development Bank
CBD Central Business District

CITES Convention on International Trade in Endangered Species of Wild

Fauna and Flora

CSIR Council for Scientific and Industrial Research
DCP Decommissioning and Site Closure Plan

DEMC District Environmental Management Committees

EA Environmental Assessment EHU Environmental Health Unit

EIS Environmental Impact Statements
EPA Environmental Protection Authority

ERO ECOWAS Rice Observatory

ESIA Environmental Impact Assessment

ESMP Environmental and Social Management Plan
FASDEP Food and Agriculture Sector Development Policy

FAW Fall Army Worm

FBGs Farmer Based Groups

FBOs Farmer Based Organizations

FID Factories Inspectorate Division

FROGGIE Forest Reserves of Ghana Information Exhibitor

GAP Gender Action Plan

GIDA Ghana Irrigation Development Authority
GMMB Ghana Museum and Monument Board

GNFS Ghana National Fire Service
GRC Grievance Redress Committee
ISS Integrated Safeguards System

LEAP Livelihood Empowerment Against Poverty

MED Metro Education Directorate

METASIP Medium Term Agriculture Sector Investment Plan

MoFA Ministry of Food and Agriculture

MSME Micro Small and Medium Scale Enterprises
NADMO National Disaster Management Organization

NRDS National Rice Development Strategy

OSs Operational Safeguards
PAFs Project Affected Framers
PAPs Project Affected Persons

PCR Project Completion/Technical Review

PIU Project Implementation Unit
PSC Project Steering Committee
RAP Resettlement Action Plan
RCC Regional Coordinating Council

REWARD Resilient Rice Regional Value Chains In West Africa

SDHMT Sub-district Health Management Team
SIP Savannah Investment Programme

UNFCCC United Nations Framework Convention on Climate Change

VLD Voluntary Land Donation

VSLA Village Savings and Loans Associations

WRC Water Resources Commission

EXECUTIVE SUMMARY

The Resilient Rice Regional Value Chains in West Africa (REWARD) Project is being implemented by the Government of Ghana through the Ministry of Food and Agriculture with the support of the African Development Bank (AfDB) aimed at addressing disruptions in food systems in Ghana.

Specific activities to be undertaken in selected Inland Valleys include but not limited to: development of water control and conveyance systems; construction of drainage systems to collect water out of command areas; construction of access roads into the valleys; and land development for crop cultivation. The programme will also seek to address issues with women and youth drawn from the Gender Action Plan (GAP).

0.1 Objectives

The overall goal of the project is to increase rice production in order to contribute to industrialization, youth employment and food security. The specific objectives of the project are to:

- Increase rice productivity and production thus increased incomes for farmers, particularly women and young people;
- Increase the resilience and adaptive capacities of rice farms and production systems; and
- Increase the marketing and intra-regional trade of rice.

0.2 Components and main activities

The project components and activities comprise:

No	Component	Sub-Component and Activities			
	Name				
1	Production	Sub-component 1.1: Sustainable climate-resilient infrastructure and			
	and	management services in rice production systems			
	Productivity	Key interventions will include:			
		Development of Agricultural Zones			
		Sustainable Land and Water Management (SLWM)			
		Form and build capacity of Water Users Association			
		Social infrastructure development			
		Sub-component 1.2: Improved availability and access to climate-resilient inputs,			
		mechanization services and knowledge			
		Key interventions will include:			
		Seed Delivery Systems			
		Fertilizers and Pest Control Management Systems			
		Agricultural Mechanization Services Delivery			
		Extension Delivery			

No	Component	Sub-Component and Activities				
	Name					
2	Processing and	Sub-component 2.1: Modernized processing infrastructure and strengthening				
	Marketing	capacities of value chain actors				
		nis component will focus on:				
		The construction and installation of processing and storage infrastructure to				
		minimise post-harvest losses and enhance value addition.				
		Development of information systems using innovative technologies (incl.				
		digital) and consumer-oriented branding to improve access to market.				
3	Policy and	Key activities under this component will include:				
	Governance	Support to policy reforms and harmonization at regional/national levels				
		Finalize the National Rice Development Strategy II (NRDS).				
		Organise policy dialogues and workshops to discuss issues relevant to the rice				
		sub-sector.				
		Coordinate activities to ensure synergies among rice value chain stakeholders				
		and projects to boost production, processing, marketing and consumption of				
		locally-produced rice.				
		Enhance control and regulations for agricultural inputs at regional/national				
		levels.				
4	Programme	This component will be responsible for:				
	Coordination	Day-to-day management of project activities to ensure harmony and				
	and	coherence.				
	Management	Establishment or nesting of Project Implementation Unit (PIU) under existing				
		PIU to support the coordination and management of the project.				
		Development of Regional and National Management and monitoring systems				
		based on digital technologies to ensure tracking of results at Regional and				
		National levels, and in line with ECOWAS Rice Observatory (ERO).				

0.3 Project Activities in the Savelugu Nakpanzoo Rice Valley

The specific project activities to be implemented in the Savelugu Nakpanzoo Rice Valley at the preparatory, construction and operation phases of the project implementation are:

0.3.1 Preparatory Phase

The preparatory phase activities include:

- Identification of beneficiary community and farmers for rice production;
- Conduct of relevant studies, including socio-economic surveys and resettlement related studies;
- Development and Implementation of Environmental and Social Management Plan (ESMP);
- Request for applications and screening of applicant farmers; and
- Assessment of soil suitability and GIS mapping of commercial farms using ICT.

0.3.2 Construction Phase

The construction phase activities will include the following:

• Rehabilitation of existing access routes;

- Construction of mini work camp;
- Vegetation clearance and land preparation;
- Winning of construction materials from borrow pits (site yet to be determined);
- Transportation of materials to and from project site;
- Construction of drainage channels and flood protection works;
- Provision and installation of farm infrastructure such as farm houses and storage facilities;
- Waste disposal (cleared vegetation, construction waste etc.); and
- Decommissioning of mini work camp.

The vegetation will be cleared using suitable machinery for land development to ensure that top soils are not unduly disturbed. Some activities to be undertaken will involve land levelling and In-field bunding. Bunds which are earthen embankments will be created to retain rainfall runoff. The plots will be formed to conform to the direction of the contours, in this way reducing the earth movement during bunding and levelling to the minimum. The levels of the plots will be set to balance cut and fill. Bunding and land levelling will form the major activities in plot formation. Pegging out of plots boundaries to the standard size of plots will be required during the levelling. All levelled plots would be portioned and bunded by in-field contour bunds into plots.

Roads linking valleys to towns which are mostly in deplorable states will be maintained to reduce postharvest losses which has been a major problem confronting farmers. Access roads will be maintained to permit the use of agricultural machinery in the cropping zone to do tillage, deliver inputs and send out produce.

0.3.3 Operation Phase

The operation phase activities include:

- Production and promotion of rice;
- Support for out-grower contractual arrangements;
- Conduct surveillance and collect data on pests attacking the Rice in the project zones with specific reference to FAW;
- Community sensitization, Establishment of fire belts and enforcement of community fire by-laws to deal with the impact of bush fires;
- Promotion of quality standards for rice, maize and soybean production, storage and processing;
- Support business development, including improvements in business processes of existing commercial farmers;
- Enhance access to market information (e.g. quantity, quality, timing and pricing);
- Promote the development of allied services (packaging, new distribution networks for rice products, transport services, new agro-input delivery systems, etc.);
- Support to feed millers to improve feed stock and expand processing capacity;
- Promote the sustainable use of agro-chemicals;
- Enhance investment facilitation and promotion to increase the number of commercial producers and processors in the Savannah regions; and
- Capacity building for women and youth in small-scale commercial rice business management and entrepreneurship, including mentorship.

0.4 Analysis of Alternative Project Options

The proposed project considered some feasible options including:

- Site selection;
- Resettlement related options
- Power supply;
- Sources of water;
- Water Management Systems;
- Waste management; and
- Project implementation versus No Project implementation.

These are further discussed in the table below.

Option/ Method of		Potential Environmental, Social, Technological and Economic				Preferred Option
Deployment			Implica	Treferred Option		
Site	e Selection					
1.	Nakpanzoo	Ad	vantages	Dis	advantages	Nakpanzoo was
	Valley	1.	Size of the valley	1.	Underdeveloped rice	selected as the
		2.	Potential benefit to farming		fields	preferred valley
			communities with limited			because of its
			access to developed rice			potential benefit
			fields			to many more
		3.	Not a flood prone area			communities. The
		4.	Sparsely vegetated fields			large size of the
2.	Other Valleys	Ad	vantages	Dis	advantages	valley also made
		1.	Already developed rice fields	1.	Relatively small valleys in	it the preferred
			serving nearby communities		size	choice.
				2.	Valleys susceptible to	
					flooding	
				3.	Relatively dense	
					vegetation	
				4.	Potential physical	
					displacement issues	
Res	settlement relate	ed o	otions	-		-
Na	kpanzoo	Ad	vantages	Disadvantage		The preferred
		1.	Chief is willing to donate	1.	The livelihood of thirty-	option is the
			land for the project.		three (33) farmers will be	Nakpanzoo site
		2.	The chief is willing to provide		disrupted.	due to more
			alternate land for the	2.	The affected farmers will	favourable
			affected farmers.		have to trek long	resettlement
		3.	There will be no temporary		distances to access	related
			or permanent physical		alternate farmlands	conditions.
			structures to be removed or		provided by the chief.	
			destroyed.			

Opt	tion/ Method of	Potential Environmental, Social,	. Technological and Economic	
Deployment		Implications		Preferred Option
Other Sites		Advantages	Disadvantages	
		 Vast lands available for the project. Alternative lands to be provided for any affected farmers may be closer to the community. 	 Land is owned by individuals who may not be easily willing to donate for the project. There will be more farmers affected (in excess of 40). 	
Pov	wer supply			
1.	National grid	Advantages	Disadvantages	Solar energy
	reactional girls	The cost of electricity is low decreasing production cost	Unreliable power supply from frequent power cuts	installations (Option 2) such as
2.	Solar energy	Advantages	Disadvantages	solar powered
	installations	 Presents a clean and sustainable source of electricity Low operational costs Meets the objective of Technology transfer and climate friendliness 	1. Expensive capital cost	pumps are preferred for the pump irrigation.
Sou	urces of Water			
1.	Groundwater	 Advantages Relatively reliable source all year round Seasonal variations are minimal Relatively stable water quality 	Disadvantages 1. Expensive to access and abstract 2. Challenges of overexploitation to meet high demands and associated threat of land subsidence 3. May require farms of boreholes to meet demand 4. Threat of high iron and fluoride concentration in aquifers in the northern	Option 3, which is the use of rain water appears to be the most preferred option as it will be easier to implement water management plans
2.	Surface water Rain harvesting	Advantages 1. Easier to abstract and use Advantages 1. Easy to trap and store	parts of the country Disadvantages 1. Seasonal variations in flow 2. Vulnerable to pollution Disadvantages 1. Source is unreliable	

Op	tion/ Method of Deployment	Potential Environmental, Social, Implica	_	Preferred Option
Wa	ater Managemen		Evaporation losses are high in the dry months of the year	
1.	The head- bund system	 Advantages Water stored in the ponds is conserved and can be used for additional irrigation during dry spells because of the small nature of the storage ponds. The technique allows for deep water infiltration into the soil by trapping the water, thereby enhancing the soil's water retention capacity. This system also help to prevent soil erosion and gully formation by reducing the speed and volume of surface runoff. 	Disadvantages 1. Developing of bunds can be laborious and may demand more manpower if size of farm is huge. 2. Having head-bund system in areas with adequate rainfall or irrigation may cause waterlogging which may affect crop growth.	The preferred option is the head-bund system as it is ideal for small to medium-sized farms. It also allows for deep water infiltration into the soil by trapping water, thereby enhancing the soil's water retention capacity which is very essential in rice production.
2.	The central-	Advantages	Disadvantages	
	drain system	 The water levels in the rice fields, especially those near the central drain, can be controlled to mitigate against excessive flooding of the fields. Help reduce soil salinity. With water levels being controlled, crops receive optimal water amounts leading to better growth and yield. 	 This system is only suitable for areas with high rainfall and not arid conditions. The central drain can be a conduit for soil erosion if not maintained properly. 	
3.	The	Advantages	Disadvantages	
	interceptor- canal system	In periods of high rainfall, the fields are better protected from any rapid overflow of water from the stream and from the lateral runoff from the uplands.	1. Water can be lost from the canals through seepage into the ground and evaporation, reducing the overall efficiency of the irrigation system.	

Opt	tion/ Method of	Potential Environmental, Social	. Technological and Economic	
-	Deployment	Implica	-	Preferred Option
4.	The contour- bund system	2. The interceptor-canal system can be used to irrigate the rice fields during dry spells in the rainy season. Advantages 1. The stream used for	2. It can be challenging to distribute water evenly across large areas with this system, as some parts of the irrigated land can receive more water than others. 3. Canals require regular maintenance, such as desilting and repairing leaks, which can be expensive and laborintensive. Disadvantages 1. Contour bunds are not	
Wa	ste Managemen	irrigation is effectively obliterated and water is allowed to cascade from one levelled area to the next by way of built outlets or spillways to the next field.	suitable for uneven or eroded land as overtopping of excess water with subsequent breakage may occur at low spots.	
1.	Composting	Advantages	Disadvantages	Option 1,
	plant	 Improvements in soil quality. Enhances the structure of the soil. Eco-friendly. Fully organic fertilizer. Higher yields. 	 Requires initial investment. Efficiency depends on the amount of organic waste May attract rats, snakes, and bugs. Requires space Unpleasant smell 	composting is a better option as it is ecofriendly and could be used to improve soil quality on farms. It will also keep waste away from
2.	Municipal	Advantages	Disadvantages	landfill, which
	Waste Dump/ landfill sites	 Straightforward concept to deal with waste. Filled land can be reused for other community purposes. Landfills can prevent 	 Completed landfill areas can settle and requires maintenance. Requires proper planning, design, and operation 	already have limited space.
		environmental dumping.Good for waste that is non-recyclable.	design, and operation. 3. Can contribute to groundwater pollution. 4. Landfills can be a breeding ground for bacteria.	

	Option/ Method of Potential Environmental, Social, Technological and Econo Deployment Implications			Preferred Option		
		ntion versus No Project Implementation				
1.	Project		vantages		advantages	Project
	Implementati	1.	Enhancing rice production,	1.	Potential displacement	implementation is
	on	2.	Strengthening market		issues	the preferred
			systems,	2.	Depriving other projects	option as the
		3.	Improving farmer		from accessing scarce	benefits outweigh
			livelihoods.		resources	that of the no
		4.	Supporting research to			project
			produce breeder seeds,			implementation
		5.	Ensuring widespread access			option
			to seed of improved rice			
			varieties.			
		6.	Facilitate the supply of key			
			inputs such as fertilizers and			
			pesticides			
2.	No Project	Ad	vantages	Dis	advantages	
	Implementati	1.	Project resources can be	1.	Food security challenges	
	on		channeled into other	2.	High Cost of Land	
			development programs		Development:	
				3.	Inadequate Irrigation and	
					Poor Water	
					Management.	
				4.	Limited availability of	
					quality breeder,	
					foundation and certified	
					seeds:	
				5.	Inadequate use of	
					Improved Agro Inputs:	
				6.	Inadequate access to	
					mechanized services	
				7.	Poor knowledge of good	
					agronomic practices	
				8.	Poor quality of processing	
					and storage facilities	

0.5 Institutional and legal framework for implementation of the project

0.5.1 Institutional roles and responsibilities

The key stakeholder institutions identified include:

- Ministry of Food and Agriculture;
- Water Resources Commission;
- Lands Commission;
- Environmental Protection Authority;

- Local Government Authority; and
- Traditional Authorities.

Their roles and mandates as well as relevance to the project are summarised as follows:

Institution	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
Ministry of Food and Agriculture (MOFA)	MOFA promotes sustainable agriculture and agribusiness through research and technology development, effective extension and other support services to farmers, processors, and traders for improved human livelihood. The Food and Agriculture Sector Development Policy (FASDEP II) and the Medium-Term Agricultural Sector Investment Plan (METASIP) seeks to guide development and interventions in the agriculture sector. The Resilient Rice Regional Value Chains in West Africa Project (REWARD) of MoFA also seeks to develop agriculture in Ghana in line with the country's efforts at poverty reduction and ensuring food security by promoting inclusive commercial farming along selected commodity value chains.	Regional and District Departments of Agriculture have the mandate to offer extension services and support to ensure sustainability and the successful implementation of the project
Water Resources Commission (WRC)	WRC was established by an Act of Parliament (Act 522 of 1996) with the mandate to regulate and manage Ghana's Water Resources and co-ordinate government policies in relation to them. The Act stipulates that ownership and control of all water resources are vested in the President on behalf of the people, and clearly defines the WRC as the overall body responsible for water resources management in Ghana. The functions of the WRC as established under Act 522 among other things are to: Formulate and enforce policies in water resources conservation, development and management in the country; Coordinate the activities of the various agencies (public and private) in the development and conservation of water resources; Enforce, in collaboration with relevant agencies, measures to control water pollution; and Be responsible for appraising water resources development project proposals, both public and private, before implementation.	The REWARD Project will collaborate with the WRC for the protection of water bodies

Institution	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
Local Government Authority	The Regional Coordinating Council (RCC) and the Metropolitan /Municipal/District Assemblies (MMDAs) are responsible for the overall development of the region and metropolis/municipality/district respectively. Acts 462 and 480, which established the current district assembly structure, designate the District/Municipal/Metropolitan Assembly as the planning authority, charged with the overall development of the district. With regard to environmental management at the district level, the District Environmental Management Committees (DEMC) has been set up by law (Act 462) to among other things: Promote and provide guidelines for the establishment of community-level environmental committees to put into effect the environmental programmes of the Assembly in the community; and Plan and recommend to the DA, strategies and activities for the improvement and protection of the environment with emphasis on fragile and sensitive areas, river courses etc.	The project is located in the Savelugu Municipal and will be influenced by decisions and plans of the Northern Regional Coordinating Council and the identified Assembly. The Assembly will play key roles in the successful implementation and other related activities of the project.
Lands Commission	The Lands Commission was established by Article 258 of the 1992 Constitution and the Lands Commission Act, 2008 (Act 767). The functions of the Lands Commission include amongst others; Advise the Government, local authorities and traditional authorities on the policy framework for the development of particular areas of the country to ensure that the development of individual pieces of land is coordinated with the relevant development plan for the area concerned; Ensure that through sound, sustainable land use planning, socio-economic activities are consistent with sound land use through sustainable land use planning in the long-term national development goals; and Promote community participation and public awareness at all levels in sustainable land management and development practices to ensure the highest and best use of land.	The REWARD Project will be implemented in line with the objectives of the Commission for sustainable development of land and conform to the development goals of the MMDAs.

Institution	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
Environmental Protection Authority	 The EPA is the body responsible for regulating the environment and ensuring the implementation of government policies on the environment. The functions of the Authority include: Ensuring compliance with any laid down environmental impact assessment procedures in the planning and execution of development projects, including compliance in the respect of existing projects; Promoting effective planning in the management of the environment; Imposing and collecting environmental protection levies in accordance with the Environmental Protection Act 2025, Act 1124 or regulations made under the Act; and Acting in liaison and co-operation with government agencies, Municipal Assemblies and other bodies and institutions to control pollution and generally protect the environment. 	The REWARD Project will obtain environmental permit from the EPA and will follow all EPA procedures and requirements in the implementation of the project.
Traditional Authorities	In Ghana, people of common descent owe allegiance to a symbol of collective authority, such as the 'stool' for the Akans of southern Ghana or the 'skin' for the northern peoples. Traditional authorities play a role in the administration of the area. At the village level, family and land disputes and development issues are also traditionally dealt with by the village chief and elders. In addition to providing an important leadership role, especially in the more rural areas, chiefs act as custodians of stool/skin land, can mobilise their people for developmental efforts and arbitrate in the resolution of local disputes. Although chiefs have no direct political authority, some are appointed by the Government or Municipal Assemblies.	The proposed project site falls under the Dagbon Traditional Council and the Nankpazoo community who are key project stakeholders.

0.5.2 Policies, Legislative and regulatory requirements for the implementation of the ESMP

The relevant policies and legal frameworks include:

Policies and Plans

- Ghana Shared Growth and Development Agenda, 2010;
- National Environmental Policy, 2012;
- National Land Policy, 1999;
- National Water Policy, 2024;
- National Climate Change Policy, 2013;

- National Gender Policy, 2015;
- Riparian Buffer Zone Policy, 2014;
- Food and Agriculture Sector Development Policy, FASDEPII (MOFA);
- National Environmental Action Plan/Policy, 1994; and
- National Employment Policy, 2012.

National legal framework

- The Constitution of the Republic of Ghana, 1992;
- Ghana Investment Promotion Centre Act 1994, Act 478;
- Environmental Protection Act 2025, Act 1124;
- Environmental Assessment Regulations 2025, LI 2504
- Fees and Charges (Miscellaneous Provisions) Act, 2022 (Act 1080);
- Water Resources Commission Act 1996, Act 522;
- The Water Use Regulations 2001, LI 1692;
- Ghana Meteorological Agency Act 2004, Act 687.

Agriculture sector legislation and related requirements

Plants and Fertilizer Act 2010 (Act 803).

Local governance, planning and other institutional requirements

- Local Governance Act, 2016 (Act 936);
- National Building Regulations, 1996 (LI 1630);
- The State Lands Act, 1962 (Act 125);
- Lands Commission (LC) Act 2008, Act 767;
- Land Use and Spatial Planning Act, 2016 (Act 925)

Labour, Health, Safety, Security and Social Protection


- Labour Act, 2003 (Act 651);
- Occupational Safety and Health Policy of Ghana (Draft, 2004);
- Workmen's Compensation Law, 1987 (PNDCL 187);
- National Workplace HIV/AIDS Policy.

Environmental regulations


- Ghana Standards for Drinking Water (GS 175:2017 5th);
- Ghana Standard for Environmental Protection Requirements for Effluent Discharge (GS1212, 2019);
- Ghana Standards for Environment and Health Protection Requirements for Ambient Air Quality and Point Source/Stack Emissions (GS 1236, 2019);
- Ghana Standards for Health Protection Requirements for Ambient Noise Control (GS 1222, 2018);
- Ghana Standards for Environment and Health Protection Requirements for Motor Vehicle Emissions (GS1219, 2018);
- Factories, Offices and Shops Act, 1970 (Act 328);
- Water Resources Commission (WRC) Act 1996, Act 522;
- Ghana National Fire Service Act, 1997 (Act 537);
- Fire Precaution (Premises) Regulations, 2003 (LI1724).

0.6 Brief Description of the Project location in Savelugu Municipality

The Savelugu Municipality, with Savelugu as the administrative capital, is located in the Northern Region of Ghana. It was carved out of the Western Dagomba District Council in 1988 under the Local Government Act 462, 1993 by Legislative Instrument (LI) 1450. Nanton District was also subsequently carved out of the then Savelugu Nanton Municipal Assembly changing the name currently to Savelugu Municipal Assembly. The Municipality, covering an area of 1,599 sq. km., is bounded to the north by West Mamprusi Municipal, to the south by Sagnerigu Municipality, to the east by South Karaga and Nanton Districts, and Kumbungu District to the west.



Map of Ghana showing the beneficiary districts including Savelugu



Location map of Savelugu Municipality showing the Nakpanzoo valley

0.6.1 Environmental and Social Baseline Conditions for the Savelugu Municipality

Physical Environment

The land in the municipality is generally flat with gentle undulating low relief throughout. The general range of the altitude for the municipality ranges from 400-800 ft. above sea level. The northern part

of the municipality has some gentle slopes whiles the southern part is characterised by some slight hills. The area is drained mainly by the White Volta and its tributaries such as the River Kuldanali, which stretches to constitute a natural boundary between the municipality and Kumbungu District. There are other waterbodies such as the Oxbow Lake, rivers and streams. The effect of the drainage system is felt mostly in the northern part of the Municipality covering the areas between Nabogu and Kukuobilla. These areas are prone to periodic flooding during the wet season, thus making them suitable for rice cultivation.

The municipality's geology is Middle and Upper Voltaian in age. The shale and mudstone of the Upper Voltaian cover the southern section of the Municipality. This underlying rock formation, which has a different water potential for subterranean water than the higher Voltaian formation, determines subsurface water potential in general. Sandstone, shale, and siltstone make up the middle Voltaian, which covers the northern portion of the Municipality. As a result, borehole drilling in the northern half is likely to be more successful than in the southern section.

With an average rainfall of 600mm, the region has a dry and rainy climate. The season begins with sporadic rainfall in April, which intensifies as the season progresses, with the average rainfall rising from 600mm to 1000mm. The district's average temperature is 34°C, with temperatures ranging from 42°C to 16°C. The dry harmattan winds, which bring high temperatures and low humidity, encourage high rates of evaporation and transpiration, resulting in water shortages.

Biological Environment

The area is in the interior (Guinea) Savanna woods, which has drought-resistant flora that does not entirely shed its leaves throughout the lengthy dry season. The less inhabited northern section of the municipality contains richer vegetation, largely secondary forest, but the densely populated south has been degraded by human activities like as farming, bush burning, and tree chopping, among others. Shea trees (which give nuts for producing sheabutter) and dawadawa trees (which provide seeds for condiments) are two notable plants. The majority of these are economically valuable and serve as key sources of income, particularly for women. Large-scale cattle husbandry, as well as the production of staples like as rice, groundnuts, yams, and cassava, are possible in the area.

Socio-economic Environment

The Municipal Assembly, led by the Municipal Chief Executive, is the municipal's primary administrative organisation. The municipality has 22 decentralised departments to handle various concerns in the district in order to increase decentralisation, and there are additional authorised governance structures in the municipal that strive to aid with governance and planning within the district. Traditional authority, youth associations, religious entities, and development partners are among these groups. The zonal councils are the district's four sub-government bodies. The Savelugu, Pong Tamale, Diare, and Moglaa Zonal councils are the ones in question. The district's highest decision-making body, the general assembly, is comprised of 36 elected officials, 16 appointed officials, two members of parliament, and the municipal chief executive.

The population of the Municipality, according to 2021 Population and Housing Census, is 122,888 comprising 60,390 (49.1%) males and 62,498 (50.9%) females. With a growth rate of 3%, the

population of the Municipality is 130,825 in 2021. The population growth in absolute terms within the medium-term period (2010 to 2017) is 11%. Females constitute 51.5% of the population and males 48.5%. This indicates a sex ratio of 94.1 males per 100 females. The population density in 2010 was 78 persons per sq. km and in 2025 it is expected to be 93 Persons per sq. km. The municipality has a high level of illiteracy with 69.2% of the population 11 years and older incapable of reading or writing in any language. In terms of sex, approximately 78.5% of females 11 years and older cannot read or write with that of males constituting 59.1%. Thus 7 out of every 10 females in the municipality cannot read and write.

The sanitation and waste management situation is poor as 67.2% of the households have no toilet facility thereby resorting to open defecation. The percentage of households which use the public toilet (WC/KVIP/pit pan) constitute 19.5%. About 59.5% of urban households and 72.5% of the rural households have no toilet facilities. About 32.3% of the urban households use public toilet (WC/KVIP/pit pan), while in the rural areas, 10.9% households use the KVIP.

Agriculture is the mainstay of the people employing 74.1% in the areas of skilled agriculture, forestry and fishery works. Crop farming dominates (97.0%) the types of agricultural activities engaged in followed by livestock farming (68.7%). Other employment avenues include, elementary occupation, craft and related trades, and service and sales work.

The land tenure system which is predominantly customary, operates under the patrilineal mode of property inheritance. Although this system has recorded considerable changes with regards to land transfer due to population pressures, urbanization, commercial agriculture and legislative interventions, it remains male inclined. It thus excludes women from ownership and limit access rights by inheritance. In most cases, women in the municipality rely on "borrowed lands" for use which is granted based on their status to males as relatives- daughters, sisters or wives. This short-term interest can be terminated at any time by the owner, hence exposing women to tenure insecurity.

0.6.2 Site Specific Conditions within Nakpanzoo Valley

In addition to the above description, the site specific measurements and observations are summarised below:

Physical Characteristics

Air Quality (Particulate Matter and Gases)

Active air quality monitoring was carried out between 7th and 10th April 2025 at the proposed project site, that is within the Nakpanzoo valley. Sampling was done in compliance with the requirements of GS 1236:2019 as shown in the Table below.

Environment and Health Protection- Requirements for Ambient Air Quality and Point Sources/Stack Emissions (GS 1236:2019).

S/N	Air Quality Parameter	Maximum Limits	Averaging Time
1	Carbon monoxide, mg/m³	10	8 hours
2	Sulphur dioxide (SO ₂), μg/m ³	50	24hours
3	Nitrogen oxides (measured as NO ₂), μg/m ³	150	24hours

4	PM ₁₀ , μg/m ³	70	24hours
5	PM _{2.5} , μg/m ³	35	24hours

The sampling and analysis of ambient particulate matter concentrations was done according to the ASTM Test Method D4096-17. Particulate matter ($PM_{2.5}$ and PM_{10}) was sampled at the Nakpanzoo valley for 24 hours using ARA N-FRM Air Sampler set to a flow rate of 16.7 L/min drawing air through the inlet onto a 47mm quartz filter for analysis.

The Particulate Matter (PM_{2.5}) concentrations monitored at the proposed Nakpanzoo Rice Valley and its nearest sensitive receptors (Fulani Hamlets) were 30.00 μ g/m³ and 16.00 μ g/m³ respectively which are within the Ghana Standard (GS 1239:2019) permissible value of 35 (μ g/m³) but exceeded the WHO 2021 limit of 15 μ g/m³.

The Particulate Matter (PM $_{10}$) concentration of 109.00 µg/m³ recorded at the proposed Nakpanzoo Rice valley significantly exceeded both the national (70 µg/m³) and international (45 µg/m³) thresholds. This suggests high coarse particulate pollution, likely arising from mechanical disturbances during farming, vehicular movement, and possibly wind-driven dust due to the site's open, dry landscape.

Sampling of gases including SO₂, NO₂ and CO was done at the Nakpanzoo site using the Aeroqual A-S500 meter. For SO₂ and NO₂ 24 hour averages were used and 8 hours for CO.

Air quality measurements for nitrogen dioxide (NO_2), sulphur dioxide (SO_2), and carbon monoxide (CO) at both the proposed Nakpanzoo rice valley site and the nearest sensitive receptor (Fulani hamlets) were all below the minimum detection limit of 0.06 mg/m³ at the time of sampling. This showed that the gases were below both the WHO guideline of 4 mg/m³ and the Ghanaian maximum of 100 mg/m³ suggesting that current sources of combustion—either vehicular, industrial, or domestic—are minimal or absent in the area.

Ambient Noise

For the purposes of establishing the ambient noise levels in the proposed project area, a noise assessment was undertaken between 7^{th} and 10^{th} April 2025. Measurements were done with a High Precision TSI Quest Sound Level Meter, Model Type 1 which was calibrated at 114 dB (A) before each measurement. Statistical indices computed include L_{Aeq} , L_{max} , L_{min} and L_{peak} .

The equivalent continuous sound level (L_{Aeq}) recorded at the project site (Nakpanzoo valley) was 46.1 dB(A), with a maximum noise level (L_{max}) of 54.2 dB(A), a minimum noise level (L_{min}) of 38.6 dB(A) and a peak (L_{peak}) of 62.5 dB(A). The high L_{Peak} value indicate intermittent spikes in noise, possibly from livestock, human voices, motorbikes, or other community activities. All other values were below the Ghana and IFC EHS standard threshold of 55 dB(A) for residential, institutional zones and well below 70 dB(A) for commercial or industrial zones.

The relatively low ambient noise reflects the rural, undeveloped nature of the site. The main contributors to the existing noise environment are natural sources (e.g., wind, birds) and occasional human activity, such as subsistence farming activities and pedestrian or motorbike movement along rural paths.

At the nearest Fulani hamlet, L_{Aeq} is measured at 52.9 dB(A), L_{max} at 63.3 dB(A), L_{min} at 32.6 dB(A) and L_{Peak} at 71.5 dB(A). The L_{Aeq} is still within the residential threshold of 55 dB(A). The high L_{max} and L_{Peak} values indicate intermittent spikes in noise, possibly from livestock, human voices, motorbikes, or other community activities.

<u>Soil</u>

The project site has marginal, with shallow soil depth as the major limitation with a soil depth <50 cm. The soil texture is sandy with clay content <6%. The topsoil tends to be droughty, while the subsoil has a high level of gravel and concretions (hard, compact masses). The soils are therefore prone to erosion and have low moisture and nutrient-holding capacity. The status of exchangeable calcium and magnesium may be low and declining.

Biological Characteristics

Flora

The Nakpanzoo valley is a seasonally flooded farmland with isolated trees. Intensive rice cultivation and cattle grazing have impacted negatively on the vegetation. Some of the tree species found on the site are *Parkia biglobosa*, *Diospyros mespiliformis*, *Lannea acida*, *Vitellaria paradoxa*, *Mitragyna inermis and Tamarindus indica*. The herb and shrub species included Flueggea virosa, *Ziziphus spina-christi*, *Asparagus africanus*, *Grewia carpinifolia* and *Clerodendrum thyrsoideum*.

Fauna

Most of the large mammals which were common in the area have moved away due to human activities such as farming and cattle grazing as well as wildfires.

Notable among these are the elephant, lion, leopard, warthog, several parrots, terns, songbirds (passerines), land tortoises, pythons other snakes, lizards, bats, birds of prey, mongooses, bovids (e.g. the African buffalo and several duikers), egrets, ducks, pigeons. A number of the species known to occur in the area are of both national and global (IUCN, CITES) conservation significance.

Conclusion

None of the floral and faunal species recorded in the project site are of conservation concern due to the project area being an extensively modified habitat. Very few cases of *Vitellaria paradoxa* (shea tree) which is of some economic importance to the community were observed on the project site. These are however found extensively and commonly in other areas of the municipality. The project will therefore have no significant impact on the existing flora and fauna as well as their habitat, and also on the ecosystem services of the project area.

Socio-economic Characteristics

Farming is the dominant primary source of income for the Nankpazoo community, with an overwhelming 100% of respondents (70no. households) sampled relying on it. All respondents interviewed identified their ethnicity as Dagomba. This indicates complete ethnic homogeneity within the surveyed sample from the Nankpazoo community. All respondents (100%) interviewed identified themselves as Moslem. This uniformity suggests that Islam is the predominant religion among those

surveyed in the Nankpazoo community. The majority of the community members rely on borehole as their primary source of water otherwise would resort to the river.

Majority of the respondents (95%) report that their household use "No facility/Bush" for sanitation. One household reported having a Flush Toilet (3%). This indicates very low access to improved sanitation.

0.7 Potential Moderate and Major Impacts

The process of determining an impact's significance involves two main steps:

- Assessing Impact Magnitude This is based on extent, duration, scale, and frequency. Magnitude is rated as negligible, small, medium, or large for negative impacts, while positive impacts are simply noted as beneficial. Judgement and experience guide this evaluation.
- Assessing Receptor Sensitivity This is determined by legal standards, the importance of the receptor, its capacity to absorb change, and its ability to recover.

Once both magnitude and sensitivity are established, a significance rating is assigned using a standard matrix (see Table below), then refined through professional judgement. Significance is classified as *minor*, *moderate* or *major*.

	Sensitivity			
Magnitude	Low [1]	Medium [2]	High [3]	
Negligible [0]	Negligible [0]	Negligible [0]	Negligible [0]	
Small [1]	Negligible [1]	Minor [2]	Moderate [3]	
Medium [2]	Minor [2]	Moderate [4]	Major [6]	
Large [3]	Moderate [3]	Major [6]	Major [9]	

Key: Negligible – 0 to 1, Minor – 2, Moderate – 3 to 4, Major – 6 to 9

The table below outlines the potential environmental and social issues and their significant impacts associated with the REWARD Project.

Potential Impacts and their significant impact

AfDB No.	Impacts	Description	Magnitude	Sensitivity	Significance
Preparator	y Phase				
OS 1	Environmental and Social	Poor assessment of environmental	Large [3]	High [3]	Major [9]
	Assessment	and social risks and impacts			
OS 5	Involuntary Resettlement, Land	Land related disputes	Medium [2]	Medium [2]	Moderate [4]
	Acquisition, Population	Impact on livelihoods (Economic	Medium [2]	Medium [2]	Moderate [4]
	Displacement and Compensation	displacement)			
		Physical displacement	Negligible [0]	High [3]	Negligible [0]
0S 6	Biodiversity, renewable	Removal of vegetation and	Medium [2]	Medium [2]	Moderate [4]
	resources and ecosystem	displacement of wildlife			
	services				
Construction	on Phase				
OS2	Labour conditions, health and	Project site accidents/incidents and	Medium [2]	High [3]	Major [6]
	safety	animal/insect threat/bites			
		Poor labour working conditions	Medium [2]	High [3]	Major [6]
		Sexual Harassment (SH) and	Medium [2]	High [3]	Major [6]
		Gender Based Violence (GBV)			
OS3	Resource Efficiency and Pollution	Soil erosion and Contamination	Medium [2]	Medium [2]	Moderate [4]
	Prevention and Management	Air Pollution	Medium [2]	Medium [2]	Moderate [4]
		Water Pollution	Medium [2]	Medium [2]	Moderate [4]
		Noise and Vibration	Medium [2]	Medium [2]	Moderate [4]
		Waste generation and Disposal	Medium [2]	Medium [2]	Moderate [4]
0 S4	Community Health Safety and	Traffic Management	Medium [2]	Medium [2]	Moderate [4]
	Security	Visual / Aesthetic Impacts	Medium [2]	Medium [2]	Moderate [4]
		Fire outbreak	Medium [2]	Medium [2]	Moderate [4]
		Public health issues	Small [1]	High [3]	Moderate [3]
		Security concerns	Small [1]	Medium [2]	Minor [2]

AfDB No.	Impacts	Description	Magnitude	Sensitivity	Significance
		Risk of Drowning	Medium [2]	Medium [2]	Moderate [4]
Operation	Stage				
OS2	Labour conditions, health and	Farm incidents/accidents	Medium [2]	High [3]	Major [6]
	safety	Poor labour working conditions	Medium [2]	High [3]	Major [6]
		Sexual Harassment (SH) and	Medium [2]	High [3]	Major [6]
		Gender Based Violence (GBV)			
		Child Labour	Medium [2]	High [3]	Major [6]
OS3	Resource Efficiency and Pollution	Soil erosion and degradation	Medium [2]	Medium [2]	Moderate [4]
	Prevention and Management	Air Pollution	Medium [2]	Medium [2]	Moderate [4]
		Water Pollution	Medium [2]	Medium [2]	Moderate [4]
		Noise and Vibration	Medium [2]	Medium [2]	Moderate [4]
		Solid waste generation and disposal	Medium [2]	Medium [2]	Moderate [4]
0 S4	Community Health Safety and	Fire Outbreak	Medium [2]	Medium [2]	Moderate [4]
	Security	Polluted Waterbodies	Medium [2]	Medium [2]	Moderate [4]
		Sexual Transmitted Diseases	Medium [2]	Medium [2]	Moderate [4]
		Security concerns	Small [1]	Medium [2]	Minor [2]
		Flooding	Medium [2]	High [3]	Major [6]
		Traffic management	Small [1]	Medium [2]	Minor [2]
		Risk of Drowning	Medium [2]	Medium [2]	Moderate [4]
Decommis	sioning Phase				
OS2	Labour conditions, health and	Workplace incidents/accidents	Medium [2]	High [3]	Major [6]
	safety				
OS3	Pollution prevention and control,	Waste generation and disposal	Medium [2]	Medium [2]	Moderate [4]
	hazardous materials and				
	resource efficiency				
OS4	Community Health, Safety and	Traffic management	Medium [2]	Medium [2]	Moderate [4]
	Security				

0.8 Public Consultations

0.8.1 Stakeholders consulted

Stakeholder institutions and affected communities identified and consulted include the Ministry of Food and Agriculture, Ministry of Lands, PIU, EPA, Fire Service, Savelugu Municipal Assembly, Commercial farmers, Agro- Input Suppliers, Traditional Authorities and Focus Groups (including women and youth) within the project communities.

All stakeholders consulted expressed enthusiasm about the project and indicated their readiness to lend their support for its successful implementation. Below are some pertinent issues raised by, and discussed with the stakeholders.

• Employment and Livelihoods

- The project will generate short- and long-term job opportunities for skilled and unskilled local labour, including women. However, unmet expectations regarding opportunities could result in social agitation or unrest.
- Labour and employment issues such as delayed wages, discriminatory practices, or exclusion of women and youth could undermine project credibility.
- Transparent, inclusive recruitment and training plans must be clearly communicated and coordinated with local stakeholders.
- Food Security, Economic Growth and Market Development
 - Project benefits such as food security, and improved access to mechanization and input services which will raise agricultural productivity and income for value chain actors must be shared with stakeholders to obtain their buy-in for a smooth project implementation.
 - The project will stimulate local commerce and attract new investments in processing, marketing, and quality control services.
 - o Increased agricultural output will reduce rice imports and help Ghana conserve foreign exchange.
- Knowledge, Capacity Building, and Technology Transfer
 - o Training of farmers and stakeholders in good agricultural practices will promote climatesmart farming, reduce losses, and improve resilience.
 - Introduction of modern technologies and digital tools (e.g. RiceAdvice, pest control methods)
 will enhance productivity and efficiency in farming.
- Land Access, Tenure, and Use
 - Farmers and landowners may be either physically or economically displaced by the project and should be engaged extensively on the impacts and mitigation measures including compensation.
 - o Improper land acquisition or voluntary land donations which are not transparent and inclusive may lead to disputes and restrict access to traditional lands and resources.
 - Tenant farmers and informal land users may be overlooked in consultation or compensation processes if stakeholder mapping is not comprehensive.
- Water Use and Resource Consumption
 - Water-intensive rice cultivation may increase pressure on local water resources, especially during dry periods.
 - o Inclusive planning and monitoring involving local communities and water user associations are essential to ensure fair and sustainable water use.

• Environmental Degradation

- o Site clearing and infrastructure development may result in loss of vegetation and some trees.
- Soil degradation and erosion may occur due to land preparation, bare farmlands, and construction activities.
- Dust, emissions, and fumes from construction and operations may degrade local air quality, especially on untarred roads.
- Runoff, domestic waste, chemicals, and effluent may pollute surface and groundwater, affecting aquatic life and users.
- Operation of machinery and vehicle movement will generate noise and vibration, causing nuisance to nearby communities.

Pesticide and Agrochemical Use

- The application of synthetic fertilizers and pesticides poses risks of water pollution, biodiversity loss, and adverse health impacts on farmers and surrounding communities.
- Capacity building is needed for smallholder farmers on Integrated Pest Management (IPM),
 safe handling practices, and the use of environmentally safer alternatives.

Health, Safety, and Labour Conditions

- Workers face risks of injuries, accidents, insect/animal bites, agrochemical exposure, dust-inhalation and equipment-related injuries during construction and operation.
- Poor labour conditions, including lack of contracts and inadequate welfare facilities, may expose workers to exploitation and health risks.
- o Fires from negligence or improper burning could cause property loss and injuries.

Social Risks and Community Impacts

- Presence of workers may increase incidents of gender-based violence, rape, and defilement in host communities.
- Pollution and unsafe practices may lead to spread of communicable diseases, including HIV/AIDS and cholera.
- Rising social tensions, theft, confrontations, and conflicts may emerge between workers and locals over cultural, financial, or sexual issues.
- Increased road traffic may cause congestion and accidents due to broken-down or poorly parked haulage vehicles.
- Local communities must be made aware of potential risks and emergency response protocols must be clearly established.

Gender-Based Violence, Sexual Exploitation and Abuse, and Child Labour

- Labour influx during construction and agro-industrial operations may increase the risk of GBV,
 SEA, and child labour.
- Without strong safeguards, women, girls, and persons with disabilities may face heightened vulnerabilities.
- Community engagement is crucial to raise awareness, strengthen prevention mechanisms, and ensure access to referral and support services.

• Grievance Redress

- The project must implement a well-functioning and accessible Grievance Redress Mechanism (GRM) that all stakeholders can use.
- Existing community grievance structures should be formally recognized and integrated into the broader project-level redress system.

0.8.2 Key concerns raised by stakeholders consulted and proposed solutions

A summary of their major issues and concerns raised as well as responses and their preferred solutions are given in the table:

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
Project Implementer	Ministry of Food and Agriculture (Savelugu)	 The department is aware that land has been acquired for the project. The farmers rely on rain-fed agriculture which makes farming less reliable and profitable. The Department must be well-resourced (finance/logistics) for monitoring/supervision of the project. Farmers should be supported with farm inputs and machinery for land preparation and crop harvesting to reduce post-harvest losses through farmer service centers. Main agriculture problem in the area is lack of irrigation therefore this should be factored into the project planning. All relevant stakeholders should be involved in the project. There should be ready markets for the rice that will be produced. The road network in the area should be improved to enhance mobility of people and goods. 	 The issues raised were acknowledged and the MoFA team referred to the project documents for relevant information. E.g. The SEP provides the focal area of engagements for participants The project is expected to have a positive impact on community members as it will create jobs in the rice value chain thereby reducing rural migration to towns for jobs which do not exist.
Regulatory Institution	Environmental Protection Authority	 Compensation issues will arise if there are PAPs in the valley. Compensation should be addressed through comprehensive RAP. There must be valuation of properties if any, as well as compensation for any form of displacement. Environmental permit is required for the project. 	• Assurance was given to the EPA team that the project will follow all EPA guidelines and that the EPA will be involved in providing monitoring and support for the implementation of the project. Additionally, budget may be considered for their role.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
Other Government Institutions	Water Resources Commission	 Biodiversity conservation should be a consideration in the project implementation. If there are RAP issues, it should be handled properly in order not to impoverish persons involved. There will be field visits by the EPA team to monitor environmental compliance during implementation. Education on agrochemicals use for farmers to avoid pollution of local water bodies. 	Concerns of WRC officials were noted and that they will be consulted to participate in the project implementation as and when the need arises.
	Savelugu Municipal Assembly	 The assembly is willing to provide support to any project that will improve the productivity of farmers in the community. Compensation issues are important to the assembly and must be comprehensively addressed. A grievance mechanism should be established to assist the PIU to resolve complaints and grievances in a timely, effective and efficient manner. Main agricultural challenges in the area are the lack of mechanization and the high cost of agricultural input. There is concern about the inadequate road network and the roads are mostly in poor condition. Assembly members and the beneficiary community leadership should be particularly well sensitized about the project to ensure smooth implementation. 	All the relevant stakeholders will be engaged and the ESIA will provide mitigation measures especially for farmers who will be directly affected by the project implementation. The Assembly will assist in any grievance mechanism measures implemented by the project.
	National Disaster Management Organization, Savelugu	Seasonal floods occur regularly during the rainy season leading to loss of	The challenges of NADMO team were noted as well as their importance to the project.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		farmlands and food insecurity. Drought is also experienced during the dry season leading to bushfires. NADMO is concerned that communities farm close to waterways. Project should ensure improved drainage and proper construction within the valley to avoid flooding.	Budget will be allocated in the ESMP for the training of fire fighters and community volunteers to handle bush fires as well provide education on the effects of bush fires on the project.
	Ghana National Fire Service	 The project should put measures in place to preserve existing water bodies as this serves as farm boundaries and also helps to curb bush fires. The GNFS should be adequately resourced to train fire volunteers from the farming communities. Fire incidents have minimized in recent times due to continuous education of the public. Main causes of fire is the indiscriminate burning of bushes (i.e. deliberate, post-harvest). Most fire occurrence happen between the months of November and January. The adverse effects of fire outbreaks are loss of income, soil fertility, lives and properties. The closest Fire station is about 10km which is minimally equipped. The local Fire service station will be on hand to assist the project when/ if required including involvement in 	 The challenges of GNFS team were noted as well as their importance to the project. As part of the ESMP, resources will be provided to support the training of participants as well as community volunteers.
Community based business entities	Small Holder Farmer	community education Common crops cultivated include soybean, maize, rice, sorghum, yam, cassava and groundnut. Urgent needs include tractor service, access to	The challenges of participants were noted and they were assured of the benefits that the project will offer them.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
stakeholders		agrochemicals including fertilizers. Concerns about the poor road network need to be addressed. Inputs and credit support will be required for the beneficiaries on the project. Drought and pest resistant seed varieties should be provided for production. Ready market for produce is key to encourage more people to get involved. Land preparation support is required before planting. Existing farmers on the proposed project site must be compensated if they are to move out. Gender bias/political influences should be avoided in the project implementation. Farmers should be trained on sustainable farm practices by extension officers. The road in the project area should be improved especially	Existing farmers' fears were allayed as they were assured of compensation payments if they got adversely affected by the project. Roads leading to project sites will be improved to enhance movement of goods.
	Aggregators Agro Input Dealers	 during the rainy season. Low purchasing power of farmers. High transportation cost due to poor road network. Lack of access to finance. Inadequate storage infrastructure. There are no formal agreements between aggregators and farmers. Aggregators carry out limited processing of the rice such as cleaning and drying prior to transporting to local markets. Main business activities include trading of fertilizers, seeds, chemicals, tools and equipment, sourced from local distributors. 	Concerns were well noted and participants were assured of benefits that the project will bring to them as their businesses will be positively impacted. Participants were advised to intensify their efforts in educating the farmers including the proper disposal of empty containers of

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		 Customers are mostly small-holder farmers. Peak season is between March and June of the year. They offer technical advice/training to farmers. Some concerns include difficulty in connecting to suppliers, inadequate storage facilities, high transport cost and lack of access to finance. The agro input dealers mostly source their goods from local distributors on cash and carry basis. They are hardly out of stock. All transactions are manual. 	agrochemicals and fertilizers by licensed waste management company.
Civil Society Organizations (CSO)	Farmer Based Organization (FBO)	 The project should avoid political bias. Vulnerable groups should be given special consideration during project implementation Traditional authorities are important for the success of the project. Agricultural inputs should be subsidized to ensure affordability to farmers. Extensive consultation should be conducted to comprehensively address any land reallocation issues. The use of agro-chemicals and the management of waste from organic fertilizers should be properly managed to prevent the contamination of water bodies flowing through the valleys. The herdsmen cattle feeding on waste/plants especially in the dry season can also help in waste management. Farmers are in urgent need of easy access to affordable finance. A close cooperation is required between farmers and suppliers, credit/financial services etc. A cooperative 	Participants were assured that the REWARD project was a non-partisan one and that the project will require their support in providing advocacy and training.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
Community	Traditional	arrangement among farmers facilitated by CSOs/ NGOs will be useful Initiatives by the Rural Enterprise Programme to provide financial support to farmers is a good one which includes business advisory services. The REP is challenged by high illiteracy levels, difficulty in loan repayment by programme beneficiaries and inadequate finance. Land is predominantly owned	The project was explained
stakeholders	Authority	by the traditional authorities and mostly used for farming and livestock. Some concerns include conflicts with herdsmen, compensation for displaced farmers, fairness in selection of project beneficiary farmers. They recommend timely supply of seeds and agrochemicals, and improvement in the road network. Incidences of gender-based violence, sexual exploitation or abuse cases are uncommon in the project area. There are usual petty quarrels between members of the opposite sex but these are settled amicably by family heads/parents or traditional authority depending on which is readily available and accessible.	to participants to make them understand the benefits to the project communities. Participants assistance were sought to ensure cooperation from affected farmers. The leaders were thanked for donating their lands for the project. The LEAP will be implemented to support vulnerable persons who may be affected by the project e.g. bicycles will be given to farmers to aide in transportation to their farms. The Grievance redress mechanism will be put in place to ensure farmers benefit and not suffer from the project implementation.
	Womens' Group	 Women are mostly vulnerable and will require special assistance from the project. Concerns include difficulty in accessing ready market for farm produce, lack of processing facilities. Local groups include VSLA which provide some financial support to the women. 	 The womens' value to the community was acknowledged and as such, the project has been designed to benefit women and encourage their full participation. There will be no room for sexual harassment and in the unlikely event of that happening, the case

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		 Vulnerable households mostly receive support from Livelihood Empowerment Against Poverty (LEAP). 	should be reported to the relevant authorities.
	Men's Group	 Main source of livelihood is farming and rearing of livestock. Deforestation has contributed to unreliable rainfall patterns and has affected the planting (June – December). Their top concerns are the poor road network, lack of access to potable drinking water and financial support. They have confidence in the extension support service and that must be made more effective. Processing facilities are needed to support their farming activities. 	 Participants' concerns were acknowledged and they were assured of job opportunities that will arise from the project. In addition, local persons will be considered first for any job opportunity. Participants were referred to the grievance redress process to address any concerns
	Youth group	 The youth are willing and available to participate in the project as this will help to reduce unemployment and alleviate poverty. Ready markets for the rice produce will be required to ensure reliable flow of income. Irrigation is necessary to make the project more effective and sustainable. Extension officers should play a major role in the implementation of the project. 	 Concerns of participants were acknowledged and they were assured of job opportunities that will arise from the project. In addition, local persons will be considered first for any job opportunity. Participants were referred to the grievance redress process to address any concerns.

0.9 Environmental and Social Management Plan

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati
Prepai	ratory Phase											
OS1	Environmental and Social Assessment	Poor assessment of environmental and social risks and impacts	Unidentified risks and impacts could prevent or stall project implementation. Selection of unqualified persons for assessment studies	Project proponent (MoFA), environment, community	Major [9]	 Detailed and high quality assessment of environmental and social risks Selection of qualified ESIA consultant Environmental permit acquisition 	• PIU	358,000/33,966 35,000/3,321	Lender	Project E&S Instruments (ESIA, RAP, SEP, PMP) EPA Permit	E&S Report Permit	Apr – Sep 2025 31st Oct 2025
OS5	Involuntary resettlement, land acquisition, population displacement and compensation	Land related disputes	Proposed site is owned by is owned by the chief of Nakpanzoo.	Farmers; Community	Moderate [4]	 Acquire signed Voluntary Land Donation (VLD) forms Provide training on completion of VLD forms 	PIU ESIA Consultant	2,000/190 2,500/237	Lender	Signed VLD	Signed VLD	Sep 2025
		Impact on livelihoods	The project activities could restrict thirty three (33) farmers access to lands that were otherwise used for farming.	Project affected Farmers	Moderate [4]	 Develop a Resettlement Action Plan (RAP)/ Livelihood Restoration Plan Implement the Resettlement Action Plan (RAP) Build PIU's capacity for RAP 	 RAP Consultant PIU RAP Consultant 	80,000/7,590 75,690/7,181 20,000/1,900	PIU/Lender Lender PIU/Lender	RAP Report RAP Implementat ion report Training for RAP	RAP Report RAP Implementat ion audit Training	Sep 2025 Qtr 1, 2026
						implementation				implementat ion team	reports	
OS6	Biodiversity, renewable resources and ecosystem services	Destruction of vegetation and displacement of wildlife	The project site is an already disturbed area due to previous human activities such as farming. The floristic analysis conducted identified <i>Grewia carpinifolia</i> which is of national conservation concern on the site. Aside that, none of the other species identified at the site are of conservation concern according to the Forest Reserves of Ghana Information Exhibitor (FROGGIE) data base.	Flora and Fauna	Moderate [4]	 Restrict vegetation clearance to the required area only and prohibit hunting of animals which may stray to the project area by providing temporary fences. This must be included in the contractor's bill of quantities and code of Conduct. Train contractor's E&S Officer on ESMP requirements. Develop a flora conservation plan for <i>Grewia carpinifolia</i> to ensure that they do not disappear from the project site. 	• Contractor • PIU	20,000/1,900	PIU	Installation of Fence Training for E&S officer	Physical inspection Training reports	Before construction Before construction

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			Site clearing will not lead to any major destruction of biodiversity of significant importance, only a few trees and destruction of the habitats of some animals.									
Constr	uction Phase											
OS 2	Labour conditions, health and safety	Project Site incidents/accidents	Project site accidents/incidents and animal/insect threat/bites	All Project workforce, Vulnerable categories of workers, Women	Major [6]	Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training	Project Contractor	50,000/4,744	PIU	Records and purchase of PPEs, training on PPE use, house-keeping, emergency response etc.	Review of CESMP OHS audits	Before construction During construction
		Poor labour working conditions	Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions. Workers could face issues of discrimination, forced labour, child labour, freedom of association and collective bargaining, lack of or ineffective worker grievance redress mechanisms	workforce, Vulnerable	Major [6]	 Adhere to national labour laws as provided in the Labour Act of 2003 (Act 651) and international best practice such as provisions of AfDB ISS (2023) OS 2 on Labour and Working Conditions Specific considerations should include the following: Provide all workers with signed contracts Provide welfare facilities as required. Encourage frequent breaks and job-rotation to reduce impact of the hot weather on workers. Require workers to sign Code of Conduct 	Project Contractor	120,000/11,385	PIU	Signed contract, welfare facilities, Grievance redress mechanism/ records	E&S audits	During construction

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati
						 Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. Provide adequate training for workers on safety, GBV, SEA/SH, child labour/human rights, social norms. Establish an effective worker grievance redress mechanism 						
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Presence of workers and increase in incidents of rape, defilement, child molestation and GBV.		Major [6]	 Include the requirements of policies on GBV, SEA/SH, Child Labour and Human Rights in the contractor's Code of Conduct Provide training for workers on required lawful conduct and legal consequences for failure to comply with laws on non-discrimination and GBV Insert clause requiring contractors and consultants to cooperate with law enforcement agencies investigating cases of gender-based violence A minimum requirement of female employment should be indicated in contract documents Contact numbers of representative on the Grievance Redress Committee and GBV Service Providers should be pasted around the project site and within the immediate project zone Discuss issues of Gender Based Violence at daily Toolbox meetings Display on site posters prohibiting sexual exploitation and harassment. 		80,000/7,590	PIU	Clauses on GBV, SEA/SH, Child Labour and Human Rights in the contractor's Code of Conduct	Review of contractor's code of conduct	During construction

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and Contamination	Excavation for foundation of structures could lead to soil erosion and creation of gullies through runoff	Soil	Moderate [4]	•	Develop an Erosion Management Plan	Contractor	50,000/4,744	PIU/Lender	Erosion Managemen t Plan	Inspection/ review	Before construction
			especially in the rainy season Soil contamination could			•	Implement the Erosion Management Plan	Contractor	100,000/9,488		Sediment traps	Inspection	During construction
			also occur from inappropriate disposal of waste oil, spilled oil during machinery operation and maintenance as well as fuel storage sites and leaks from vehicle refuelling			•	Train contractor's E&S Officer on ESMP requirements	PIU	20,000/1,898		Training on erosion managemen t	Training records	During construction
		Air Pollution	Emission of fumes and dust from transport of materials especially on untarred routes to project site. Baseline air quality data (PM _{2.5} – 30μg/m³, PM ₁₀ – 109μg/m³, NO ₂ , SO ₂ and CO were all below the minimum detection limit of 0.06 mg/m3 at the time of sampling. This shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds except for PM ₁₀ whose higher value could be attributed to high coarse particulate pollution, likely arising from mechanical disturbances during farming, vehicular movement, and possibly wind-driven dust due to the site's open, dry landscape.	members of the	Moderate [4]	•	Trucks and heavy machinery with a valid emission test pass certificate should only be allowed on the project site. Dust pollution must be reduced by ensuring that drivers do not speed especially on untarred roads. Suppress dust by watering dusty construction areas. Ensure the use of nose mask in dusty environment.	Project Contractor	60,000/5,693	PIU/Supervisi ng Engineer	Valid emission test certificate Speed limit signage Wet road surfaces Complaints/ grievances	Inspection	During construction

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring	Means of Verification	Timetable for Implementati
							-	supervision)		D. 1. 10	Indicator		on
		Water Pollution	Sediment and waste oil	Pools of water	Moderate [4]	•	Undertake construction in the dry	Project Contractor		PIU/Supervisi	Sediment	Inspection	During
			transport into nearby				season			ng Engineer	traps		construction
			water bodies.	valley.		•	Carry out maintenance activities						
			Domestic waste from the				away from water bodies		60,000/5,693				
			construction workers and			:	Install sediment traps		10,000/949		Taalbay	Taalbay	
			food vendors providing services to the			•	Educate workers on the importance of waste management.		10,000/949		Toolbox	Toolbox	
			construction crew.				importance of waste management.				exercises	records	
		Noise and	Operation of construction	Health of project	Moderate [4]		Ensure construction activities are	Project Contractor	20,000/1,898	PIU/Supervisi	Noise	Noise	During
		Vibration	equipment, movement of	workforce and	moderate [1]		carried out during the day.	i roject communica	20,000, 2,000	ng Engineer	emission	monitoring	construction
			haulage vehicles and	members of the			Provide and enforce wearing of				levels	report	
			tooting of horns.	surrounding			hearing protection by workers						
				communities			Sensitize workers on effects of						
							noise pollution				Complaints/	Records of	
							Ensure the use of well				grievances	complaints/	
							serviced/maintained vehicles and					grievances	
							other equipment with acceptable						
							noise emission levels.						
		Waste generation	Clearance of vegetation at	Health of project	Moderate [4]	•	Ensure that contractor develops	Project Contractor	100,000/9,488	PIU/Supervisi	Inventory of	Inspection/r	During
		and Disposal	project site, construction	workforce and			and implements a detailed			ng Engineer	waste	eview of	construction
			debris, pieces of	members of the			Construction Waste Management				generated/d	records/inve	
			steel/metal, packaging	Local			Plan.				isposed	ntory	
			materials, plastic pieces,	communities		•	Ensure efficiency in the use of						
			human waste etc. if not	within the			materials.						
			disposed properly could	project area		•	Reuse materials such as pieces of						
			clog drains and facilitate				wood, and metals.						
			the outbreak of sanitary				Recycle scrap metal						
			related diseases such as			•	Ensure collection and proper						
			cholera.				disposal of construction debris						
						•	Provide adequate waste bins for						
							waste collection and segregation						
						•	Sensitize workers on waste						
							management						
						•	Develop SOPs for managing						
							hazardous and non-hazardous						
OS4	Community Health, Safety	Traffic	Transport of materials and	Local	Moderate [4]	•	waste. Avoid transportation of materials	Project Contractor	50,000/4,744	PIU/Supervisi	Records of	Review/	During
U34	and Security	Management	equipment to and from the		Moderate [4]	ľ	and workers during peak hours	Froject Contractor	30,000/4,744	ng Engineer	traffic	inspection of	During construction
	and Security	Management		near the project			Train drivers on and ensure			IIS LIISIIICCI	incident and	records	Construction
			· ·	area of influence			adherence to the Highway Code				accidents	iecorus	
			townships raises	area or minuence			Ensure regular maintenance of				accidents		
			traffic/public safety				vehicles						
		1	traffic/public safety				VEHICLES	l		<u> </u>			

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati
			concerns. Broken-down, inappropriately parked or slow-moving haulage/construction trucks could lead to road accidents and traffic			•	Use flagmen and designated parking areas for safety onsite				Community complaints/ grievances		
		Visual / Aesthetic		Local	Moderate [4]	•	Maintain tidy construction sites (good housekeeping).	Contractor PIU	20,000/1,898	PIU	Site	Site	During
		Impacts	machinery, material stockpiles, temporary work camps; Vegetation clearance, earthworks (bare ground); Dust plumes.	communities (Nakpanzoo), commuters.		•	Minimize area of land clearance beyond essential footprint. Locate temporary facilities at unobtrusive areas to reduce visibility. Promptly rehabilitate disturbed areas post-construction. (grading, seeding). Ensure permanent structures (patios, sheds) use materials/colours that blend			Lender	tidiness. Area cleared. Community feedback (via GRM).	Inspections, Photographi c records	construction
		Fire Outbreak	Fire outbreaks from	Vegetation,	Moderate [4]	•	reasonably with the surroundings. Create fire belts to prevent spread	Project Contractor	50,000/4,744	PIU/Supervisi	Records of	Review/	During
			negligence of workers or the community burning refuse, game hunting and workers not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property.	communities near the project			of fire into the active working areas. Sensitize workers and community on the dangers of bushfires Store flammable materials away from fire sources Designate cooking and smoking areas onsite. Provide fire-fighting equipment onsite. Train workers on fire fighting and			ng Engineer	fire incidence Training on fire safety and risk	inspection of records	construction
							where applicable include community fire volunteers						
		Public Health Issues	Pollution of local water bodies will adversely affect the health of users. Sexual relations between workers and locals may	communities near the project	Moderate [3]	•	Potable water tanks or containers could be used on the project site to keep water for drinking. Sexual harassment or violence on the project site will not be	Project Contractor	60,000/5,693	PIU/ Supervising Engineer	Potable water tanks on site	Physical inspection	During construction
			bring about increase in sexually transmitted				tolerated and project contractor should be made aware of such				Records of sensitization	Review of records	

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			diseases including HIV/AIDs.			 incidences to ensure that any complaints are addressed in accordance with the law. Undertake sexual health education programs for workers and also ensure they desist from irresponsible sexual behaviour during project implementation. Encourage handwashing after work and if possible provide hand sanitizers to workers. Encourage workers to get vaccinated. Provide information, instructions and trainings on STDs, drug abuse etc. to the workers to create awareness. 				of workers on GBV/SH Availability of condoms in washrooms Availability of hand washing sinks/basins and sanitizers on site	Inspection	
						Provide female and male condoms to the community and workers.						
		Security Concerns	Violent behaviour and confrontations between workers and locals. Workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over illicit sexual affairs, child labour, drunk driving, accidents and destruction of property.	Local communities near the project area of influence	Minor [2]	 Sensitize local community on cultural tolerance and grievance mechanisms to prevent confrontations Migrant workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. The contractor should prioritize employing locals especially the youth who may be unemployed which can ultimately lead to unrest or other social vices. 		30,000/2,846	PIU	Community meetings Toolbox exercises Number of locally employed workers	Inspection of community meeting minutes Review of toolbox records Inspection of records of locally employed workers	During construction
		Risk of Drowning	Any borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for workers	workforce and Local communities near the project	Moderate [4]	 Fence dug outs or borrow pits to prevent drowning. Provide warning signage at borrow pit sites. Sensitize community members on risk of drowning 	Project Contractor	100,000/9,488	PIU	Presence of fence and signage Records of drowning	Inspection	During construction

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			especially contract staff								incidents/ac		
			who are not familiar with								cidents		
			the local terrain. Children										
			who may play around the								Records of		
			sites and unsuspecting								community		
			community members may								sensitization		
			also be at risk of drowning								programmes		
			especially when it rains and										
			the place get flooded. It										
			must be noted however,										
			that the specific locations										
			for the borrow pits are yet										
			to be determined by the										
			project contractor and that										
			will be done before work										
			commences.										
Operat	ion Stage	T				1							
OS2	Labour conditions, health	Farm	Farm accidents/incidents	All Farm workers,	Moderate [4]	•	Develop and implement an	Municipal MoFA/	300,000/28,463	Regional	Records of	Review of	During
	and safety	incidents/accidents		Vulnerable			Occupational, Health and Safety	Assembly		MoFA	training on	ESMP	operation
			threat/bites	categories of			Management Plan that covers at a				PPE use,		
				workers, Women			minimum good housekeeping,				housekeepin		
							provision and use of PPE,				g,	OHS audits	
							incident/accident reporting and				emergency		
							investigation, emergency response				response		
							and training				etc.		
						•	Training and sensitization of						
							farmers on the use of PPE, farm						
							implements and agro-chemicals						
		Poor labour	Lack of employment		Moderate [4]	•	Adhere to national labour laws as	· ·	200,000/18,975	Regional	Number of	Review of	During
		working conditions	contracts could lead to				provided in the Labour Act of 2003	Department of		MoFA	labour	the records	operation
			farm workers being paid	Vulnerable			(Act 651) and international best	Community			related		
			rates below the stipulated	categories of			practice such as provisions of AfDB	Development			complaints		
			national minimum wage or	workers, Women			ISS (2023) OS 2 on Labour and				and		
			work under poor				Working Conditions				grievances		
			conditions. Farm workers			•	Specific considerations should						
			could be exposed to				include the following:						
			discrimination, forced and			-	Provide all workers with signed						
			child labour, restriction of				contracts						
			freedom of association and			-	Provide welfare facilities as						
			collective bargaining, non-				required.						
			existent or ineffective farm										

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati
			worker grievance redress mechanism.			 Encourage frequent breaks and job-rotation to reduce impact of the hot weather on workers. Require workers to sign Code of Conduct Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. Provide adequate training for farm workers on safety, GBV, SEA/SH, child labour/human rights, social norms. Establish an effective grievance redress mechanism for farm 						
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Presence of migrant farm workers could increase incidents of rape, defilement and GBV.	Women	Moderate [4]	 workers Provide sensitization and training for farm workers on required lawful conduct, access to GBV service providers and legal consequences for failure to comply with laws on non-discrimination and GBV Farm owners to be encouraged to employ females as farm workers. 	Department of Community	100,000/9,488	Regional MoFA	Number of recorded incidents of GBV/SH cases	Review of records	During operation
		Child Labour	Employment and deployment of Children under the working age at the expense of their education and exposure to hazards that endanger their health and wellbeing.	Children	Moderate [4]	 Prohibit the employment of children under age 15 on farms. Ensure children who spend time with their parents on the farm do not do so at the expense of their education and well-being. 	1	50,000/4,744	Regional MoFA	Number of recorded incidents of child labour cases	Review of records	During operation
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and degradation	Abuse of fertilizer use could lead to soil degradation. Leaving farmlands bare especially after harvesting could expose the soil to erosion.	Soil	Moderate [4]	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management.	Municipal MoFA	100,000/9,488	Regional MoFA	Training of farmers on soil, water and nutrient managemen t		During operation

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati
		Air Pollution	Use of farm machinery,	Health of farm	Moderate [4]	•	Practicing No-till or Low-till	Municipal MoFA	100,000/9,488	Regional	Training of	Inspection of	During
			clearing of dry lands and	workers and			methods where crop residues are	-		MoFA	farmers on	training	Operation
			emission of fumes/dust	surrounding			retained on the field or				good	records	
			from tricycles or	community			incorporated into the soil can help				farming		
			motorcycles conveying	members.			decompose the stubble naturally,				practices		
			farmers and farm produce				reducing the need for stubble						
			especially on untarred				burning.						
			routes from farms are			•	Mobile, small-scale threshers can						
			some of the activities that				be used in place of manual						
			have the potential of				threshing so as to reduce the						
			affecting the air quality				amount of dust or rice chuff						
			within the project area.				emitted into the atmosphere.						
			Stubble burning to prepare			•	Minimizing dust generation						
			the field for the next				activities as much as possible						
			planting season can also				especially during windy periods.						
			affect the air quality within			•	Vehicle speed, particularly on						
			the project area.				untarred roads transporting farm						
			Baseline air quality data				produce and agric inputs to and						
			$(PM_{2.5} - 30\mu g/m^3, PM_{10} -$				from the farm will be strictly						
			109μg/m ³ , NO ₂ , SO ₂ and				controlled to minimize dust						
			CO were all below the				generation.						
			minimum detection limit of										
			0.06 mg/m3 at the time of										
			sampling. This shows that										
			the project area's airshed										
			is not degraded as all										
			parameters are within the										
			emissions thresholds										
			except for PM ₁₀ whose										
			higher value could be										
			attributed to high coarse										
			particulate pollution, likely										
			arising from mechanical										
			disturbances during										
			farming, vehicular										
			movement, and possibly										
			wind-driven dust due to										
			the site's open, dry										
			landscape.										

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
		Water Pollution	Sediment laden with excess fertilizers and other agrochemicals and waste oil transport into nearby water bodies. Pollution of watercourses caused by wastes generated by farm workers as well as runoff from land used for growing rice (containing fertilisers, pesticides and herbicides etc.).	Water quality of water which has gathered as ponds in the valley.	Moderate [4]	 Provide education to farmers on the MoFA extension guide on soil, water and nutrient management. There will be proper timing in the application of fertilizers/herbicides and other agrochemicals considering the crop's nutrient needs and soil conditions in order to maximize fertilizer uptake and minimize leaching and runoff. Implement Pest Management Plan (PMP) Provision of on-site sanitation facilities and encourage the farm workers to use it. Educate farm workers to avoid open defecation. Sediments traps will be designed and constructed within the farm lands to contain contaminated sediments which will later be harvested for producing blocks for building. 	Municipal MoFA	300,000/28,463	Regional MoFA	Training of farmers on good farming practices	Inspection	During operation
		Noise and Vibration	Noise from activities like tilling the land for the next planting season, threshing the rice after cultivating and screaming sounds from farmers or labourers to scare away birds can all generate noise. Tricycles and motorbikes conveying farmers and farm produce to the milling factories or markets could generate some noise including the sounds from tooting horns.	and members of communities close to the		 Scare crows should be encouraged instead of the screaming sounds from farmers or labourers to scare away birds. Use threshing machines with soundproofing devices 	Municipal MoFA Municipal MoFA	50,000/4,744 75,000/7,116	Regional MoFA	Sensitization of farmers Sensitization	MoFA participation in community engagement	Throughout the operational phase
		generation and disposal	waste, i.e. empty containers of	workers and the Local community.		the MoFA extension guide on compost production using rice husk, straw, and other organic waste.			MoFA	of farmers	participation in community engagement	the operational phase

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			as breeding grounds for mosquitoes. Threshing will produce rice husk that may pile up to form heaps of waste.			 Provide adequate waste sk collect empty container agrochemicals and fertilize disposal by a licenced management company. Good housekeeping shoul encouraged on farms. Implement Pest Management (PMP) 	s of rs for waste d be					
OS4	Community Health Safety and Security	Fire Outbreak	Fire outbreaks from negligence of farm workers and community members, burning refuse, game hunting, cooking and not properly extinguishing stubs of cigarette. These fires could spread to adjoining farms causing injuries to persons and destruction of property.	Rice farms, nearby vegetation, farm workers and local community.	Moderate [4]	` '	and away soking oment ghting	100,000/9,488	Regional MoFA	Sensitization of farmers	Participation in community engagement meetings by MoFA/GNFS and NADMO.	Throughout the operational phase
		Traffic Management Security Concern	Transportation of farmers and farm produce through communities raises traffic/public safety concerns. Violent behaviour and confrontations between migrant farm workers and	Local communities Farm workers and Local communities	Minor [2]	 Drivers should exercise of when driving through cross areas such as markets. Installation of speed rum check speeding vehicles. Identify safe parking areas of roads to allow for unloading long-term parking of vehicles. Sensitize local community cultural tolerance and gries mechanisms at community displayed. 	main g and y on MoFA/Assembly vance	30,000/2,846	PIU/ Supervising Engineer PIU/ Supervising Engineer	Records of traffic incident and accidents Community complaints/ grievances Records of traffic incident and	MoFA and Assembly participation in community engagement meetings MoFA and Assembly participation	phase
			locals. Farm workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over sexual affairs, child labour,			to prevent confrontations Migrant farm workers shown made aware of the common cultural and traditional values/beliefs so they may against them.	inity's tional			accidents Community complaints/ grievances	in community engagement meetings	phase

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			drunk driving, accidents and destruction of property.			•	Farm owners should prioritize employing locals into their farms especially the youth who may be unemployed which can ultimately lead to unrest or other social vices.						
		Polluted Waterbodies	Pollution of local water bodies from contaminated sediments and run-off will adversely affect the health of community members.	Farm workers and Local communities	Moderate [4]	•	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management. Educate farm workers to avoid open defecation.	Municipal MoFA	50,000/4,744	Regional MoFA	Sensitization of farmers	MoFA participation in community engagement meetings	Throughout the operational phase
		Sexual Transmitted Diseases	migrant farm workers and	Farm workers and Local communities	Moderate [4]	•	Undertake sexual health education programs for farm workers to desist from irresponsible sexual behaviour.	Municipal MoFA/ Municipal Health Directorate	50,000/4,744	Regional MoFA	Sensitization of farmers	Participation in community engagement meetings by MoFA and the Municipal Health Directorate	Throughout the operational phase
		Flooding	The project implementation could be adversely affected by events of flood from torrential rainfall in the wet season especially in low-lying areas affecting properties and lives.	Farmers, Local community, Flora and Fauna	Major [6]		Educate farmers and community on early warning signs of flood. Discourage the siting of farms within or close to river beds. Collaborate with spatial planning and disaster management agencies, using disaster maps and systems, to stay away from floodprone areas. Infrastructure for agricultural establishments should be constructed preferably on high grounds. Sensitive farmers on the benefits of insurance cover for equipment and personnel.	MoFA/Assembly/NA DMO	150,000/14,231	Regional MoFA	Sensitization of farmers	Participation in community engagement meetings by MoFA, the Assembly and NADMO.	Throughout the operational phase
		Risk of Drowning	Any borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This	Local community	Moderate [4]	•	Maintenance of dug outs or borrow pits fence to prevent drowning.	Municipal MoFA	50,000/4,744	Regional MoFA	Sensitization of community members/ farmers	Participation in community engagement	Throughout the operational phase

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			can pose the risk of drowning for communities in the project area especially children.			•	Provide and replace warning signage at borrow pit sites when necessary. Sensitize community members on risk of drowning					meetings by MoFA.	
Decom	missioning Phase												
OS2	Occupational health and safety (OHS) impacts and risks	Project Site incidents/accidents	Project site accidents/incidents and animal/insect threat/bites	All Project workforce, Vulnerable categories of workers, Women	Major [6]	٠	Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training	Project Contractor	50,000/4,744	PIU	Records and purchase of PPEs, training on PPE use, housekeepin g, emergency response etc.	Review of ESMP OHS audits	Immediately after construction
OS3	Resource Efficiency and Pollution Prevention and Management	Waste generation and Disposal	Clearance of vegetation at project site, construction debris, pieces of steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog drains and facilitate the outbreak of sanitary related diseases such as cholera.	workforce and members of the Local communities within the	Moderate [4]	•	Ensure efficiency in the use of materials. Reuse materials such as pieces of wood, and metals. Recycle scrap metal Ensure collection and proper disposal of construction debris Provide adequate waste bins for waste collection and segregation Sensitize workers on waste management Develop SOPs for managing hazardous and non-hazardous waste. Develop and ensure implementation of Pest Management Plan (PMP)	Project Contractor	120,000/11,385	PIU	Inventory of waste generated/ Disposed of	Inspection/ review of records/ inventory	Immediately after construction
OS4	Community Health and Safety	Traffic Management			Moderate [4]		Avoid transportation of materials and workers during peak hours Train drivers on and ensure adherence to the Highway Code Ensure regular maintenance of vehicles	Project Contractor	50,000/4,744	PIU	Records of traffic incident and accidents	Review/ inspection of records	Immediately after construction

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			concerns. Broken-down,			Use flagmen and designated				Community		
			inappropriately parked or			parking areas for safety onsite.				complaints/		
			slow-moving							grievances		
			haulage/construction									
			trucks could lead to road									
			accidents and traffic									
			congestion especially on									
			busy roads.									

0.10 Environmental Monitoring

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
CONS	STRUCTION PHASE					
1	Project site accidents/incidents	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Nakpanzoo valley	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
2	Poor labour working conditions	 Availability of copies of signed contracts Human Resource Management Plan/Recruitment Policy Complaints lodged by workers 	Nakpanzoo valley construction site	Quarterly	PIU Environmental and Social Safeguards Specialists	31,620 (3,000)
3	Soil impacts and sediment transport	 Observable change in turbidity of water in drains or water bodies Observable oil sheen in drain Observation of rills/gullies 	Nakpanzoo valley construction site and Immediate environs	Monthly	PIU Environmental Safeguards Specialist	42,160 (4,000)
4	Air and Noise Pollution	Number of complaints by community members/workers	Nakpanzoo valley construction site and Immediate environs	Monthly	PIU Environmental Safeguards Specialist	52,700 (5,000)
5	Waste generation and inefficient management	 Number of mobile toilets and dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site 	Nakpanzoo valley construction site and Immediate environs	Weekly	PIU Environmental Safeguards Specialist	26,245 (2,490)

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
		Complaints by workers/community members				
6	Traffic accident risks/Public safety concerns	 Grievance records Traffic related incidents/accidents Records of accidents, incidents and near misses. 	Nakpanzoo valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
7	Visual / Aesthetic Impacts	Site tidiness.Area cleared.Community feedback (via GRM).	Nakpanzoo valley	Monthly	PIU Environmental and Social Safeguards Specialists	5,375 (510)
8	Fire outbreaks	 Fire related incidents/accidents Records of fire incidents and near misses. Number of functional fire extinguishers onsite 	Nakpanzoo valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
9	Public health issues	 Number of sensitization campaigns Number of condoms distributed to Contractor's staff in a month Number of STD cases reported to local health facilities involving encounters with Contractor's staff 	Nakpanzoo valley construction site and immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	47,430 (4,500)
10	Security and SH/GBV concerns	Number of conflicts/cases reported to the Grievance Redress Committee/Community Liaison Officer	Nakpanzoo valley construction site and immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	36,890 (3,500)

No.	Potential	Monitoring Indicators/Means of	Monitoring Site	Frequency	Responsibility	Cost Estimate/ Year
	Environmental and	verification			(Implementation/	GHS (USD)
	Social Impacts				Monitoring)	
		Number of conflicts/cases dealt with				
		by the Grievance Redress Committee				
		Number of crimes such as theft,				
		defilement and rape reported,				
		investigated, and concluded by the				
		police involving the Contractor's				
		workers				
Sub-1	Гotal					400,520 (38,000)
OPER	RATIONAL PHASE					
1	Farm	Records of accidents, incidents and	Nakpanzoo valley Farm	Monthly	Municipal MoFA	31,620 (3,000)
	accidents/incidents	near misses.			Extension officers/	
		Records of PPE disbursed			Regional MoFA	
		Housekeeping				
2	Poor labour working	Availability of copies of signed	Nakpanzoo valley Farm	Monthly	Municipal MoFA	42,160(4,000)
	conditions	contracts			Extension officers/	
		Complaints lodged by farm hands and			Regional MoFA	
		other workers				
3	Soil impacts and	Observable change in turbidity of	Nakpanzoo valley Farm	Monthly	Municipal MoFA	52,700 (5,000)
	sediment transport	water in drains or water bodies	and immediate		Extension officers/	
		Observable oil sheen in drain	environs		Regional MoFA	
		Observation of rills/gullies				
4	Air and Noise Pollution	Number of complaints by community	Nakpanzoo valley Farm	Monthly	Municipal MoFA	31,620 (3,000)
		members/farmhands	and community		Extension officers/	
					Regional MoFA	

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
5	Waste generation and inefficient management	 Presence of toilet facilities and number dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site Complaints by farm workers/community members 	Nakpanzoo valley Farm and immediate environs	Weekly	Municipal MoFA Extension officers/ Regional MoFA	52,700 (5,000)
6	Traffic accident risks/Community safety concerns	 Grievance records Traffic related incidents/accidents Records of all accidents, incidents and near misses. 	Nakpanzoo valley Farm/ community and immediate environs	Monthly	Municipal MoFA Extension officers/ Regional MoFA	52,700 (5,000)
7	Fire outbreaks	 Fire related incidents/accidents Records of fire incidents and near misses. Number of functional fire extinguishers onsite 	Nakpanzoo valley Farm and immediate environs	Monthly	Municipal MoFA Extension officers/ Regional MoFA	31,620 (3,000)
8	Community health issues	 Number of sensitization campaigns Number of condoms distributed to farm workers or placed at convenient places in a month Prevalence of STD cases reported to local health facilities 	Nakpanzoo valley Farm/ community and immediate environs	Monthly	Municipal MoFA Extension officers/ Regional MoFA	47,430 (4,500)
9	Security and SH/GBV concerns	Number of conflicts/cases reported to the Grievance Redress Committee/Community Liaison Officer	Nakpanzoo valley Farm/ community and immediate environs	Monthly	Municipal MoFA Extension officers/ Regional MoFA	36,890 (3,500)

No.	Potential	Monitoring Indicators/Means of	Monitoring Site	Frequency	Responsibility	Cost Estimate/ Year
	Environmental and	verification			(Implementation/	GHS (USD)
	Social Impacts	1333.3			Monitoring)	(002)
	·	 Number of conflicts/cases dealt with by the Grievance Redress Committee Number of crimes such as theft, defilement and rape reported, investigated, and concluded by the police involving workers or patrons 				
10	Risk of Drowning	Number of drowning cases reported and investigated involving unsuspecting community members and animals.	Dugout (from the previous sand winning site now used as water source)	Weekly	Municipal MoFA Extension Officers, Municipal Assembly/ Regional MoFA	31,620 (3,000)
Sub-t	otal					411,060 (39,000)
DECO	MMISSIONING PHASE					
1	Project site accidents/incidents	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Nakpanzoo valley	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
2	Waste generation and inefficient management	 Number of mobile toilets and dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site Complaints by workers/community members 	Nakpanzoo valley construction site and Immediate environs	Weekly	PIU Environmental Safeguards Specialist	31,620 (3,000)
3	Traffic accident risks/Public safety concerns	Grievance records Traffic related incidents/accidents	Nakpanzoo valley and Immediate environs	Monthly	PIU Environmental and Social	52,700 (5,000)

No.	Potential	Monitoring Indicators/Means of	Monitoring Site	Frequency	Responsibility	Cost Estimate/ Year		
	Environmental and	verification			(Implementation/	GHS (USD)		
	Social Impacts				Monitoring)			
		• Records of accidents, incidents and			Safeguards			
		near misses.			Specialists			
Sub-t	Sub-total							
TOT		948,600 (90,000)						

0.11 Institutional capacity to implement ESMP

The capacity assessment presented in the table provides a description of institutional roles, their existing capacities, the gaps that may hinder performance, and actionable recommendations to close these gaps. The responsibility and budget to implement the recommendations have been included in the ESMP budget.

Institutional Roles, Capacity Gaps and Recommendations

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
MoFA (District &	Lead	Regional/district	Weak safeguards	Provide intensive
Regional)	implementer;	offices have limited	integration at	training on safeguards
	coordination,	environmental and	local level; and	compliance;
	extension,	social safeguards	limited tools for	Supply digital data
	safeguards	knowledge.	monitoring	collection tools;
	compliance	However, national		Integrate ESMP
		divisional office has		indicators into MoFA
		stronger capacity		M&E systems
Project	Safeguards	Adequately staffed	Limited	Strengthen
Implementation	oversight and	with environmental	operational	coordination
Unit (PIU)	project	and social	linkages with	platforms with MoFA,
	management	safeguards officers	district	EPA, and District
			institutions	Assembly; and
				formalize reporting
				schedules
EPA (Regional	Regulatory	Strong technical	Inability to	Engage EPA to
Office)	oversight; and	expertise, but	conduct regular	improve support at
	participation in	logistics	field inspections	regional level such as
	joint inspections	constrained (e.g.,	due to lack of	vehicles, field logistics,
		transport, field	resources	and budget for regular
		equipment)		compliance
				monitoring
Savelugu	Local governance;	Some competence	Weak capacity in	Provide structured
Assembly	grievance	in grievance	grievance redress	training on grievance
	redress;	handling, but	aligned with	mechanisms and
	community	limited awareness	ESMP	safeguards at
	mobilization	of safeguards		district/regional levels
CSIR – Water	Technical	Adequate technical		Formalize role in ESMP
Research Institute	monitoring of	competence and	field	monitoring with
	water quality	facilities	implementation	budget and data-
				sharing mandate
CSIR – Soil	Technical	Adequate technical	Underutilized in	Formalize role in ESMP
Research Institute	monitoring of soil	competence and	project-specific	monitoring with
	quality	facilities	monitoring	budget and data-
				sharing mandate

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
GNFS	Fire education,	Strong institutional	Limited	Engage GNFS to
(Regional/District)	prevention, and	mandate, but	firefighting	improve fire-fighting
	response	inadequate fire	equipment;	equipment resources
		hydrants, tenders,	inadequate	at the district level;
		and trained	training capacity	build capacity on
		personnel		prevention and
				community training
				methods
NADMO (District	Disaster risk	Active but under-	Staffing and	Engage district
Office)	education,	resourced with	logistical deficits	NADMO to recruit
	preparedness,	limited staff and	constrain rapid	additional staff;
	and response	logistics	response	provide disaster
				response logistics
				(vehicles, equipment);
				and build staff
				capacity
NGOs/CSOs	Community	Active presence but	Weak technical	Provide training in
	engagement and	limited technical	understanding of	safeguards,
	sensitization	expertise on	ESMP safeguards	participatory
		safeguards		monitoring, and
				technical engagement

MoFA should establish formal coordination mechanisms, including joint monitoring schedules and shared reporting platforms to enhance accountability and synergy across agencies.

0.12 Grievance Redress Mechanism

The activities of the project may generate grievances arising from the interaction between project and local authorities/community, workers and the host community. Some potential grievances identified and likely to occur during project implementation include:

- Complaints from the local community on the conduct of workers, especially sexual harassment and other gender-based offenses;
- Complaints related to noise, dust, traffic incidents;
- Restriction of access to persons who otherwise were using portions of land e.g. for grazing
- Failure to consider the recruitment of local man-labour;
- Non-respect of the habits and customs of the host community by the contractor/ consultants/ MoFA personnel etc;
- Non-compliance with the measures or provisions contained in the ESMP.

In managing grievances, the REWARD project proposed measures for resolution of grievances that may arise due to project implementation. This is a three-tier grievance redress structure which are;

- Community level structures (1st Tier) These includes; a Grievance Redress Committee and Sitelevel Grievance Redress Mechanism.
- District level structure (2nd Tier) Municipal Grievance Redress Committee

• Project-wide level structure (3rd Tier) – Project Grievance Redress Committee

Community Level (1st Tier):

- Includes Community Grievance Redress Committees (GRCs) and site-level Grievance Redress Mechanisms (GRMs).
- Handles initial complaints from individuals or communities related to agricultural or infrastructure activities.
- Site-level GRMs are managed by contractors and report monthly to the project team; oversight is provided by the PIU Environmental and Social Safeguard Specialists.

District Level (2nd Tier):

- Municipal Grievance Redress Committees (Municipal GRCs) address unresolved complaints from the community level or cases where community GRCs fail to act within 30 days.
- They meet quarterly or as needed for urgent matters.

Project Level (3rd Tier):

- Project Grievance Redress Committee led by the Project Coordinator or Social Safeguard Specialist.
- Handles cases escalated from the municipal level, especially if not resolved in 30 days or if the complainant is dissatisfied with the resolution.

0.13 ESMP Implementation Budget

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
		Cost (USD)	Cost (GHS)
Preconstruction	- E & S assessment and permit acquisition.	37,287	393,000
(Preparatory) Phase	- Training and completion of VLD forms.	427	4,500
	- RAP/LRP Implementation and capacity building for PIU.	13,237	139,520
	Fencing of site to restrict vegetation clearanceTraining of E&S officers on ESMP.	2,841	30,000
- Sub Total		53,792	567,020
Construction Phase	 Development and implementation of an Occupational, Health and safety management plan. 	4,735	50,000
	 Labour force management and training on safety, discrimination, GBV, SEA/SH, child labour/human rights and ethical conduct. 	18,939	200,000
	- Erosion management and ESMP training for contractor's E&S team	16,098	170,000
	- Air quality deterioration abatement measures and PPE provision	5,682	60,000
	- Water pollution abatement measures	6,629	70,000
	- Noise abatement measures implementation and PPE provision	1,894	20,000
	- Waste management including hazardous and non-hazardous waste	11,364	120,000

Project Stage Project Activities		Estimated ESMP	Estimated ESMP
	·	Cost (USD)	Cost (GHS)
	- Traffic management and road safety training for drivers	4,735	50,000
	 Implementation of fire prevention/fighting measures and training for workers and community 	4,735	50,000
	- Management of grievances including GBV, SEA/SH, child labour/human rights	5,682	60,000
- Sensitization of workers and commount cultural tolerance and conflict management		2,841	30,000
	- Management and community sensitization on drowning risks	9,470	100,000
Sub-Total		92,804	980,000
Operation Phase	- Development and implementation of occupational health and safety plan/measures	28,463	300,000
	- Sensitization on good labour practices, rights and ethical conduct.	18,975	200,000
	- GBV sensitization for farm owners/workers	9,569	100,000
	- Child labour sensitization for farm owners	4,744	50,000
	- Education on soil, water and nutrient management for farmers.	9,488	100,000
	- Education of farmers on air quality deterioration abatement measures	9,488	100,000
	 Education on soil, water, and nutrient management, waste management, pollution prevention and PMP Implementation 	28,463	300,000
	- Sensitization of farmers on noise abatement measures	4,744	50,000
	 Waste management including provision of skips, collection/disposal and education on composting 	7,116	75,000
	 Fire risk management and sensitization of farmers on fire-fighting techniques. 	9,488	100,000
	 Education of farmers on soil, water and nutrient management. 	4,744	50,000
	- Sexual health education programs for farm workers to promote public health	4,744	50,000
	- Flood risk assessment and management	14,231	150,000
	- Sensitization of workers and community on cultural tolerance, and conflict management	2,841	30,000
	- Traffic management and road safety training for drivers	4,744	50,000
	- Management and community sensitization on drowning risks	4,744	50,000
Sub Total		166,508	1,755,000
Decommissioning Phase	- Development and implementation of an Occupational, Health and safety plan.	4,735	50,000
1 11030	- Waste management including hazardous and non-hazardous waste	11,364	120,000
	- Traffic management and road safety training for drivers.	4,735	50,000
Sub Total		20,834	220,000

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
		Cost (USD)	Cost (GHS)
Grievance Redress		79,000	832,660
Mechanism (GRM)			
Resettlement		7,181	75,690
Action Plan			
Implementation			
Environmental &		25,000	263,500
Social Performance			
Audit			
RAP Completion		7,000	73,780
Audit			
Sub Total		118,181	1,245,560
Total		452,119	4,767,580

0.14 Decommissioning

A Decommissioning and Site Closure Plan (DCP) is required to guard against the remote possibility of abandoning temporary constructed structures. Should such a circumstance arise, the potential would exist for impacts from abandonment of the facility such as aesthetic impacts and potential trespassing and safety concerns.

The specific objectives in managing the decommissioning process will be:

- To ensure that rehabilitation and decommissioning are carried out in a planned sequential manner, consistent with best practice;
- To ensure that agreed post-project land-use outcomes are achieved; and
- To avoid on-going liability.

A Full Decommissioning Report is expected to be prepared in the event of any such activity for approval by the EPA and any other requisite state agencies.

Pre-Decommissioning Assessment

Prior to any decommissioning, the EPA will be notified and an assessment will be carried out to identify any potential environmental impacts that need to be addressed and mitigated in the decommissioning process.

Decommissioning Phase Activities

Some of the activities that will be undertaken during the decommissioning phase will mostly be the dismantling and removal of structures and equipment.

Dismantling and Removal of Structures and Equipment

All decommissioning and restoration activities will be in accordance with all applicable state and local permits and requirements and will include the following specific activities:

• Hardware retirement: All power sources would be disconnected from structures and equipment before dismantling commences. Cranes and/or other machinery will be used for the disassembly

- and removal of structures and associated installations. These will either be transported whole for reconditioning and reuse or dissembled into salvageable, recyclable, or disposable components;
- Foundation removal: All foundation materials will be removed as per EPA guidelines or requirements. The remaining excavation will be filled with clean sub-grade material, compacted to a density similar to surrounding sub-grade material, and finished with topsoil;
- Monitoring: A monitoring and remediation period of two years immediately following the
 completion of any decommissioning and restoration activities will be undertaken. If agricultural
 impacts are identified during this period, follow-up restoration efforts will be implemented; and
- Area restoration: Areas where subsurface components are removed will be graded to match
 adjacent contours, stabilized with an appropriate seed mix, and allowed to re-vegetate naturally.
 All community roads, impacted by Project decommissioning activity, if any, will be restored to
 original condition upon completion of decommissioning.

Solid Waste Management

All solid waste resulting from the decommissioning process will be evacuated by handlers commissioned by the Municipal Solid Waste Department.

Post-Decommissioning Assessment

Removal of machinery, equipment and all other materials related to the project will be completed within one year of decommissioning. At the end of the decommissioning exercise, the EPA will be invited to carry out a post-decommissioning assessment to establish compliance with all regulatory requirements and issue a certificate to that effect. The Decommissioning and Closure Plan will be finalized and submitted to the relevant authorities for approval at least six months prior to closure of the site.

A report describing the performance of the final DCP in working towards its objectives, based on monitoring results, and the extent to which it has been complied with, will be submitted to the EPA. The report will be provided to documented stakeholders and will otherwise be publicly available on request. Files and documents used to collate information regarding closure commitments, licenses, approvals and other information concerning closure will be catalogued and maintained in accordance with standard practices.

0.15 Conclusion

The proposed project will be implemented in accordance with relevant national laws and best international practices provided by the applicable Operational Safeguards of the AfDB Integrated Safeguard System.

Stakeholders have been identified and their suggestions and concerns obtained through the consultation and engagement process have been highlighted in the report and addressed. A Stakeholder Engagement Plan (SEP) has been proposed to ensure continued engagement of all stakeholders and the implementation of a grievance redress mechanism to ensure harmony in the project implementation.

The potential adverse impacts of the project have been identified. Adequate mitigation measures have been proposed to manage the moderate to major adverse impacts. Also, management and monitoring

plans have been designed to ensure that the proposed mitigation measures are adequately implemented. The institutional capacities have been assessed and gaps identified with recommendations.

The assessments have shown that the project generally has moderate impacts on the environment and the impacts could be further mitigated with the adoption of good environmental, health and safety practices. A Pest Management Plan (PMP) is required to ensure judicious and safe use of agrochemicals as well as safe disposal of obsolete chemicals and empty containers.

The Chief of the Nakpanzoo community has donated the land for the project. A Resettlement Action Plan has been proposed to mitigate the livelihood impacts on thirty- three (33) farmers who will vacate their farm lands for use by the project.

The project holds immense benefit for the Nakpanzoo community, the municipal and region regarding food security, job creation, growth of MSMEs, etc. The entire country will benefit from improved food security, increased knowledge and adoption of best agricultural practices for rice production, etc.

1.0 INTRODUCTION

1.1 Background of the Project

The Government of Ghana (GoG) through the Ministry of Food and Agriculture (MoFA), in collaboration with the African Development Bank (AfDB) is undertaking the Resilient Rice Regional Value Chains in West Africa (REWARD) Project.

The Project seeks to develop some selected inland valleys to promote rice production in the Northern part of Ghana specifically, the Northern, Upper West, North-East and Savannah Regions to boost preparedness against food insecurity and improve the resilience of food systems in Ghana.

Specific activities to be undertaken in these selected Inland valleys include but not limited to: development of water control and conveyance systems; construction of drainage system to collect water out of command areas; construction of access roads into the valleys; and land development for crop cultivation. The programme will also seek to address issues with women and youth drawn from the Gender Action Plan (GAP).

This development objective will be achieved through improving farmers' access to usable weather, climate and advisory services; improving access to local climate information services through digital information platforms; facilitating the co-production of services between private and public sector; increasing farmers' access to agricultural and nutrition sensitive technologies developed by a consortium of National Centers of Specialization (NCoS), Consultative Group for International Agricultural Research (CGIAR) and other international research institutes; establishing spatial information system to design and plan climate resilience land management practices; promoting private sector involvement in regional agricultural trade; and supporting women farmers to access services to improve marketing along target commodity value chain.

In line with environmental permitting requirements as provided under the Environmental Protection Act, 2025 (Act 1124), the Environmental Assessment Regulations of 2025 (LI 2504), this assessment has been carried out by SAL Consult Limited to help understand the likely implications of the proposal in order to inform the environmental permitting decision-making prior to project implementation in the Savelugu Municipal area. Also, the ESIA will ensure the project and subprojects comply with the requirements of the Bank's Operational Safeguards System (OSS). The main objective of REWARD-Ghana is to reduce importation of rice by increasing competitive local rice production, processing, income, and job creation, which will lead to improved nutrition and food security in a sustainable manner and contribute to reducing poverty through a private-public sector driven interventions along the rice value chain. The specific objectives of the project are;

- To increase rice productivity and production thus increased incomes for farmers, particularly women and young people;
- To increase the resilience and adaptive capacities of rice farms and production systems; and
- To increase the marketing and intra-regional trade of rice.

1.2 Purpose of the ESIA

The scope of work for the ESIA study is to among other things:

- Provide technical description of the proposed project and identify all activities of environmental/social concerns;
- Analyse project alternative and investigate options to the project development in relation to the
 project site, design, and the "no action alternative" which assumes that the Project is not
 implemented.
- Establish the existing environmental and socio-economic baseline conditions of the project area of influence:
- Predict and examine all the significant environmental impacts on the surrounding communities and the general environment during implementation of the proposed project and advise on appropriate mitigation and abatement measures against potential adverse impacts;
- Provide a monitoring program for predicted impacts and mitigation measures;
- Provide an Environmental and Social Management Plan (ESMP) integrating Grievance Redress Mechanism (GRM);
- Document the socio-economic and cultural advantages and disadvantages associated with the proposed project for stakeholders and interested groups to make an informed decision on the level of environmental compromise and permitting.
- Provide a plan to guide the development of an emergency response plan for the project;
- Provide guidelines to be followed in the event of decommissioning; and
- Carry out public consultations and include the outcome in the ESIA report with arrangements to address stakeholder concerns.

1.3 Methodology for the Assessment Process

This report has been prepared in accordance with applicable African Development Bank and Ghanaian environmental assessment guidelines and involves the following activities:

- Data gathering; The Consultant assembled and evaluated relevant baseline data relating to the biophysical and socio-economic environment to be influenced by the project. The baseline data include climate, topography and relief, geology and soil, vegetation, demography, access to basic services and socio-economic conditions. In addition, this report has scoped out the issues and provided general assessment of the impacts.
- Stakeholder identification and consultations; Key stakeholders identified include Ministry of Food and Agriculture (Department of Agriculture, Savelugu Municipal), Environmental Protection Authority (EPA) of Ghana, Savelugu Municipal Assembly, Lands Commission, Ghana National Fire Service, Produce Suppliers, Commercial Farmers, Farmer Based Organizations, Assembly Representatives, Community Focus Groups including Traditional Authority, Youth Groups, Women Groups etc. Stakeholders were engaged in April 2025 and the outcome of engagements with key stakeholders have been reviewed and incorporated in the study (See Details in Section 6 and Annex 5).
- **Data collation and analysis;** The report preparation involved review of project documents, related Environmental Impact Statements (EIS), as well as EPA, and AfDB reference documents as follows:
 - Project Documents (Project Implementation Document);
 - o District Profile for the Savelugu Municipal;
 - Medium Term Development Plan;

- Population and Housing Census Report, 2021;
- Technical sheets for project development;
- Ghana EPA Guidelines;
- o GoG and AfDB Reference Documents;
- Sector policy documents and regulations; and
- Relevant international conventions.

1.4 The ESIA Report Content and Structure

EPA guidelines for preparation of ESIA and the AfDB Operational Safeguards System (OSS) guided the preparation of this ESIA report. The outline of the report includes the following:

- A non-technical executive summary;
- An introduction describing the ESIA purpose, objectives, approach and methodology;
- A description of the project, with an emphasis on subproject scope;
- Analysis of alternatives;
- Policy, legal and administrative framework;
- Baseline environmental and social conditions of the Savelugu Municipal area;
- Stakeholder Engagement and public consultations and disclosure;
- Potential environmental and social issues and impacts;
- Proposed mitigation measures;
- Environmental and social management plan requirements;
- Decommissioning;
- Capacity building and training required to implement the ESMP;
- ESMP implementation budget;
- Conclusion; and
- Annexes.

2.0 PROJECT DESCRIPTION

This section provides a detailed description of the Project in relation to its location, the key project components and an overview of the proposed activities that are to take place during the planning/preparatory, operation, and implementation phase.

2.1 Project Location

The programme will cover generally the Savannah Ecological Zone of Ghana and specifically focus on 7 Districts within four (4) administrative regions thus Northern, Upper West, North-East and Savannah Regions, that have the potential for rice production.

The Savelugu Municipality where this project site is situated is located in the Northern Region of Ghana. The Northern Region makes up one of the sixteen political regions of Ghana and it is located in the Northern belt between longitude 0.1495° W and Latitude 9.3673° N. The region shares boundary with the North East Region to the North, the Savannah Region to the west, Oti Region to the south, and neighbouring country, i.e. the Republic of Togo to the east (see **Figure 2-1**). The Northern Region of Ghana administratively consist of 1 Metropolitan Assembly, 4 Municipal Assemblies and 11 District Assemblies.

The Savelugu Municipality which has a total land area of about 125.79 sq. km is located at the northern part of the Northern Region of Ghana. It shares boundaries with West Mamprusi Municipal to the North, Karaga and Nanton Districts to the East, Kumbungu District to the West and Sagnerigu Municipality to the South. The Municipality has about 81 communities with a lot of the communities concentrated at the southern part.

The proposed Project will be implemented in the selected site (shown in **Table 2-1** and **Figure 2-2** below) which have been identified by the Ministry of Food and Agriculture (MOFA) for Environmental and Social Impact Assessment Studies and subsequent development (if found suitable) for improved rice production.

Table 2-1: Project Beneficiaries

NO.	REGION	DISTRICT	VALLEY
1.	Northern	Savelugu	Nankpazoo



Figure 2-1: Map of Ghana showing the beneficiary districts including Savelugu




Figure 2-2: Location map of Savelugu Municipal showing the Nakpanzoo valley

2.2 Project Components

The Project has four (4) main components namely; production and productivity, processing and marketing, policy and governance, and project coordination and management.

Component 1: Development of sustainable and climate-resilient rice production systems

Sub-component 1.1: Sustainable climate-resilient infrastructure and management services in rice production systems. Key interventions will include:

i. Development of Agricultural Zones

This sub-component will seek to develop new lands and rehabilitate existing water regulatory infrastructure to increase area under rice production. This will leverage on Agricultural Zones being established by Government to address the issue of access to large tracts of land, to drive sustainable and commercially oriented agriculture with the aim to significantly expand Ghana's rice productive capacity.

Under each Agricultural Zone large contiguous tract of arable land of not less than 300 hectares will be designed and developed within which a modern agricultural economic enclave will be located with the intention to create a viable ecosystem for the community to engage in commercial farming. Government will partner with the community for this project. Key activities will include land clearing, bunding of fields, construction of boreholes and small offices, construction of drying patios, farm access tracks, machinery and equipment.

The Ministry of Food and Agriculture (MoFA) has identified various locations across the country which has the potentials of being the food baskets for the country. Some of the potential locations identified for establishment of the Agricultural Zones include the Mamprugu Moagduri district in the North-East region, Mion, Tamale Metro and Savelugu Municipal in the Northern Region, West Gonja in the Savannah Region, Wa and Nandom Municipal in the Upper West Region.

The African Development Bank and other Development Partners since 2015 have supported the development of about 1,700 ha of various valleys for rice production. These valleys will be upgraded with the necessary infrastructure (drying patios etc), including setting up of an agricultural mechanization services centers into an Agricultural Economic Enclave.

ii. Sustainable Land and Water Management (SLWM)

This intervention seeks to enhance environmental resilience and agricultural productivity, to address productivity barriers and opportunities in agriculture and environmental services. These SLM and CSA technologies are being incorporated to address the interplay between agriculture, biodiversity loss, and climate change.

Climate variability and change affects rice production, and may result in increased cost of production, low yields, increased post-harvest losses, low farm income, food insecurity among others if appropriate mitigation and adaptation measures are not put in place.

The Ministry of Food and Agriculture (MoFA) developed a National Climate-Smart Agriculture and Food Security Action Plan (2016 - 2020), with the aim to facilitate and operationalize the national climate change policy for effective integration of climate change into food and agricultural sector development policies and programmes. In line with the CSA Action Plan, the following CSA technologies would be mainstreamed into all activities of the REWARD Project:

- a) Real-time climate and weather information system:
- b) Climate resilient seeds
- c) Soil Nutrient Management
- d) Ecological Organic Agriculture (EOA)
- e) Water Conservation and Management
- f) Alternative Wetting and Drying (AWD)
- g) Build capacity on SLM technologies

iii. Form and build capacity of Water Users Association:

According to the legislative instrument (L.I. 2230) passed on 12th February 2016, Water Users Association (WUA) is to be formed on all public irrigation infrastructures constructed by government and other parties on behalf of or in concert with the government. By this L.I. 2230, the Water User Associations are responsible for the Organisation, Maintenance and Management of the Irrigation infrastructure in their service area. The process of formation involved sensitisation, formation and capacity building of the farmers.

The capacities of the existing Water Users' Associations (WUAs) would be strengthened and new one's formed at the newly constructed sites, to function properly.

iv. Social infrastructure development:

This will support development of rural feeder roads, to enhance transportation of inputs, produce and mobility of humans within the Agricultural Economic Enclaves. It will also support development of water and sanitation facilities and services within the enclaves.

Sub-component 1.2: Improved availability and access to climate-resilient inputs, mechanization services and knowledge

Key interventions will include:

i. Seed Delivery Systems

This will support production of improved seeds in collaboration with Research Institutions (Council for Scientific and Industrial Research - Crop Research Institute and Savannah Agricultural Research Institute), Universities and Grains and Legumes Development Board (GLDB). Identified research institutes will be supported with funding to produce adequate quantities of breeder and foundation seeds, for the production of certified seeds by trained and certified seed growers at the targeted irrigation schemes. Resilient varieties like CSIR-Banse Rice (83 days) would be promoted.

Adequate support would also be provided to seed regulatory institutions for monitoring and certification of all classes of seeds. About 244 kg of breeder seeds and 12.2 MT of foundation seeds will be required for project period. The seed unit in Tamale will be rehabilitated and renovated and equipped with modern seed processing facility.

ii. Fertilizers and Pest Control Management Systems

Improve access to agro chemicals (fertilizers and pesticides) through input credits: The proposed project will facilitate access to agro-inputs through input credit system. This will be done through payment guarantee for identified commissioned aggregators to supply/provide agro-inputs to farmers, who will in turn repay in kind at the end of every cropping season.

Optimizing the use of quality agro-inputs are essential for sustainable agriculture production, ensuring optimal crop yields, minimizing environmental impact and meeting food production demands. Capacities of the value-chain actors would be enhanced to provide efficient utilization which would translate to quality and higher yields for better incomes.

iii. Agricultural Mechanization Services Delivery

One key feature of Government Policy on Agriculture is the comprehensive utilization of mechanization services for land preparation, seeding/planting, fertilizer application, crop maintenance/protection, harvesting and post-harvest management to increase productivity of rice. In the same vein, Agricultural Mechanization Service Providers or Agricultural Mechanization Services Centers (AMSECs) would be supported to offer dedicated mechanized services to farmers in the selected Agricultural Economic Enclaves.

iv. Extension Delivery

The role and importance of agricultural extension delivery in Ghana's overall agricultural growth and development like in many other jurisdictions cannot be over emphasized. Agricultural Extension plays a key interface between agricultural research and the farmer and other agricultural value chain actors by packaging technologies into suitable transmittable forms, interventions and innovations that could be utilized by farmers and other value chain. This will be achieved through:

- Promote increased and sustained programme participation
- Incremental adoption of inputs and technologies leading to an increased on-site productivity
- Improved post-production activities
- Capacity building and monitoring of operations of extension officers
- Building and promotion of synergies between extension and research
- Build Skill and Capacity of Machinery Operators and AMSEC managers

<u>Component 2: Development of rice processing clusters, agro-industry and commercial linkages for trade</u> facilitation

Sub-component 2.1: Modernized processing infrastructure and strengthening capacities of value chain actors

This component will focus on construction and installation of processing and storage infrastructure to minimise post-harvest losses and enhance value addition. It will develop information systems using innovative technologies (incl. digital) and consumer-oriented branding to improve access to market.

Additionally, this component will promote private sector investment by supporting business, with special focus on women and youth, and improve availability of financial services across the value chain to facilitate lending to processors, farmers, and other actors.

Promote the consumption of Ghana Rice: Events and promotional activities would as well be organized to encourage the consumption of Ghana rice.

Component 3: Policy/regulatory reforms at the national and regional levels and innovation-oriented regional technical support, for competitive rice value chains in the face of imports

Key activities under this component will include:

- Support to policy reforms and harmonization at regional/national levels
- Finalize the National Rice Development Strategy II (NRDS).
- Organise policy dialogues and workshops to discuss issues relevant to the rice sub-sector.
- Coordinate activities to ensure synergies among rice value chain stakeholders and projects to boost production, processing, marketing and consumption of locally-produced rice.
- Enhance control and regulations for agricultural inputs at regional/national levels.

Component 4: Programme Coordination and Management

This component will be responsible for day-to-day management of project activities to ensure harmony and coherence. A Project Implementation Unit (PIU) will be established or nested under existing PIU to support the coordination and management of the project. Regional and National Management and monitoring systems based on digital technologies will be developed to ensure tracking of results Regional and National levels, and in line with ECOWAS Rice Observatory (ERO).

2.3 Project Activities

The proposed Project will be implemented in seven (7) Districts within four (4) administrative regions thus Northern, Upper West, Savannah and North-East Regions, as indicated in the **Table 2-2**. The valleys will be upgraded with necessary infrastructure, such as water conservation bunds and drains, drying patios and farm access tracks.

Table 2-2: Proposed Rice Valleys for Development

No	Region	District	Community	Valleys	Area (ha)	Project Activities
1	Northern	Mion	Tindatua	Sakoya, Bogni	350	New land development with machinery support, drying patios, farm roads etc
2		Tamale Metro	Nyankpala	SARI	50	Construct bunds and drains of existing area for SARI for seed production
3		Savelugu	Napkanzoo	Nankpanzo o	300	Rehabilitation of existing valley, reshaped bunds and spot improvement of farm tracks
4	North East	Mamprugu Moagduri	Kubori/ Zanwara	Kubori	250	Land development packaged (bunds, drying patios and site office)

No	Region	District	Community	Valleys	Area (ha)	Project Activities
5	Upper West	Nandom	Nandom- Kpee	-	200	Machinery support with drying patios and land development
			Ко	Gbafin	150	Machinery support with drying patios and land development
6		Wa Municipal	Charia	Kolivege Bor	350	Land development with drying patios inclusive
			Sing	-	200	Reshaping of bunds, drying patios and drainage construction to convey excess water out of the fields
7	Savannah	West Gonja	Busunu	-	200	Land development and bunds
	TOTAL				2,050	-

Source: Department of Agriculture, 2024

The specific project activities to be expected within the Savelugu Municipal area during the REWARD Project will be:

Preparatory Phase

The preparatory phase activities include:

- Identification of beneficiary farmers for rice production
- Conduct of relevant studies, including socio-economic surveys and resettlement related issues
- Development and Implementation of Environmental and Social Management Plan (ESMP)
- Request for applications and screening of applicant farmers
- Assessment of soil suitability and GIS mapping of commercial farms using ICT.

Construction Phase

The construction phase activities will include the following:

- Rehabilitation of existing access routes
- Construction of mini work camp
- Vegetation clearance and land preparation
- Winning of construction materials from borrow pits (site yet to be determined)
- Transportation of materials to and from project site
- Construction of drainage channels and flood protection works
- Provision and installation of farm infrastructure such as farm houses and storage facilities
- Waste disposal (cleared vegetation, construction waste etc.)
- Decommissioning of mini work camp

The vegetation will be cleared using suitable machinery for land development to ensure that top soils are not unduly disturbed. Some activities to be undertaken will involve land levelling and In-field bunding.

Bunds which are earthen embankments will be created to retain rainfall runoff. The plots will be formed to conform to the direction of the contours, in this way reducing the earth movement during bunding and levelling to the minimum. The levels of the plots will be set to balance cut and fill. Bunding and land levelling will form the major activities in plot formation. Pegging out of plots boundaries to the standard size of plots will be required during the levelling. All levelled plots would be portioned and bunded by infield contour bunds into plots.

Roads linking valleys to towns which are mostly in deplorable states will be maintained to reduce postharvest losses which has been a major problem confronting farmers. Access roads will be maintained to permit the use of agricultural machinery in the cropping zone to do tillage, deliver inputs and send out produce.

Operation Phase

The operation phase activities include:

- Production and promotion of rice.
- Support for out-grower contractual arrangements.
- Conduct surveillance and collect data on pests attacking the Rice in the project zones with specific reference to FAW.
- Community sensitization, Establishment of fire belts and enforcement of community fire by-laws to deal with the impact of bush fires.
- Promotion of quality standards for rice, maize and soybean production, storage and processing
- Support business development, including improvements in business processes of existing commercial farmers
- Enhance access to market information (e.g. quantity, quality, timing and pricing)
- Promote the development of allied services (packaging, new distribution networks for rice products, transport services, new agro-input delivery systems, etc.)
- Support to feed millers to improve feed stock and expand processing capacity
- Promote the sustainable use of agro-chemicals;
- Enhance investment facilitation and promotion to increase the number of commercial producers and processors in the Savannah regions
- Capacity building for women and youth in small-scale commercial rice business management and entrepreneurship, including mentorship.

3.0 ANALYSIS OF ALTERNATIVES

This chapter investigates options to the Project development in relation to the Project site, design, and the "no action alternative" – which assumes that the Project is not implemented.

The consideration of Project alternatives is in compliance with Environmental Assessment Regulation LI 2504, which states that an EIA development for any project should outline the main alternatives for the proposed undertaking, taking into account the main technology, equipment, and location.

The proposed project considered some feasible options in respect of their potential environmental and social impacts. These are analysed in **Table 3-1** and include:

- Site selection;
- Resettlement related options
- Power supply;
- Sources of water;
- Water Management Systems;
- Waste management; and
- Project implementation versus No Project implementation.

Table 3-1: Analysis of Alternative Project Options

Op	Option/ Method of Potential Environmental, Social, Deployment Implicat		_	Preferred Option
Site	Site Selection			
1.	Nakpanzoo Valley	 Advantages Size of the valley Potential benefit to farming 	Disadvantages 1. Underdeveloped rice fields	Nakpanzoo was selected as the preferred valley
		communities with limited access to developed rice fields 3. Not a flood prone area 4. Sparsely vegetated fields		because of its potential benefit to many more communities. The large size of the
2.	Other Sites	Advantages 1. Already developed rice fields serving nearby communities	Disadvantages 1. Relatively smaller valleys in size 2. Valleys susceptible to flooding 3. Relatively dense vegetation 4. Potential displacement issues	valley also made it the preferred choice.
Res	settlement related	lissues		1
1.	Nakpanzoo	Advantages1. Chief is willing to donate land for the project.	Disadvantage	The preferred option is the Nakpanzoo site due

Or	otion/ Method of	Potential Environmental, Social,	Technological and Economic	
•	Deployment	Implicat	-	Preferred Option
		 The chief is willing to provide alternate land for the affected farmers. There will be no temporary or permanent physical structures to be removed or destroyed. 	 The livelihood of thirty-three (33) farmers will be disrupted. The affected farmers will have to trek longer distances to access alternate farmlands provided by the chief. 	to more favourable resettlement related conditions.
2.	Other Sites	Advantages	Disadvantages	
		 Vast lands available for the project. Alternative lands to be provided for any affected farmers may be closer to the community. 	 Land is owned by individuals who may not be easily willing to donate for the project. There will be more farmers affected (in excess of 40). 	
Pov	wer supply			
1.	National grid	Advantages 1. The cost of electricity is low decreasing production cost	Disadvantages 1. Unreliable power supply from frequent power cuts	Solar energy installations (Option 2) such as
2.	Solar energy	Advantages	Disadvantages	solar powered
	installations	 Presents a clean and sustainable source of electricity Low operational costs Meets the objective of technology transfer and climate friendliness 	2. Expensive capital cost	pumps are preferred for the pump irrigation.
Sou	urces of Water			
1.	Groundwater	 Relatively reliable source all year round Seasonal variations are minimal Relatively stable water quality 	 Expensive to access and abstract Challenges of overexploitation to meet high demands and associated threat of land subsidence May require farms of boreholes to meet demand Threat of high iron and fluoride concentration in aquifers in the northern 	Option 3, which is the use of rain water appears to be the most preferred option as it will be easier to implement water management plans

Or	otion/ Method of	Potential Environmental, Social,	Technological and Economic	
•	Deployment	Implicat		Preferred Option
2.	Surface water	Advantages 1. Easier to abstract and use	Disadvantages 1. Seasonal variations in flow 2. Vulnerable to pollution	
3.	Rain harvesting	Advantages 1. Easy to trap and store	Disadvantages 1. Source is unreliable 2. Evaporation losses are high in the dry months of the year	
Wa	ater Management	Systems		
1.	The head- bund system	 Advantages Water stored in the ponds is conserved and can be used for additional irrigation during dry spells because of the small nature of the storage ponds. The technique allows for deep water infiltration into the soil by trapping the water, thereby enhancing the soil's water retention capacity. This system also help to prevent soil erosion and gully formation by reducing the speed and volume of surface runoff. 	1. Developing of bunds can be laborious and may demand more manpower if size of farm is huge. 2. Having head-bund system in areas with adequate rainfall or irrigation may cause waterlogging which may affect crop growth.	The preferred option is the headbund system as it is ideal for small to medium-sized farms. It also allows for deep water infiltration into the soil by trapping water, thereby enhancing the soil's water retention capacity which is very essential in rice production.
2.	The central-	Advantages	Disadvantages	
	drain system	 The water levels in the rice fields, especially those near the central drain, can be controlled to mitigate against excessive flooding of the fields. Help reduce soil salinity. With water levels being controlled, crops receive optimal water amounts leading to better growth and yield. 	 This system is only suitable for areas with high rainfall and not arid conditions. The central drain can be a conduit for soil erosion if not maintained properly. 	

Op	otion/ Method of	Potential Environmental, Social,	_	Preferred Option
	Deployment	Implicat		-
3.	The	Advantages	Disadvantages	
	interceptor-	1. In periods of high rainfall, the	1. Water can be lost from	
	canal system	fields are better protected	the canals through	
		from any rapid overflow of	seepage into the ground	
		water from the stream and	and evaporation,	
		from the lateral runoff from	reducing the overall	
		the uplands.	efficiency of the irrigation	
		2. The interceptor-canal system	system.	
		can be used to irrigate the	2. It can be challenging to	
		rice fields during dry spells in	distribute water evenly	
		the rainy season.	across large areas with	
			this system, as some	
			parts of the irrigated land	
			can receive more water	
			than others.	
			3. Canals require regular	
			maintenance, such as	
			desilting and repairing	
			leaks, which can be	
			expensive and labor-	
			intensive.	
4.	The contour-	Advantages	Disadvantages	
	bund system	1. The stream used for	1. Contour bunds are not	
		irrigation is effectively	suitable for uneven or	
		obliterated and water is	eroded land	
		allowed to cascade from one	as overtopping of excess	
		levelled area to the next by	water with subsequent	
		way of built outlets or	breakage may occur at	
		spillways to the next field.	low spots.	
Wa	ste Management	Option		
1.	Composting	Advantages	Disadvantages	Option 1,
	plant	1. Improvements in soil quality.	1. Requires initial	composting is a
		2. Enhances the structure of	investment.	better option as it
		the soil.	2. Efficiency depends on the	is ecofriendly and
		3. Eco-friendly.	amount of organic waste	could be used to
		4. Fully organic fertilizer.	3. May attract rats, snakes,	improve soil quality
		5. Higher yields.	and bugs.	on farms. It will
			4. Requires space	also keep waste
			5. Unpleasant smell	away from landfill,

Or	otion/ Method of	Potential Environmental, Social	Technological and Economic	
O,	Deployment	Implica	_	Preferred Option
2.	Municipal	Advantages	Disadvantages	which already have
	Waste Dump/ landfill sites	 Straightforward concept to deal with waste. Filled land can be reused for 	Completed landfill areas can settle and requires maintenance.	limited space.
		other community purposes. 3. Landfills can prevent environmental dumping.	 Requires proper planning, design, and operation. Can contribute to 	
		4. Good for waste that is non-recyclable.	groundwater pollution. 4. Landfills can be a breeding ground for bacteria.	
Pro	ject Implementati	on versus No Project Implementati	on	
1.	Project Implementation	 Advantages Enhancing rice production, Strengthening market 	Disadvantages 1. Potential displacement issues	Project implementation is the preferred
		systems,Improving farmer livelihoods.Supporting research to produce breeder seeds,	Depriving other projects from accessing scarce resources	option as the benefits outweigh that of the no project
		 Ensuring widespread access to seed of improved rice varieties. 		implementation option
		 Facilitate the supply of key inputs such as fertilizers and pesticides 		
2.	No Project	Advantages	Disadvantages	
	Implementation	Project resources can be channeled into other development programs	 Food security challenges High Cost of Land Development: Inadequate Irrigation and Poor Water Management. Limited availability of quality breeder, 	
			foundation and certified seeds: 5. Inadequate use of Improved Agro Inputs: 6. Inadequate access to mechanized services 7. Poor knowledge of good agronomic practices	

Option/ Method of Deployment	Potential Environmental, Social, Implicat	nological and Economic	Preferred Option
		Poor quality of processing and storage facilities	

4.0 POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK

National and sector legislation and policies relevant to the agriculture sector have been reviewed in this section. Also, institutional requirements, international conventions, AfDB safeguard policies, and national environmental quality guidelines for the management of environmental and social issues have been considered. These have been summarized in **Table 4-1 to Table 4-6** under the following themes:

- National Policies and Plans
- National legal framework;
 - Agriculture sector legislation and related requirements;
 - Local governance, planning and other institutional requirements;
 - Public Health, Safety, Security and Social Protection;
 - o Environmental legislation in Ghana;
- National Institutional Framework;
- International Policies and Conventions
 - o African Development Bank safeguard policies; and
 - o International conventions.

4.1 National Policies and Plans

The policies and plans reviewed and applied in the assessment include:

- Ghana Shared Growth and Development Agenda, 2010;
- National Environmental Policy, 2012;
- National Land Policy, 1999;
- National Water Policy, June 2024;
- National Climate Change Policy, 2013;
- National Gender Policy, 2015;
- Hazardous Child Labour Activity Framework, 2016;
- National Plan of Action Phase II for the Elimination of the Worst Forms of Child Labour in Ghana, 2017-2021;
- Riparian Buffer Zone Policy, 2014;
- Food and Agriculture Sector Development Policy, FASDEPII (MOFA);
- National Environmental Action Plan/Policy, 1994; and
- National Employment Policy, 2012

Table 4-1: National Policies and Plans

No.	Policies and Plans	Applicability to Proposed Project
1.	Ghana Shared Growth and Development Agenda, 2010	The REWARD Project is in accord
	It provides for the Vision for the Agricultural, Environment and Natural	with the focus of the policy.
	Resource Sectors in Chapter four. The main focus of the agricultural sector is	
	to accelerate the modernization of agriculture and ensure its linkage with	
	industry through the application of science, technology and innovation.	
	The modernized agriculture sector is expected to underpin the	
	transformation of the economy through job creation, increased export	

No.	Policies and Plans	Applicability to Proposed Project
	earnings, food security, and supply of raw materials for value addition and	•
	rural development as well as significant reduction in the incidence of	
	poverty.	
2.	National Environmental Policy, 2012	The proposed project seeks to
	The ultimate aim of the Policy is to improve the surroundings, living	promote sustainable
	conditions and the quality of life of the entire citizenry, both present and	development by including
	future. It seeks to promote sustainable development through ensuring a	economic, social and
	balance between economic development and natural resource conservation.	environmental considerations.
	The policy thus makes a high-quality environment a key element supporting	
	the country's economic and social development.	
3.	National Land Policy, 1999	The project sites will not be in
	The key aspects of the policy relevant to the project include:	protected areas, forests or
	The use of any land in Ghana for sustainable development, the protection	wildlife estate.
	of water bodies and the environment and any other socioeconomic activity	The implementation of the
	will be determined through national land use planning guidelines based on	project will conform to the
	sustainable principles in the long-term national interest.	environmental laws of the
	Land categories outside Ghana's permanent forest and wildlife estates are	country which includes,
	available for such uses as agriculture, timber, mining and other extractive	registration with EPA, Preliminary
	industries, and human settlement within the context of a national land use	Environmental and Social
	plan.	Assessment and obtaining an
	All land and water resources development activities must conform to the applicance of the country and where Environmental Impact.	environmental permit prior to
	environmental laws in the country and where Environmental Impact Assessment report is required this must be provided. Environmental	commencement.
	protection within the 'polluter pays' principle will be enforced.	
4.	National Water Policy, 2024	The project's Environmental and
	The National Water Policy (revised 2024) is a framework formulated to guide	Social Management Plan (ESMP)
	the sustainable use, management and planning of water resources for	must include mitigation measures
	drinking and other domestic uses. It is targeted at water users, water	against over-exploitation of water
	managers and practitioners, investors, decision makers and policy makers	resources and also against water
	within central and local government structures, non-governmental	pollution which emanate from
	organisations (NGOs) and international development agencies. The revised	agrochemicals and unsustainable
	policy (2024) also recognises the various cross-sectoral opportunities and	agricultural practices. The
	challenges related to water use and its links with other relevant sectoral	irrigation designs must include
	policies such as those on sanitation, agriculture, transport and energy.	water use efficiency techniques
	The objective of Section 2.3.5 Focus Area 4 –Water for Food Security is to	especially for the chosen crops".
	ensure availability of water in sufficient quantity and quality for the	
	cultivation of food crops, watering of livestock and sustainable freshwater	
	fisheries to achieve sustainable food security for the country. The relevant	
	policy measures and/or actions to be undertaken include:	
	(i) encouraging efficient use of fertilizers to reduce pollution of water	
	bodies and ensure conservation of water, and	
	(ii) promoting and encouraging water use efficiency techniques in	
	agriculture and reducing transmission losses of water in irrigation	
	systems.	

No.	Policies and Plans	Applicability to Proposed Project
5.	National Environmental Action Plan/Policy, 1994	The design and implementation of
	The National Environmental Action Plan was initiated to define a set of policy	the proposed project will take into
	actions, related investments and institutional strengthening activities that	consideration measures to
	would make Ghana's development strategy more environmentally	promote the sustainable use of
	sustainable. The Plan formulated a national environmental policy as the	natural resources and ensure
	framework for implementing the Action Plan.	environmental management.
	The Policy aims at ensuring a sound management of resources and the	
	environment and to avoid any exploitation of these resources in a manner	
	that might cause irreparable damage to the environment. Specifically, it	
	provides for maintenance of ecosystems and ecological processes essential	
	for the functioning of the biosphere, sound management of natural	
	resources and the environment, and protection of humans, animals and	
	plants and their habitats.	
6.	National Employment Policy, 2012	The proposed project is consistent
	The National Employment Policy indicates that poverty is still high at about	with the strategy of the
	28.5 percent and that there is a strong correlation between the employment	employment policy to promote
	situation and poverty. The policy states that the key source of demand for	farm and non-farm rural
	labour emanates from the productive sectors of the economy, namely,	employment.
	agriculture, industry and service. One of the key strategies of the	
	employment policy is to promote farm and non-farm rural employment	
	through modernization of agriculture, improving the productivity of farmers	
	and contract farming arrangements, promoting effective linkages between	
7	farm and non-farm activities among others.	The project will not discriminate
7.	National Gender Policy, 2015 The National Gender Policy aims at mainstreaming gender equality concerns	The project will not discriminate against women and the
	into the national development processes by improving the social, legal, civic,	vulnerable in the local
	political, economic and socio-cultural conditions of the people of Ghana. It	communities. The criteria for
	also seeks to empower the vulnerable groups particularly women, children,	selecting beneficiary farmers will
	and people with special needs such as persons with disabilities and the	consider gender and disability
	marginalized.	consider gender and disability
8.	Hazardous Child Labour Activity Framework (HAF), 2016	The proposed project is consistent
	The overall objective of the Hazardous Child Labour Activity Framework	with the Hazardous Child Labour
	(HAF) project enacted in 2016 is to develop a comprehensive, age-	Activity Framework and will not
	appropriate contextually relevant and acceptable hazardous child labour	involve any child in a hazardous
	framework to drive research, intervention, monitoring and enforcement.	activity.
	The framework was formed to facilitate identification, quantification and	
	evaluation of hazardous child labour and raise evidence for future studies. It	
	will also provide the best options for intervention and evaluation to	
	safeguard the health, safety, development and education of children.	
	This framework, guided by ILO Convention 182 (which requires each country	
	through tripartite arrangements to develop a list of hazardous sectors and	
	activities) and its recommendations, addresses the limitations of existing lists	
	and focuses on child-centred strategies that consider both risks and	
	beneficial child work.	

No. **Policies and Plans Applicability to Proposed Project** 9. National Plan of Action Phase II for the Elimination of the Worst Forms of The design and implementation of Child Labour in Ghana, 2017-2021 the proposed project will take into The Ghana National Plan of Action for the elimination of the worst forms of consideration the measures of the child labour phase II (2017-2021) was launched in 2017 to address the National Plan of Action Phase II for identified gaps of the National Plan of Action Phase I (NPA1). The Ghana's the elimination of the worst forms of child labour in Ghana. National Plan of Action Phase I (NPA1) for the Elimination of the Worst Forms of Child Labour (2009-2015) was enacted to address child labour through various interventions, including strengthening technical capacity, enhancing public awareness and empowering communities. The NPA2 aims to build on the gains made subsequent to the implementation of the NPA1 (2009-2015) with the view to utilise the good practices and lessons learned to address the challenges of child labour in a more effective and sustainable way. The main objective of the NPA 2 is to reduce the worst forms of child labour to the barest minimum (<10%) by 2021 while laying strong social, policy and institutional foundations for the elimination and prevention of all forms of child labour in the longer term. The Plan is composed of upstream strategies designed to reinforce awareness creation on child labour, leading to social mobilization and advocacy for improved policy implementation in the areas of education and technical/vocational training, social protection, law enforcement, labour inspection and youth employment; coupled with improvements in coordination and resource mobilization. The upstream strategies will underpin sets of downstream interventions formulated to address child labour directly at the municipal and community levels. These sets of interventions will aim at effective provision and monitoring of social services and economic empowerment programmes by local government administrations and promoting community empowerment and sustainable action against child labour. 10. National Climate Change Policy, 2013 The climate-resilient technology The Policy is built on seven (7no.) systematic pillars and the objective of the to be adopted for the proposed project includes use of improved Policy is to mitigate and ensure an effective adaptation in key sectors of the economy, such as agriculture and food security, natural resources seed varieties and irrigation management, energy, industry and infrastructure among others. Under the systems. Agriculture and Food Security area, the key objectives are: The project will develop human Develop climate-resilient agriculture and food systems for all agroresource capacity to adapt to ecological zones; and changing climate as part of the Develop human resource capacity for climate-resilience. modernisation of the scheme. The key actions to achieve these objectives which are related to the improve post-harvest proposed project include: management through the Develop climate-resilient cropping and livestock systems as well as crop provision of storage and varieties and livestock breeds tolerant to flooding, drought and salinity; processing facilities and Promote appropriate technologies for small-scale irrigation, water re-use infrastructure and water harvesting; and

No.	Policies and Plans	Applicability to Proposed Project
	■ Improve post-harvest capacity, e.g., storage and processing facilities and	
	infrastructure.	
11.	Buffer Zone Policy, 2011	The setback distances provided
	The policy aims at providing comprehensive measures and actions that	for the water pollution hazards is
	would guide the creation of vegetative buffers for the preservation and	factored in the 100 meter buffer
	functioning of the nation's water bodies and vital ecosystems. The	distance observed by the project
	recommended buffer widths provided in the Policy include:	for the siting of storage facilities
	• Minor perennial streams: 10 to 20 meters; and	for agrochemicals, septic systems
	■ Important seasonal streams: 10 to 15 meters.	and waste bins.
	The Policy also designates the following as water pollution hazards and must	
	be setback from any stream or water body by the following distances:	
	■ Storage of hazardous substances – 45 meters	
	■ Raised septic systems – 75 meters	
	■ Solid waste landfills – 90 meters	
12.	Food and Agriculture Sector Development Policy (FASDEP)	The project will significantly
	The revised FASDEP of 2006 (FASDEP II) emphasizes the sustainable	advance the achievement of the
	utilization of all resources and commercialization of activities in the sector	FASDEP objectives through
	with market-driven growth in mind and with emphasis on environmental	improved efficiency and
	sustainability.	management of the scheme. The
	The Medium Term Agriculture Sector Investment Plan (METASIP) developed	project will ensure sustainable
	to implement FASDEP II over the medium term 2011-2015 includes the	utilization of resources and
	following programmes:	sustainable land and
	■ Food security and emergency preparedness;	environmental management
	Improved growth in incomes;	including through the use of a
	■ Increased competitiveness and enhanced integration into domestic and	more efficient irrigation system.
	international markets;	
	Sustainable management of land and environment; and	
	 Science and technology applied in food and agriculture development 	

4.2 National Legal Framework

The regulatory areas reviewed and applied in the assessment in compliance with national requirements include:

- The Constitution of the Republic of Ghana, 1992;
- Ghana Investment Promotion Centre Act 1994, Act 478;
- Environmental Protection Act 2025;(Act 1124);
- Environmental Assessment Regulations 2025, LI 2504
- Fees and Charges (Miscellaneous Provisions) Act, 2022 (Act 1080);
- Water Resources Commission Act 1996, Act 522;
- The Water Use Regulations 2001, LI 1692;
- Ghana Meteorological Agency Act 2004, Act 687.

Table 4-2: National Legal Framework

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
1.	The Constitution of the Republic of Ghana, 1992	This is the overarching
	The Constitution includes some provisions to protect the right of	legislative framework of
	individuals to private property and also sets principles under which	Ghana.
	citizens may be deprived of their property in the public interest	Articles 18 and 20 provides
	(described in Articles 18 and 20).	conditions for the acquisition
	(**************************************	of property (in this case land)
	Article 18 provides that "Every person has the right to own property	for development projects and
	either alone or in association with others."	compensation
	citates district of in association with others.	Compensation
	In Article 20, the Constitution describes the circumstances under which	
	compulsory acquisition of immovable properties in the public interest	
	can be done. It includes:	
	the development or utilization of property for public benefit	
	 reasonable justification is provided for acquisition 	
	the prompt payment of fair and adequate compensation	
	• resettlement of displaced persons on suitable alternative land with	
	due regard for their economic well-being, social and cultural	
	values.	
2.	Ghana Investment Promotion Centre Act 1994, Act 478	The proposed project has
	The Ghana Investment Promotion Centre Act 1994 (Act 478) requires	environmental impacts and
	that every investor wishing to invest in the country must in its appraisal	measures have been proposed
	of proposed investment projects or enterprises, "have regard to any	in the ESIA/ESMP to address
	effect the enterprise is likely to have on the environment and measures	the impacts.
	proposed for the prevention and control of any harmful effects to the	
	environment".	
3.	Environmental Protection Act 2025, Act 1124	The project will be in
	The Environmental Protection Act 2025 (Act 1124) amends the name of	compliance with the
	the regulator from the Environmental Protection Agency to the	Environmental Assessment
	Environmental Protection Authority and confers additional powers on	(EA) procedures for approval
	the Authority beyond the issue of environmental permits. Act 1124	of the EPA.
	consolidates the various legislations that regulate environmental	The proposed project will
	protection in the country, such as the Hazardous and Electronic Waste	involve the clearing of
	Control and Management Act, 2016 (Act 917) and the Pesticides	vegetation and generation and
	Control and Management Act, 1996 (Act 528). Act 1124 also establishes	disposal of waste. Also,
	the Environmental Protection Authority to regulate, protect, co-	considering that the project
	ordinate, and exercise general oversight over climate change and	area is over 40 hectares and
	environmental matters.	according to the EPA
	Part II of the Act 1124 specifically deals with pesticides control and	classification, a permit has to
	management. This section of the Act provides the rules for registration,	be obtained.
	pesticides classification, approval, clearance, using, disposing of and	The Pest Management Plan
	non- disclosure of confidential information, the granting of license,	(PMP) will address concerns of
	labelling and pesticides inspections.	relevant stakeholders with

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
		regards to pests and pesticides.
4.	Environmental Assessment Regulations 2025, LI 2504	The Project will be guided by LI
	The Environmental Assessment Regulations 2025 (LI 2504) enjoins any	2504 including registering with
	proponent or person to register an undertaking with the Authority and	the EPA and obtaining an
	obtain an Environmental Permit prior to the commencement of the	environmental permit.
	project. This regulation allows the EPA to place proposed undertakings	
	at the appropriate level of environmental assessment. The LI 2504	
	seeks to ensure that development is undertaken in a sustainable	
	environment.	
5.	Fees and Charges (Miscellaneous Provisions) Act, 2022 (Act 1080)	Processing and permit fees are
	The Fees and Charges (Miscellaneous Provisions) 2022 (Act 1080) sets	required for initial
	out the fee regime for processing and environmental permits,	registration, submission of
	associated with the Environmental Assessment Regulations. This Act	ESIA report and registration of
	replaces the 2019 Amendment.	sub-projects.
	Processing and permit fees are required for initial registration, and	
	upon submission and approval of Preliminary Environmental Report	
6.	(PER). Water Resources Commission (WRC) Act 1996, Act 522	The project will put in place
0.	The Water Resources Commission Act, 1996 (Act 522) establishes and	measures to prevent the
	mandates the Water Resources Commission (WRC) as the sole agency	pollution of water collected in
	responsible for the regulation and management of the utilisation of	the valley.
	water resources and for the co-ordination of any policy in relation to	
	them.	
	The Act states under Section 24 that any person who pollutes or fouls	
	a water resource beyond the level that the EPA may prescribe commits	
	an offence and is liable on conviction to a fine or a term of	
	imprisonment or both.	
7.	Water Use Regulations 2001, LI 1692	Project managers will ensure
	The Water Use Regulations 2001, LI 1692 prohibits the use of water	the continuous renewal of
	resources without authority from the Water Resources Commission. It	water use permits through the
	provides procedures for allocating permits for various water uses	appropriate tariff setting and
	including domestic, commercial, municipal, industrial, agricultural,	compliance with permit
	power generation, water transportation, fisheries (aquaculture),	requirements
	environmental, recreational and underwater (wood) harvesting. The	
	Act provides under section 16 for any person to apply to the	
	Commission in writing for the grant of water right. The Regulations also	
	prescribe the raw water charges and processing fees to be paid by	
	prospective water users with respect to the water use permits. The	
	Commission is also mandated to request for evidence that an	
	environmental impact assessment or an environmental management	
	plan has been approved by the EPA before issuance of the Water Use	
	Permit.	

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
8.	Ghana Meteorological Agency 2004, Act 687	The project managers will
	This Act establishes the Ghana Meteorological Agency, which replaces	liaise with the Ghana
	the Meteorological Services Department. The Agency is to provide	Meteorological Agency
	meteorological information, advice, and warnings for the benefit of	regularly especially in seeking
	agriculture, civil and military aviation among others to mitigate the	meteorological information
	effects of natural disasters such as floods, storms and droughts on	and advice
	socio-economic development and projects. The Agency is to provide	
	the accurate data on climatic which are relevant for establishing	
	climate change trends.	

4.2.1 Agriculture Sector Legislation and Related Requirements

The agriculture sector legislation reviewed include:

Plants and Fertilizer Act 2010 (Act 803);

Table 4-3: Agriculture Sector Legislation and Related Requirements

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
:	Plants and Fertilizer Act 2010 (Act 803)	The Plant Protection
	The Act provides for the efficient conduct of plant protection to prevent	Regulatory Services Division
	the introduction and spread of pests and diseases, to regulate imports and	(PPRSD) of MoFA will ensure
	exports of plants and planting materials; the regulation and monitoring of	that all seeds/plant materials
	the exports, imports and commercial transaction in seeds and related	are safe and also put in
	matters; and control and regulation of fertilizer trade.	monitoring mechanism to
		prevent the spread of pests
		and diseases from the project
		site to other parts of the
		country.

4.2.2 Local Governance and Planning Requirements

The relevant legislation reviewed include:

- Local Governance Act, 2016 (Act 936);
- National Building Regulations, 1996 (LI 1630);
- The State Lands Act, 1962 (Act 125);
- Lands Commission (LC) Act 2008, Act 767; and
- Land Use and Spatial Planning Act, 2016 (Act 925).

Table 4-4: Local Governance and Planning Requirements

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
1.	Local Governance Act, 2016 (Act 936)	The input of the Physical
	This Act establishes and regulates the local government system and	Planning and Roads
	gives authority to the RCC and the Municipal Assembly to exercise	Departments of the Municipal
	political and administrative power in the regions and districts	Assemblies will be sought in
	respectively. This includes initiation of development programmes as	designing water distribution
	well as development, improvement and management of human	networks
	settlements and the environment through departments such as the	
	Urban/Feeder Roads and Physical Planning Departments.	
2.	National Building Regulations, 1996 (LI 1630)	The project will involve
	The National Building Regulations, 1996 (LI 1630) make it an offence for	development of agricultural
	any individual to undertake any development without the acquisition of	infrastructure such as sheds,
	a Building Permit from the appropriate authority. This ensures that	storage etc. and the necessary
	buildings are well planned and are in conformity with the Assembly's	building permit will be
	plan designs of an area. The LI 1630 ensures that buildings are well	acquired.
	planned, consistent with the Assembly's spatial plan for an area.	
3.	The State Lands Act, 1962 (Act 125)	The project implementation
	The Act 125 vests the authority to acquire land for the public interest in	will result in some form of
	the President of the Republic. It also gives responsibility for registering	displacement or disturbance,
	a claim on the affected person or group of persons, and provides details	and due process will be
	of the procedure to do this. The State Lands Act, 1962 provides some	followed in accordance with
	details to be taken into consideration when calculating compensation	the relevant provisions of this
	such as definitions for cost of disturbance, market value, replacement	Act
	value, and so on.	
4.	Lands Commission (LC) Act, 2008 (Act 767)	The Project will be
	The Lands Commission Act 2008 re-establishes the Lands Commission	implemented in line with the
	to integrate the operations of public service land institutions in order to	objectives of the Commission
	secure effective and efficient land administration to provide for related	for sustainable development
	matters. The objectives of the Commission are to (i) promote the	of land and conform to the
	judicious use of land by the society and (ii) ensure that land	development goals of the
	development is in conformity with the nation's development goals.	MMDAs.
5.	Land Use and Spatial Planning Act, 2016 (Act 925)	The project design will be
	The Land Use and Spatial Planning Act, 2016 (Act 925) regulates land	guided by planning schemes
	use through a decentralised planning system to ensure judicious use of	and local plan guides
	land in order to improve quality of life, promote health and safety in	developed by the Land Use
	respect of human settlements and generally provide for spatial aspects	and Spatial Planning
	of socio-economic development and related matters.	Departments/District or
		Municipal Assemblies

4.2.3 National Labour, Environmental Quality, Health, Safety and Social Guidelines

The reviewed legislation includes:

- Labour Act, 2003 (Act 651);
- Occupational Safety and Health Policy of Ghana (Draft, 2004);
- Workmen's Compensation Law, 1987 (PNDCL 187);
- National Workplace HIV/AIDS Policy;
- Environmental Impact Assessment Guideline for the agricultural Sector (EPA, 2010);
- Ghana Standard for Environmental Protection Requirements for Effluent Discharge (GS1212, 2019);
- Ghana Standards for Environment and Health Protection Requirements for Ambient Air Quality and Point Source/Stack Emissions (GS 1236, 2019);
- Ghana Standards for Health Protection Requirements for Ambient Noise Control (GS 1222, 2018);
- Ghana Standards for Environment and Health Protection Requirements for Motor Vehicle Emissions (GS1219, 2018);
- Ghana National Fire Service Act, 1997 (Act 537);
- Fire Precaution (Premises) Regulations, 2003 (LI1724);
- Control of bush fires law of 1983 (PNDC L 46)
- Control and Prevention of Bush Fire Law (PNDC L 229);
- Children's Act 1998, Act 560; and
- Alternative Dispute Resolution Act 2010 (Act 798).

Table 4-5: National Labour, Environmental Quality, Health, Safety and Social Guidelines

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
1.	Labour Act, 2003 (Act 651) The Labour Act 2003 (Act 651) Section 118(1) stipulates that it is the duty of an employer to ensure that satisfactory, safe and healthy conditions are provided for every worker. Under these provisions, a worker is required to report situations that he believes may pose "an imminent and serious danger to his or her life, safety or health".	Construction activities could result in injuries and fatalities. HSE issues have been duly assessed and provided for in the proposed ESMP for the project
2.	Occupational Safety and Health Policy of Ghana (Draft, 2004) The statement of the Occupational Safety and Health Policy of Ghana (Draft, 2004) is: 'to prevent accidents and injuries arising out of or linked with or occurring in the course of work, by minimising as far as reasonably practicable the cause of the hazards in the working environment and, therefore the risk to which employees and the public may be exposed'. The policy is derived from provisions of the International Labour Organisation (ILO) Conventions 155 and 161. The policy document highlights specific strategies, activities promotion and awareness creation which ensure that workers engaged at the construction and operation stages of the project are protected.	Potential sources of accidents and injuries that could occur in the course of work, have been identified and incorporated into safeguards for minimising safety and health risks and hazards as required by the draft OSH Policy.
3.	Workmen's Compensation Law, 1987 (PNDCL 187)	The Labour policy and employment contracts will provide for workmen

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	It is to provide for the payment of compensation to workmen for personal injuries caused by accidents arising out and in the course of their employment. The tenets of the law place a large share of the burden of supporting workers injured at the workplace on the shoulders of the employers.	compensation in the event of injury.
4.	National Workplace HIV/AIDS Policy The broad objectives of the National Workplace HIV/AIDS Policy, among others, are to provide protection from discrimination in the workplace to people living with HIV and AIDS; prevent HIV and AIDS spread among workers; and provide care, support and counselling for those infected and affected. The project will institute a plan of action to prevent HIV/AIDS spread through awareness creation.	The project duration will be short-term and use just a few migrant workers. This will reduce the potential for HIV spread but an HIV policy will be provided as required by the national policy
5.	Environmental Impact Assessment Guidelines for the Agricultural Sector (EPA, 2010) The Agriculture Sector Guidelines is meant to assist the Environmental Protection Authority (EPA) in the implementation of its Environmental Impact Assessment procedures in Ghana. The document is in two parts. Part I deals with the background and methodology. Areas covered include overview of the agricultural sector, environmental assessment processes, environmental management programme and project decommissioning. Part II covers information and tools used in the environmental impact assessment. This includes the legal framework for EIA procedures in agriculture, general screening criteria, environmentally sensitive areas in agriculture and impact identification, evaluation and mitigation measures. It is intended to provide guidelines that will be used through all stages of an Agricultural Project Cycle; i.e. identification, preparation, appraisal, implementation and post-implementation monitoring.	These guidelines were taken into consideration in preparing this ESIA report. Also, all other project activities will follow these guidelines
6.	Ghana Standard for Environmental Protection - Requirements for Effluent Discharge (GS1212, 2019) Ghana Standard for Environmental Protection - Requirements for Effluent Discharge (GS1212, 2019); specifies requirements for sector specific effluent quality and also gives guideline discharge into the environment.	Effluent from both construction and operation phases will be managed as specified in the proposed ESMP
7.	Ghana Standards for Environment and Health Protection - Requirements for Ambient Air Quality and Point Source/Stack Emissions (GS 1236, 2019) Ghana Standards for Environment and Health Protection - Requirements for Ambient Air Quality and Point Source/Stack Emissions (GS 1236, 2019) specifies the requirements and methods of analysis for ambient air. It also	Dust and vehicular emissions will be controlled as specified in the proposed ESMP

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	specifies the requirements and test methods for point source or stack emissions based on the sources of energy.	
8.	Ghana Standards for Health Protection - Requirements for Ambient Noise	Noise generated at both the
	Control (GS 1222, 2018)	construction and operation
	Ghana Standards for Health Protection - Requirements for Ambient Noise Control (GS 1222, 2018) specifies the requirements for acceptable ambient noise levels within categorized locations. According to the Standards, the test method should be in accordance with the relevant test methods given in GS 1253:2018 (Acoustics- Guide for the measurement of outdoor Aweighted sound levels	stages will be monitored as stated in the proposed ESMP to ensure it does not exceed acceptable limits
9.	Ghana Standards for Environment and Health Protection - Requirements	Vehicles for transportation
	for Motor Vehicle Emissions (GS1219, 2018) Ghana Standards for Environment and Health Protection - Requirements for Motor Vehicle Emissions specifies the requirements for exhaust emissions of motor vehicles as well as tractors, farm equipment (such as combine harvester, etc.), mobile industrial / construction machines (such as excavators).	of materials and workers will produce fumes but will be managed with regular maintenance as stipulated in the proposed ESMP
10.	Ghana National Fire Service Act, 1997 (Act 537)	The project area is prone to
	The Ghana National Fire Service (GNFS) Act, 1997 (Act 537) re-established the National Fire Service to provide for the management of undesired fires and to make provision for related matters. The objective of the Service is to prevent and manage undesired fire. For the purpose of achieving its objective, the Service shall organise public fire education programmes to create and sustain awareness of the hazards of fire, heighten the role of the individual in the prevention of fire and provide technical advice for building plans in respect of machinery and structural layouts to facilitate escape from fire, rescue operations and fire management.	bushfires so the Fire Service will be engaged to provide education/sensitization on fire prevention and fighting.
11.	The Fire Precaution (Premises) Regulations 2003, LI 1724 The Fire Precaution (Premises) Regulations 2003 (LI 1724) requires all premises intended for use as workplaces to have Fire Certificates and confers enforcement powers on the Ghana National Fire Service (GNFS) to demand a fire certificate for premises that are put to use as a place of work.	Fire certificates will be obtained for warehouses and project offices.
12.	Control of Bush Fires Law of 1983 (PNDCL 46)	Bushfire is a risk to the
	It seeks to control the setting of bushfires by criminalizing the intentional, reckless, or negligent causing of such fires and holding the offender liable for all consequences of the fire.	proposed project and will be guided by these Laws to take lawful action against any such offender.
13.	Control and Prevention of Bushfire law, PNDCL 229	The project area has been designated as an environmentally sensitive

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	Section 2 defines "starting of a bushfire". A person starts a bushfire if an action of that person results in the uncontrolled burning of a farm, forest or grassland. The Chief Conservator of Forests or the Chief Game and Wildlife Officer may authorize starting of fires by authorized officers in Conservation Areas under section 4.	area as climatic conditions make it prone to bushfires. Measures have been proposed in this report to deal with fire risks.
14.	The Children's Act 1998, Act 560 The Act spells out the rights of the child, quasi-judicial/judicial child adjudication, parentage /custody/access/maintenance, fosterage/adoption and employment of children issues. The Act defines a child as a person below the age of 18 years. The minimum age for admission of a child to employment is fifteen years and the minimum age for the engagement of a person in hazardous work is eighteen years. No person shall engage a child in exploitative labour and labour is exploitative of a child if it deprives the child of its health, education or development.	The Project will be guided by this Act in the employment of labour for the proposed project and will ensure all labour engaged by the Contractors are not below the minimum age.
15.	Alternative Dispute Resolution Act 2010 (Act 798) The purpose of the Act is to "provide for the settlement of disputes by arbitration, mediation and customary arbitration, to establish an Alternative Dispute Resolution Centre and to provide for related matters." The Act further defines Alternative Dispute Resolution "as the collective description of methods of resolving disputes otherwise than through the normal trial process" (Section 135). The ADR Act covers both domestic and international arbitration in Ghana and the enforcement of both domestic and foreign arbitral awards within the jurisdiction.	The REWARD Project will ensure that the alternative dispute resolution option is used to address disputes and conflicts instead of the more expensive and timeconsuming legal court system under this project.

4.3 National Institutional Framework

The stakeholder institutions identified include:

- Ministry of Food and Agriculture;
- Water Resources Commission;
- Lands Commission;
- Environmental Protection Authority;
- Local Government Authority; and
- Traditional Authorities.

The roles and responsibilities of the Project Implementation Unit (PIU), implementing agencies and other stakeholders, legislative and regulatory requirements for the implementation of the ESMP are provided under **section 9** of this report.

Table 4-6: National Institutional Framework

No.	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
1.	Ministry of Food and Agriculture (MOFA) MOFA promotes sustainable agriculture and agribusiness through research and technology development, effective extension and other support services to farmers, processors, and traders for improved human livelihood. The Food and Agriculture Sector Development Policy (FASDEP II) and the Medium-Term Agricultural Sector Investment Plan (METASIP) seeks to guide development and interventions in the agriculture sector. The Resilient Rice Regional Value Chains in West Africa Project (REWARD) of MoFA also seeks to develop agriculture in Ghana in line with the country's efforts at poverty reduction and ensuring food security by promoting inclusive commercial farming along selected commodity value chains.	Regional and Municipal/District Departments of Agriculture have the mandate of offering extension services and support to ensure sustainability and the successful implementation of the project
2.	Water Resources Commission (WRC) WRC was established by an Act of Parliament (Act 522 of 1996) with the mandate to regulate and manage Ghana's Water Resources and co-ordinate government policies in relation to them. The Act stipulates that ownership and control of all water resources are vested in the President on behalf of the people, and clearly defines the WRC as the overall body responsible for water resources management in Ghana. The functions of the WRC as established under Act 522 among other things are to: Formulate and enforce policies in water resources conservation, development and management in the country; Coordinate the activities of the various agencies (public and private) in the development and conservation of water resources; Enforce, in collaboration with relevant agencies, measures to control water pollution; and Be responsible for appraising water resources development project proposals, both public and private, before implementation.	The REWARD Project will collaborate with the WRC for the protection of any water collected in the valley.

No.	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
3.	Local Government Authority The Regional Coordinating Council (RCC) and the Metropolitan /Municipal/District Assemblies (MMDAs) are responsible for the overall development of the region and metropolis/municipality/district respectively. Acts 462 and 480, which established the current district assembly structure, designate the District/Municipal/Metropolitan Assembly as the planning authority, charged with the overall development of the district. With regard to environmental management at the district level, the District Environmental Management Committees (DEMC) has been set up by law (Act 462) to among other things: promote and provide guidelines for the establishment of community-level environmental committees to put into effect the environmental programmes of the Assembly in the community; and plan and recommend to the DA, strategies and activities for the improvement and protection of the environment with emphasis on fragile and sensitive	The project is located in the Savelugu Municipal area and will be influenced by decisions and plans of the Northern Regional Coordinating Council and the identified Assembly. The Assembly will play key roles in the successful implementation and related activities of the project.
4.	areas, river courses etc. Lands Commission The Lands Commission was established by Article 258 of the 1992 Constitution and the Lands Commission Act, 2008 (Act 767). The functions of the Lands Commission include amongst others; advise the Government, local authorities and traditional authorities on the policy framework for the development of particular areas of the country to ensure that the development of individual pieces of land is coordinated with the relevant development plan for the area concerned; ensure that through sound, sustainable land use planning, socio-economic activities are consistent with sound land use through sustainable land use planning in the long-term national development goals; and promote community participation and public awareness at all levels in sustainable land management and development practices to ensure the highest and best use of land.	The REWARD Project will be implemented in line with the objectives of the Commission for sustainable development of land and conform to the development goals of the MMDAs.

No.	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
5.	Environmental Protection Authority	The REWARD Project
	The EPA is the body responsible for regulating the environment and ensuring the implementation of government policies on the environment. The functions of the Authority include:	will follow and abide by all EPA procedures in the implementation of the project.
	 ensuring compliance with any laid down environmental impact assessment procedures in the planning and execution of development projects, including compliance in the respect of existing projects; 	
	 promoting effective planning in the management of the environment; imposing and collecting environmental protection levies in accordance with the Environmental Protection Act 2025, Act 1124 or regulations made under the Act; and 	
	 acting in liaison and co-operation with government agencies, District Assemblies and other bodies and institutions to control pollution and generally protect the environment. 	
6.	Traditional Authorities	The proposed project
	In Ghana, people of common descent owe allegiance to a symbol of collective authority, such as the 'stool' for the Akans of southern Ghana or the 'skin' for the northern peoples. Traditional authorities play a role in the administration of the area. At the village level, family and land disputes and development issues are also traditionally dealt with by the village chief and elders.	site falls under the Dagbon Traditional Council that is a key stakeholder in the project.
	In addition to providing an important leadership role, especially in the more rural areas, chiefs act as custodians of stool/skin land, can mobilise their people for developmental efforts and arbitrate in the resolution of local disputes. Although chiefs have no direct political authority, some are appointed by the Government or Municipal/District Assemblies.	

4.4 International Policies and Conventions

Some international requirements, standards and guidelines reviewed include the African Development Bank Operational Safeguards and other International Conventions which are further discussed in this section.

4.4.1 African Development Bank Operational Safeguards

The African Development Bank (AfDB) has an updated Integrated Safeguards System (ISS), published in 2023, which contains published Operational Safeguards (OSs) to guide the safe development of projects it funds. The applicable Operational Safeguards are described in the **Table 4-7** below. The AfDB requirements are not inconsistent with the national requirements and therefore no implementation conflicts are foreseen.

Table 4-7: Operational Safeguards of AfDB

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
1.	OS1– Environmental and social assessment	Borrowers or clients are responsible for conducting the environmental and social assessment (Strategic Environmental and Social Assessment, or SESA, or Environmental and Social Impact Assessment, or ESIA) and for developing, as an integral part of project documentation, an appropriate plan for managing possible impacts. It categorises proposed projects into categories 1, 2, 3, 4 and 5 based on the extent of adverse impacts anticipated from the project.	Applicable	OS1 is applicable because the REWARD Project will be based on the development and rehabilitation of agriculture infrastructures, which may pose adverse environmental and social risks. The REWARD Project risks will be managed throughout the implementation of mitigation measures prescribed in the site specific ESMPs. The project will prepare an ESIA and conduct extensive stakeholder engagements.
2.	OS2- Labour and Working Conditions	This OS outlines the main requirements for borrowers or clients to protect the rights of workers and provide for their basic needs. When the borrower or client intends to employ a workforce for a project, it develops and implements a human resources policy and procedures appropriate to the nature and size of the project, with the scale of the workforce in alignment with this OS and with applicable national laws. The OS requires the protection of the workforce through the institution of appropriate health and safety measures taking into account risks inherent in the particular sector and specific classes of hazards in the borrower's work and does not	Applicable	The Contractor shall comply with the Labour laws and Occupational Health and Safety Best Practice. Preparation of an occupational health and safety plan. Develop a worker grievance redress mechanism. Training of workers on OHS procedures.

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
		support the use of child labour and forced labour.		
3.	OS3- Resource Efficiency and Pollution Prevention and Management	This OS outlines the main pollution prevention and control requirements for borrowers or clients to achieve high quality environmental performance, and efficient and sustainable use of natural resources, over the life of a project. It draws on and aligns Bank operations with existing international conventions and standards related to pollution, hazardous materials and waste, and related issues.	Applicable	OS3 is applicable because potential environment and social impact due to emissions of pollutants and waste is anticipated during the construction phase. Likewise, agriculture development activities will involve the use of improved application of fertilizers and agrochemicals, as well as result in the production of agriculture wastes. These will be managed as per measures prescribed in the ESMP. The project will prepare and implement a Pest Management Plan (PMP).
4.	OS 4– Community Health, Safety and Security	This OS outlines the risks and impacts of the project to the health and safety of the Affected Communities during the project lifecycle and establish preventive and control measures consistent with Best International Practices and commensurate with their nature and magnitude of impacts.	Applicable	OS4 is applicable because the implementation of the project will have some impact on beneficiary communities as well as those close to the project site. The communities have been engaged on the project and there will be continuous engagement of all nearby communities.
5.	OS5— Land Acquisition, Restrictions on Access to Land and Land Use, and Involuntary Resettlement	It relates to Bank-financed projects that cause the involuntary resettlement of people. It seeks to ensure that when people must be displaced they are treated fairly, equitably, and in a socially and culturally sensitive manner; that they receive compensation and resettlement assistance so that their standards of living,	Applicable	OS5 is applicable because there will be loss of livelihood due to land acquisition. Some community members may be restricted from accessing farm lands. The project will develop a process to minimize the impact of the project affected persons through the preparation and implementation of Resettlement Action Plan (RAP) which will include Livelihood

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
		income-earning capacity, production levels and overall means of livelihood are improved; and that they share in the benefits of the project that involves their resettlement.		Restoration Plan (LRP) and a Voluntarily Land Donation (VLD) process.
6.	OS6 – Habitat and Biodiversity Conservation and Sustainable Management of Living Natural Resources	This Operational Safeguard (OS) outlines the requirements for borrowers or clients to (i) identify and implement opportunities to conserve and sustainably use biodiversity and natural habitats, and (ii) observe, implement, and respond to requirements for the conservation and sustainable management of priority ecosystem services	Applicable	OS6 is applicable since the proposed interventions will involve the clearing of vegetation and possible impact of local flora and fauna.
7.	OS 7 – Vulnerable Groups	The client will identify, through an environmental and social risks and impacts assessment process, all communities of Indigenous peoples within the project area of influence who may be affected by the project. Also the client will ensure that vulnerable groups and individuals are identified as early as possible in Bank Group operations and that engagement is meaningful, taking into account individuals' and communities' specificities and delivered in an appropriate form, manner and language. The client will adopt a gender-responsive approach to the management of E&S impacts, which takes into account the rights and interests of women	Not applicable	There are no indigenous people on the project site or within the project communities of influence. The Project will prepare a Resettlement Action Plan (RAP) with due cognizance of the interests of vulnerable persons especially women, the elderly, People with disabilities (PWDs) etc. The engagement will be meaningful, taking into account individuals' and communities' specificities and delivered in an appropriate form, manner and language.

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
		and girls, men, and boys, including paying specific attention to the differentiated burden of impacts that women and girls might face.		
8.	OS8 – Cultural Heritage	This OS outlines the need of the client must protect cultural heritage from the adverse impacts of project activities and support its preservation. Clients should also promote the equitable sharing of benefits from the use of cultural heritage.	Applicable	There are no sensitive sites like shrines and cemeteries within the proposed project areas. However, water bodies in many Ghanaian societies are believed to house deities. These cultural/traditional beliefs and norms will be documented and respected as part of project implementation.
9.	OS9 - Financial Intermediaries	FIs are required to monitor and manage the environmental and social risks and impacts of their portfolio and FI subprojects, and monitor portfolio risk, as appropriate to the nature of intermediated financing. The way in which the FI will manage its portfolio will take various forms, depending on a number of considerations, including the capacity of the FI and the nature and scope of the funding to be provided by the FI.	Not Applicable	The project design does not foresee the need for a financial intermediary during project implementation.
10.	OS 10 - Stakeholder Engagement and Information Disclosure	Stakeholder Engagement and Information Disclosure recognizes the importance of open and transparent engagement between the Client and project stakeholders as an essential element of good international practice. Effective stakeholder engagement can improve the environmental and social sustainability of projects,	Applicable	All Stakeholders relevant to the project will be engaged according to the prepared stakeholder engagement plan. The stakeholder engagement plan will be updated as required and implemented together with a functional grievance redress mechanism.

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
		enhance project acceptance, and make a significant contribution to successful project design and implementation.		

4.4.2 International Conventions

Ghana is a signatory to some of the international conventions that are relevant to the proposed project and it is imperative to analyse the project in light of the commitments made under such conventions. The relevant international conventions are summarised **Table 4-8** below.

Table 4-8: International Policies and Framework

No.	Legal Framework and Key Compliance Requirements	Ratification Date	Applicability to Proposed Project
1.	United Nations Convention on Biological Diversity The three goals of the CBD are to promote the conservation of biodiversity, the sustainable use of its components, and the fair and equitable sharing of benefits arising out of the utilization of genetic resources. The convention calls for the adoption of national strategies, plans and programmes for the conservation and sustainable use of biological diversity into their relevant sectoral and cross-sectional plans, programmes and policies. One of the tools that are prescribed for the management of biodiversity is an environmental assessment. Article 14 of the convention deals with impact assessment and minimization of adverse impacts.	29 August 1994	Ghana is a signatory to these international conventions which are also are relevant to the proposed project. The proposed project has potential impacts on biodiversity and will have to implement appropriate climate change adaptation measures. Ghana, being a signatory of these conventions, will work towards the achievement of the respective goals of these conventions. The ESIA will identify endangered species in the project area and recommend appropriate mitigation measures for their protection and conservation.
2.	Convention on International Trade in Endangered Species of Wild Fauna and Flora (CITES) The objective of the Convention is to conserve wildlife and prevent international trade from threatening species with extinction.	14 November 1975	The Project has not identified any endangered species listed on the CITES on the project farmlands.

No.	Legal Framework and Key Compliance Requirements	Ratification Date	Applicability to Proposed Project
3.	Requirements United Nations Framework Convention on Climate Change (UNFCCC) The UNFCCC provides the basis for global action to protect the climate system for present and future generations. The ultimate objective of this Convention and any related legal instruments that the Conference of the Parties may adopt is to achieve, in accordance with the relevant provisions of the Convention, stabilization of greenhouse gas concentrations in the atmosphere at a level that would prevent dangerous anthropogenic interference with the climate system. Such a level should be achieved within a time frame sufficient to allow ecosystems to adapt naturally to climate change, to ensure that food production is not threatened and to enable economic development to proceed in a sustainable manner.	06 September 1995	Project The REWARD Project is a government agricultural initiative and is therefore bound by the requirements of the regulation.

5.0 ENVIRONMENTAL AND SOCIAL BASELINE CONDITIONS

Baseline conditions give the existing status of the environment in the proposed project area of influence before the commencement of the project activities. The information serves the purpose of a base reference against which the changes due to the implementation of the project can be measured. The description which is informed by relevant literature available/documents from stakeholders, presents a general understanding of the conditions within Savelugu Municipal area which is the host district and where necessary, the Northern Region of Ghana. The site-specific context describes the prevailing conditions at the project sites based on field observation and assessments.

5.1 Savelugu Municipal Baseline Conditions

5.1.1 Physical Environment

The physical environment encompasses all natural and built factors in the locality. This section gives a description of the characteristics of physical environment of the Savelugu Municipal area.

Climate

The area experiences a dry and rainy with an average rainfall of 600mm. The season is ushered in by erratic rainfall in April with increased intensity as the season continues with the average rising from 600mm to 1000mm. The mean temperature of the municipal ranges from 42°C to 16°C, with an average temperature of 34°C. The generally high temperatures as well as the low humidity brought about by the dry harmattan winds favour high rates of evaporation and transpiration, leading to water deficiencies.

Rainfall

Owusu (2018) carried out a detailed study on rainfall changes in the savannah zone of northern Ghana from 1961 to 2010. The study examined rainfall variability, trends, and impacts on agriculture and water resource management in the region.

The zone experiences a unimodal rainfall regime that lasts between 5 and 6 months, as shown in **Figure 5-1**. Rainfall is influenced by the Inter-Tropical Discontinuity (ITD) and other atmospheric systems. The mean annual rainfall total is around 1000mm and 90% of the rain occurs from May to October. Rainfall in the region is highly variable, both at the annual and multi-decadal scale (CARE International, 2013). Rain onset is erratic, making forecasting for agricultural applications very difficult.




Figure 5-1: Unimodal rainfall regime of northern Ghana, represented by Tamale, 1960-2010.

The trend analysis of rainfall data from four stations (Navrongo, Tamale, Wa, Yendi) showed a decline in rainfall during the 1970s and 1980s, with minimal recovery post-2000. However, the recovery is insufficient to match the wetter periods of the 1950s and 1960s.

The region also experiences high inter-annual and multi-decadal variability, alternating between dry and wet phases every 20–30 years. The 1950s and 1960s were wetter, followed by droughts in the 1970s and 1980s, and a slight recovery post-2000 (see **Figure 5-2**).




Figure 5-2: Mean annual rainfall total and standard deviation for northern Ghana.

The average monthly total rainfall data from the year 2015 to 2024 for Tamale (the nearest meteorological station) is described in **Figure 5-3** below. The figure shows a distinct difference between wet season and dry season. The dry season is between November and March and wet season between April and October, peaking in September.

The highest average total monthly rainfall was recorded in September with a value of 180 mm making it the wettest month and the lowest was recorded in January (<10 mm).




Figure 5-3: Average Monthly rainfall (Ghana Meteorological Agency, 2025)

Temperature

Figure 5-4 shows the average monthly maximum and minimum temperatures. The hottest months mostly fall between February and March (37–39°C) which is the peak of the dry season. The lowest average minimum temperature was recorded in January (20°C) which usually coincide with the Harmattan, accompanied by cooler mornings and cooler nights.




Figure 5-4: Average monthly Minimum and Maximum temperature

(Ghana Meteorological Agency, 2025)

Relative Humidity

The month of January recorded the lowest average monthly relative humidity while the highest was recorded in August. There is a steady decline in humidity levels between October and December with December marking the return to dry season conditions. The pattern indicated is typical for a tropical savanna climate with distinct wet and dry seasons. (**Figure 5-5**).




Figure 5-5: Average Monthly Relative Humidity

(Ghana Meteorological Agency, 2025)

Sunshine

High values of sunshine were recorded in November and December, with a gradual decline from June to August. Sunshine hours begin to increase again from September, peaking in November. This rise marks the end of the rainy season and return to drier, sunnier conditions. (Figure 5-6).




Figure 5-6: Average Total Sunshine Hours

(Ghana Meteorological Agency, 2025)

Wind Speed

As shown in **Figure 5-7**, the general trend indicate that the wind speed fluctuates over the years with two broad periods i.e. high winds from January to July, peaking in April and low winds from September to November. December marks a return to higher wind speeds.

Wind speed variation is generally described as moderate ranging roughly from 2.8 m/s to 4.6 m/s. The difference between the highest and lowest months is significant enough to impact activities dependent on wind including farming.




Figure 5-7: Average Monthly Wind Speed

(Ghana Meteorological Agency, 2025)

Water Resources

Ground Water

The occurrence of groundwater in Ghana is associated with 3 main geological formations. These are the basement complex, comprising crystalline igneous and metamorphic rocks; the consolidated sedimentary formations underlying the Volta basin (including the limestone horizon); and the mesozoic and cenozoic sedimentary rocks. The basement complex and the Voltaian formation cover 54 percent and 45 percent of the country respectively. The remaining 1 percent consists of mesozoic and cenozoic sediments. Groundwater occurrence in the basement complex is associated with the development of secondary porosity as a result of jointing, shearing, fracturing and weathering. The depths of aquifers are normally between 10m and 60m, and yields rarely exceed 6 m³/hr. In the mesozoic and cenozoic formations occurring in the extreme south eastern and western part of the country, the aquifer depths vary from 6 m to 120 m. There are also limestone aquifers, some of which are 120 m to 300 m in depth. The average yield in the limestone aquifers is as high as 180 m³/hr. In all, the total actual renewable water resources are estimated to be 53.2 billion m³ per year. All recharge to water resources is precipitation.

The quality of groundwater resources in Ghana is generally good except for some cases of localised pollution and areas with high levels of iron, fluoride and other minerals. Salinity in certain groundwater occurrences is also found especially in some coastal aquifers. **Figure 5-8** shows a map of the Ground Water Potential Zones in Ghana (Murali Krishna Gumma & Paul Pavelic, 2012) .




Figure 5-8: Ground Water Potential Zones in the Northern part of Ghana (Source: Murali Krishna Gumma & Paul Pavelic, 2012)

Surface Water

The land in the municipality is generally flat with gentle undulating low relief throughout. The general range of the altitude for the municipality ranges from 400-800 ft. above sea level (see **Figure 5-9**). The northern part of the municipality has some gentle slopes whiles the southern part is characterised by some slight hills. The area is drained mainly by the White Volta and its tributaries such as the River Kuldanali, which stretches to constitute a natural boundary between the Municipality and Kumbungu District (see **Figure 5-10**). There are other waterbodies such as the Oxbow Lake, rivers and streams. The effect of the drainage system is felt mostly in the northern part of the Municipality covering the areas between Nabogu and Kukuobilla. These areas are prone to periodic flooding during the wet season, thus making them suitable for rice cultivation.




Figure 5-9: Elevation Map of the Savelugu Municipal

(Source: SAL Consult, 2025)




Figure 5-10: Drainage Map of the Savelugu Municipal

(Source: SAL Consult, 2025)

Geology and Soils

The geology of the municipality is of Middle and Upper Voltaian formation. The Upper Voltaian covers the southern part of the Municipality and consists of shale and mudstone (see **Figure 5-11**). Underground water potential is generally determined by this underlying rock formation, which has varying water potential for underground water compared to the upper Voltaian formation. The middle Voltaian covers the northern part of the Municipality and comprises sandstone, shale and siltstone. Consequently, borehole drilling is expected to have a higher success rate in the northern rather than the southern section. **Figure 5-12** shows the Soil Map of the Savelugu Municipality.




Figure 5-11: Soil Map of the Savelugu Municipal

(Source: SAL Consult, 2025)




Figure 5-12: Geology Map of the Savelugu Municipal

(Source: SAL Consult, 2025)

5.1.2 Biological Environment

Vegetation

The area lies in the interior (Guinea) Savanna woodland with vegetation that is drought resistant and hardly shed their leaves completely during the long dry season. The northern part of the municipality which is sparsely populated has denser vegetation mostly with secondary forest and the populous south on the other hand, is depleted by human activities such as farming, bush burning and tree felling among others. Notable trees are shea trees, (the nuts which are used for making sheabutter) and dawadawa that provides seeds used for condimental purpose. Most of these are of economic value and serve as important means of livelihood especially for women. The area is suitable for large-scale livestock farming, as well as the cultivation of staples like rice, groundnuts, yams, cassava, maize, cowpea and sorghum. **Figure 5-13** shows the Land Use Map of the Savelugu Municipality.




Figure 5-13: Vegetation Map of the Savelugu Municipal (Source: SAL Consult, 2025)

5.1.3 Socio-economic Environment

Governance Structure

The main administrative structure in the district is the Municipal Assembly headed by the Municipal Chief Executive. In order to improve the decentralization, aim of the country the municipality has 22 decentralized departments to handle various issues in the district, there are other approved governance structures in the district that seek to assist with the governance and planning within the district. These groups include traditional authorities, youth associations, religious bodies and development partners. The district has 4 sub governance structures known as the zonal councils. They are the Savelugu, Pong Tamale, Diare and Moglaa Zonal councils. The highest decision body; the general assembly in the district is made up of 36 elected persons, 16 appointed persons, 2 members of parliament and the municipal chief executive.

Demography

The population of the Municipality, according to the 2021 Population and Housing Census, is 122,888 comprising 60,390 (49%) males and 62,498 (51%) females. With a growth rate of 3%, the population of the Municipality is 130,825 in 2021. The population growth in absolute terms within the medium-term period (2010 to 2017) is 11%. Females constitute 52% of the population and males 49%. This indicates a sex ratio of 94 males per 100 females. The population density in 2010 was 78 persons per sq. km and in 2025 it is expected to be 93 Persons per sq. km.

Majority (63%) of the population live in urban areas with 37% living in rural areas. Three out of every five persons in the municipal live in the rural communities (60%). Out of the total population, about (44%) falls within age groups 0-14 years; age group 15-39 has (41%), 40-64 years (9%) while about six (6%) per cent of the total population is 65 years and over.

The working age group (19-60 years) accounts for 51% of the population and the dependency age group account for 55% of the population. The aged is about 6% of the population of the Municipality, whiles the school age group account for 52% of the population. 60% (94,702) of the Municipality's population live in rural areas.

The population of the municipality is 122,888 comprising 60,390 (49%) males and 62,498 (51%) females. This is about 5% and 1% of the regional and national population respectively. The population density is 77 persons per sqkm with a total of 23,085 households and an average household size of 5 persons per household which is equal to the regional average. Majority (63%) of the population live in urban areas with 37% living in rural areas.

Compound houses are the common (74%) type of dwelling units occupied by households in the municipality followed by huts/buildings/houses (same compound) (15%) and separate houses (7%). Compound houses are common type of housing units occupied by household in both urban and rural areas. Higher proportions of both male (75%) and female (74%) live in compound houses.

Ethnically, the municipality is predominantly Dagombas (88%) and Frafra (<1.0%). The other ethnic groups are Mamprusis, Ewes and Gonjas. Islam is the dominant religion, representing (95%) followed by Christianity and other religions.

Education and Literacy

The municipality has a high level of illiteracy with 69% of the population 11 years and older incapable of reading or writing in any language. In terms of sex, approximately 79% of females 11 years and older cannot read or write with that of males constituting 59% (Ghana Statistical Service, 2010 Population and Housing Census). Thus 7 out of every 10 females in the municipality cannot read and write.

For the literate population, those who are literate in English and Ghanaian language constitute 66% whiles those who are literate in English only form 28%. Also, more males (68%) are literate in English and Ghanaian language compared to 62% of females. For the age groups, more than 50% of the population from all ages could read and write in English and Ghanaian language.

The Municipality is zoned into six educational circuits for administrative purposes namely Savelugu East, Savelugu West, Diare North, Diare South, Pong-Tamale and Moglaa. There are two Senior High Schools located at Savelugu and Pong-Tamale. There is also a school for the deaf, a Veterinary college and two Vocational schools located in Savelugu and Pong-Tamale. There is also a Girls Model JHS. There are 95 Early Childhood Development Centers [Kindergartens] 66 Primary Schools and 34 JHS.

Among the population 3 years and older, 59% have never attended school, 8% have attended in the past and 33% are currently attending school. In terms of sex distribution, 51% of males and 67.0% of females three years and older in the municipality have never attended school. There are currently more males in school than females, with 38% of males in school whiles only 27% of females in the school (Medium Term Development Plan for Savelugu Municipality, 2022-2025).

Economic Activities

Agriculture is the mainstay of the people employing 74% in the areas of skilled agriculture, forestry and fishery works. Crop farming dominates (97%) the types of agricultural activities engaged in followed by livestock farming (69%). Other employment avenues include, elementary occupation, craft and related trades, and service and sales work.

There are limited industrial activities with agro-processing constituting the main industrial activities i.e. sheanut processing, groundnuts processing, cotton ginnery, and rice processing. Apart from Shebu Industry that uses modern technology to process sheanut on a large scale for export, traditional small-scale methods dominate agro processing in the municipality. These small-scale activities are a major employer of women.

There are a number of tourism potentials in the municipality among which include the Saakpuli Slave Market, Tuunaayili, the former seat of the Dagomba Kingdom, Yoggu, which is said to be where the chief priest settled long ago and an Oxbow Lake at Zonchangni. However, these are yet to be fully exploited for economic gains.

Utilities and Services

Energy

The main source of energy for lighting is electricity with 42.0% of dwelling units connected to the national grid. This is followed by kerosene lamp (38%), flashlights/torch (17%), generator (1%) and others.

Fuelwood and charcoal are the main sources of cooking fuel by 96% of households. The use of wood as cooking fuel is high in both urban (83%) and rural (93%) localities. Higher proportion of urban household use charcoal (12%) and gas (2%) as compare to the rural households which depend less on gas (1%) and charcoal (4%).

Water

Some (40%) of the households in the municipality use water from bore (holes/pump/tube well) while 19% depend on (public tap/stand pipe). The use of (dugout/pond/lake/dam/canal) for drinking is relatively high accounting for 13%, there are wide variations in the main source of drinking water between urban and rural localities. Whiles (Public tap/stand pipe) accounts for 35 % as the main source of water in urban areas, (bole holes/pump/tube well) accounts for 54.9% in rural areas.

The proportion of urban dwelling units that use pipe-borne water as the main source of drinking water is 51% compared with 13% in rural localities. Households that use (borehole/pump/tube/well) as main source of water for domestic purposes accounts for 37%, while those who use (Public tap/stand pipe) and pipes born outside dwelling account for 15% and 7.0% respectively. The (public tap/stand pipe) is the prevalent source of water for other domestic purposes in the urban areas (27%) while the rural areas depend mainly on water from borehole/pump/tube well (51%).

Sanitation and Waste Management

The sanitation and waste management situation is poor as 67% of the households have no toilet facility thereby resorting to open defecation. The percentage of households which use the public toilet (WC/KVIP/pit pan) constitute 20%. About 60% of urban households and 73% of the rural households have no toilet facilities. About 32% of the urban households use public toilet (WC/KVIP/pit pan), while in the rural areas, 11% households use the KVIP.

Seven in ten (71%) of households in the Municipality dispose of liquid waste onto the street/outside dwelling, 6% dispose of liquid waste through drainage into a pit (soak away), a little more than 1.0% use the sewerage system. Majority of households in both urban (74%) and rural (69%) localities dispose of their liquid waste onto the street/outside dwelling although this practice is a little more prevalent in the urban areas than in rural areas.

The dominant method of solid waste disposal in the Municipality is the public dump (50%). Almost one in five of households dump their solid waste indiscriminately. Whiles 28% of households in urban areas dump solid waste in designated public dump container, only 6% of rural households dump solid waste in public containers. Indiscriminate dumping of solid waste is more prevalent in the rural localities, 26% than in the urban localities 15%.

Communication

Mobile phones are owned and used by some 25% of persons 12 years and older for communication. A considerably higher proportion of males (36%) than females (16%) own mobile phones. On computer ownership, only 2% of the total households have desktop or laptop computers with 2% using internet services. The low level of ICT use in the municipality could be attributed to the low level of literacy and educational attainment.

Health

The municipality has one (1) hospital at Savelugu, four (4) health centres at Savelugu, Pong Tamale, Moglaa and Diare, two (2) private clinics at Savelugu (Nasara & Modern Surgical) and Twelve (12) operational CHPS zones, Seven (7) CHPS compounds at Dipali, Pigu, Kuldanaali, Bunglung, Nambagla, Yong and Kukobilla. The major diseases found in the Municipality include Malaria, Upper Respiratory Tract Infection, Diarrhea, Rheumatism/joint pain, Typhoid Fever, Hypertension, Anemia Skin Diseases and Pneumonia.

Transportation

Except a few communities especially the settler farmer communities, majority of the communities are interconnected with feeder roads. However, over 50% of the roads are seasonally unmotorable. The efficient road transport is along the Tamale-Bolgatanga trunk road and there are vehicle services to about 80% of rural communities in the municipality where the bulk of the food crops are produced.

Land Ownership/Tenure

Allodial title is held or vested in traditional stools or skins, in some traditional areas. In other traditional areas, this is held by subgroups such as sub stools, clans and families as well as individuals. Allodial owners hold their interest under customary law and are not subject to any restrictions on their use rights or any obligations except for those imposed by the law (statutory law).

The land tenure system, which is predominantly customary, operates under the patrilineal mode of property inheritance. Although this system has recorded considerable changes with regards to land transfer due to population pressures, urbanization, commercial agriculture, and legislative interventions, it remains male inclined. It thus excludes women from ownership and limit access rights by inheritance. In most cases, women in the Municipality rely on "borrowed lands" for use which is granted based on their status to males as relatives- daughters, sisters, or wives. This short-term interest can be terminated at any time by the owner, hence exposing women to tenure insecurity.

5.2 Characteristics of the Project site (Nakpanzoo valley)

The immediate beneficiary community, i.e. the Nankpazoo community has been identified based on the availability of land for commercial farming. This section describes the environmental and social conditions in the community and project vicinity. **Plate 5-1** below shows a photo of the Nankpazo valley.



Plate 5-1: The Nankpazoo Valley (SAL Consult, 2025)

5.2.1 Air Quality

Active air quality monitoring was carried out between 7th and 10th April 2025 at the proposed project site, that is within the Nankpazoo valley and the sampling was done in compliance with the requirements of GS 1236:2019 as shown in **Table 5-1**.

Table 5-1: Environment and Health Protection- Requirements for Ambient Air Quality and Point Sources/Stack Emissions (GS 1236:2019).

S/N	Air Quality Parameter	Maximum Limits	Averaging Time
1	Carbon monoxide, mg/m ³	10	8 hours
2	Sulphur dioxide (SO ₂), μg/m ³	50	24hours
3	Nitrogen oxides (measured as NO ₂), μg/m ³	150	24hours
4	PM ₁₀ , μg/m ³	70	24hours
5	PM _{2.5} , μg/m ³	35	24hours

Particulate Matter

The sampling and analysis of ambient particulate matter concentrations was done according to the ASTM Test Method D4096-17. Particulate matter ($PM_{2.5}$ and PM_{10}) was sampled at the Nankpazoo valley and its nearest sensitive receptor (Fulani hamlets) for 24 hours using ARA N-FRM Air Sampler set to a flow rate of 16.7 L/min drawing air through the inlet onto a 47mm quartz filter for analysis. **Plate 5-2** and **Plate 5-3** below show the mounted equipment at the Nankpazoo valley and its nearest sensitive receptor (Fulani hamlets).





Plate 5-2: ARA N-FRM Setup for PM_{2.5} and PM₁₀ sampling at the proposed Nakpanzoo rice valley (SAL Consult, 2025)



Plate 5-3: ARA N-FRM Setup for PM_{2.5} and PM₁₀ sampling at the nearest sensitive receptor (Fulani hamlets)

Results

The Particulate Matter (PM_{2.5}) concentrations monitored at the proposed Nakpanzoo Rice Valley and its nearest sensitive receptors (Fulani Hamlets) were 30.00 μ g/m³ and 16.00 μ g/m³ respectively which are within the Ghana Standard (GS 1239:2019) permissible value of 35 (μ g/m³) but exceeded the WHO 2021 limit of 15 μ g/m³.

For the valley, this indicates moderate dust elevated levels, potentially influenced by agricultural activities, including open burning, tilling, and dust resuspension from unpaved paths or dry soils which were observed during the monitoring period. Although the excess is marginal for the sensitive receptor

(hamlets), it is significant given the vulnerable status of rural and nomadic populations who often lack access to healthcare and live in natural-ventilated or semi-open structures.

The Particulate Matter (PM₁₀) concentration of 109.00 μ g/m³ recorded at the proposed Nakpanzoo Rice valley significantly exceeded both the national (70 μ g/m³) and international (45 μ g/m³) thresholds. This suggests high coarse particulate pollution, likely arising from mechanical disturbances during farming, vehicular movement, and possibly wind-driven dust due to the site's open, dry landscape.

Given its location in a proposed rice farming valley, the elevated PM_{10} levels may also result from local land preparation and use of machinery, particularly during dry periods when soil particles become airborne easily at adjacent land uses.

The PM₁₀ level recorded at the nearest sensitive receptor was 28.00 $\mu g/m^3$ which was well below both the Ghanaian (70 $\mu g/m^3$) and WHO (45 $\mu g/m^3$) standards, indicating a relatively cleaner atmosphere in terms of coarse particulate matter. The lower values could be attributed to distance from intensive land use, limited vehicular activity, and natural vegetation acting as a filter.

Figure 5-14 shows a graphical presentation of compliance and/or exceedance of particulates to GSA/WHO Standards.




Figure 5-14: Graph showing compliance and or exceedance of particulates to GSA/WHO Standards (SAL Consult, 2025)

Gases (NO₂, SO₂ and CO)

The Aeroqual Series 500(A-S500) Gas Meter, a high rated device that enables accurate real time surveying of common indoor and outdoor air pollutants, was used to determine the concentration levels of NO_2 , SO_2 and CO (Plate 5-4 and Plate 5-5). The ambient concentrations were recorded for every minute, from which hourly concentrations were calculated and mean concentrations determined.





Plate 5-4: Gases monitoring at the proposed Nankpazoo valley (SAL Consult, 2025)



Plate 5-5: Gases monitoring at the nearest sensitive receptor (Fulani Hamlets) (SAL Consult, 2025)

Results

Air quality measurements for nitrogen dioxide (NO₂), sulphur dioxide (SO₂), and carbon monoxide (CO) at both the proposed Nakpanzoo rice valley site and the nearest sensitive receptor (Fulani hamlets) were all below the minimum detection limit of 0.06 mg/m³ at the time of sampling (see **Figure 5-15**). This showed that the gases level were below both the WHO guideline of 4 mg/m³ and the Ghanaian maximum of 100 mg/m³ suggesting that current sources of combustion—either vehicular, industrial, or domestic—are minimal or absent in the area.




Figure 5-15: Graphs of gases monitored at the valley and Fulani hamlets (SAL Consult, 2025)

NB: Readings reported as "< (value)" indicate the concentration was below the instrument's Minimum Detection Limit (MDL). The MDLs are based on manufacturer specifications for the Aeroqual sensor heads used: 9.4 μ g/m³ for Nitrogen Dioxide (NO₂), 26.2 μ g/m³ for Sulfur Dioxide (SO₂), and 0.06 mg/m³ for Carbon Monoxide (CO).

5.2.2 Ambient Noise

For the purposes of establishing the existing ambient noise levels in the proposed project area, a noise assessment was undertaken between 7th and 10th April 2025.

Noise measurements/recordings were taken with a High Precision TSI Quest Sound Level Meter, Model Type 1. The sound level meter has an in-built calibrator and was calibrated before each measurement/recordings were taken. The noise meter was calibrated at 114 dB (A) prior to the measurement. The following statistical indices was computed L_{Aeq}, L_{max}, L_{min} and L_{peak}.

The ambient noise levels (L_{EQ} values) recorded at the Nankpazoo rice valley was compared to the Ghana Standard (GS 1222:2018) and IFC guideline values. **Plate 5-6** and **Plate 5-7** show the photograph of the daytime noise monitoring at the project site and its nearest sensitive receptor.





Plate 5-6: Ambient Noise monitoring at the proposed Nakpanzoo Rice Valley (SAL Consult, 2025)



Plate 5-7: Ambient Noise monitoring at the nearest sensitive receptor (hamlets) (SAL Consult, 2025)

Results

The equivalent continuous sound level (L_{Aeq}) recorded at the project site (Nakpanzoo valley) was 46.1 dB(A), with a maximum noise level (L_{max}) of 54.2 dB(A), a minimum noise level (L_{min}) of 38.6 dB(A) and a peak (L_{peak}) of 62.5 dB(A). The high L_{Peak} value indicate intermittent spikes in noise, possibly from livestock, human voices, motorbikes, or other community activities. All other values were below the Ghana and IFC EHS standard threshold of 55 dB(A) for residential, institutional zones and well below 70 dB(A) for commercial or industrial zones.

The relatively low ambient noise reflects the rural, undeveloped nature of the site. The main contributors to the existing noise environment are natural sources (e.g., wind, birds) and occasional human activity, such as subsistence farming and pedestrian or motorbike movement along rural paths.

At the nearest Fulani hamlet, L_{Aeq} is measured at 52.9 dB(A), L_{max} at 63.3 dB(A), L_{min} at 32.6 dB(A) and L_{Peak} at 71.5 dB(A). The L_{Aeq} is still within the residential threshold of 55 dB(A). The high L_{max} and L_{Peak} values indicate intermittent spikes in noise, possibly from livestock, human voices, motorbikes, or other community activities.

Figure 5-16 shows a graphical presentation of compliance and/or exceedance of noise levels to residential and industrial standards.




Figure 5-16: Night time Ambient noise levels measured at the Valley and its nearest sensitive receptor (SAL Consult, 2025)

5.2.3 Water Resources

The Northern Region is located within the Volta Basin. The major sub-basins of the Volta include the Black and White Volta Rivers, the Oti River and the Lower Volta, including Lake Volta.

Groundwater

There was no groundwater available for sampling in the project area at the time of visit. The closest borehole to the project site is about 2.5 km away.

Surface Water

Storm water gathers in pools in the project area during the rainy season and this also serves as a source of water for the community. Water is mainly used for domestic activities such as cooking, bathing, washing of clothes and cleaning.

At the time of visit in April 2025, which was in the dry season, the waterbodies had dried up making sampling impossible.

5.2.4 Soils

Generally, the soils in the Northern region are suitable for cereal crop production including rice. The project site is expected to have marginal, with shallow soil depth as the major limitation with a soil depth <50 cm. The soil texture may be sandy with clay content <6%. The topsoil may tend to be droughty, while the subsoil may have a high level of gravel and concretions (hard, compact masses). The soils are therefore prone to erosion and have low moisture and nutrient-holding capacity. The status of exchangeable

calcium and magnesium may be low and declining. The chemical and physical analysis of soil samples taken from the Savelugu-Nanton area is presented in **Table 5-2**.

Table 5-2: Chemical and physical analysis of soil samples

Location	Depth	Depth	Site	pН	OC ^a	TNP	OM ^c	Bray's a	available		Exc	changea	ble cati	ons (cmo	(+)/kg)		Base	Partic	le size a	analysis	Textur
				(g/kg)	(g/kg)	(g/kg)	P (mg/kg)	K (mg/kg)	Ca	Mg	K	Na	TEB	Exch. Acidity	ECEC	(%)	Sand (%)	Silt (%)	Clay (%)		
Savelugu-Nanton	0-20	Duko	6.34	97	8	167	11	109.57	4.54	4.01	0.13	0.06	8.74	0.12	8.86	98.6	56.3	41.5	2.2	S. loam	
		Libga	5.5	38	3	66	7.89	41.93	2.67	0.53	0.36	0.12	3.68	0.7	4.38	84.0	53.7	42.0	43	S. loam	
		Kansheigu	6.37	79	7	136	8.85	95.7	2.27	12	0.14	80.0	3.69	0.12	3.81	96.9	47.0	50.9	2.1	Si loam	
		Jana	6.18	71	6	122	8.13	52.08	4.27	1.09	0.17	0.07	5.6	0.15	5.75	97.A	31,4	62.6	6	Si loam	
		Manguli	5.94	75	6	129	3.99	3821	2.94	2.14	0.18	0.06	5.32	0.2	5.52	96.4	35.9	58.0	6.1	Si loam	
	20-40	Duko	6.59	67	6	116	5.02	68.65	4.81	0.27	0.3	0.12	5.5	80.0	5.58	98.6	52.6	45.3	2.1	S. loam	
		Libga	5.75	34	3	59	2.87	2638	1.34	0.53	80.0	0.04	1.99	0.6	2.59	76.8	TLA	22.6	6	S. leam	
		Kansheiga	6.2	53	4	91	3.27	50.05	1.6	0.53	0.22	80.0	2.43	0.15	2.58	94.2	56.6	41.4	2.03	5. loam	
		Jana	5.93	60	5	103	3.03	40.24	1.76	1.71	0.17	80.0	3.72	0.25	3.97	93.7	28.4	63.6	8.05	S loam	
		Manguli	5.87	71	2	122	3.11	40.92	2.67	2.14	0.17	80.0	5.06	0.35	5.41	93.5	35.7	543	10	Si loan	
	0-15	Kpallung	7.59	228	9	393	13.15	88.6	9.88	3.47	0.09	0.05	13.49	0.05	13.54	99.6	48.6	41.0	10.4	Loam	
		Tibali	6.11	96	9	166	67.77	61.21	5.34	1.07	0.16	0.13	6.7	0.13	6.83	98.1	44.5	44.5	11	Loam	
		Botingli	7.09	81	11	140	8.05	89.28	5.61	0.8	0.19	0.13	6.73	0.05	6.78	99.3	76.2	13.8	10	S. loam	
	15-30	Kpallung	7.19	181	7	312	3.59	58.84	6.68	1.6	0.09	0.05	8.42	0.05	8.47	99.4	49.0	41.0	10	Loam	
		Tibali	6.2	75	6	129	239	46.67	5.34	1.34	0.13	0.09	6.9	0.12	7.02	98.3	41.7	44.3	14	Loam	
		Botingli	6.82	60	8	103	4.15	55.46	5.34	1.07	0.13	0.09	6.63	0.1	6.73	98.5	77,0	12.0	11	S. loam	

(Source: Tetteh et.al, 2016)

5.2.5 Biodiversity

The Nakpanzoo Rice field is a seasonally flooded farmland with isolated trees (see **Plate 5-8**). Intensive rice cultivation and cattle grazing have impacted negatively on the vegetation. Some of the tree species found on the site are *Parkia biglobosa*, *Diospyros mespiliformis*, *Lannea acida*, *Vitellaria paradoxa*, *Mitragyna inermis and Tamarindus indica*. The herb and shrub species included Flueggea virosa, *Ziziphus spina-christi*, *Asparagus africanus*, *Grewia carpinifolia* and *Clerodendrum thyrsoideum*.



Plate 5-8: Nakpanzoo Valley – Farmland (harvested Rice field) with isolated trees (Sal Consult, 2025)

Floral Survey

A flora survey was conducted in April 2025 with an initial reconnaissance survey done within the project site and external boundaries to obtain an overview of the extent, topography and complexity of the vegetation. Sample quadrats of size 20 m x 20 m were studied in the proposed site and a total of 2 vegetation samples were taken during the survey. The locations of the samples were recorded with a Garmin 64s GPS. **Table 5-3** shows the sample location coordinates and their associated vegetation types.

The ecological significance and national conservation status of the species encountered were defined using the ecological guild and star rating system (see **Table 5-4**) adopted in the Forest of Ghana Geographic Information Exhibitor manual (Hawthorne, 1993). The Global conservation status **(Table 5-5)** of each species was determined using the International Union of Conservation of Nature (IUCN) red list of threatened species (IUCN, 2024).

Table 5-3: Coordinates of sampling locations and associated vegetation types

Site	Lat (N)	Long (W)	Description
Nakpanzoo Valley (Site A)	N 09.76164	W 000.80905	Farmland/isolated trees (rice field)
Nakpanzoo Valley (Site B)	N 09.76437	W 000.79485	Rice field with isolated trees

(SAL Consult, 2025)

Table 5-4: Star Rating system

Rating	Description
Black Star species	Species rare internationally and at least uncommon in Ghana; urgent attention to
	conservation of populations needed
Gold Star species	Fairly rare internationally and/or locally
Blue star species	Widespread internationally but rare in Ghana or vice-versa
Scarlet star species	Common, but under serious pressure from heavy exploitation
Red Star species	Common, but under pressure from exploitation
Pink Star species	Common and moderately exploited. Also, non-abundant species of high potential value
Green Star species	No particular conservation concern, common in Ghana

Table 5-5: IUCN Red List categories

Category	Description
Extinct (EX)	A taxon is Extinct when there is no reasonable doubt that the last individual has died. A
	taxon is presumed Extinct when exhaustive surveys in known and/or expected habitat,
	at appropriate times (diurnal, seasonal, annual), throughout its historic range have failed
	to record an individual. Surveys should be over a time frame appropriate to the taxon's
	life cycle and life form.
Extinct in the Wild	A taxon is Extinct in the Wild when it is known only to survive in cultivation, in captivity
(EW)	or as a naturalized population (or populations) well outside the past range. A taxon is
	presumed Extinct in the Wild when exhaustive surveys in known and/or expected
	habitat, at appropriate times (diurnal, seasonal, annual), throughout its historic range
	have failed to record an individual. Surveys should be over a time frame appropriate to
	the taxon's life cycle and life form.
Critically Endangered	A taxon is Critically Endangered when the best available evidence indicates that it meets
(CR)	any of the criteria A to E for Critically Endangered, and it is therefore considered to be
	facing an extremely high risk of extinction in the wild.
Endangered (EN)	A taxon is endangered when the best available evidence indicates that it meets any of
	the criteria for Endangered, and it is therefore considered to be facing a very high risk of
	extinction in the wild.
Vulnerable (VU)	A taxon is Vulnerable when the best available evidence indicates that it meets any of the
	criteria for Vulnerable, and it is therefore considered to be facing a high risk of extinction
	in the wild.
Near Threatened	A taxon is Near Threatened when it has been evaluated against the criteria but does not
(NT)	qualify for Critically Endangered, Endangered or Vulnerable now, but is close to
	qualifying for or is likely to qualify for a threatened category in the near future.
Least Concern (LC)	A taxon is Least Concern when it has been evaluated against the criteria and does not
	qualify for Critically Endangered, Endangered, Vulnerable or Near Threatened.
	Widespread and abundant taxa are included in this category

Category	Description
Data Deficient (DD)	A taxon is Data Deficient when there is inadequate information to make a direct, or
	indirect, assessment of its risk of extinction based on its distribution and/or population
	status. A taxon in this category may be well studied, and its biology well known, but
	appropriate data on abundance and/or distribution are lacking.
Not Assessed (NA)	A taxon is Not yet Assessed when it is has not yet been evaluated against the criteria

(IUCN, 2024)

Results and Floral Analysis

The species lists for the sample analysed are presented in **Table 5-6** while the floristic analysis of the project site is presented in **Table 5-7**. The sampling recorded a total of 21 species in 18 genera belonging to 7 flowering plant families. The families with high species representation were the Fabaceae (8), Combretaceae (5) and Anacardiaceae (3). The rest of the families were poorly represented with less than 3 species each. The diversity of species on the site is low. This is not surprising since most of the herbs and shrubs have been destroyed by cultivation, bushfires and cattle grazing.

Table 5-6: Sample profiles and species composition of Nakpanzoo Valley

Farmland with isolated trees (Rice field) Flooded area	Rice field with isolated trees
N 09.76164	N 09.76437
W 000.80905	W 000.79485
Elev. 116m	Elev. 113m
Species	Species
Parkia biglobosa	Tamarindus indica
Azadirachta indica	Azadirachta indica
Diospyros mespiliformis	Diospyros abyssinica
Lannea acida	Vitellaria paradoxa
Flueggea virosa	Carissa edulis
Vitellaria paradoxa	Gardenia aqualla
Diospyros abyssinica	Acacia senegal
Commiphora africana	
Clerodendrum sp	
Nauclea latifolia	
Ziziphus Spina-christi	
Mitragyna inermis	
Crossopteryx febrifuga	
Balanites aegyptiaca	
Ficus sp	
Asparagus africanus	
Grewia carpinifolia	
Tamarindus indica	
Acacia sp	
Gardenia aqualla	
Tamarindus indica	

(SAL Consult, 2025)

Table 5-7: Floristic Analysis of Nakpanzoo Valley

Species	Family	Life Form	Guild	Star Rating	IUCN
Pterocarpus erinaceus	Fabaceae	Tree	Non forest	NE	EN
			Savana/planted		
Anogeissus leiocarpus	Combretaceae	Tree	NE	Green	LC
Lannea acida	Anacardiaceae	Tree	Non forest	NE	LC
			Savana/planted		
Combretum	Combretaceae	Tree	Non forest	NE	LC
adenogonium			Savana/planted		
Terminalia avicennioides	Combretaceae	Tree	Non forest	NE	LC
			Savana/planted		
Terminalia macroptera	Combretaceae	Tree	Non forest	NE	LC
			Savana/planted		
Acacia gourmaensis	Fabaceae	Tree	Non forest	NE	LC
			Savana/planted		
Daniellia oliveri	Fabaceae	Tree	Non forest	NE	LC
			Savana/planted		
Detarium microcarpum	Fabaceae	Tree	Non forest	NE	LC
			Savana/planted		
Erythrina sigmoidea	Fabaceae	Tree	Non forest	NE	LC
			Savana/planted		
Parkia biglobosa	Fabaceae	Tree	Non forest	NE	LC
			Savana/planted		
Piliostigma thonningii	Fabaceae	Tree	Non forest	NE	LC
			Savana/planted		
Cochlospermum	Cochlospermacea	Shrub	NE	NE	NE
planchonii	е				
Gardenia aqualla	Rubiaceae	Shrub	NE	NE	NE
Combretum nigricans	Combretaceae	Tree	NE	NE	NE
Diospyros mespiliformis	Ebenaceae	Tree	NE	Green	NE
Hannoa undulata	Anacardiaceae	Tree	Non forest	NE	NE
			Savana/planted		
Sclerocarya birrea	Anacardiaceae	Tree	Non forest	NE	NE
			Savana/planted		
Acacia senegal	Fabaceae	Tree	Non forest	NE	NE
			Savana/planted		
Adansonia digitata	Malvaceae	Tree	Non forest	NE	NE
-			Savana/planted		
Vitellaria paradoxa	Sapotaceae	Tree	Non forest	NE	VU
			Savana/planted		

(SAL Consult, 2025)

The Life form composition of the flora (**Table 5-8**) showed a dominance of the Tree Life form (about 76%) followed by the Shrub and Climber life forms with a representation of 14.3% and 9.5% respectively in the flora. The herb layer was absent, due possibly to the effects of intense cultivation.

Table 5-8: Life Form Composition of the Flora

Life form	No.	%
Climber	2	9.5
Herb	-	-
Shrub	3	14.3
Tree	16	76.2
Total	21	100

(SAL Consult, 2025)

The ecological guilds of the species, which gives an indication of the developmental/successional stage of the vegetation, shows a dominance of savanna species (71.4%), other guilds being poorly represented (**Table 5-9**).

Table 5-9: Ecological Guilds of the Flora

Guild	No.	%
NPLD	1	4.8
Pioneer	1	4.8
NE	4	19
Non Forest Savanna/Planted	15	71.4
Total	21	100

Legend: NE: Not evaluated; NFS/P: Non-Forest Savanna/Planted species; NPLD: Non-Pioneer Light Demander (SAL Consult, 2025)

Species of National Conservation Concern

Inspection of **Table 5-7** reveals that that one species of conservation concern *Grewia carpinifolia* (Blue Star) according to the Froggie data base was recorded on the site. However, it must be noted that *Vitellaria paradoxa* (Shea tree) which was also sited is a tree of economic importance to the local people in the project area (the seeds of *Vitellaria paradoxa* seeds are collected for shea butter production by local women).

Species of Global Conservation Concern

Table 5-10 shows that only 1 Vulnerable species (*Vitellaria paradoxa*) was recorded on the project site. The rest of the species (95%) were either Least Concern or Not Evaluated and do not merit conservation action globally.

Table 5-10: IUCN Red List Status Composition of the Flora

IUCN Red list Status	Number (No.)	Percentage (%)				
LC	16	70				
NE	6	26				
VU	1	4				
Total	23	100				

(SAL Consult, 2025)

Fauna of the project site

The faunal list of the project (see **Table 5-11**) was based on the information gathered through interviews and observation which involved recording any animal sightings while driving or walking along the main road or animal trails to the areas bordering the proposed project site and identification of animal spoors. General walks through the project sites to spot animal spoors (any sign left by a living animal, such as feeding sites, regular pathways, tracks, footprints, faecal pellets, nests, etc.) were also undertaken. The animals identified were classified as either Schedule 1 (S.1) or Schedule 1 (S.2) depending on the degree of protection they enjoy under the national wildlife conservation regulation (Schedules, 1995) as follows:

- S.1. (Schedule 1) The hunting, capturing or destroying of these species is prohibited at all times.
- S.2. (Schedule 2) The hunting capturing or destroying of these species is absolutely prohibited between 1st August and 1st December of any season. The hunting, capturing or destroying of any young animal, or adult accompanied by its young, of these species is absolutely prohibited at all times.

According to the hunters interviewed, most of the large mammals which were common in the area have moved away due to human activities such as farming and cattle grazing as well as wildfires. Notable among these are the elephant, lion, leopard, warthog, several parrots, terns, songbirds (passerines), land tortoises, pythons other snakes, lizards, bats, birds of prey, mongooses, bovids (e.g. the African buffalo and several duikers), egrets, ducks, pigeons. A number of the species known to occur in the area are of both national and global (IUCN, CITES) conservation significance.

Table 5-11: Fauna of the Project Area

	Name	Conservat	Conservation Significance			
Order	Common	Species	IUCN	National	Abundance Status	
	Bushbuck	Tragelaphus scriptus	LC	II	Rare	
Artiodactyla (Even-toed	Common Duiker	Sylvicapra grimmia	LC	II	Rare	
ungulates)	Oribi	Ourebia ourebi	LC	II	Rare	
	Red River Hog	Potamochoerus porcus	LC	II	Rare	
	African Civet	Civettictis civetta	LC	II	Rare	
Carrierana (Carreirana)	Common Slender Mongoose	Herpestes sanguineus	LC	II	Common	
Canivora (Carnivores)	Common Kusimanse	Crossarchus obscurus	LC	II	Common	
	Marsh Mongoose	Atilax paludinosus	LC	II	Common	
Lagomorpha	African Savanna Hare	Lepus microtis	LC	Not Listed	Common	
	Gambian Pouched Rat	Cricetomys gambianus	LC	Not Listed	Common	
	Grasscutter	Thryonomys swinderianus	LC	Not Listed	Common	
Rodentia	Gambian sun squirrel	Heliosciurus gambianus	LC	Not Listed		
	Guinea multimammate mouse	Mastomys erythroleucus	LC	Not Listed		
	Stripped Ground Squirrel	Euxerus erythropus	LC	Not Listed	Abundant	
	Common Frog	Amnirana galamensis	LC	Not listed		
Anura (Frogs and Toads)	Common Toad	Sclerophrys regularis	LC	Not listed		
	Crowned Bull Frog	Hoplobatrachus occipitalis	LC	Not listed		
Squamata	Agama Lizard	Agama agama	LC	Not listed		
(Snakes and Lizards)	African Rock Python	Python sebae	NT	II		
•	Boomslang	Dispholidus typus	LC	Not listed		
	Forest Cobra	Naja melanoleuca	LC	Not listed		
	Gaboon Viper	Bitis gabonica	LC	Not listed		
	Hissing Sandsnake	Psammophis sibilans	LC	Not listed		
	Night Adder	Causus rhombeatus	LC	Not listed		
	Nile Monitor	Varanus niloticus	LC	I		

Order	Name		Conservation Significance		Abundance
	Common	Species	IUCN	National	Status
	Puff Adder	Night Adder	LC	Not listed	
	Savanna Monitor	Varanus exanthematicus	LC	Not listed	
	Spitting cobra	Naja nigricollis	LC	Not listed	
Accipitriformes	Black Kite	Milvus migrans	LC	1	
	Shikra	Accipiter badius	LC	I	
	Lizard Buzzard	Kaupifalco monogrammicus	LC	ı	
Bucerotiformes	African Grey Hornbill	Lophoceros nasutus	LC	Not listed	
	West African Pied Hornbill	Lophoceros semifasciatus	LC	Not listed	
	Spur-winged lapwing	Vanellus spinosus	LC	Not listed	
Columbiformes	Laughing Dove	Spilopelia senegalensis	LC	II .	
	Red-Eyed Dove	Streptopelia semitorquata	LC	II	
Cuculiformes	Levaillant's cuckoo	Clamator levaillantii	LC	Not listed	
	Senegal Coucal	Centropus senegalensis	LC	Not listed	
Galliformes	Double-spurred Spurfowl	Pternistis bicalcaratus	LC	П	
	Stone Partridge	Ptilopachus petrosus	LC	II	
	Western Grey Plantain-eater	Crinifer piscator	LC	Not listed	
Passeriformes	African Blue Flycatcher	Elminia longicauda	LC	Not listed	
	African Pied Wagtail	Motacilla aguimp	LC	Not listed	
	Black-crowned Tchagra	Tchagra senegalus	LC	Not listed	
	Bronze Mannikin	Permestes cucullata	LC	Not listed	
	Common Bulbul	Pycnonotus barbatus	LC	Not listed	
	Long-tailed Glossy Starling	Lamprotornis caudatus			
	Long-tailed nightjar	Caprimulgus climacurus	LC	Not listed	
	Melodious Warbler	Hippolais polyglotta			
	Northern Grey-headed Sparrow	Passer griseus	LC	Not listed	

Order	Name		Conservat	Conservation Significance	
	Common	Species	IUCN	National	_ Abundance Status
	Orange-Cheeked Waxbill	Estrilda melpoda	LC	Not listed	
	Red-breasted swallow	Cecropis semirufa	LC	Not listed	
	Village Weaver	Ploceus cucullatus	LC	Not listed	
	White-fronted Black Chat	Oenanthe albifrons	LC	Not listed	
Pelecaniformes	Cattle Egret	Bubulcus ibis	LC	1	

(SAL Consult, 2025)

Conclusions

None of the floral and faunal species recorded are of conservation concern due to the project area being an extensively modified habitat. Very few cases of *Vitellaria paradoxa* (shea tree) which is of some economic importance to the people were observed on the project site. These are found extensively and commonly in many other areas of the municipality. The project will have no significant impact on the existing flora and fauna as well as their habitat, and also the ecosystem services of the area.

5.2.6 Socio-economic Environment – Project site (Nankpazoo Community)

Demography

Seventy (70) households were sampled for the survey in the Nakpanzoo community of which fifty- eight (58) were males (83%) and 12 were females (17%) household heads/members. This indicates a predominantly male respondent sample.

The ages of the 70 respondents ranged from 18 to 66 years, with an average age of approximately 42 years. All respondents were 18 years or older. The largest group of respondents (57%) falls within the 31-50 years age bracket, followed by those aged 51 years and above (24%). Younger adults, aged 18-30 years, constitute 18% of the respondents. This age distribution indicates a predominantly adult respondent base, actively involved in household and economic activities (see **Figure 5-17**).




Figure 5-17: Age range of respondents

Sixty- Five (65) out of the 70 households sampled comprise a total of 502 individuals, with an average household size of approximately 8 persons. Household sizes range from a minimum of 2 to a maximum of 20 members.

Overall, within these 65 households, there are 245 males (49%) and 257 females (51%), indicating a slightly higher proportion of females. On average, households have about 3 males and 4 females.

The distribution of household sizes shows that households with 7-9 members are the most common (31%), followed closely by those with 4-6 members (29%). There is also a notable proportion of very large households (13+ members) which account for 18% of the sample and comprise a significant portion of the total individuals. The male/female composition remains relatively balanced across most household size categories, though larger households naturally contain more individuals of each sex. A small percentage of households (7%) reported having at least one member with a form of disability (see **Figure 5-18**). The

types of disabilities mentioned included being crippled, blind, or having other conditions such as goiter or partial blindness.




Figure 5-18: A pie chart Showing Disability status of households

Ethnicity and Religion

All 70 respondents (100%) identified their ethnicity as Dagomba. This indicates complete ethnic homogeneity within the surveyed sample from the Nakpanzoo community. All 70 respondents (100%) identified their religion as Moslem. This uniformity suggests that Islam is the predominant religion among those surveyed in the Nakpanzoo community.

Education and Literacy

A significant 70% of respondents reported having no formal education. A smaller percentage completed primary school (13%), while 11% were SHS dropouts, and only 3% completed SHS. This highlights low levels of formal educational attainment within the respondent group.

Educational Level	Count	Percentage (%)
None (No formal Ed.)	49	70
Completed Primary School	9	13
SHS Drop out	8	11
Completed SHS	4	6

Economic Activities

Farming is the dominant primary source of income, with an overwhelming 94% of households relying on it. Only a very small percentage (6%) cited livestock rearing as their primary income source. This underscores the agrarian nature of the community's economy.

Livestock rearing is the most common secondary source of income, engaged by 47% of the population of households sampled. Farming also serves as a secondary income source for 23%. A small percentage engage in small business/trade or other activities like a motorcycle business, while 27% did not specify a

secondary income source. **Figure 5-19** gives a graphical representation of the secondary source of income for respondents.

Majority of respondents (64%) identified themselves as self-employed, which is consistent with primary engagement in farming and livestock rearing. A significant portion (36%) described themselves as unemployed. In this context, "unemployed" likely signifies the absence of formal wage employment rather than a complete lack of work, as most are involved in subsistence agriculture.




Figure 5-19: Secondary source of income for respondents

Utilities and Services

Source of Drinking Water

All 70 surveyed households (100%) reported relying on a dugout or dam as their main source of drinking water. The distance to this water source varied: 27% reported it being 2.4 km away, 26% stated 2km, and 20% said 3km, with other distances also mentioned. This reliance on surface water sources, often at some distance, can pose health risks and time burdens.

Sanitation Facility

Access to improved sanitation is extremely limited, with 96% of households reporting having no facility and using the bush for defecation. Only one household (1%) reported using a pit latrine with a slab. This widespread open defecation has significant public health implications.

Sanitation Facility	Count	Percentage (%)
No facility/Bush	68	96
Pit Latrine with slab	1	2
Blank Entry	1	2

Main Source of Energy for Cooking

Firewood is the universal source of energy for cooking, with all 70 households (100%) relying on it. This complete dependence on firewood can contribute to deforestation and indoor air pollution.

Main Source of Energy for Lighting

The vast majority of households (97%) use electricity provided by the Northern Electricity Distribution Company (NEDCO) as their main source of energy for lighting. A very small number use kerosene lamps (1%) or solar power (1%). This indicates relatively good access to electricity for lighting purposes within the community.

Main Source of Energy for Lighting	Count	Percentage (%)
Electricity (NEDCO)	67	97
Kerosene Lamp	1	1
Solar Power	1	1
Electricity (unspecified)	1	1

<u>Health</u>

Malaria is by far the most common health condition, reported by 86% of households. Fever was also frequently mentioned (39%), followed by ulcers (31%), diarrhoea (14%), and high blood pressure (10%). This highlights a significant burden of infectious diseases, particularly malaria.

Common Health Condition	Households Reporting	Percentage (%)
Malaria	60	86
Fever	27	39
Ulcer	22	31
Diarrhoea	10	14
High blood pressure	7	10

When seeking medical care, 70% of respondents prefer public hospitals. Traditional medicine also plays a vital role, being the preference for 57% of households. Private hospitals (13%), pharmacists/chemists (7%), and community health centers (1%) are less frequently preferred options. Respondents could choose more than one provider.

Preferred Medical Service Provider	Count	Percentage (%)
Public Hospital	49	70
Traditional Medicine	40	57
Private hospital	9	13
Pharmacist/Chemist	5	7
Community health center/post	1	1

6.0 STAKEHOLDER CONSULTATIONS

The ESIA preparation included preliminary stakeholder identification, some initial consultations and analysis of the requirements with key stakeholders. The key project stakeholders identified for consultations included government and non-governmental organizations. Stakeholder consultation is a process and should continue through the design stage of the project implementation phase.

6.1 Objectives of the consultations

The main objective of consultations with stakeholders is to discuss and provide relevant information on the project. Specifically, to achieve the following objectives:

- Provide some information about the proposed project;
- Provide opportunities for stakeholders to discuss their opinions and concerns;
- Provide and discuss with stakeholders, alternatives considered to reduce anticipated impacts;
- Identify and verify significance of environmental, social and health impacts; and
- Inform the process of developing appropriate mitigation and management guidelines.

6.2 Stakeholders consulted and concerns raised

The project was presented and explained to all stakeholders and were encouraged to share their concerns and perceived risks. The stakeholders were generally enthused about the project and indicated their readiness to lend their support for the successful implementation of the project.

Below are the key environmental and social issues discussed with the stakeholders.

- Employment and Livelihoods
 - The project will generate short- and long-term job opportunities for skilled and unskilled local labour, including women. However, unmet expectations regarding opportunities could result in social agitation or unrest.
 - Labour and employment issues such as delayed wages, discriminatory practices, or exclusion of women and youth could undermine project credibility.
 - Transparent, inclusive recruitment and training plans must be clearly communicated and coordinated with local stakeholders.
- Food Security, Economic Growth and Market Development
 - Project benefits such as food security, and improved access to mechanization and input services which will raise agricultural productivity and income for value chain actors must be shared with stakeholders to obtain their buy-in for a smooth project implementation.
 - The project will stimulate local commerce and attract new investments in processing, marketing, and quality control services.
 - o Increased agricultural output will reduce rice imports and help Ghana conserve foreign exchange.
- Knowledge, Capacity Building, and Technology Transfer
 - Training of farmers and stakeholders in good agricultural practices will promote climate-smart farming, reduce losses, and improve resilience.
 - o Introduction of modern technologies and digital tools (e.g. RiceAdvice, pest control methods) will enhance productivity and efficiency in farming.

Land Access, Tenure, and Use

- o Farmers and landowners may be either physically or economically displaced by the project and should be engaged extensively on the impacts and mitigation measures including compensation.
- Improper land acquisition or voluntary land donations which are not transparent and inclusive may lead to disputes and restrict access to traditional lands and resources.
- Tenant farmers and informal land users may be overlooked in consultation or compensation processes if stakeholder mapping is not comprehensive.

Water Use and Resource Consumption

- Water-intensive rice cultivation may increase pressure on local water resources, especially during dry periods.
- o Inclusive planning and monitoring involving local communities and water user associations are essential to ensure fair and sustainable water use.

Environmental Degradation

- o Site clearing and infrastructure development may result in loss of vegetation and some trees.
- Soil degradation and erosion may occur due to land preparation, bare farmlands, and construction activities.
- Dust, emissions, and fumes from construction and operations may degrade local air quality, especially on untarred roads.
- Runoff, domestic waste, chemicals, and effluent may pollute surface and groundwater, affecting aquatic life and users.
- Operation of machinery and vehicle movement will generate noise and vibration, causing nuisance to nearby communities.

• Pesticide and Agrochemical Use

- The application of synthetic fertilizers and pesticides poses risks of water pollution, biodiversity loss, and adverse health impacts on farmers and surrounding communities.
- Capacity building is needed for smallholder farmers on Integrated Pest Management (IPM), safe handling practices, and the use of environmentally safer alternatives.

Health, Safety, and Labour Conditions

- Workers face risks of injuries, accidents, insect/animal bites, agrochemical exposure, dustinhalation and equipment-related injuries during construction and operation.
- Poor labour conditions, including lack of contracts and inadequate welfare facilities, may expose workers to exploitation and health risks.
- Fires from negligence or improper burning could cause property loss and injuries.

Social Risks and Community Impacts

- Presence of workers may increase incidents of gender-based violence, rape, and defilement in host communities.
- Pollution and unsafe practices may lead to spread of communicable diseases, including HIV/AIDS and cholera.
- Rising social tensions, theft, confrontations, and conflicts may emerge between workers and locals over cultural, financial, or sexual issues.
- Increased road traffic may cause congestion and accidents due to broken-down or poorly parked haulage vehicles.
- Local communities must be made aware of potential risks and emergency response protocols must be clearly established.
- Gender-Based Violence, Sexual Exploitation and Abuse, and Child Labour

- Labour influx during construction and agro-industrial operations may increase the risk of GBV,
 SEA. and child labour.
- Without strong safeguards, women, girls, and persons with disabilities may face heightened vulnerabilities.
- Community engagement is crucial to raise awareness, strengthen prevention mechanisms, and ensure access to referral and support services.

• Grievance Redress

- The project must implement a well-functioning and accessible Grievance Redress Mechanism (GRM) that all stakeholders can use.
- Existing community grievance structures should be formally recognized and integrated into the broader project-level redress system.

The stakeholders identified and consulted are given in **Annex 5** which provides details of the engagement including locations, dates, stakeholders who participated, pictures, the main concerns raised by participants, responses and commitments of MOFA. **Annex 6** gives the attendance sheet of the stakeholders engaged.

A summary of the outcome of the consultations for key stakeholders is provided in **Table 6-1**. These are mostly concerns and suggestions/interventions from government institutions, community based business entities, farmer-based organizations, and affected communities.

Table 6-1: Details of stakeholders identified and consulted

Group of stakeholders	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
Project Implementer	Ministry of Food and Agriculture (Savelugu)	 The department is aware that land has been acquired for the project. The farmers rely on rain-fed agriculture which makes farming less reliable and profitable. The Department must be well-resourced (finance/logistics) for monitoring/supervision of the project. Farmers should be supported with farm inputs and machinery for land preparation and crop harvesting to reduce post-harvest losses through farmer service centers. Main agriculture problem in the area is lack of irrigation therefore this should be factored into the project planning. 	 The issues raised were acknowledged and the MoFA team referred to the project documents for relevant information. E.g. The SEP provides the focal area of engagements for participants The project is expected to have a positive impact on community members as it will create jobs in the rice value chain thereby reducing rural migration to towns for jobs which do not exist.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
Regulatory	Environmental Protection Authority	 All relevant stakeholders should be involved in the project. There should be ready markets for the rice that will be produced. The road network in the area should be improved to enhance mobility of people and goods. Compensation issues will arise if there are PAPs in the valley. Compensation should be addressed through comprehensive RAP. There must be valuation of properties if any, as well as compensation for any form of displacement. Environmental permit is required for the project. Biodiversity conservation should be a consideration in the project implementation. If there are RAP issues, it should be handled properly in order not to impoverish persons involved. There will be field visits by the EPA team to monitor environmental compliance during implementation. 	Assurance was given to the EPA team that the project will follow all EPA guidelines and that the EPA will be involved in providing monitoring and support for the implementation of the project. Additionally, budget may be considered for their role.
Other Government Institutions	Water Resources Commission	Education on agrochemicals use for farmers to avoid pollution of local water bodies.	 Concerns of WRC officials were noted and that they will be consulted to participate in the project implementation as and when the need arises.
	Savelugu Municipal Assembly	 The assembly is willing to provide support to any project that will improve the productivity of farmers in the community. Compensation issues are important to the assembly and must be comprehensively addressed. 	 All the relevant stakeholders will be engaged and the ESIA will provide mitigation measures especially for farmers who will be directly affected by the project implementation. The Assembly will assist in any grievance mechanism

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		A grievance mechanism	measures implemented
		should be established to	by the project.
		assist the PIU to resolve	
		complaints and grievances	
		in a timely, effective and	
		efficient manner.	
		Main agricultural challenges	
		in the area are the lack of	
		mechanization and the high	
		cost of agricultural input.	
		There is concern about the	
		inadequate road network	
		and the roads are mostly in	
		poor condition.	
		Assembly members and the	
		beneficiary community	
		leadership should be	
		particularly well sensitized	
		about the project to ensure	
		smooth implementation.	
	National	Seasonal floods occur	• The challenges of
	Disaster	regularly during the rainy	NADMO team were noted
	Management Organization,	season leading to loss of	as well as their
	Savelugu	farmlands and food	importance to the
	Javeraga	insecurity.	project.
		Drought is also experienced	Budget will be allocated
		during the dry season	in the ESMP for the
		leading to bushfires.	training of fire fighters
		NADMO is concerned that	and community
		communities farm close to	volunteers to handle bush
		waterways.	fires as well provide
		Project should ensure	education on the effects of bush fires on the
		improved drainage and	project.
		proper construction within	project.
	Chana National	the valley to avoid flooding.	The shallowers of CNEC
	Ghana National Fire Service	The project should put	 The challenges of GNFS team were noted as well
	THE SELVICE	measures in place to preserve existing water	
		preserve existing water bodies as this serves as farm	as their importance to the project.
		boundaries and also helps to	, ,
		curb bush fires.	 As part of the ESMP, resources will be
		• The GNFS should be	provided to support the
		adequately resourced to	training of participants as
		train fire volunteers from	well as community
		the farming communities.	volunteers.
		the ranning communities.	10.4

Group of S	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
Community S	Small Holder Farmer	 Fire incidents have minimized in recent times due to continuous education of the public. Main causes of fire is the indiscriminate burning of bushes (i.e. deliberate, postharvest). Most fire occurrence happen between the months of November and January. The adverse effects of fire outbreaks are loss of income, soil fertility, lives and properties. The closest Fire station is about 10km which is minimally equipped. The local Fire service station will be on hand to assist the project when/ if required including involvement in community education Common crops cultivated include soybean, maize, rice, sorghum, yam, cassava and groundnut. Urgent needs include tractor service, access to agrochemicals including fertilizers. Concerns about the poor road network need to be addressed. Inputs and credit support will be required for the beneficiaries on the project. Drought and pest resistant seed varieties should be provided for production. Ready market for produce is key to encourage more people to get involved. Land preparation support is 	The challenges of participants were noted and they were assured of the benefits that the project will offer them. Existing farmers' fears were allayed as they were assured of compensation payments if they got adversely affected by the project. Roads leading to project sites will be improved to enhance movement of goods.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		 Existing farmers on the proposed project site must be compensated if they are to move out. Gender bias/political influences should be avoided in the project implementation. Farmers should be trained on sustainable farm practices by extension officers. The road in the project area should be improved especially during the rainy season. 	
	Aggregators	 Low purchasing power of farmers. High transportation cost due to poor road network. Lack of access to finance. Inadequate storage infrastructure. There are no formal agreements between aggregators and farmers. Aggregators carry out limited processing of the rice such as cleaning and drying prior to transporting to local markets. 	Concerns were well noted and participants were assured of benefits that the project will bring to them as their businesses will be positively impacted.
	Agro Input Dealers	 Main business activities include trading of fertilizers, seeds, chemicals, tools and equipment, sourced from local distributors. Customers are mostly small-holder farmers. Peak season is between March and June of the year. They offer technical advice/training to farmers. Some concerns include difficulty in connecting to suppliers, inadequate 	Participants were advised to intensify their efforts in educating the farmers including the proper disposal of empty containers of agrochemicals and fertilizers by licensed waste management company.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders		•	Responses
		storage facilities, high transport cost and lack of access to finance. The agro input dealers mostly source their goods	
Civil Society	Farmer Board	from local distributors on cash and carry basis. They are hardly out of stock. All transactions are manual.	De dicional de la constant de la con
Civil Society Organizations (CSO)	Farmer Based Organization (FBO)	 The project should avoid political bias. Vulnerable groups should be given special consideration during project implementation Traditional authorities are important for the success of the project. Agricultural inputs should be subsidized to ensure affordability to farmers. Extensive consultation should be conducted to comprehensively address any land reallocation issues. The use of agro-chemicals and the management of waste from organic fertilizers should be properly managed to prevent the contamination of water bodies flowing through the valleys. The herdsmen cattle feeding on waste/plants especially in the dry season can also help in waste management. Farmers are in urgent need of easy access to affordable finance. A close cooperation is required between farmers and suppliers, credit/financial services etc. A cooperative arrangement 	Participants were assured that the REWARD project was a non-partisan one and that the project will require their support in providing advocacy and training.
		among farmers facilitated	

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		 by CSOs/ NGOs will be useful Initiatives by the Rural Enterprise Programme to provide financial support to farmers is a good one which includes business advisory services. The REP is challenged by high illiteracy levels, difficulty in loan repayment by programme beneficiaries 	
		and inadequate finance.	
Community stakeholders	Traditional Authority	 Land is predominantly owned by the traditional authorities and mostly used for farming and livestock. Some concerns include conflicts with herdsmen, compensation for displaced farmers, fairness in selection of project beneficiary farmers. They recommend timely supply of seeds and agrochemicals, and improvement in the road network. 	 The project was explained to participants to make them understand the benefits to the project communities. Participants assistance were sought to ensure cooperation from affected farmers. The leaders were thanked for donating their lands for the project. The LEAP will be implemented to support vulnerable persons who may be
	Womens'	 Incidences of gender-based violence, sexual exploitation or abuse cases are uncommon in the project area. There are usual petty quarrels between members of the opposite sex but these are settled amicably by family heads/parents or traditional authority depending on which is readily available and accessible. 	affected by the project e.g. bicycles will be given to farmers to aide in transportation to their farms. The Grievance redress mechanism will be put in place to ensure farmers benefit and not suffer from the project implementation.
	Group	 Women are mostly vulnerable and will require special assistance from the project. 	 The womens' value to the community was acknowledged and as such, the project has been designed to benefit

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
	Men's Group	 Concerns include difficulty in accessing ready market for farm produce, lack of processing facilities. Local groups include VSLA which provide some financial support to the women. Vulnerable households mostly receive support from Livelihood Empowerment Against Poverty (LEAP). Main source of livelihood is 	women and encourage their full participation. There will be no room for sexual harassment and in the unlikely event of that happening, the case should be reported to the relevant authorities.
	Men's Group	 Main source of livelihood is farming and rearing of livestock. Deforestation has contributed to unreliable rainfall patterns and has affected the planting (June – December). Their top concerns are the poor road network, lack of access to potable drinking water and financial support. They have confidence in the extension support service and that must be made more effective. Processing facilities are needed to support their farming activities. 	 Participants' concerns were acknowledged and they were assured of job opportunities that will arise from the project. In addition, local persons will be considered first for any job opportunity. Participants were referred to the grievance redress process to address any concerns
	Youth group	 The youth are willing and available to participate in the project as this will help to reduce unemployment and alleviate poverty. Ready markets for the rice produce will be required to ensure reliable flow of income. Irrigation is necessary to make the project more effective and sustainable. Extension officers should play a major role in the 	 Concerns of participants were acknowledged and they were assured of job opportunities that will arise from the project. In addition, local persons will be considered first for any job opportunity. Participants were referred to the grievance redress process to address any concerns.

Group of stakeholders	Stakeholders	•			Proposed Solution/ Responses
		implementation project.	of	the	

6.3 Public disclosure

AfDB requires that environmental reports for projects are made available to project affected groups, local NGOs, and the public at large. Public disclosure of EIA documents or environmental reports is also a requirement of the Ghana EIA procedures (Annex 1). The report should be disclosed to all relevant stakeholders to make inputs or comments. Public notice in the media should be served for that purpose.

6.4 Grievance Redress Mechanism

The activities of the project may generate grievances arising from the interaction between project and local authorities/community, workers and the host community etc. Some potential grievances identified and likely to occur during project implementation include:

- Complaints from the local community on the conduct of workers, especially sexual harassment and other gender-based offenses;
- Complaints related to noise, dust, traffic incidents; and
- Restriction of access to persons who otherwise were using portions of land e.g. for grazing
- Failure to consider the recruitment of local man-labour;
- Non-respect of the habits and customs of the host community by the actors of the site;
- Non-compliance with the measures or provisions contained in the ESMP.

In managing grievances, the REWARD project proposed measures for resolution of grievances that may arise due to project implementation. This is a three-tier grievance redress structure which are:

- Community level structures (1st Tier) These includes; a Grievance Redress Committee and Site-level Grievance Redress Mechanism.
- District level structure (2nd Tier) Municipal Grievance Redress Committee
- Project-wide level structure (3rd Tier) Project Grievance Redress Committee

Community Level (1st Tier):

- Includes Community Grievance Redress Committees (GRCs) and site-level Grievance Redress Mechanisms (GRMs).
- Handles initial complaints from individuals or communities related to agricultural or infrastructure activities.
- Site-level GRMs are managed by contractors and report monthly to the project team; oversight is provided by Environmental and Social Safeguard Specialists.

District Level (2nd Tier):

- Municipal Grievance Redress Committees (Municipal GRCs) address unresolved complaints from the community level or cases where community GRCs fail to act within 30 days.
- They meet quarterly or as needed for urgent matters.

Project Level (3rd Tier):

- Project Grievance Redress Committee led by the Project Coordinator or Social Safeguard Specialist.
- Handles cases escalated from the district level, especially if not resolved in 30 days or if the complainant is dissatisfied with the resolution.

Each level functions progressively, allowing for escalation of unresolved or unsatisfactorily resolved issues. The composition of the Grievance Redress Committees/Structures at the various levels in the **Table 6-2** below.

Table 6-2: Composition of Grievance Redress Committees / Structures

Membership of Committees	s / Structures				
Community Grievance Redress Committee	Site-level Grievance Redress Mechanism	Municipal Grievance Redress Committee	Project Grievance Redress Committee		
Assembly member for the community	Site Environmental Officer	Municipal Director of Agriculture /Rep	Project Coordinator		
Chief	Representatives of site workers	Municipal Planning Officer	Social Safeguard Specialist		
Agriculture Extension Agent (AEA) in charge of the community	PAP representative	Municipal Land Officer	Environmental Safeguard Specialist		
PAP representative		Municipal Community Development Officer (formerly Social Welfare Officer)	Any other project Specialist who would be required		

- Setting up of a Grievance Redress Committee (GRC) at the community level and the district level to receive and address grievances from stakeholders.
 - At the community level, the GRC will be made up of the Assemblyman, the Chief, Agriculture Extension Agent (AEA), and a representative of the project affected persons (PAPs). The Assemblyman will be responsible for receiving grievances and subsequently liaise with the other members of the GRC to have the issue resolved.
 - At the district level, the GRC will be made up of the Municipal Director of Agriculture, the Municipal Planning Officer, Municipal Land Officer and the Municipal Community Development Officer.
 - At the Project level, the GRC will be made up of the Project coordinator, Social Safeguard Specialist, Environmental Safeguard Specialist and any other project Specialist who would be required.
- The PIU will constantly engage project affected persons through its Stakeholder and Public Disclosure
 Plan. This will keep the communities informed of developments on the project, including planned
 activities, project impacts and mitigation measures, grievance mechanism, the right to submit
 complaints and the compensation process.

• Building capacity of the Assemblymen to ensure they can engage the communities, record and ensure grievances are resolved.

Grievances are expected to be communicated either verbally (in a language of choice) or in writing to the GRC. Upon receipt of complaints, timely responses are expected to be given. It is expected that if grievances cannot be resolved locally, then these will be referred quickly to the Municipal Council GRC for resolution.

Actions to be taken to address the grievance will be agreed upon by the GRC, and progress of implementation of agreed measures reported to the Local community, Municipal Assembly, PIU and Ministry of Food and Agriculture on a weekly and monthly basis.

A grievance management procedure indicating activities and timeframe for resolution of issues is shown in **Figure 6-1**.




Figure 6-1: Procedure for Grievance Redress GRM operating budget

Table 6-3 presents the operating budget of the GRM. This budget is estimated at USD 79,000.

Table 6-3: GRM Implementation Budget Summary

Headings	Unit	Quantity	Unit cost (USD)	Total cost (USD)
Reproduction and distribution of forms	Lump sum	1	5,000	5,000
Organization of GRM awareness and public campaigns in local communities	Session	20	2,000	40,000
Training of members of the two (02) committees on the GRM (community level and municipal level)	Session	2	2,000	4,000
Support for the operating of complaints management committees (communities and district)	Monthly	60	500	30,000
Total cost of the implementation of GRM				79,000

7.0 POTENTIAL ENVIRONMENTAL AND SOCIAL ISSUES AND IMPACTS

The Impact Assessment methodology provided in this Chapter sets out the approach used to characterize and evaluate the potential environmental and social effects associated with the REWARD Project.

The entire EIA process can be described as a systematic approach to identifying, describing and evaluating the potential environmental and social effects, and developing measures that will be implemented to manage these effects. These measures include ones that avoid or reduce the significance of adverse effects to an acceptable level and enhancing beneficial effects of the project.

The typical EIA process, including Impact Assessment stages, is indicated in Figure 7-1 below.




Figure 7-1: EIA Process

7.1 Impact Assessment

In undertaking the assessment of impacts, the consultant has drawn upon, among others:

- Its knowledge of sources of potential impacts associated with the REWARD Project;
- An identification of the main environmental and social resources and receptors from the baseline data collection; and
- The results of the various stakeholder engagements.

The assessment methods described below present the criteria for determining receptor sensitivity, impact magnitude and impact significance. The impact assessment for this study includes:

- Identification of Potential Environmental and Social Issues and Impacts; and
- Evaluation and interpretation of impacts.

The Impact mitigation and control strategy is present in the ensuing chapter.

7.1.1 Identification of Potential Environmental and Social Issues and Impacts

The potential environmental and social impacts of the proposed project have been identified and assessed as positive/beneficial or negative/adverse comprehensively. These have been described for the various phases of the Project consisting of:

- 1. Construction phase activities;
- 2. Operational phase activities; and
- 3. Decommissioning phase activities

7.1.2 Evaluation and Interpretation of Impacts

The significance of each impact has been evaluated and compared with national, international as well as applicable industry standards. The methodology for evaluating an impact is outlined below:

Impact Identification and Characterization

Impacts are described in terms of their characteristics, including the impact's type and the impact's spatial and temporal features (namely extent, duration, scale and frequency). The definitions of the terms used are described in **Table 7-1**.

Table 7-1: Impact Characteristics

Characteristic	Definition	Terms
Туре	A descriptor indicating the relationship of the impact to the Project (in terms of cause and effect).	Direct - Impacts that result from a direct interaction between the Project and a resource/receptor (e.g., between occupation of a plot of land and the habitats which are affected). Indirect - Impacts that follow on from the direct interactions between the Project and its environment as a result of subsequent interactions within the environment (e.g., viability of a species population

Characteristic	Definition	Terms
		resulting from loss of part of a habitat as a result of the Project occupying a plot of land). Cumulative - Impacts that result from the incremental impacts of one action/activity when added to past, present, and reasonably foreseeable future actions/activities.
Duration	The time period over which a resource / receptor is affected.	Temporary - (associated with the notion of reversibility). Can be short, medium and long term: Short term – typically lasts from days to months. Medium-Long term – typically lasts from one to many years. Permanent – (i.e. irreversible)
Extent	The reach of the impact (i.e. physical distance an impact will extend to).	On-site - impacts that are limited to the Project site. Local - impacts that are limited to the Project site and adjacent area. Regional - impacts that are experienced at a regional scale, i.e. beyond adjacent properties, covering the metropolis and beyond National - impacts that are experienced at a national scale. Trans-boundary/International - impacts that are experienced outside of Ghana
Scale	Quantitative measure of the impact (e.g. the size of the area damaged or impacted, the fraction of a resource that is lost or affected, etc.). or the professional viewpoint of the measure of impact.	Quantitative measures as applicable for the feature or resources affected/ professional viewpoint of expert as applicable for the feature or resource in terms of severity of impact measure (i.e. minor, moderate, severe)
Frequency	Measure of the constancy or periodicity of the impact.	No fixed designations; intended to be a numerical value or a qualitative description.
Likelihood	Characteristic that pertains to unplanned events determined either qualitatively or quantitatively estimated on the basis of experience and/or evidence that such an outcome has previously occurred.	Unlikely – The event is unlikely but may occur at some time during normal operating conditions. Possible – The event is likely to occur at some time during normal operating conditions. Likely - The event will occur during normal operating conditions (i.e., it is essentially inevitable).

Determining Impact Magnitude

Once an impact's characteristics are defined, the next step is to estimate impact's "magnitude". Magnitude is typically a function of the following impact characteristics (as applicable):

- 1. extent;
- 2. duration;
- 3. scale; and
- 4. frequency.

Magnitude (from small to large) is in practice a continuum, and evaluation along the spectrum requires the exercise of professional judgement and experience. Each impact is evaluated on a case-by-case basis, and the rationale for each determination is noted. The universal magnitude designations, for negative effects, are: negligible, small, medium and large. The magnitude designations themselves are universally consistent, but the definition for the designations varies by issue. In the case of a positive impact, no magnitude designation has been assigned as it is considered sufficient for the purpose of the impact assessment to indicate that the Project is expected to result in a positive impact.

Determining Receptor Sensitivity

The other principal step necessary to assign significance for a given impact is to define the sensitivity of affected receptor. The importance and sensitivity of environmental (physical and biological) and socioeconomic receptors within will be determined based on:

- 1. Relevant legislative or policy standards or guidelines;
- 2. The relative importance/value assigned to existing socio-economic or environmental features/receptor;
- 3. The capacity of the receptor to absorb change; and
- 4. The recoverability of the receptor.

Table 7-2 provides a general definition of sensitivity ranking for environmental and socio-economic receptors, which are then tailored by technical subject matter experts.

Table 7-2: Sensitivity Criteria

	Low	Medium	High			
Biological and	d Physical Receptors - Sensitiv	vity Criteria				
Criteria	Ecosystem Value: An area or species which has local or no value Capacity for Change and Recovery: The receptor is not sensitive to changes in the surrounding environment and has a natural ability (i.e. without human enhancement) for a rapid rate of recovery to pre-impacted status within few days/months.	Ecosystem Value: An area or species which are recognized as being of regional importance; and/or Capacity for Change and Recovery: The receptor is relatively sensitive to changes in the surrounding environment and has moderate capacity to absorb change without significantly	Ecosystem Value: An area or species which is recognized as being of international and national importance and/or is legally protected; and/or Capacity for Change and Recovery: The receptor is highly sensitive to changes in the surrounding environment and has no / low capacity to absorb change without significantly altering its present			

	Low	Medium	High		
		altering its present character; natural recovery possible after one year.	character; no / slow natural recovery.		
Socio-Econom	nic Receptors - Sensitivity Crit	eria			
Criteria	Socioeconomic Value: A socio-economic activity of limited local or no value; and /or Capacity for Change and Recovery: The receptor is not sensitive to changes in the surrounding environment and has a natural ability (i.e. without human enhancement) for a rapid rate of recovery to pre-impacted status within days/weeks.	Socioeconomic Value: A socio-economic activity which is recognized as being of regional importance; and/or Capacity for Change and Recovery: A socio-economic activity which has the capacity to recover after one year.	Socioeconomic Value: A socio-economic activity which is recognized as being of international / national importance and/or a resource or area which is legally protected; and/or Capacity for Change and Recovery: The receptor has no / low capacity to absorb change without significantly altering its present character; no / slow natural recovery.		

Assessing Impact Significance

Once magnitude of impact and sensitivity of a receptor have been ranked, the significance can be determined for each impact. The impact significance rating was determined, using the matrix provided in **Table 7-3**, and impact significance definitions as presented in **Table 7-4**, which ensure a consistent approach throughout the impact assessment. The significance matrix provides basic guidance for the determination of impact significance. However, the resulting significance level is also interpreted based on professional judgement and expertise, and adjusted if necessary.

The impact ratings are categorised as follows:

- Minor significance;
- Moderate significance; and
- Major significance.

Table 7-3: Impact Significance

	Sensitivity	Sensitivity							
Magnitude	Low [1]	Medium [2]	High [3]						
Negligible [0]	Negligible [0]	Negligible [0]	Negligible [0]						
Small [1]	Negligible [1]	Minor [2]	Moderate [3]						
Medium [2]	Minor [2]	Moderate [4]	Major [6]						
Large [3]	Moderate [3]	Major [6]	Major [9]						

Key: Negligible – 0 to 1, Minor – 2, Moderate – 3 to 4, Major – 6 to 9

Table 7-4: Impact significance definitions

Significance of Impact

Major	Significant . Impacts with a " Major " significance are likely to have damaging and lasting changes to the functioning of a receptor, and may have broader consequences (e.g. on function of the ecosystem or on community well-being). These impacts are a priority for mitigation in order to avoid or reduce their significance.
Moderate	Significant . Impacts with a " Moderate " significance are likely to be noticeable and result in lasting changes to baseline conditions, which may cause hardship to or degradation of the receptor. Broader consequences for the ecosystem or community are not anticipated. These impacts are a priority for mitigation in order to avoid or reduce their significance.
Minor	Detectable but Not Significant . Impacts with a " Minor " significance are expected to be noticeable changes to baseline conditions, beyond what would naturally occur, but are not expected to cause hardship or degradation. These impacts in most cases do not require mitigation and are not a concern of the decision-making process.
Negligible	Impacts with a "Negligible" significance are expected to be almost unnoticeable in terms of affecting the baseline conditions. These impacts do not require mitigation and are not a concern of the decision-making process.

The matrix and significance definitions will be used to assess adverse impacts of the Project. Significance rankings will not be determined for beneficial impacts; instead, these will be described in qualitative terms and, where applicable, measures to maximize benefits will also be described.

For all Significant impacts (Moderate or Major) identified by the assessment, additional mitigation measures will be proposed aimed at reducing their residual significance to as low as reasonably practicable (ALARP). For Not Significant impacts (Minor and Negligible), all design/control measures should be adhered to with monitoring and reporting implemented as required.

7.1.3 Mitigation and Control

All significant impacts identified will be subject to mitigation and control through preventive, reductive and offset measures as well as optimizing the viability and potential benefits that the project may generate. The selection of mitigation measures will consider a standard mitigation hierarchy, whereby preference is given to avoiding impacts altogether and subsequently to minimizing the impact, repairing its effects, and/ or offsetting the impact through actions in other areas as illustrated in **Figure 7-2**. Where the effectiveness of mitigation measures is uncertain, or depends on assumptions about operational procedures, monitoring programmes and/or operations/management procedures will define the required practice.




Figure 7-2: Mitigation Hierarchy

The environmental and social management plan (ESMP) framework will be developed for the project and its facilities in accordance with Environmental Assessment Regulations 2025, LI 2504 and the AfDB OS standards. The ESMP framework will present a programme for the implementation of mitigating measures and the identified impacts of the project during the construction and operation phases.

7.2 Potential Environmental Risks and Social Issues

Potential impacts of the REWARD Project on the physical, biological and social environments have been identified and are discussed below in this section.

7.3 Project Area of Influence (AoI)

The ESIA gives an identification, qualitative assessment and classification of potential environmental and social impacts and their respective management options based on the general project design concepts. The REWARD Project will have both positive and negative social, economic and environmental impacts at different levels.

There are two (2) AoIs: i.e. Area of Direct Influence (ADI) and Area of Indirect Influence (AII) for the REAWARD Project. These have been defined to properly identify environmental and social impacts and risks associated with the project in the sections below.

7.3.1 Environmental Area of Influence

The Area of Direct Influence (ADI) for the project includes the physical and biological components such as the vegetation, fauna, surface/groundwater resources, soils etc. at the project area and the community (i.e. Nankpazoo) around the project area.

The area of indirect influence (AII) is the territory where indirect or induced environmental impacts; i.e. those that occur at a different site from where the action causing the environmental impact occurs and at a different time compared with the time when the action causing the environmental impact occurred.

The All for the project includes 1-10 km zone around ADI (depending on the affected receptors, for example for groundwater it can be broader than for biodiversity), the transit routes for materials and personnel or workers.

7.3.2 Social Area of Influence

For social impacts, the ADI will include the households and the community that will be impacted by the Project due to:

- ✓ their location within or in close proximity to the Project footprint (including footprint of associated facilities);
- ✓ their location within the Area(s) of Influence for environmental resources, such as air or water quality, noise and vibration, visual and landscape, etc.;
- ✓ impacts on livelihood resources that will be affected by the Project (agricultural or grazing land, forest resources, fishing); or
- ✓ their connection to cultural, social or health resources that will be impacted by the Project.

The Area of Indirect Influence will also include populations that will experience indirect or induced impacts that may not be within the direct control of the Project, such as:

- ✓ economic opportunities associated with employment and economic spend;
- ✓ interaction with the workforce;
- ✓ use of services by the workforce; and
- ✓ in-migration.

7.4 Community influence and vulnerable groups

Construction activities may impact adversely on local communities especially those which are located in close proximity to these activities.

Vulnerable groups are those at risk of becoming more vulnerable due to impacts from project implementation. These vulnerable people include, but not limited to:

Disabled persons, whether mentally or physically challenged;

- Elderly, usually from 70 years and above;
- Very sick and or physically weak individuals;
- People without formal land rights;
- Migrants/settlers;
- Women; and
- Children.

7.5 Institutional Influence

The major institutions to be influenced or involved in the proposed project include:

- Ministry of Food and Agriculture;
- Project Implementation Unit;
- Water Resources Commission;
- Lands Commission;
- Forestry Commission
- Environmental Protection Authority;
- Regional Coordinating Council;
- Municipal Assembly;
- Fire Service; and
- NADMO.

7.6 Potential Positive Impacts

The significant positive impacts of the proposed project are outlined as follows:

- Creation of job opportunities;
- Increased commerce and boost to local economy;
- Food security;
- Adoption of good agricultural practices;
- Technology transfer
- Save the Government of Ghana from importing rice and thereby save foreign exchange for Ghana

7.6.1 Creation of job opportunities

Job opportunities for skilled, semi-skilled and unskilled labour will be created at the construction and operation phases as locals, including women, will be recruited for short-term and long-term jobs. During construction of various agricultural value chain support infrastructure (assembly/construction of semi-industrial units, construction of warehouses etc.), labourers and piece workers will be engaged. The presence of workers will create an opportunity for food vendors, shop owners and other business operators in the communities to make some income. At the operation phase, there will be increase in the number of agricultural jobs leading to income generation and poverty reduction.

7.6.2 Increased commerce and boost to local economy

Agricultural productivity will increase quantitatively due to increased access to mechanization services by rice farmers. This will result in higher revenue for players within the value chain such as farmers, input suppliers, transport operators, feed millers etc. Also, the project will improve and facilitate establishment

of local services for marketing, processing, quality control services and development of new investment opportunities.

7.6.3 Food security

Increase in production capacity coupled with availability of storage facilities will make produce available all year round and improve reliance on local agricultural produce and product. This will reduce the importation of agricultural produce across borders and improve food security.

7.6.4 Adoption of good agricultural practices

The proposed project will involve the community and the local stakeholders throughout the project cycle equipping them with knowledge and skills in agricultural practices. The project will present the local stakeholders with a learning opportunity on good practices, such as climate smart agriculture, efficient water management, fertilizer application, among others leading to reduction in losses and better pest and disease management.

7.6.5 Technology transfer

Farmers will be exposed to new technologies for geomapping, crop management, pest and disease management, processing, etc. that were otherwise not known to them. For instance, applications such as the RiceAdvice decision support; will provide farmers guidelines for specific field conditions via smart phones. For pest and disease control, technologies that counter threats from parasitic striga, health-threatening aflatoxins and the invasion by Fall Army Worm will be made available to farmers. Facilitation of farmer access to mechanical and motorized shellers, threshers, improved seed variety and breeds will all increase productivity of farmers and increase their savings.

7.7 Moderate and Major Negative Impacts

The environmental impacts of the project have been grouped as moderate and major impacts based on their significance. Also, impacts have been considered at the various phases of the project, i.e., preparatory, construction and operation. The moderate and major adverse impacts are described below and in **Table 7-5**, **Table 7-6**, **Table 7-7** and **Table 7-8** for Preparatory, Construction, Operational and Decommissioning Phases respectively.

Preparatory phase

- Land related disputes Acquisition of lands by farmers without following due process could result in land-related disputes
- **Impact on livelihoods** The project activities could restrict locals access to lands that were otherwise used as pasture areas.
- **Destruction of vegetation -** Site clearing will lead to the destruction of some common vegetation and a few trees.

Construction phase

• Soil degradation – Levelling, as part of land preparation, and excavation for foundation of structures such as sheds and warehouses could lead to soil erosion and creation of gullies through runoff

- especially in the rainy season. Also, oil spillages from the maintenance of construction equipment and vehicles could contaminate soils and affect flora and soil fauna
- **Air pollution** Levelling of land and transport of materials on untarred roads will lead to emission of particulate matter i.e. dust and fumes and adversely affect air quality, especially in the dry season.
- Water pollution Disposal of domestic waste from construction workers and food vendors and deposition of sediment, waste oil etc. via runoff into nearby water bodies. i.e. water collected in the valleys.
- **Noise and vibration** Generation of noise and vibration beyond acceptable limits from operation of construction equipment, movement of haulage vehicles and tooting of horns could be a nuisance to residents of nearby communities and other sensitize organisms.
- Waste generation and disposal Clearance of vegetation and levelling of land at project site will
 generate vegetative waste and excavated spoil. Other wastes such as construction debris, pieces of
 steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog
 drains, produce foul smell and facilitate the outbreak of sanitary related diseases such as cholera
- Inefficient waste management Inefficient waste management during construction, operation and maintenance leading to excess consumption of materials, generation of wastes/emissions, pollution of soils and water.
- Visual intrusion Presence of construction machinery, material stockpiles, temporary work camps;
 Vegetation clearance, earthworks (bare ground); dust plumes, may intrude on the visual sensitivity of the Nakpanzoo community.
- Occupational health and safety Construction workers could be exposed to workplace and trafficrelated accidents/incidents as well as animal/insect threat/bites during land preparation, civil works and transportation of materials or persons.
- **Poor labour working conditions** Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions. Also, the absence of welfare facilities like toilets, sheds could affect their health or lead to indiscriminate defecation.
- Traffic management Transport of materials and equipment to and from the project site through communities and towns raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage/construction trucks could lead to road accidents and traffic congestion especially on busy roads.
- **Fire outbreak** Fire outbreaks from negligence of workers or the public burning refuse, game hunting and workers not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property.
- Gender based violence Presence of workers and increase in incidents of rape, defilement and GBV
- Public health issues Pollution of local water bodies will adversely affect the health of users. Sexual
 relations between workers and locals may bring about increase in sexually transmitted diseases
 including HIV/AIDs.
- **Risk of Drowning** Burrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains.
- **Security concerns** Violent behaviour and confrontations between workers and locals. Workers who are deemed to be financially sound could be victims of theft and burglary. Potential conflict over sexual affairs, child labour, drunk driving, accidents and destruction of property.

Operation phase

- **Soil erosion** Leaving farmlands bare especially after harvesting could expose the soil to wind erosion from the strong winds in the dry season
- Air Pollution Operation of equipment and vehicles will generate fumes that adversely affect the air
 quality. In addition, haulage of products and inputs such as fertilizers, pesticides, seeds especially on
 untarred routes to and from farms or agricultural establishments will generate dust and fumes.
- **Pollution of Soils and Water** Wastes, workforce sewage effluent, as well as runoff from cultivated land (containing fertilizers, pesticides and herbicides etc.) could pollute surface water, reduce its quality and make it unsuitable for use
- Odours Odours associated with waste may have nuisance value for nearby receptors.
- Noise and Vibration Noise and vibration from operation of processing equipment, equipment
 maintenance, movement of haulage vehicles, tooting of horns could be a nuisance to persons within
 the project community or nearby communities
- Waste generation and disposal Improper disposal of vegetative waste from weeding, harvests, domestic waste from workers and effluent from installations could create unsightly scenes and aid in the production of vermin. Also, it could serve as breeding grounds for disease causing vectors like mosquitoes, houseflies etc.
- Inefficient waste management Inefficient waste management during operation and maintenance leading to excess consumption of materials, generation of wastes/emissions, pollution of soils and water.
- Occupational health and safety Workplace and traffic accidents/incidents and animal/insect threat/bites.
- **Poor labour working conditions** Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions.
- Traffic management Haulage of produce, inputs and equipment to and from farms through communities raises traffic/public safety concerns. Broken-down, inappropriately parked or slow moving haulage trucks could lead to road accidents and traffic congestion especially on busy roads.
- **Fire outbreak** Fire outbreaks from negligence of workers or the public burning refuse, game hunting and not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property.
- Gender based violence Presence of workers and increase in incidents of rape, defilement and GBV.
- **Risk of Drowning** Burrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains.
- Public health issues Pollution of local water bodies will adversely affect the health of users. Sexual
 relations between workers and locals may bring about increase in sexually transmitted diseases
 including HIV/AIDs.
- Snake bite risks Farm workers on rice fields are likely to be exposed to snake bites which may result in hospitalization or fatality.
- Security concerns Violent behaviour and confrontations between workers and locals as a result of sexual affairs, child labour, drunk driving, accidents and destruction of property. Workers who are deemed to be financially sound could be victims of theft and burglary.
- **Flooding** The project implementation could be adversely affected by events of flood from torrential rainfall in the wet season especially in low-lying areas affecting properties and lives.

Decommissioning phase

- Occupational health and safety Workplace and traffic accidents/incidents and animal/insect threat/bites.
- Inefficient waste management Inefficient waste management during decommissioning leading to excess consumption of materials, generation of wastes/emissions, pollution of soils and water.
- Waste generation and disposal Improper disposal of waste from dismantling of machine parts could
 create unsightly scenes. Also, it could serve as breeding grounds for disease causing vectors like
 mosquitoes etc.
- Traffic management Transport of materials and equipment to and from the project site through
 communities and towns raises traffic/public safety concerns. Broken-down, inappropriately parked or
 slow-moving haulage/construction trucks could lead to road accidents and traffic congestion
 especially on busy roads.

7.7.1 Preparatory Phase: Moderate and Major adverse impacts

The preparatory phase moderate and major adverse impacts are provided in **Table 7-5.**

 Table 7-5:
 Preparatory Phase Potential Adverse Impacts

AfDB	AfDB OS				Sensitivity						
No.	Description	Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS1	Environmental and Social Assessment	Poor assessment study of environmental and social risks and impacts	Project proponent (MoFA), environment, community	Unidentified risks and impacts could prevent or stall project implementation. Selection of unqualified persons for assessment studies	Unlikely	Direct	Permanent	Regional	High [3]	Large [3]	Major [9]
OSS	Involuntary resettlement, land acquisition, population displacement and compensation Impact on livelihoods (economic displacement)	Farmers	Proposed site which covers an area of 300 Ha is purportedly owned by the chief of the Nakpanzoo community with no known land disputes over the land at the proposed site.	Unlikely	Direct	Temporary	Local	Medium [2]	Medium [2]	Moderate [4]	
		livelihoods (economic	Farmers	The project activities could restrict thirty three (33) farmers access to lands that were otherwise used for farming.	Likely	Direct	Permanent	Local	Medium [2]	Medium [2]	Moderate [4]

AfDD	ASDR OC				Sensitivity						
AfDB No.	AfDB OS Description	Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Physical Displacement	Farmers	There will be no physical movement of properties from the project site during project implementation.	Unlikely	Direct	Temporary	Local	High [3]	Negligible [0]	Negligible [0]
OS6	Biodiversity, renewable resources and ecosystem services	Destruction of vegetation and displacement of wildlife	Flora and Fauna	The project site is an already disturbed area due to previous human activities such as farming. The floristic analysis conducted identified <i>Grewia carpinifolia</i> which is of national conservation concern on the site. Aside that, none of the other species identified at the site are of conservation concern according to the Forest Reserves of Ghana Information Exhibitor (FROGGIE) data base. Isolated cases of <i>Vitellaria paradoxa</i> (shea tree) which is of some economic importance to the local people were also recorded on the project site. This is not of biodiversity and	Likely	Direct	Permanent	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB No.	AfDB OS Description	Potential Impact	Receptor(s)	Sources of Impact							
					Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				economic significance because they are found extensively in other areas of the municipality.							
				Site clearing will not lead to any major destruction of biodiversity of significant importance.							

7.7.2 Construction Phase: Moderate and major adverse impacts

The Construction phase moderate and major adverse impacts are provided in **Table 7-6** below.

Table 7-6: Construction Phase Potential Adverse Impacts

AfDB	AfDB OS	Risk/Potential Impact	Receptor(s)	Sources of Impact	Sensitivity						
No.	Description				Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS2	Labour conditions, health and safety	Workplace incidents/accidents	All Project workforce, Vulnerable categories of workers, Women	Project site accidents/incidents and animal/insect threat/bites. Ghana has recorded over 59,000 snake bite cases between 2015 and 2020 with an average 9,900 cases reported annually. The Savannah Region has a relatively high incidence of snake bites as per the Ghana Health Service (2020).	Likely	Direct	Short- term	On-site	High [3]	Medium [2]	Major [6]
		working conditions	All Project workforce, Vulnerable categories of workers, Women	Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions. Workers could face issues of discrimination, forced labour, child labour, freedom of association and collective bargaining, lack of or ineffective worker grievance redress mechanisms.	Likely	Direct	Short- term	On-site	High [3]	Medium [2]	Major [6]
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Women, Children	Presence of workers and increase in incidents of rape, defilement, child molestation and GBV. Culturally, women and children have limited rights compared to men in northern Ghana making GBV issues relatively pronounced in the project areas.	Likely	Direct	Short- term	Local	High [3]	Medium [2]	Major [6]

AfDD	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Sensitivity						
AfDB No.					Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS3	Pollution prevention and control, hazardous materials and resource efficiency	Soil erosion and contamination	Soil	Excavation for foundation of structures could lead to soil erosion and creation of gullies through runoff especially in the rainy season. The project area due to its sparse vegetation cover is highly susceptible to erosion especially in low-lying areas like the valleys. Soil contamination could also occur from inappropriate disposal of waste oil, spilled oil during machinery operation and maintenance as well as fuel storage sites and leaks from vehicle refuelling.	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]
		Air Pollution	Health of workers and members of the surrounding communities	Emission of fumes and dust from transport of materials especially on untarred routes to project site. Baseline air quality data i.e. $PM_{2.5} - 30\mu g/m^3$, $PM_{10} - 109\mu g/m^3$, NO^2 , SO^2 and CO were all below the minimum detection limit of $0.06~mg/m^3$ at the time of sampling. This shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds except for PM_{10} whose higher value could be attributed to high coarse particulate pollution, likely arising from mechanical disturbances during farming, vehicular movement, and possibly wind-driven dust due to the site's open, dry landscape.	Likely	Direct	Temporary	Local	Medium [2]	Medium [2]	Moderate [4]

4655	1622.00	D: 1 /D							Sensitivity				
AfDB No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)		Sources of Impac	t	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Water Pollution	Pools of water in the valley.	waterbodies cou		port into nearby ne already turbid season.	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]
				construction wo average of 20 w total of 10 kg/o generated per d 0.5 kg/day Also,	orkers and food orkers at the cons day domestic sol ay using a per cap a total BOD load	r waste from the vendors. For an struction phase, a lid waste will be pita generation of of 0.8 kg/day will pita production of	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]
		Noise and Vibration	Health of project workforce		and tooting of ho	ent, movement of orns will generate	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]
			and members of	Equipment type	Sound pressure level at 15m (dB)	Sound pressure level at 600m (dB)							
			the surrounding	Backhoe	80	47.96							
			communities	Grader	85	52.96							
				Loader	85	52.96							
				Truck Source: Generated from	88 WKC Group Formula (2015	55.96							
				Movement of haulage vehicles/trucks and tooting of horns will at all times expose receptors to noise, albeit transient. However, at night, the impact of									

4500	4500.00	Disk/Datasatisk					Sensitivity				
AfDB No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Waste generation and disposal	Health of project workforce and members of the Local communities within the project area	noise is likely to be higher. Exposure to elevated levels of noise can cause nuisance, disturbance and even lead to hearing impairment under certain conditions. Workers are expected to be exposed to intermittent noise and vibration for the construction period which will be one dry season (approx. 4 months). Clearance of vegetation at project site, construction debris, pieces of steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog drains and facilitate the outbreak of sanitary related diseases such as cholera. Domestic and waste from the construction workers and food vendors to the construction crew. For an average of 20 workers at the construction phase, a total of 10 kg/day domestic solid waste will be generated per day using a per capita generation of 0.5 kg/day Also, a total BOD load of 0.8 kg/day will be generated assuming a per capita production of 40g/day.	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]
OS4	Community Health, Safety and Security	Traffic management	Local communities near the	Transport of materials and equipment through communities and townships raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage/construction trucks could lead to road accidents and traffic congestion	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB OS	Risk/Potential					Sensitivity				
No.	Description	Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
			project area of influence	especially on busy roads. Locals may not be used to truck traffic as the popular mode of transportation is bicycles, motorcycles and tricycles.							
		Fire outbreak	Vegetation, Project workforce and Local communities near the project area of influence	Fire outbreaks from negligence of workers or the community burning refuse, game hunting and workers not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property. A major constraint faced by the people within the fragile Savannah ecology is the issue of bushfire. Most of the vegetation cover is consumed every year by wild fire. This menace does not only affect the density and diversity of the vegetation in the Savannah ecosystem but has lowered the productivity of the land and the general agricultural output.	Likely	Direct	Temporary	Local	Medium [2]	Medium [2]	Moderate [4]
		Visual / Aesthetic Impacts	Local community (Nakpanzoo), commuters	Presence of construction machinery, material stockpiles, temporary work camps; Vegetation clearance, earthworks (bare ground); Dust plumes. Landscape is already agricultural.	Likely	Direct	Temporary	Local	Medium [2]	Medium [2]	Moderate [4]
		Public health issues	Local communities	Pollution of local water bodies will adversely affect the health of users	Likely	Direct	Short- term	Local	High [3]	Small [1]	Moderate [3]

							Sensitivity				
AfDB No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
			near the project area of influence	Sexual relations between workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	Likely	Local	Long-term	Local	High [3]	Small [1]	Moderate [3]
		Security concerns		Violent behaviour and confrontations between workers and locals.	Likely	Local	Temporary	Local	Medium [2]	Small [1]	Minor [2]
				Workers who are deemed to be financially sound could be victims of theft and burglary							
				Potential conflict over illicit sexual affairs, child labour, drunk driving, accidents and destruction of property.							
		Risk of Drowning	Project Workforce and Local community members	Borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for workers especially contract staff who are not familiar with the local terrain. Children who may play around the sites and unsuspecting community members may also be at risk of drowning especially when it rains and the place get flooded. It must be noted however, that the specific locations for the borrow pits are yet to be determined by the project contractor and that will be done before work commences.	Likely	Local	Long-Term	Local	Medium [2]	Medium [2]	Moderate [4]

7.7.3 Operation Phase: Moderate and Major adverse impacts

The Operation phase moderate and major adverse impacts are provided in **Table 7-7.**

Table 7-7: Operation Phase Potential Adverse Impacts

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS2	Labour conditions, health and safety	Occupational health and safety	Farm workers including Vulnerable categoriese.g. Women	Farm accidents/incidents and animal/insect threat/bites. Ghana has recorded over 59,000 snake bite cases between 2015 and 2020 with an average 9,900 cases reported annually. The Savannah Region has a relatively high incidence of snakes' bites as per the Ghana Health Service (2020). Exposure of workers/farmers to agrochemicals could lead to health challenges such as chemical burns, respiratory diseases from inhalation, and poisoning.	Likely	Direct	Long-term	On-site	High [3]	Medium [2]	Major [6]
		Poor labour working conditions	Farm workers including Vulnerable categories .e.g Women	Lack of employment contracts could lead to farm workers being paid rates below the stipulated national minimum wage or work under poor conditions. Farm workers could face issues of discrimination, forced and child labour, restriction of freedom of association and collective bargaining, non-	Likely	Direct	Long-term	On-site	High [3]	Medium [2]	Major [6]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				existent or ineffective farm worker grievance redress mechanism.							
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Women and Children	Presence of migrant farm workers could lead to increase in incidents of rape, defilement, child molestation and GBV. Culturally, women and children have limited rights compared to men in northern Ghana making GBV issues relatively pronounced in the project areas.	Likely	Direct	Long-term	Local	High [3]	Medium [2]	Major [6]
		Child Labour	Children	Employment and deployment of Children under the working age at the expense of their education and their exposure to hazards that endanger their health and well-being. In Ghana, children's work is mostly split between the three main areas: the agriculture, services, and industry sectors. The agricultural sector has the highest percentage of working children in the country, with 79.2% of working children between ages 5 and 14 employed in this sector (Child Labour and Forced Labour Reports, 2021). The Northern parts of Ghana has the lowest level of school attendance of children of primary school age at just 59.4 per cent of children due to child labour with most found in the	Likely	Direct	Long-term	Local	High [3]	Medium [2]	Major [6]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				agriculture and forestry sector. Children are vulnerable to snake and scorpion bites and suffer frequent accidents with poorly handled machetes while they are engaged in work in the bush. Boys tend cattle and girls collect water and firewood. (Child Protection Baseline Research Report, 2015).							
OS3	Pollution prevention and control, hazardous materials and resource efficiency	Soil erosion and degradation	Soil	Abuse in fertilizer usage could lead to soil degradation. Leaving farmlands bare especially after harvesting could expose the soil to erosion. Soil degradation could also occur from inappropriate application of fertilizers and other agro-chemicals.	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]
		Air Pollution	Health of farm workers and surrounding community members.	Use of farm machinery, clearing of dry lands and emission of fumes/dust from tricycles or motorcycles conveying farmers and farm produce especially on untarred routes from farms are some of the activities that have the potential of affecting the air quality within the project area. Stubble burning to prepare the field for the next planting season can also affect the air quality within the project area.	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				Baseline air quality data i.e. $PM2.5-30\mu g/m3$, $PM_{10}-109\mu g/m3$, $NO2$, $SO2$ and CO were all below the minimum detection limit of 0.06 mg/m3 at the time of sampling. This shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds except for $PM10$ whose higher value could be attributed to high coarse particulate pollution, likely arising from mechanical disturbances during farming, vehicular movement, and possibly wind-driven dust due to the site's open, dry landscape. Emissions from farming activities such as tilling, threshing and transportation of farm produce are therefore not expected to result in significant air quality deterioration.							
		Water Pollution	River water quality including water which has gathered as ponds in the valley.	Sediment laden with excess fertilizers and other agrochemicals and waste oil transport into nearby water bodies especially in the rainy season. Pollution of watercourses caused by wastes generated by farm workers as well as runoff from land used for growing rice	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				(containing fertilisers, pesticides and herbicides etc.).							
		Noise and Vibration	Health and wellbeing of farm workers and members of communities close to the project area	Farm workers are expected to be exposed to intermittent noise from activities like tilling of the land for the next planting season, threshing the rice after cultivating and screaming sounds from farmers or labourers to scare away birds can all generate noise. Tricycles and motorbikes conveying farmers and farm produce to the milling factories or markets could also generate some noise including the sounds from tooting horns.	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]
		Solid waste generation and disposal	Health of farm workers and members of the Local communities within the project area	Improper disposal of waste, i.e. empty containers of agrochemicals and fertilizers which can serve as breeding grounds for mosquitoes. Threshing will produce rice husk that may pile up to form heaps of waste. Domestic waste can also be generated from farm workers. For an average of 10 workers at the construction phase, a total of 5 kg/day domestic solid waste will be generated per day using a per capita generation of 0.5 kg/day. Also, a total BOD	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				load of 0.4 kg/day will be generated assuming a per capita production of 20g/day.							
O54	Community Health, Safety and Security	Polluted Waterbodies	Farm workers and Local communities	Pollution of water gathered as ponds from contaminated sediments generated by activities of farm workers as well as runoff from land used for growing rice (containing fertilisers, pesticides and herbicides etc.) will adversely affect the health of community members.	Likely	Direct	Local	Local	Medium [2]	Medium [2]	Moderate [4]
		Sexual Transmitted Diseases		Sexual relations between migrant farm workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	Likely	Direct and Indirect	Long-term	Local and Regional	Medium [2]	Medium [2]	Moderate [4]
		Security concerns		Violent behaviour and confrontations between migrant farm workers and locals. Farm workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over sexual affairs, child labour, drunk driving, accidents and destruction of property.	Likely	Direct	Long-term	Local	Medium [2]	Small [1]	Minor [2]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Flooding	Community members, Farmers, Flora and Fauna	The project implementation could be adversely affected by events of flood from torrential rainfall in the wet season especially in low-lying areas affecting properties and lives.	Likely	Direct	Temporary	Regional	High [3]	Medium [2]	Major [6]
		Traffic management	Local communities	Transportation of farmers and farm produce through communities raises traffic/public safety concerns.	Likely	Direct	Long-term	Local	Medium [2]	Small [1]	Minor [2]
		Fire outbreak	Rice farms, nearby vegetation, farm workers and local community.	Fire outbreaks from negligence of farm workers and community members, burning refuse, game hunting, cooking and not properly extinguishing stubs of cigarette. These fires could spread to adjoining farms causing injuries to persons and destruction of property. A major constraint faced by the people within the fragile Savannah ecology is the issue of bushfire. Most of the vegetation cover is consumed every year by wild fire. This menace does not only affect the density and diversity of the vegetation in the Savannah ecosystem but has lowered the productivity of the land and the general agricultural output.	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB AfDB OS	Risk/Potential Impact					Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Risk of Drowning	Farmers and Local community members	Burrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. These pits may be left for communities as a water source and may pose the risk of drowning especially for children.	Likely	Local	Long-Term	Local	Medium [2]	Medium [2]	Moderate [4]

7.7.4 Decommissioning Phase: Moderate and major adverse impacts and specific measures

The Decommissioning phase moderate and major adverse impacts are provided in **Table 7-8.**

Table 7-8: Decommissioning Phase Potential Adverse Impacts

A CDD	4500.00	Diel /Detectiel					Sensitivity				
No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS2	Labour	Workplace	All Project	Project site accidents/incidents and animal/insect	Likely	Direct	Short-term	On-site	High [3]	Medium [2]	Major [6]
	conditions,	incidents/accidents	workforce,	threat/bites. Ghana has recorded over 59,000 snake							
	health and		Vulnerable	bite cases between 2015 and 2020 with an average							
	safety		categories of	9,900 cases reported annually. The Northern Region							
			workers,	has a relatively high incidence of snakes bites as per							
			Women	the Ghana Health Service (2020).							
OS3	Pollution	Waste generation	Health of	Clearance of vegetation at project site, construction	Likely	Direct	Short-term	Local	Medium	Medium [2]	Moderate [4]
	prevention	and disposal	project	debris, pieces of steel/metal, packaging materials,					[2]		
	and		workforce	plastic pieces, human waste etc. if not disposed							

A (DD	4(55.00	Distribute and all					Sensitivity				
AfDB No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
	control,		and	properly could clog drains and facilitate the							
	hazardous		members of	outbreak of sanitary related diseases such as							
	materials		the Local	cholera.							
	and		communities	Domestic and waste from the construction workers							
	resource		within the	and food vendors to the construction crew. For an							
	efficiency		project area	average of 20 workers at the construction phase, a							
				total of 10 kg/day domestic solid waste will be							
				generated per day using a per capita generation of							
				0.5 kg/day Also, a total BOD load of 0.8 kg/day will							
				be generated assuming a per capita production of							
				40g/day.							
OS4	Community	Traffic	Local	Transport of materials and equipment through	Likely	Direct	Short-term	Local	Medium	Medium [2]	Moderate [4]
	Health,	management	communities	communities and townships raises traffic/public					[2]		
	Safety and		near the	safety concerns. Broken-down, inappropriately							
	Security		project area	parked or slow-moving haulage/construction trucks							
			of influence	could lead to road accidents and traffic congestion							
				especially on busy roads. Locals may not be used to							
				truck traffic as the popular mode of transportation							
				is bicycles, motorcycles and tricycles.							

7.7.5 Cumulative Negative Impacts of the Project

The REWARD Project seeks to enhance climate resilience, agricultural productivity, and rural infrastructure within the Savelugu Municipality. Given the area's agrarian economy and limited industrialization, interventions occur under low development pressure (Savelugu MTDP, 2022–2025). This cumulative impact assessment (CIA) examines combined environmental and social effects of REWARD alongside existing and planned developments, focusing on additive and synergistic interactions.

Natural resources such as soils, rivers, forests, and pasturelands experience moderate pressure from bush burning, overgrazing, and illegal tree felling. However, large-scale agriculture and infrastructure remain minimal, constrained by low urbanization and limited funding. The municipality's cumulative environmental footprint is modest, with localized land degradation but overall stable ecological conditions, providing a sound baseline for REWARD implementation.

Key Development Drivers and Interactions

Agriculture

Agriculture dominates livelihoods in the district. Expansion of cultivation, especially under projects promoting improved irrigation and mechanization, presents potential cumulative pressures on soils and water resources. However, the majority of farms remain small-scale with rain-fed systems, and existing agro-processing uses low-technology, small-scale operations. Planned interventions by the Assembly emphasize sustainable agri-business and capacity building of smallholder farmers, which align with REWARD's objectives. Consequently, the cumulative interaction between REWARD's agricultural support and ongoing local programs is expected to be positive, enhancing productivity while promoting soil conservation and climate-smart practices.

Infrastructure

Infrastructure remains basic, with unpaved, often impassable rural roads. The Medium-Term Development Plan highlights underinvestment in transport, education, and health infrastructure. Planned works focus on minor road upgrades, market improvements, and small-scale public facilities, as shown in the table below. REWARD's support for feeder roads will complement municipal efforts, enhancing connectivity and market access without adding significant ecological stress.

Zonal Council	Community Problems	Development Needs and Aspirations	Location/Community
	Poor Road Conditions	Construction of an access bridge/culvert	Daboli,
	Dilapidated classroom block/Inadequate Educational Infrastructure	Provision of Educational Infrastructure	Sanzi,Yiwogu Sankpem,Langdoo yili
	No Residential Accommodation for Teachers	Residential Accommodation for Teachers	Nabogu,Kpendua
Pong Tamale	Limited access to Electricity	Extension of Electricity to community	Chahi Yapalsi,Pong Tamale.Wayaayo,Kpong
Tamaic	Inadequate Water/Boreholes	Construction of new boreholes, maintenance of existing ones and small town water projects	Kpendua,Boggu,Tindang,Tibali,K uldanali,Nakpkanzoo, Sanzi
	Rehabilitation of Community Market Structures	Provision of Market Structures	Zonal Council wide
	21. Poor environmental sanitation	Regular cleaning of the environment by Zoom Lion	Silimboma,Kpaling Yepalsi, Pong Tamale

Assessment of Cumulative Effects

Physical Environment

Potential cumulative effects on land, soil, and water are expected to be minor and localized. The district's limited industrial and infrastructural footprint reduces the risk of significant additive degradation. The introduction of REWARD's agricultural and water management interventions may lead to incremental land conversion and short-term sediment generation during construction. However, these are mitigated by the project's design emphasis on climate-smart practices and erosion control. Considering the absence of heavy industrial or mining activities, the cumulative impacts on air quality, hydrology, and noise environment are negligible.

Biological Environment

Cumulative effects on vegetation and biodiversity are minor. Although existing pressures include bush burning and charcoal production, these are diffused and community-driven. REWARD's interventions will likely reduce rather than exacerbate ecological strain by promoting sustainable land management under community-based planning. The incremental habitat modification from road and irrigation works is expected to be limited to disturbed lands and agricultural corridors.

Socio-economic Environment

At the social level, the additive impacts of REWARD and municipal initiatives are overwhelmingly beneficial. Improved agricultural productivity, employment during construction, and enhanced road access will raise local incomes and food security. Given that industrial activity remains low, competition for land and labour is minimal, reducing risks of social displacement. Potential negative cumulative effects, such as increased migration, gender disparities, or localized resource conflicts, are expected to be minor and manageable through participatory planning and equitable benefit distribution.

Future Development Scenarios

Savelugu is unlikely to face rapid industrialization or urban expansion soon. Future projects remain small-scale, emphasizing basic infrastructure and agriculture rather than extractive industries. Consequently, cumulative development pressures will remain low. REWARD, aligned with municipal sustainability goals, contributes positively to the overall environmental profile and demonstrates integrated, climate-resilient rural development.

Conclusion

The cumulative impact of the REWARD Project is minor and not significant. With few large-scale developments in the area, REWARD's synergy with local initiatives will deliver net positive outcomes including stronger livelihoods, improved land management, and enhanced infrastructure without exceeding environmental thresholds. Overall, the project is environmentally sustainable and socially beneficial within Savelugu's developmental context.

8.0 MITIGATION MEASURES

Mitigation and enhancement measures for the potential adverse impacts have been proposed in this section to ensure that the project impacts are managed within reasonable and acceptable limits. The general rules followed in designing the mitigation measures are listed below:

- Avoidance of major impacts: major impacts are impacts where an accepted limit or standard may be exceeded, or large magnitude impacts occur to highly valued/sensitive resources/receptors;
- Reduction of major and moderate impacts: moderate impacts are impacts within accepted limits
 and standards. Moderate impacts may cover a broad range, from a threshold below which the
 impact is minor, up to a level that might be just short of breaching an established (legal) limit; and
- Minor impacts occur where effects are experienced, but the impact magnitudes are sufficiently small and well within accepted standards, and/or the receptors are of low sensitivity/value.

The potential adverse impacts associated with the project will be managed using the mitigation hierarchy (**Section 7.1.3**, **Figure 7-2**), giving priority to avoidance whenever possible before minimization, repair and offset. Some mitigation measures have been considered as part of the project design, however, risks and impacts not mitigated through design can be mitigated to the barest minimum using the proposed measures below. Residual impacts are expected to be low or negligible post-mitigation and monitoring programmes will be instituted for confirmation.

8.1 Recommended Mitigation Measures for Identified Impacts

Table 8-1 provides a summary of the significant impacts, as per the evaluation. The application of the mitigation measures is expected to reduce both moderate and major adverse impacts identified to either negligible or minor residual impacts.

Table 8-1: Proposed Mitigation and Management Measures for Identified Impacts

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
Prepara	tory phase	1			
OS1	Environmental and Social Assessment	Poor assessment study of environmental and social risks and impacts	Project proponent (MoFA), environment, community	Major [9]	 The project will carry out detailed assessment of environmental and social risks and propose mitigation measures for identified moderate to major adverse impacts. The Project will select a qualified consultant to undertake the assessment studies.
OS5	Involuntary resettlement, land	Land related disputes	Farmers	Moderate [4]	Land will not be acquired for the project as it is donated by the chief of the Nakpanzoo community. The chief to sign the VLD forms
	acquisition, population displacement and compensation	Impact on livelihoods		Moderate [4]	 The Resettlement Action Plan (RAP) will provide an understanding of what impact subprojects will have on the thirty- three (33) project affected farmers. The RAP will propose changes that aim at avoiding or minimizing livelihood disruption and involuntary resettlement impacts for the affected farmers. The RAP will ensure the impacts are properly assessed and all Project-Affected-farmers (PAFs) are identified and their assets that are affected are recorded and valued for adequate compensation. The RAP will ensure identified PAFs and valued affected assets, are provided with adequate compensation packages whether in cash or kind based on the extent of displacement. The RAP will provide opportunity to address grievances, and provide support for resolution of grievances.
OS6	Biodiversity, renewable resources and ecosystem services	Destruction of vegetation and displacement of wildlife	Flora and Fauna	Moderate [4]	 Restrict vegetation clearance to the required area only and prohibit hunting of animals which may stray to the project area by providing temporary fences. This must be included in the contractor's bill of quantities and code of Conduct. Train contractor's E&S Officer on ESMP requirements.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					Develop a flora conservation plan for <i>Grewia carpinifolia</i> to ensure that they do not disappear from the project site.
Constru	ction phase				
OS2	Occupational health and safety (OHS) impacts and risks	Project Site incidents/accidents	All Project workforce, Vulnerable categories of workers, Women	Major [6]	 Good housekeeping around work area must be ensured to prevent slips, trips & falls. Only trained and competent workers should be allowed to carry out work and must be well briefed on safe working procedures. Appropriate work platforms and PPE must be used for specific tasks such as work at height. Mandatory and basic PPE including hardhat, hand gloves, safety goggles, HiVis and safety boots must be worn. Have accident and incident reporting form available to record accidents and near-misses The Project Contractor will implement and maintain an OHS management system taking into account specific risks associated with the project, legal requirements and duty of care. The Project Contractor will be responsible for ensuring that all affiliated sub-contractors comply with the OHS management system. The OHS management system will be in-line with recognized international best practice.
		Poor labour working conditions	All Project workforce, Vulnerable categories of workers, Women	Major [6]	 Provide all workers with signed contracted that are consistent with national labour laws Provide welfare facilities such as potable drinking water, shades, restrooms etc. for workers. Encourage frequent breaks and job-rotation to reduce impact of the weather on workers. Require workers to sign Code of Conduct and provide adequate training to both the workers and the communities

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					 Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. Establish an effective worker grievance redress mechanism.
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Women, Children	Major [6]	 Include in works contract clauses on mandatory and regular training for workers on required lawful conduct and legal consequences for failure to comply with laws on non-discrimination and GBV. Insert clause requiring contractors and consultants to cooperate with law enforcement agencies investigating cases of gender-based violence. A minimum requirement of female employment should be indicated in contract documents. Clauses prohibiting rape, defilement and other Gender based Violence as well as child and forced labour should be inserted into works contracts. Contact numbers of representative on the Grievance Redress Committee and GBV Service Providers should be pasted around the project site and within the immediate project zone Discuss issues of Gender Based Violence at daily Toolbox meetings Display on site posters prohibiting sexual exploitation and harassment.
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and contamination	Soil	Moderate [4]	 Landscape should be reinstated or regenerated to reflect its original general view before the project. All excavations and trenches should immediately be backfilled and compacted to its original state. Not undertake site clearance, piling, excavation and access road construction during the raining season to minimize erosion and runoff. Ensure that construction activities are restricted to designated work areas to avoid damage and disturbance outside of the site.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Air Pollution Water Pollution	Health of workers and members of the surrounding communities Water quality of water collected as ponds in the project area.	Moderate [4]	 In case of accidental/unintended spillage, immediately collect contaminated soil and stored as hazardous waste. Make available on site, all equipment and materials required to execute a clean-up. Utilize existing roads to access the site. Ensure that activities are confined to designated construction areas, limiting soil exposure and disturbance to the construction site only. Trucks and heavy machinery with a valid emission test pass certificate should only be allowed on the project site. Dust pollution must be reduced by ensuring that drivers do not speed especially on untarred roads. Suppress dust by watering dusty construction areas. Ensure the use of nose mask in dusty environment. Conduct regular maintenance on trucks to prevent oil leakages that could be washed together with sediment into nearby waterbodies Manage leaked oil by placing trays under trucks to collect leaked oil. Provide impervious storage area, especially for fuel and lubricant, hazardous waste, etc. Not store hazardous materials near natural drainage channels. Ensure that any temporary refuelling tanks are bunded. Have available on site, all equipment and materials necessary to execute clean up. Maintain logbook for water consumption. Progressively adopt less water consuming module cleaning methods. Adhere to agreed arrangements for the disposal of aqueous effluents. Proper handling of materials and wastes to prevent transport into water bodies. Avoid extensive land clearing, excavation, trenching etc. activities during heavy rainfall events to prevent runoff carrying contaminants to surface water (ponds in the project area)

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Noise and Vibration	Health and wellbeing of workers and members of communities close to the project area	Moderate [4]	 Obtaining water permits for ground water usage as required by Ghanaian law, WRC Act 522 (1996). Clean construction equipment away from surface waters. Monitor and record the volume of water used. Ensure water usage and disposal align with national legislation and, where applicable, international best practices, and track any deviations from the estimated water use. Develop and implement a groundwater quality monitoring program to closely monitor changes in aquifer water levels, groundwater quality, and availability. Unnecessary tooting of horn by truck drivers must be avoided. A noise assessment must be carried out for all heavy machinery prior to use at the site to ensure noise levels are in compliance with EPA's guidelines values. Noise should be kept to a minimum with hearing protection used as deemed necessary for workers. Earmuffs or earplugs are recommended for ear protection. The level of noise must be continuously assessed to keep it within acceptable limits. All equipment and tools must be checked for suitability for the task. All construction equipment and hand tools should be operated by trained, experienced and competent persons, and where required persons must produce operator's license upon request. Ensure the use of well serviced/maintained vehicles and other equipment with acceptable noise emission levels.
		Waste generation and Disposal	Health of members of the Local communities within the project area	Moderate [4]	 Provide silencers on all noise generating equipment. Ensure that contractor develops and implements a detailed Construction Waste Management Plan. Ensure that construction debris are collected from work sites to avoid blocking of drains and waterways. Waste bins must be provided and well labelled for waste segregation and disposal.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
OS4	Community Health,	Traffic Management	Local communities	Moderate [4]	 Only licensed waste management companies must be engaged to collect and dispose of waste collected from the site. Regular briefing or training on waste management must be provided to workers at the site. Have SOPs for managing hazardous and non-hazardous waste. The Highway Code must be strictly followed. Driver training must be
054	Community Health, Safety and Security	Traffic Management	Local communities near the project area of influence	Moderate [4]	 The Highway Code must be strictly followed. Driver training must be provided as part of induction training and permit to drive and transportation of materials to project site issued. Trained flagmen (to slow down traffic) or trained stop-go men (to halt traffic) must be used to ensure safety when trucks are leaving the project site. Stop-go men and flagmen must also wear high visibility vests and use approved stop-go signs or flags. Vehicles to be used on the project must provide maintenance records, and must also be inspected by a competent person before allowed on the project. Have checklists available to manage vehicle and equipment maintenance and management Arrangements must be made for truck drivers to ensure peak times are avoided for haulage of materials to site. Ensure that all trucks used are serviced regularly to maintain optimal performance and ensure safety. Identify safe parking areas off main roads to allow for unloading and long-term parking of vehicles. Have accident and incident reporting form to record accidents and near-misses.
		Visual / Aesthetic Impacts	Project community	Moderate [4]	 Maintain tidy construction sites (good housekeeping). Minimize area of land clearance beyond essential footprint. Locate temporary facilities at unobtrusive areas to reduce visibility.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Fire Outbreak	Vegetation, Project workforce and Local communities near the project area of influence	Moderate [4]	 Promptly rehabilitate disturbed areas post-construction. (grading, seeding). Ensure permanent structures (patios, sheds) use materials/colours that blend reasonably with the surroundings. Clear zones of land around the project site and other infrastructure should be created to prevent fires from spreading. These can be created by clearing vegetation or planting fire-resistant vegetation. There should be regular clearing of areas with dry vegetation to reduce the amount of flammable material available for a fire. Workers should designate areas for cooking and possible smoking to prevent fire from spreading in the likelihood of it happening. Access to water and other fire suppression equipment should be ensured, and workers should be trained on effective fire suppression techniques. Local communities should be educated about the dangers of bushfires,
		Public health issues	Local communities near the project area of influence	Moderate [4]	 the importance of safe disposal of debris, and the role of fire prevention in maintaining healthy ecosystem. Potable water tanks or containers could be used on the project site to keep water for drinking. Sexual harassment or violence on the project site will not be tolerated and project contractor should be made aware of such incidences to ensure that any complaints are addressed in accordance with the law. Undertake sexual health education programs for workers and also ensure they desist from irresponsible sexual behaviour during project implementation.
					Encourage handwashing after work and if possible, provide hand sanitizers to workers.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					 Encourage workers to get vaccinated. Provide information, instructions and trainings on STDs, drug abuse etc. to the workers to create awareness. Provide female and male condoms to the community and workers.
		Security Concerns	Local communities near the project area of influence	Minor [2]	 Sensitize local community on cultural tolerance and grievance mechanisms to prevent confrontations Migrant workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. The contractor should prioritize employing locals especially the youth who may be unemployed which can ultimately lead to unrest or other social vices.
		Risk of Drowning	Project workforce and Local communities near the project area of influence.	Moderate [4]	 Any dug out or borrowed pits should be fenced to prevent unsuspecting community members from falling and drowning in it. In situations where the burrowed pit will not be in use, it should be reclaimed. There will be pictorial signages mounted close to the pit to warn the community about the danger of drowning.
Operati	on phase				
OS2	Occupational health and safety (OHS) impacts and risks	Workplace incidents/accidents	Farm workers, Vulnerable categories of workers, Women	Moderate [4]	 Good housekeeping around farm area must be ensured to prevent slips, trips & falls. Only trained and competent farm workers should be allowed to carry out work on the farm and must be well briefed on safe working procedures. Farm owners should ensure they and their farm workers are always in their PPE's when working on the farm. E.g. wellington boots etc. Potable water tanks or containers could be used on farms to keep water for drinking instead of using empty containers/gallons of fertilizers and agro-chemicals that can pose health risk to farmers.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					Develop and ensure implementation of Pest Management Plan (PMP)
		Poor labour working conditions	Farm workers, Vulnerable categories of workers, Women	Moderate [4]	 Safe, clean, and comfortable housing should be provided for migrant farm workers, either on-site or in nearby communities, with consideration for their needs and cultural sensitivities. Provide all farm workers with signed contracts that are consistent with national labour laws. Encourage frequent breaks and job-rotation to reduce the impact of the hot weather on farm workers. Establish an effective farm worker grievance redress mechanism. Fair wages, working conditions, and contracts that comply with labour laws should be implemented so that labourers can benefit from fair labour practices. Hiring of locals for labour, skills training for migrant workers, and support for local businesses to create broader economic opportunities should be prioritized.
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Women	Moderate [4]	 Educate farm workers on SH and GBV issues and make them sign code of conduct. Offenders will be reported to the local law enforcement agencies and if found guilty punished to serve as deterrent to potential offenders. No discrimination based on gender, marital status, nationality, age, religion, or sexual orientation will be tolerated toward employees or job applicants.
		Child Labour	Children	Moderate [4]	 Children who spend time with their parents on the farm should not be allowed to do so at the expense of their education and well-being. Children under the working age of 15 should not be engaged in hazardous work on the farms.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and degradation Air Pollution	Health of farm workers and surrounding community members.	Moderate [4]	 Application of fertilizer will be controlled so that it does not lead to soil degradation. Education of farmers on proper application of fertilizer and pesticides to prevent abuse. Develop and ensure implementation of Pest Management Plan (PMP) After harvesting, crop residue comprising process residue (straw, husks, skins, trimmings, among others) and field residue (stalks and stubble/stems, leaves of crops) will be tilled into the soil to improve the soil structure and soil organic matter content. Farmers will be sensitised to adopt minimum tillage during planting seasons to reduce the susceptibility of the soil to erosion and hardpan formation associated with continuous ploughing at the same depth. Farmers will utilise cover crops at erosion-prone areas in sections. Practicing No-till or Low-till methods where crop residues are retained on the field or incorporated into the soil can help decompose the stubble naturally, reducing the need for stubble burning. Mobile, small-scale threshers can be used in place of manual threshing so as to reduce the amount of dust or rice chuff emitted into the atmosphere. Minimizing dust generation activities as much as possible especially during windy periods. Vehicle speed, particularly on untarred roads transporting farm produce and agric inputs to and from the farm will be strictly controlled to minimize dust generation.
		Water Pollution	Water quality of water which has gathered as ponds in the valley.	Moderate [4]	There will be proper timing in the application of fertilizers/herbicides and other agrochemicals considering the crop's nutrient needs and

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					soil conditions in order to maximize fertilizer uptake and minimize leaching and runoff. Develop and ensure implementation of Pest Management Plan (PMP) Provision of on-site sanitation facilities and encourage the farm workers to use it. Educate farm workers to avoid open defecation. Sediments traps will be designed and constructed within the farm lands to contain contaminated sediments which will later be harvested for producing blocks for building.
		Noise and Vibration	Health and wellbeing of workers and members of communities close to the project area	Moderate [4]	 Scare crows should be encouraged instead of the screaming sounds from farmers or labourers to scare away birds. The use of threshing machines with design specifications and operational adjustments that use soundproofing and vibration damping materials should be utilised during the harvesting periods in order to reduce noise and vibration to its barest minimum level. Ensure the use of well serviced/maintained vehicles and other equipment with acceptable noise emission levels when transporting farm produce and farmers from the farm. Provide silencers on all noise generating equipment.
		Solid waste generation and Disposal	Health of farm workers and the Local community.	Moderate [4]	 Rice husk has a high potential for the use as fuel. The project should take steps to identify potential investors that will process the husk to be used as fuel for boilers, in concrete production, or as a material for various industrial application. Farmers should be educated to use rice husk, straw, and other organic waste for composting which can eventually be used as fertilizer. There should be provision of adequate waste skips to collect empty containers of agrochemicals and fertilizers for disposal by licenced waste management company. Develop and ensure implementation of Pest Management Plan (PMP)

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					Good housekeeping should be encouraged on farms.
OS4	Community Health, Safety and Security	Traffic Management	Local communities	Minor [2]	 Drivers should exercise caution when driving through crowded areas such as markets. Installation of speed rumps to check speeding vehicles. Identify safe parking areas off main roads to allow for unloading and long-term parking of vehicles.
		Fire Outbreak	Rice farms, nearby vegetation, farm workers and local community.	Moderate [4]	 Clear zones of land around the rice fields and other infrastructure should be created to prevent fires from spreading. These can be created by clearing vegetation or planting fire-resistant vegetation. There should be regular clearing of areas with dry vegetation to reduce the amount of flammable material available for a fire. Farmers should designate areas for cooking and possibly smoking to prevent fire. Access to water and other fire suppression equipment should be ensured, and farmers should be trained on effective fire suppression techniques. The municipal fire service should train community members as fire guards to serve as the first point of contact when there is fire outbreak within the project area.
		Polluted Waterbodies	Farm workers and Local communities	Moderate [4]	 Educate farm workers to avoid open defecation. Sediments traps will be designed and constructed within the farm lands to contain contaminated sediments which will later be harvested for producing blocks for building. Potable water tanks or containers could be used on farms to keep water for drinking instead of using empty containers/gallons of fertilizers and agro-chemicals that can pose health risk to farmers.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Sexual Transmitted Diseases	Farm workers and Local communities	Moderate [4]	 Sexual harassment or violence on farms will not be tolerated and community leaders should be made aware of such incidences to ensure that any complaints are addressed in accordance with the law. Undertake sexual health education programs for farm workers and also ensure they desist from irresponsible sexual behaviour during project implementation.
		Security Concerns	Farm workers and local communities	Minor [2]	 Sensitize local community on cultural tolerance and grievance mechanisms at community durbars to prevent confrontations Migrant farm workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. Farm owners should prioritize employing locals into their farms especially the youth who may be unemployed which can ultimately lead to unrest or other social vices.
		Risk of Drowning	Farmers and local community members	Moderate [4]	 The community has proposed that the rain water collected in the borrow pit may be used as their source of water for watering their crops in the dry season. However, dug out or burrowed pits should be fenced to prevent unsuspecting community members from falling and drowning in it. In situations where the burrowed pit will not be in use, it should be reclaimed. There will be pictorial signages mounted close to the pit to warn the community about the danger of drowning.
		Flooding	Farmers, Community members, Flora and Fauna	Major [6]	 Educate farmers and community on early warning signs of flood. Discourage the siting of farms within or close to river beds. Collaborate with spatial planning and disaster management agencies, using disaster maps and systems, to stay away from flood-prone areas. Infrastructure for agricultural establishments should be constructed preferably on high grounds.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					Provide insurance cover for equipment and personnel

Table 8-2: Beneficial Impacts of the Project

No.	Beneficial Impact	Details of potential Project Impact						
1	Creation of job	Job opportunities for skilled, semi-skilled and unskilled labour will						
	opportunities	be created at the construction and operation phases as locals,						
		including women, will be recruited for short-term and long-term						
		jobs.						
2	Increased commerce	Agricultural productivity will increase quantitatively due to						
	and boost to local	increased access to mechanization services by rice farmers.						
	economy							
3	Food Security	Increase in production capacity coupled with availability of storag						
		facilities will make produce available all year round and improve						
		reliance on local agricultural produce and product. This will reduce						
		the importation of agricultural produce across borders and						
		improve food security.						
4	Adoption of good	The proposed project will involve the community and the local						
	agricultural practices	stakeholders throughout the project cycle equipping them with						
		knowledge and skills in agricultural practices.						
5	Technology transfer	Farmers will be exposed to new technologies for geo-mapping,						
		crop management, pest and disease management, processing, etc.						
		that were otherwise not known to them						

9.0 ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN

This section presents the Environmental and Social Management Plan (ESMP), **Table 9-1** that is designed to operationalize the environmental and social commitments presented in this ESIA report. The ESMP presents a set of management, mitigation and monitoring measures to be taken at different stages of the project implementation. It sets out record keeping required to ensure that mitigation measures and monitoring are effective and results duly communicated to stakeholders.

SAL Consult Ltd

Ministry of Food and Agriculture, Ghana

Table 9-1: Environmental and Social Management Plan

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
OS1	Environmental and Social Assessment	Poor assessment of environmental and social risks and impacts	Unidentified risks and impacts could prevent or stall project implementation. Selection of unqualified persons for assessment studies	proponent	Major [9]	 Detailed and high quality assessment of environmental and social risks Selection of qualified ESIA consultant Environmental permit acquisition 	• PIU	358,000/33,966 35,000/3,321	Lender	Project E&S Instruments (ESIA, RAP, SEP, PMP) EPA Permit	E&S Report Permit	Apr – Sep 2025 31st Oct 2025
OS5	Involuntary resettlement, land acquisition, population displacement and compensation	Land related disputes	Proposed site is owned by is owned by the chief of Nakpanzoo.	Farmers; Community	Moderate [4]	 Acquire signed Voluntary Land Donation (VLD) forms Provide training on completion of VLD forms 		2,000/190 2,500/237	Lender	Signed VLD	Signed VLD	Sep 2025
		Impact on livelihoods	The project activities could restrict thirty three (33) farmers access to lands that were otherwise used for farming.	Project affected Farmers	Moderate [4]	 Develop a Resettlement Action Plan (RAP)/ Livelihood Restoration Plan Implement the Resettlement Action Plan (RAP) 	RAP ConsultantPIU	80,000/7,590 75,690/7,181	PIU/Lender Lender	RAP Report RAP Implementat ion report	RAP Report RAP Implementat ion audit	Sep 2025 Qtr 1, 2026
						Build PIU's capacity for RAP implementation	RAP Consultant	20,000/1,900	PIU/Lender	Training for RAP implementat ion team	Training reports	Qtr 1, 2026
OS6	Biodiversity, renewable resources and ecosystem services	Destruction of vegetation and displacement of wildlife	The project site is an already disturbed area due to previous human activities such as farming. The floristic analysis conducted identified <i>Grewia carpinifolia</i> which is of national conservation concern on the site. Aside that, none of the other species identified at the site are of conservation concern according to the Forest Reserves of Ghana Information Exhibitor	Flora and Fauna	Moderate [4]	 Restrict vegetation clearance to the required area only and prohibit hunting of animals which may stray to the project area by providing temporary fences. This must be included in the contractor's bill of quantities and code of Conduct. Train contractor's E&S Officer on ESMP requirements. Develop a flora conservation plan for <i>Grewia carpinifolia</i> to ensure that they do not disappear from the project site. 	• PIU	20,000/1,900	PIU	Installation of Fence Training for E&S officer	Physical inspection Training reports	Before construction Before construction

SAL Consult Limited

Ministry of Food and Agriculture, Ghana

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
			Site clearing will not lead to any major destruction of biodiversity of significant importance.									
Constr	uction Phase											
OS 2	Labour conditions, health and safety	Project Site incidents/accidents	Project site accidents/incidents and animal/insect threat/bites	All Project workforce, Vulnerable categories of workers, Women	Major [6]	Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training	Project Contractor	50,000/4,744	PIU	Records and purchase of PPEs, training on PPE use, house-keeping, emergency response etc.	Review of CESMP OHS audits	Before construction During construction
		Poor labour working conditions	Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions. Workers could face issues of discrimination, forced labour, child labour, freedom of association and collective bargaining, lack of or ineffective worker grievance redress mechanisms	workforce, Vulnerable categories of workers, Women	Major [6]	 Adhere to national labour laws as provided in the Labour Act of 2003 (Act 651) and international best practice such as provisions of AfDB ISS (2023) OS 2 on Labour and Working Conditions Specific considerations should include the following: Provide all workers with signed contracts Provide welfare facilities as required. Encourage frequent breaks and job-rotation to reduce impact of the hot weather on workers. Require workers to sign Code of Conduct Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. 		120,000/11,385	PIU	Signed contract, welfare facilities, Grievance redress mechanism/ records	E&S audits	During construction

SAL Consult Limited

Ministry of Food and Agriculture, Ghana

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
							Provide adequate training for workers on safety, GBV, SEA/SH, child labour/human rights, social norms. Establish an effective worker grievance redress mechanism						
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Presence of workers and increase in incidents of rape, defilement, child molestation and GBV.	Women, Children	Major [6]		Include the requirements of policies on GBV, SEA/SH, Child Labour and Human Rights in the contractor's Code of Conduct Provide training for workers on required lawful conduct and legal consequences for failure to comply with laws on non-discrimination and GBV Insert clause requiring contractors and consultants to cooperate with law enforcement agencies investigating cases of genderbased violence A minimum requirement of female employment should be indicated in contract documents Contact numbers of representative on the Grievance Redress Committee and GBV Service Providers should be pasted around the project site and within the immediate project zone Discuss issues of Gender Based Violence at daily Toolbox meetings Display on site posters prohibiting sexual exploitation and	Project Contractor	80,000/7,590	PIU	Clauses on GBV, SEA/SH, Child Labour and Human Rights in the contractor's Code of Conduct	Review of contractor's code of conduct	During construction
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and Contamination	Excavation for foundation of structures could lead to soil erosion and creation of gullies through runoff especially in the rainy season		Moderate [4]	•	Management Plan	Contractor	50,000/4,744	PIU/Lender	Erosion Manage- ment Plan Sediment traps	Inspection/ review Inspection	Before construction During construction
			Soil contamination could also occur from			•	Train contractor's E&S Officer on ESMP requirements	PIU	20,000/1,898		Training on erosion	Training records	During construction

SAL Consult Limited

Ministry of Food and Agriculture, Ghana

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
No.		Air Pollution	inappropriate disposal of waste oil, spilled oil during machinery operation and maintenance as well as fuel storage sites and leaks from vehicle refuelling Emission of fumes and dust from transport of materials especially on untarred routes to project site. Baseline air quality data (PM _{2.5} – 30μg/m³, PM ₁₀ – 109μg/m³, NO ₂ , SO ₂ and CO were all below the minimum detection limit of 0.06 mg/m3 at the time of sampling. This shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds except for PM ₁₀ whose higher value could be attributed to high coarse particulate pollution, likely arising from mechanical disturbances during farming, vehicular movement, and possibly wind-driven dust due to	members of the surrounding communities	Moderate [4]	 Trucks and heavy machinery with a valid emission test pass certificate should only be allowed on the project site. Dust pollution must be reduced by ensuring that drivers do not speed especially on untarred roads. Suppress dust by watering dusty construction areas. Ensure the use of nose mask in dusty environment. 		60,000/5,693	PIU/ Supervising Engineer	Indicator manage- ment Valid emission test certificate Speed limit signage Wet road surfaces Complaints/ grievances	Inspection	During construction
		Water Pollution	the site's open, dry landscape. Sediment and waste oil transport into nearby water bodies. Domestic waste from the construction workers and food vendors providing services to the construction crew.		Moderate [4]	 Undertake construction in the dry season Carry out maintenance activities away from water bodies Install sediment traps Educate workers on the importance of waste management. 		60,000/5,693 10,000/949	PIU/ Supervising Engineer	Sediment traps Toolbox exercises	Inspection Toolbox records	During construction

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
		Noise and Vibration	Operation of construction equipment, movement of haulage vehicles and tooting of horns.	Health of project workforce and members of the surrounding communities		•	Ensure construction activities are carried out during the day. Provide and enforce wearing of hearing protection by workers Sensitize workers on effects of noise pollution Ensure the use of well serviced/maintained vehicles and other equipment with acceptable	Project Contractor	20,000/1,898	PIU/ Supervising Engineer	Noise emission levels Complaints/ grievances	Noise monitoring report Records of complaints/ grievances	During construction
		Waste generation and Disposal	steel/metal, packaging materials, plastic pieces,	workforce and members of the		•	Ensure that contractor develops and implements a detailed Construction Waste Management Plan. Ensure efficiency in the use of materials. Reuse materials such as pieces of wood, and metals. Recycle scrap metal Ensure collection and proper disposal of construction debris Provide adequate waste bins for waste collection and segregation Sensitize workers on waste management Develop SOPs for managing hazardous and non-hazardous	Project Contractor	100,000/9,488	PIU/ Supervising Engineer	Inventory of waste generated/ Disposed of	Inspection/ review of records/ inventory	During construction
OS4	Community Health, Safety and Security	Traffic Management			Moderate [4]	•	waste. Avoid transportation of materials and workers during peak hours Train drivers on and ensure adherence to the Highway Code Ensure regular maintenance of vehicles Use flagmen and designated parking areas for safety onsite	Project Contractor	50,000/4,744	PIU/ Supervising Engineer	Records of traffic incident and accidents Community complaints/ grievances	Review/ inspection of records	During construction

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
		Visual / Aesthetic Impacts	stockpiles, temporary work	Local communities (Nakpanzoo), commuters.	Moderate [4]	 Maintain tidy construction sites (good housekeeping). Minimize area of land clearance beyond essential footprint. Locate temporary facilities at unobtrusive areas to reduce visibility. Promptly rehabilitate disturbed areas post-construction. (grading, seeding). Ensure permanent structures (patios, sheds) use materials/colours that blend reasonably with the surroundings. 	• Contractor • PIU	20,000/1,898	PIU Lender	Site tidiness. Area cleared. Community feedback (via GRM).	Site Inspections , Photograp hic records	During construction
		Fire Outbreak	Fire outbreaks from negligence of workers or the community burning refuse, game hunting and workers not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property.	Project workforce and Local communities near the project	Moderate [4]			50,000/4,744	PIU/ Supervising Engineer	Records of fire incidence Training of fire safety and risk	Review/ inspection of records	During construction
		Public Health Issues	Pollution of local water bodies will adversely affect the health of users. Sexual relations between workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	communities near the project	Moderate [3]	 Potable water tanks or containers could be used on the project site to keep water for drinking. Sexual harassment or violence on the project site will not be tolerated and project contractor should be made aware of such incidences to ensure that any complaints are addressed in accordance with the law. Undertake sexual health education programs for workers and also ensure they desist from irresponsible sexual behaviour during project implementation. 		60,000/5,693	PIU/ Supervising Engineer	Potable water tanks on site Records of sensitization of workers on GBV/SH Availability of condoms in washrooms		During construction

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
							Encourage handwashing after work and if possible provide hand sanitizers to workers. Encourage workers to get vaccinated. Provide information, instructions and trainings on STDs, drug abuse etc. to the workers to create awareness. Provide female and male condoms to the community and workers.				Availability of hand washing sinks/basins and sanitizers on site	Inspection	
		Security Concerns	Violent behaviour and confrontations between workers and locals. Workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over illicit sexual affairs, child labour, drunk driving, accidents and destruction of property.	communities near the project	Minor [2]	•	Sensitize local community on cultural tolerance and grievance mechanisms to prevent confrontations Migrant workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. The contractor should prioritize employing locals especially the youth who may be unemployed which can ultimately lead to unrest or other social vices.	Project Contractor	30,000/2,846	PIU	Community meetings Toolbox exercises Number of locally employed workers	Inspection of community meeting minutes Review of toolbox records Inspection of records of locally employed workers	During construction
		Risk of Drowning	Any borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for workers especially contract staff who are not familiar with the local terrain. Children who may play around the sites and unsuspecting community members may also be at risk of drowning especially when it rains and the place get flooded. It	workforce and Local communities near the project area of influence	Moderate [4]	•	Fence dug outs or borrow pits to prevent drowning. Provide warning signage at borrow pit sites. Sensitize community members on risk of drowning.	Project Contractor	100,000/9,488	PIU	Availability of fence and signage Records of drowning incidents/ac cidents Records of community sensitization programmes	Inspection	During construction

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
			must be noted however,										
			that the specific locations										
			for the borrow pits are yet										
			to be determined by the										
			project contractor and that										
			will be done before work										
			commences.										
Opera	tion Stage		<u>, </u>			_							
OS2	Labour conditions, health	Farm	Farm accidents/incidents	All Farm workers,	Moderate [4]	•	Develop and implement an	Municipal MoFA/	300,000/28,463	Regional	Records of	Review of	During
	and safety	incidents/accidents	and animal/insect	Vulnerable			Occupational, Health and Safety	Assembly		MoFA	training on	ESMP	operation
			threat/bites	categories of			Management Plan that covers at a				PPE use,		
				workers, Women			minimum good housekeeping,				house-		
							provision and use of PPE,				keeping,	OHS audits	
							incident/accident reporting and				emergency		
							investigation, emergency response				response		
							and training				etc.		
						•	Training and sensitization of						
							farmers on the use of PPE, farm						
							implements and agro-chemicals						
		Poor labour	Lack of employment	All Project	Moderate [4]	•	Adhere to national labour laws as	Municipal MoFA /	200,000/18,975	Regional	Number of	Review of	During
		working conditions	contracts could lead to	workforce,			provided in the Labour Act of 2003	Department of		MoFA	labour	records	operation
			farm workers being paid	Vulnerable			(Act 651) and international best	Community			related		
			rates below the stipulated	categories of			practice such as provisions of AfDB	Development			complaints		
			national minimum wage or	workers, Women			ISS (2023) OS 2 on Labour and				and		
			work under poor				Working Conditions				grievances		
			conditions. Farm workers			•	Specific considerations should						
			could be exposed to				include the following:						
			discrimination, forced and			-	Provide all workers with signed						
			child labour, restriction of				contracts						
			freedom of association and			-	Provide welfare facilities as						
			collective bargaining, non-				required.						
			existent or ineffective farm			-	Encourage frequent breaks and						
			worker grievance redress				job-rotation to reduce impact of						
			mechanism.				the hot weather on workers.						
						-	Require workers to sign Code of						
							Conduct						
						-	Develop policies against						
							discrimination, forced and child						
							labour, sexual harassment and all						
							forms of abuse including restriction						
							of right to unionize or freedom of						
							speech.						

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
						 Provide adequate training for farm workers on safety, GBV, SEA/SH, child labour/human rights, social norms. Establish an effective grievance redress mechanism for farm workers 						
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Presence of migrant farm workers could increase incidents of rape, defilement and GBV.	Women	Moderate [4]	for farm workers on required lawful conduct, access to GBV	Municipal MoFA/ Department of Community Development	100,000/9,488	Regional MoFA	Number of recorded incidents of GBV/SH cases	Review of records	During operation
		Child Labour	Employment and deployment of Children under the working age at the expense of their education and exposure to hazards that endanger their health and wellbeing.	Children	Moderate [4]	children under age 15 on farms. • Ensure children who spend time	Municipal MoFA/ Department of Community Development	50,000/4,744	Regional MoFA	Number of recorded incidents of child labour cases	Review of records	During operation
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and degradation	Abuse of fertilizer use could lead to soil degradation. Leaving farmlands bare especially after harvesting could expose the soil to erosion.	Soil	Moderate [4]	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management.	Municipal MoFA	100,000/9,488	Regional MoFA	Training of farmers on soil, water and nutrient management	Inspection/ review	During operation
		Air Pollution	Use of farm machinery, clearing of dry lands and emission of fumes/dust from tricycles or motorcycles conveying farmers and farm produce especially on untarred routes from farms are some of the activities that have the potential of affecting the air quality	workers and surrounding community	Moderate [4]	 Practicing No-till or Low-till methods where crop residues are retained on the field or incorporated into the soil can help decompose the stubble naturally, reducing the need for stubble burning. Mobile, small-scale threshers can be used in place of manual threshing so as to reduce the 	Municipal MoFA	100,000/9,488	Regional MoFA	Training of farmers on good farming practices	Inspection of training records	During Operation

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
			within the project area. Stubble burning to prepare the field for the next planting season can also affect the air quality within the project area. Baseline air quality data (PM _{2.5} – 30µg/m³, PM ₁₀ – 109µg/m³, NO ₂ , SO ₂ and CO were all below the minimum detection limit of 0.06 mg/m3 at the time of sampling. This shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds except for PM ₁₀ whose higher value could be attributed to high coarse particulate pollution, likely arising from mechanical disturbances during farming, vehicular movement, and possibly wind-driven dust due to the site's open, dry			amount of dust or rice chuff emitted into the atmosphere. Minimizing dust generation activities as much as possible especially during windy periods. Vehicle speed, particularly on untarred roads transporting farm produce and agric inputs to and from the farm will be strictly controlled to minimize dust generation.						
		Water Pollution	excess fertilizers and other	gathered as	Moderate [4]	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management. There will be proper timing in the application of fertilizers/herbicides and other agrochemicals considering the crop's nutrient needs and soil conditions in order to maximize fertilizer uptake and minimize leaching and runoff. Implement Pest Management Plan (PMP)	Municipal MoFA	300,000/28,463	Regional MoFA	Training of farmers on good farming practices	Inspection	During operation

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
						•	Provision of on-site sanitation facilities and encourage the farm workers to use it. Educate farm workers to avoid open defecation. Sediments traps will be designed and constructed within the farm lands to contain contaminated sediments which will later be harvested for producing blocks for building.						
		Noise and Vibration	Noise from activities like tilling the land for the next planting season, threshing the rice after cultivating and screaming sounds from farmers or labourers to scare away birds can all generate noise. Tricycles and motorbikes conveying farmers and farm produce to the milling factories or markets could generate some noise including the sounds from tooting horns.	and members of communities close to the	Moderate [4]	•	Scare crows should be encouraged instead of the screaming sounds from farmers or labourers to scare away birds.	Municipal MoFA	50,000/4,744	Regional MoFA	Sensitization of farmers	MoFA participation in community engagement meetings	Throughout the operational phase
		Solid waste generation and disposal	waste, i.e. empty containers of	Health of farm workers and the Local community.		•	Provide education to farmers on the MoFA extension guide on compost production using rice husk, straw, and other organic waste. Provide adequate waste skips to collect empty containers of agrochemicals and fertilizers for disposal by a licenced waste management company. Good housekeeping should be encouraged on farms. Implement Pest Management Plan (PMP)	Municipal MoFA	75,000/7,116	Regional MoFA	Sensitization of farmers	MoFA participation in community engagement meetings	Throughout the operational phase

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
OS4	Community Health Safety and Security	Fire Outbreak	Fire outbreaks from negligence of farm workers and community members, burning refuse, game hunting, cooking and not properly extinguishing stubs of cigarette. These fires could spread to adjoining farms causing injuries to persons and destruction of property.	nearby vegetation, farm workers and local community.	Moderate [4]	 Create fire belts to prevent spread of fire into the active working areas. Sensitize farm workers and community on the dangers of bushfires Store flammable materials away from fire sources Designate cooking and smoking areas on farms. Provide fire-fighting equipment onsite Train farm workers on fire fighting and where applicable include community fire volunteers 	•	100,000/9,488	Regional MoFA	Sensitization of farmers	Participation in community engagement meetings by MoFA/GNFS and NADMO.	Throughout the operational phase
		Traffic Management	Transportation of farmers and farm produce through communities raises traffic/public safety concerns.		Minor [2]	 Drivers should exercise caution when driving through crowded areas such as markets. Installation of speed rumps to check speeding vehicles. Identify safe parking areas off main roads to allow for unloading and long-term parking of vehicles. 	MoFA/Assembly	50,000/4,744	PIU/Supervisi ng Engineer	Records of traffic incident and accidents Community complaints/ grievances	MoFA and Assembly participation in community engagement meetings	Throughout the operational phase
		Security Concern	migrant farm workers and locals. Farm workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over sexual affairs, child labour, drunk driving, accidents and destruction of property.	and Local communities	Minor [2]	 Sensitize local community on cultural tolerance and grievance mechanisms at community durbars to prevent confrontations Migrant farm workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. Farm owners should prioritize employing locals into their farms especially the youth who may be unemployed which can ultimately lead to unrest or other social vices. 		30,000/2,846	PIU/Supervisi ng Engineer	accidents Community complaints/ grievances	MoFA and Assembly participation in community engagement meetings	operational phase
		Polluted Waterbodies	Pollution of local water bodies from contaminated sediments and run-off will adversely affect the health of community members.	and Local communities	Moderate [4]	 Provide education to farmers on the MoFA extension guide on soil, water and nutrient management. Educate farm workers to avoid open defecation. 	Municipal MoFA	50,000/4,744	Regional MoFA	Sensitization of farmers	MoFA participation in community	Throughout the operational phase

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
											engagement meetings	
		Sexual Transmitted Diseases	Sexual relations between migrant farm workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.		Moderate [4]	Undertake sexual health education programs for farm workers to desist from irresponsible sexual behaviour.	-	50,000/4,744	Regional MoFA	Sensitization of farmers	Participation in community engagement by MoFA and the Municipal Health Directorate.	Throughout the operational phase
		Flooding	implementation could be	Farmers, Local community, Flora and Fauna	Major [6]	 Educate farmers and community on early warning signs of flood. Discourage the siting of farms within or close to river beds. Collaborate with spatial planning and disaster management agencies, using disaster maps and systems, to stay away from flood-prone areas. Infrastructure for agricultural establishments should be constructed preferably on high grounds. Sensitive farmers on the benefits of insurance cover for equipment and personnel. 	DMO	150,000/14,231	Regional MoFA	Sensitization of farmers	Participation in community engagement meetings by MoFA, the Assembly and NADMO.	Throughout the operational phase
		Risk of Drowning	Any borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for unsuspecting community members in the project area especially children.	Local community	Moderate [4]	 Maintenance of dug outs or borrow pits fence to prevent drowning. Provide and replace warning signage at borrow pit sites when necessary. Sensitize community members on risk of drowning 		50,000/4,744	Regional MoFA	Sensitization of community members/ farmers	Participation in community engagement meetings by MoFA.	Throughout the operational phase

AfDB No.	AfDB OS Description	Potential Impact/	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
OS2	Occupational health and safety (OHS) impacts and risks	Project Site incidents/accidents	Project site accidents/incidents and animal/insect threat/bites	All Project workforce, Vulnerable categories of workers, Women		Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training	Project Contractor	50,000/4,744	CIA	Records and purchase of PPEs, training on PPE use, house-keeping, emergency response etc.	Review of ESMP OHS audits	Immediately after construction
OS3	Resource Efficiency and Pollution Prevention and Management	Waste generation and Disposal	project site, construction debris, pieces of steel/metal, packaging materials, plastic pieces, human waste etc. if not	members of the Local communities		 Ensure efficiency in the use of materials. Reuse materials such as pieces of wood, and metals. Recycle scrap metal Ensure collection and proper disposal of construction debris Provide adequate waste bins for waste collection and segregation Sensitize workers on waste management Develop SOPs for managing hazardous and non-hazardous waste. Develop and ensure implementation of Pest Management Plan (PMP) 	Project Contractor	120,000/11,385	PIU	Inventory of waste generated/ Disposed of	Inspection/ review of records/ inventory	Immediately after construction
OS4	Community Health and Safety	Traffic Management	Transport of materials and equipment to and from the project site through communities and townships raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage/construction trucks could lead to road accidents and traffic	communities	Moderate [4]	 Avoid transportation of materials and workers during peak hours Train drivers on and ensure adherence to the Highway Code Ensure regular maintenance of vehicles Use flagmen and designated parking areas for safety onsite. 	Project Contractor	50,000/4,744	PIU	Records of traffic incident and accidents Community complaints/ grievances	Review/ inspection of records	Immediately after construction

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementation
			congestion especially on busy roads.									

9.1 ESMP Implementation

9.1.1 Institutional Arrangement and Responsibilities

The institutional arrangement identifies the relevant institutions and actors involved with the implementation of the ESMP, their roles and responsibilities. The main institutions or actors concerned with the implementation of the Project and the ESMP related activities are provided in **Table 9-2**. The ESMP implementation activities will be under the overall guidance of the PIU.

 Table 9-2:
 Roles and Responsibilities of Key Actors

Key Actors /	Description of Key Roles/Responsibilities	Duration	Reporting
Institutions			
PIU	 Responsible for project implementation in general. Have the overall responsibility to ensure that the project implements the construction phase management and monitoring requirements provided in the ESMP. Responsible for grievance redress procedure and its functioning and effectiveness of other litigation avoidance measures. Oversee sensitization and awareness programmes. Grievance Redress 	Throughout project implementation	Monthly
Ministry of	Project planning and design	Preparatory and	Quarterly
Food and	Payment of compensations to PAPs, if any	construction	
Agriculture	Management of contract award	phases	
	Compliance monitoring		
	Grievance redress		
EPA	Issuing of environmental permit upon review	Throughout	Annually
	and approval of ESIA	project	
	Adhoc monitoring of the sub project to ensure	implementation	
	compliance with conditions of the		
Savelugu	Environmental Permit.Adhoc monitoring of project during the	Throughout	Annually
Municipal	construction phase	project	Aillually
Assembly	Monitoring facilities during the operational	implementation	
Assembly	phase of the project to	Implementation	
	ensure that it is working properly and help		
	resolve operational phase challenges		
	Grievance Redress		

Key Actors / Institutions	Description of Key Roles/Responsibilities	Duration	Reporting
Project Consultant and Safeguards Specialist	 Ensure that project execution meets specified environmental, social, health and safety guidelines contained in the contract documents and ESMP Issue site instructions to Contractors to ensure environmental and social mitigation measures are implemented by contractors Grievance Redress 	Duration of the Preparatory and Construction phases	As required
Works Contractors /Sub Contractors	 Contractors for the civil works will be responsible for construction and installations under the project according to project specifications and designs. Contractors are responsible for reinstatement of all damaged properties. Contractors are responsible for implementation of the construction phase mitigation measures provided in the ESMP Responsible for presentation of monthly monitoring report to the PIU Responsible for remedying defects committed during construction 	Construction phase	Monthly
Grievance Redress Committee	To receive and find solutions to grievances	Preparatory and construction phases	Monthly

9.2 Monitoring and Reporting

At the project implementation stage, monitoring will be done to confirm the effectiveness of impact management, including the degree of success in implementing mitigation measures. During construction works, checks, reviews and inspections will be carried out to assess compliance with permit conditions. Monitoring will be done by the relevant institutions, the PIU, Agric Department, EPA, Savelugu Municipal Assembly, Fire Service etc. A summary of impacts, mitigation, management and monitoring measures to be implemented is captured in **Table 9-3**.

E&S Monthly monitoring reports will be prepared by the works contractor and submitted to the PIU, EPA and Assembly. The E&S monthly monitoring reports will serve as the basis for EPA's compliance monitoring in line with the permit conditions, and verification of other environmental and social safeguard commitments.

A construction completion report, which is a compilation of outcomes of the monitoring activities, in compliance with EPA's permit conditions and for the records of the Municipal Assembly, will be prepared. The completion report will form the basis for EPA's final monitoring for project completion

and closure. Also, PIU will prepare E&S monthly monitoring reports and share with the lenders to show the extent of compliance with E&S requirements of the EPA and the Bank for the construction period.

9.3 Annual E&S Compliance Audits of the Project and Cost

The Annual Environmental and Social Performance Audit (ESPA) meets AfDB's OSS requirements. The project having a duration of 5 years, 5 audits will be carried out, including one audit per year. These audits will be carried out by an independent consultant who has not carried out any activity under the project. The terms of reference of the Audit as well as each audit report will be submitted to AfDB for review and approval. The PIU will recruit an independent consultant who will be responsible for carrying out annual environmental and social compliance audits of the sub-project.

It should be noted that the annual audit will concern the entire project, therefore the cost as shown below will cover the consideration of the entire project. Also, the cost of an annual audit for both ESIA and RAP is shown in the table below.

Cost of implementing environmental and social compliance audits

	Duration	Materials required for monitoring	No. of audits	Estimated cost of an annual audit (USD)	Total amount (USD)
ESPA	Once a year	Field vehicle	5	10,000	50,000
RAP Completion Audit	Once	Field vehicle	1	7,000	7,000
TOTAL (for 5	57,000				

Table 9-3: Environmental and Social Monitoring Plan

No.	Potential	Monitoring Indicators/Means of	Monitoring Site	Frequency	Responsibility	Cost Estimate/ Year
NO.	Environmental and		Widnitoring Site	Frequency		
		verification			(Implementation/	GHS (USD)
	Social Impacts				Monitoring)	
CONS	STRUCTION PHASE			T	T	T
1	Project site	Records of accidents, incidents and	 Nakpanzoo valley 	Monthly	PIU Environmental	52,700 (5,000)
	accidents/incidents	near misses.			and Social	
		Records of PPE disbursed			Safeguards	
		Housekeeping			Specialists	
2	Poor labour working	Availability of copies of signed	Nakpanzoo valley	Quarterly	PIU Environmental	31,620 (3,000)
	conditions	contracts	construction site		and Social	
		Human Resource Management			Safeguards	
		Plan/Recruitment Policy			Specialists	
		Complaints lodged by workers				
3	Soil impacts and	Observable change in turbidity of	Nakpanzoo valley	Monthly	PIU Environmental	42,160 (4,000)
	sediment transport	water in drains or water bodies	construction site and		Safeguards	
		Observable oil sheen in drain	Immediate environs		Specialist	
		Observation of rills/gullies				
4	Air and Noise Pollution	Number of complaints by community	Nakpanzoo valley	Monthly	PIU Environmental	52,700 (5,000)
		members/workers	construction site and		Safeguards	
			Immediate environs		Specialist	
5	Waste generation and	Number of mobile toilets and dustbins	Nakpanzoo valley	Weekly	PIU Environmental	26,245 (2,490)
	inefficient	provided on site	construction site and	,	Safeguards	
	management	Cleanliness of site/housekeeping	Immediate environs		Specialist	
		Odour			-1	
		Presence of human waste on site				
		Complaints by workers/community				
		members				
		members				

No.	Potential	Monitoring Indicators/Means of	Monitoring Site	Frequency	Responsibility	Cost Estimate/ Year
	Environmental and	verification			(Implementation/	GHS (USD)
	Social Impacts				Monitoring)	
6	Traffic accident	Grievance records	Nakpanzoo valley and	Monthly	PIU Environmental	52,700 (5,000)
	risks/Public safety	Traffic related incidents/accidents	Immediate environs		and Social	
	concerns	Records of accidents, incidents and			Safeguards	
		near misses.			Specialists	
7	Visual / Aesthetic	Site tidiness.	Charia and Sing valley	Monthly	PIU Environmental	5,375 (510)
	Impacts	Area cleared.	farms and immediate		and Social	
		Community feedback (via GRM).	environs		Safeguards	
					Specialists	
8	Fire outbreaks	Fire related incidents/accidents	Nakpanzoo valley and	Monthly	PIU Environmental	52,700 (5,000)
		Records of fire incidents and near	Immediate environs		and Social	
		misses.			Safeguards	
		Number of functional fire			Specialists	
		extinguishers onsite				
9	Public health issues	Number of sensitization campaigns	Nakpanzoo valley	Monthly	PIU Environmental	47,430 (4,500)
		Number of condoms distributed to	construction site and		and Social	
		Contractor's staff in a month	immediate environs		Safeguards	
		Number of STD cases reported to local			Specialists	
		health facilities involving encounters				
		with Contractor's staff				
10	Security and SH/GBV	Number of conflicts/cases reported to	Nakpanzoo valley	Monthly	PIU Environmental	36,890 (3,500)
	concerns	the Grievance Redress	construction site and		and Social	
		Committee/Community Liaison	immediate environs		Safeguards	
		Officer			Specialists	
		Number of conflicts/cases dealt with				
		by the Grievance Redress Committee				

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification • Number of crimes such as theft,	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
		defilement and rape reported, investigated, and concluded by the police involving the Contractor's workers				
Sub-1						400,520 (38,000)
1	Farm accidents/incidents	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Nakpanzoo valley Farm	Monthly	Municipal MoFA Extension officers/ Regional MoFA	31,620 (3,000)
2	Poor labour working conditions	 Availability of copies of signed contracts Complaints lodged by farm hands and other workers 	Nakpanzoo valley Farm	Monthly	Municipal MoFA Extension officers/ Regional MoFA	42,160(4,000)
3	Soil impacts and sediment transport	 Observable change in turbidity of water in drains or water bodies Observable oil sheen in drain Observation of rills/gullies 	Nakpanzoo valley Farm and immediate environs	Monthly	Municipal MoFA Extension officers/ Regional MoFA	52,700 (5,000)
4	Air and Noise Pollution	Number of complaints by community members/farmhands	Nakpanzoo valley Farm and community	Monthly	Municipal MoFA Extension officers/ Regional MoFA	31,620 (3,000)
5	Waste generation and inefficient management	 Presence of toilet facilities and number dustbins provided on site Cleanliness of site/housekeeping Odour 	Nakpanzoo valley Farm and immediate environs	Weekly	Municipal MoFA Extension officers/ Regional MoFA	52,700 (5,000)

No.	Potential	Monitoring Indicators/Means of	Monitoring Site	Frequency	Responsibility	Cost Estimate/ Year
	Environmental and	verification			(Implementation/	GHS (USD)
	Social Impacts				Monitoring)	
		Presence of human waste on site				
		• Complaints by farm				
		workers/community members				
6	Traffic accident	Grievance records	 Nakpanzoo valley 	Monthly	Municipal MoFA	52,700 (5,000)
	risks/Community	Traffic related incidents/accidents	Farm/ community and		Extension officers/	
	safety concerns	Records of all accidents, incidents and	immediate environs		Regional MoFA	
		near misses.				
7	Fire outbreaks	Fire related incidents/accidents	Nakpanzoo valley Farm	Monthly	Municipal MoFA	31,620 (3,000)
		Records of fire incidents and near	and immediate		Extension officers/	
		misses.	environs		Regional MoFA	
		Number of functional fire				
		extinguishers onsite				
8	Community health	Number of sensitization campaigns	 Nakpanzoo valley 	Monthly	Municipal MoFA	47,430 (4,500)
	issues	Number of condoms distributed to	Farm/ community and		Extension officers/	
		farm workers or placed at convenient	immediate environs		Regional MoFA	
		places in a month				
		Prevalence of STD cases reported to				
		local health facilities				
9	Security and SH/GBV	Number of conflicts/cases reported to	 Nakpanzoo valley 	Monthly	Municipal MoFA	36,890 (3,500)
	concerns	the Grievance Redress	Farm/ community and		Extension officers/	
		Committee/Community Liaison	immediate environs		Regional MoFA	
		Officer				
		Number of conflicts/cases dealt with				
		by the Grievance Redress Committee				
		Number of crimes such as theft,				
		defilement and rape reported,				

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
		investigated, and concluded by the police involving workers or patrons				
10	Risk of Drowning	Number of drowning cases reported and investigated involving unsuspecting community members and animals.	Dugout (from the previous sand winning site now used as water source)	Weekly	Municipal MoFA Extension Officers, Municipal Assembly/ Regional MoFA	31,620 (3,000)
Sub-t	total					411,060 (39,000)
DECC	OMMISSIONING PHASE					
1	Project site accidents/incidents	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Nakpanzoo valley	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
2	Waste generation and inefficient management	 Number of mobile toilets and dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site Complaints by workers/community members 	Nakpanzoo valley construction site and Immediate environs	Weekly	PIU Environmental Safeguards Specialist	31,620 (3,000)
3	Traffic accident risks/Public safety concerns	 Grievance records Traffic related incidents/accidents Records of accidents, incidents and near misses. 	Nakpanzoo valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
Sub-total						137,020 (13,000)
TOTAL COST FOR MONITORING						948,600 (90,000)

9.4 Needs assessment of the implementing institutions

The ESMP outlines mitigation measures, monitoring indicators, and stakeholder engagement protocols to manage potential impacts on land, water, biodiversity, and local communities. MoFA and its extension officers are the project implementers to operationalize the ESMP, given their role in agricultural oversight. This assessment evaluates their readiness and identifies support mechanisms required for successful implementation.

The assessment was conducted through:

- Review of MoFA's operational structure and extension services in the Savelugu Municipal area
- Consultations with district-level officers and relevant stakeholders
- Analysis of ESMP requirements and alignment with MoFA's existing mandates
- Identification of capacity gaps and resource constraints.

9.4.1 Key Institutions

The main institutions to be involved with the implementation of the environmental and social management and monitoring plans include:

- Ministry of Food and Agriculture (MoFA);
- Project Implementation Unit (PIU);
- Environmental Protection Authority (EPA);
- Savelugu Municipal Assembly;
- CSIR-Water Research Institute;
- CSIR-Soil Research Institute;
- Ghana National Fire Service (GNFS); and
- National Disaster Management Organization (NADMO).

9.4.2 Institutional Roles, Capacity Gaps and Recommendation

The capacity assessment presented in **Table 9-4** provides a holistic picture of institutional roles, their existing capacities, the gaps that may hinder performance, and actionable recommendations to close these gaps.

Table 9-4: Institutional Roles, Capacity Gaps and Recommendations

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
MoFA (Municipal &	Lead	Regional/Municipal	Weak	Provide intensive
Regional)	implementer;	offices have limited	safeguards	training on
	coordination,	environmental and	integration at	safeguards
	extension,	social safeguards	local level; and	compliance;
	safeguards	knowledge.	limited tools for	Supply digital data
	compliance	However, national	monitoring	collection tools;
		divisional office has		Integrate ESMP
		stronger capacity		indicators into MoFA
				M&E systems

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
Project Implementation Unit (PIU)	Safeguards oversight and project management	Adequately staffed with environmental and social safeguards officers	Limited operational linkages with district institutions	Strengthen coordination platforms with MoFA, EPA, and Municipal Assembly; and formalize reporting schedules
EPA (Regional Office)	Regulatory oversight; and participation in joint inspections	Strong technical expertise, but logistics constrained (e.g., transport, field equipment)	Inability to conduct regular field inspections due to lack of resources	Engage EPA to improve support at regional level such as vehicles, field logistics, and budget for regular compliance monitoring
Savelugu Municipal Assembly	Local governance; grievance redress; community mobilization	Some competence in grievance handling, but limited awareness of safeguards	Weak capacity in grievance redress aligned with ESMP	Provide structured training on grievance mechanisms and safeguards at district/regional levels
CSIR – Water Research Institute	Technical monitoring of water quality	Adequate technical competence and facilities	Underutilized in field implementation	Formalize role in ESMP monitoring with budget and data-sharing mandate
CSIR – Soil Research Institute	Technical monitoring of soil quality	Adequate technical competence and facilities	Underutilized in project-specific monitoring	Formalize role in ESMP monitoring with budget and data-sharing mandate
GNFS (Regional/Municipal)	Fire education, prevention, and response	Strong institutional mandate, but inadequate fire hydrants, tenders, and trained personnel	Limited firefighting equipment; inadequate training capacity	Engage GNFS to improve fire-fighting equipment resources at the district level; build capacity on prevention and community training methods
NADMO (Municipal Office)	Disaster risk education,	Active but under- resourced with	Staffing and logistical deficits	Engage district NADMO to recruit

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
	preparedness,	limited staff and	constrain rapid	additional staff;
	and response	logistics	response	provide disaster
				response logistics
				(vehicles,
				equipment); and
				build staff capacity
NGOs/CSOs	Community	Active presence but	Weak technical	Provide training in
	engagement and	limited technical	understanding	safeguards,
	sensitization	expertise on	of ESMP	participatory
		safeguards	safeguards	monitoring, and
				technical
				engagement

MoFA should establish formal coordination mechanisms, including joint monitoring schedules and shared reporting platforms to enhance accountability and synergy across agencies.

9.4.3 Capacity Building Approach and Training Needs

Project institutions must fully understand the ESMP objectives, their statutory roles, and how safeguards compliance strengthens outcomes. Current institutional competence varies, with strengths in technical monitoring (e.g. CSIR, PIU) but weaknesses in safeguards integration, resource availability, and disaster/fire response systems (see **Table 9-4**).

The first step in pursuing capacity building has been to identify the specific capacity building needs of the various stakeholders. Capacity building should be viewed as more than training. It is human resource development and includes the process of equipping individuals with the understanding, skills and access to information, knowledge and training that enables them to perform effectively. It also involves organizational development, the elaboration of relevant management structures, processes and procedures, not only within organizations but also the management of relationships between the different organizations and sectors (public, private and community).

The capacity building will mostly be in the form of training workshops. A training workshop on the E&S Safeguards should be organized for the MoFA district and regional officers and the Municipal assembly and should cover the following.

- Inclusion of environmental mitigation measures and penalties in contract documents of contractor and contractor supervision;
- Environmental screening and monitoring;
- Public/community participation techniques and procedures; and
- Grievance redress mechanism.

For each group, training will be provided at different level of expertise in different areas, and would include:

- In-depth training to a level that allows trainees to go on to train others, including environmental and social procedures where relevant; and
- Sensitization or awareness-raising in which the participants are familiarized with the significance or relevance of the issues, to the extent that they can identify potential or emergent problems and request further assistance as necessary.

9.4.4 Environmental and Social Monitoring Approaches

Environmental Monitoring

Indicator	Current Status	Gap	Recommendation
Soil and water quality tracking	Ad hoc, project- specific	Lack of standardized tools and training	Provide portable testing kits and training on sampling protocols OR Engage the CSIR to carry out the monitoring
Agrochemical use monitoring	Basic advisory role	No formal tracking or reporting	Integrate pesticide use logs into extension visits

Social Safeguards

Indicator	Current Status	Gap	Recommendation
Community engagement	Informal, reactive	No structured grievance or feedback system	Develop community liaison protocols and feedback channels
Gender and vulnerability inclusion	Limited	No disaggregated data or targeted support	Train officers on inclusive engagement and social impact monitoring

9.4.5 Technical and Operational Capacity

Training and Capacity Building

- Environmental Modules: Soil conservation, water management, biodiversity protection
- Social Modules: Stakeholder engagement, grievance redress, labor monitoring
- Technical Skills: GIS mapping, mobile data collection (e.g., KoboToolbox), ESMP reporting formats

Tools and Resources

- Field tablets or smartphones for data capture
- Budget allocation for transport, field visits, and community meetings
- Access to baseline environmental and socio-economic data

9.4.6 Coordination and Accountability

To ensure accountability and adaptive management:

- Develop ESMP indicators aligned with MoFA's monitoring and evaluation (M&E) systems
- Schedule quarterly monitoring visits and biannual inter-agency review meetings
- Establish feedback loops with community representatives for transparency

 Integrate ESMP findings into MoFA's agricultural extension dashboard for mainstreaming into daily operations

Recommendations

MoFA and its extension officers play a pivotal role in safeguarding environmental and social outcomes of the proposed project. To fulfil this role effectively, the following actions are recommended:

- Capacity Building: Deliver targeted training on ESMP components;
- Resource Provision: Equip officers with monitoring tools and digital devices;
- Institutional Coordination: Formalize partnerships with EPA, NADMO, GNFS and local authorities;
- Community Engagement: Establish inclusive and responsive communication channels; and
- Monitoring Systems: Integrate ESMP indicators into MoFA's routine operations

9.5 ESMP Estimated Implementation Budget

The project will require a total of Ghc4,767,580 (US\$452,119) to implement the ESMP as outlined in the table below;

Table 9-5: Estimated budget to implement ESMP

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
		Cost (USD)	Cost (GHS)
Preconstruction (Preparatory) Phase	- E & S assessment and permit acquisition.	37,287	393,000
	- Training and completion of VLD forms.	427	4,500
	- RAP/LRP Implementation and capacity building	13,237	139,520
	for PIU.		
	- Fencing of site to restrict vegetation clearance	2,841	30,000
	- Training of E&S officers on ESMP.		
- Sub Total		53,792	567,020
Construction Phase	- Development and implementation of an	4,735	50,000
	Occupational, Health and safety management		
	plan.		
	- Labour force management and training on	18,939	200,000
	safety, discrimination, GBV, SEA/SH, child		
	labour/human rights and ethical conduct.		
	- Erosion management and ESMP training for	16,098	170,000
	contractor's E&S team		
	- Air quality deterioration abatement measures	5,682	60,000
	and PPE provision		
	- Water pollution abatement measures	6,629	70,000
	- Noise abatement measures implementation	1,894	20,000
	and PPE provision		
	- Waste management including hazardous and	11,364	120,000
	non-hazardous waste		
	- Traffic management and road safety training	4,735	50,000
	for drivers		

		Cost (USD)	0
			Cost (GHS)
	- Implementation of fire prevention/fighting	4,735	50,000
	measures and training for workers and		
	community		
	- Management of grievances including GBV,	5,682	60,000
_	SEA/SH, child labour/human rights		
	- Sensitization of workers and community on	2,841	30,000
_	cultural tolerance and conflict management		
	- Management and community sensitization on	9,470	100,000
	drowning risks		
Sub-Total		92,804	980,000
Operation Phase	- Development and implementation of	28,463	300,000
	occupational health and safety plan/measures		
	- Sensitization on good labour practices, rights	18,975	200,000
	and ethical conduct.		
	- GBV sensitization for farm owners/workers	9,569	100,000
	- Child labour sensitization for farm owners	4,744	50,000
	- Education on soil, water and nutrient	9,488	100,000
	management for farmers.		
	- Education of farmers on air quality	9,488	100,000
	deterioration abatement measures		
	- Education on soil, water, and nutrient	28,463	300,000
	management, waste management, pollution		
	prevention and PMP Implementation		
	- Sensitization of farmers on noise abatement	4,744	50,000
	measures		
	- Waste management including provision of	7,116	75,000
	skips, collection/disposal and education on	,	,
	composting		
	- Fire risk management and sensitization of	9,488	100,000
	farmers on fire-fighting techniques.		
	- Education of farmers on soil, water and	4,744	50,000
	nutrient management.		
	- Sexual health education programs for farm	4,744	50,000
	workers to promote public health	,	,
	- Flood risk assessment and management	14,231	150,000
	- Sensitization of workers and community on	2,841	30,000
	cultural tolerance, and conflict management	,	,
	- Traffic management and road safety training	4,744	50,000
	for drivers	,	,
	- Management and community sensitization on	4,744	50,000
	drowning risks	,	,
Sub Total	o and a second	166,508	1,755,000

Project Stage	Project Activities	Estimated ESMP Cost (USD)	Estimated ESMP Cost (GHS)
Decommissioning Phase	- Development and implementation of an Occupational, Health and safety plan.	4,735	50,000
	- Waste management including hazardous and non-hazardous waste	11,364	120,000
	- Traffic management and road safety training for drivers.	4,735	50,000
Sub Total		20,834	220,000
Grievance Redress		79,000	832,660
Mechanism (GRM)			
Resettlement Action Plan Implementation		7,181	75,690
Environmental & Social Performance Audit		25,000	263,500
RAP Completion Audit		7,000	73,780
Sub Total		118,181	1,245,560
Total		452,119	4,767,580

10.0 DECOMMISSIONING

A Decommissioning and Site Closure Plan (DCP) is required to guard against the remote possibility of abandoning temporary constructed structures. Should such a circumstance arise, the potential would exist for impacts from abandonment of the facility such as aesthetic impacts and potential trespassing and safety concerns. This DCP is being posted to provide a guide on details of the decommissioning activities. The purpose of this conceptual DCP is to describe the general objectives for the post project land use, and the planning processes leading to development of a final DCP.

The specific objectives in managing the decommissioning process will be:

- To ensure that rehabilitation and decommissioning are carried out in a planned sequential manner, consistent with best practice;
- To ensure that agreed post-project land-use outcomes are achieved; and
- To avoid on-going liability.

A Full Decommissioning Report is expected to be prepared in the event of any such activity for approval by the EPA and any other requisite state agencies.

10.1 Pre-Decommissioning Assessment

Prior to any decommissioning, the EPA will be notified and an assessment will be carried out to identify any potential environmental impacts that need to be addressed and mitigated in the decommissioning process.

10.2 Decommissioning Phase Activities

The decommissioning phase will primarily involve the removal of temporary structures such as construction work camps, equipment yard and storage facilities as well as dismantling of equipment used during the construction phase. These facilities will be dismantled and the areas rehabilitated to their origin and agreed conditions upon completion of construction activities. The core agricultural operations of the REWARD project, however, are expected to continue over the long term (approximately 25-30 years) and are not within this decommissioning scope as conditions may change over the years.

10.2.1 Dismantling and Removal of Structures and Equipment

During decommissioning activities, the respective Planning Department and the EPA office shall have access to the site, pursuant to reasonable notice, to inspect the results of complete decommissioning.

The removal of installations, structures, and equipment would include a complete inventory of all hardware and capturing of their final operational status. Disposal of the hardware and documentation would be planned, including any environmental concerns that may dictate disposal method.

All decommissioning and restoration activities will be in accordance with all applicable state and local permits and requirements and will include the following specific activities:

- Hardware retirement: All power sources would be disconnected from structures and equipment
 before dismantling commences. Cranes and/or other machinery will be used for the disassembly
 and removal of structures and associated installations. These will either be transported whole for
 reconditioning and reuse or dissembled into salvageable, recyclable, or disposable components;
- **Foundation removal**: All foundation materials will be removed as per EPA guidelines or requirements. The remaining excavation will be filled with clean sub-grade material, compacted to a density similar to surrounding sub-grade material, and finished with topsoil;
- Monitoring: A monitoring and remediation period of two years immediately following the
 completion of any decommissioning and restoration activities will be undertaken. If agricultural
 impacts are identified during this period, follow-up restoration efforts will be implemented; and
- Area restoration: Areas where subsurface components are removed will be graded to match
 adjacent contours, stabilized with an appropriate seed mix, and allowed to re-vegetate naturally.
 All town roads, impacted by Project decommissioning activity, if any, will be restored to original
 condition upon completion of decommissioning.

10.2.2 Solid Waste Management

All solid waste resulting from the decommissioning process will be evacuated by handlers commissioned by the Municipal Solid Waste Department.

10.3 Post-Decommissioning Assessment

Removal of machinery, equipment and all other materials related to the project will be completed within one year of decommissioning. At the end of the decommissioning exercise, the EPA will be invited to carry out a post-decommissioning assessment to establish compliance with all regulatory requirements and issue a certificate to that effect. The Decommissioning and Closure Plan will be finalized and submitted to the relevant authorities for approval at least six months prior to closure of the site.

A report describing the performance of the final DCP in working towards its objectives, based on monitoring results, and the extent to which it has been complied with, will be submitted to the EPA. The report will be provided to documented stakeholders and will otherwise be publicly available on request. Files and documents used to collate information regarding closure commitments, licenses, approvals and other information concerning closure will be catalogued and maintained in accordance with standard practices.

11.0 CONCLUSION

The proposed project will be implemented in accordance with relevant national laws and best international practices provided by the applicable Operational Safeguards of the AfDB Integrated Safeguard System.

Stakeholders have been identified and their suggestions and concerns obtained through the consultation and engagement process have been highlighted in the report and addressed. A Stakeholder Engagement Plan (SEP) has been proposed to ensure continued engagement of all stakeholders and the implementation of a grievance redress mechanism to ensure harmony in the project implementation.

The potential adverse impacts of the project have been identified. Adequate mitigation measures have been proposed to manage the moderate to major adverse impacts. Also, management and monitoring plans have been designed to ensure that the proposed mitigation measures are adequately implemented. The institutional capacities have been assessed and gaps identified with recommendations.

The assessments have shown that the project generally has moderate impacts on the environment and the impacts could be further mitigated with the adoption of good environmental, health and safety practices. A Pest Management Plan (PMP) is required to ensure judicious and safe use of agrochemicals as well as safe disposal of obsolete chemicals and empty containers.

The Chief of the Nankpazoo community has donated the land for the project. A Resettlement Action Plan has been proposed to mitigate the livelihood impacts on thirty three (33) farmers who will vacate their farm lands for use by the project.

The project holds immense benefit for the Nankpazoo community, the municipal and region regarding food security, job creation, growth of MSMEs, etc. The entire country will benefit from improved food security, increased knowledge and adoption of best agricultural practices for rice production, etc.

12.0 BIBLIOGRAPHY

CARE International. (2013) Climate Change Vulnerability and Adaptive Capacity in Northern Ghana. An Adaptation Learning Programme Report. CARE International: Accra.

Ghana Environmental Assessment Regulations, 1999 (L.I. 1652)

Ghana Meteorological Agency Climate data (2015 -2024)

Ghana Statistical Service, 2021. 2020 Population and Housing Census – District Analytical Report for Selected Project Districts.

Government of Ghana/UNICEF, 2013. Northern Region Report: Qualitative Research on Child Protection in Ghana. Government of Ghana/UNICEF: Accra, Ghana.

Government of Ghana, 2021. Medium Term Development Plan for the Savelugu Municipal Assembly, 2022 – 2025.

Hutchinson, J. and J.M. Dalziel (1954-72). Flora of West Tropical Africa. Crown Agents, London.

Medium Term Development Plan, Savelugu Municipal, 2021.

Ministry of Food and Agriculture, Department of Agriculture-Savelugu Municipal, 2024

Murali Krishna Gumma & Paul Pavelic, 2012, Mapping of groundwater potential zones across Ghana using remote sensing, geographic information systems, and spatial modelling, 2012.

Owusu, K (2018) Rainfall Changes in the Savannah Zone of Northern Ghana 1961- 2010. Weather, Vol 73, No. 2

SAL Consult Field data, 2025

Tetteh et al., (2016); Suitability of soils for cereal cropping in Northern Ghana.

The African Development Bank Group's Operational Safeguards Standards (OSS), 2024 (Revised) The 1992 Constitution of Ghana

WKC Group Formula (2015)

Yeboah et al., (2022); Variability of soil physicochemical properties under different land use types in the Guinea savanna zone of northern Ghana

13.0 ANNEXES

Annex 1: Administrative flow chart of environmental assessment procedure

Annex 2: List of environmentally sensitive areas


Annex 3: Sample Code of Conduct

Annex 4: Sample Grievance Form

Annex 5: Details of Stakeholder Engagement

Annex 6: Stakeholder Engagement Attendance Sheets

Annex 1: Administrative flow chart of environmental assessment procedure



Annex 2 List of environmentally sensitive areas

ENVIRONMENTAL ASSESSMENT REGULATIONS, 1999

SCHEDULE 5

(Regulation 30 (2))

ENVIRONMENTALLY SENSITIVE AREAS

- All areas declared by law as national parks, watershed reserves, wildlife reserves and sanctuaries including sacred groves.
- 2. Areas with potential tourist value.
- Areas which constitute the habitat of any endangered or threatened species of indigenous wildlife (flora and fauna).
- 4. Areas of unique historic, archaeological or scientific interests.
- 5. Areas which are traditionally occupied by cultural communities.
- Areas prone to natural disasters (geological hazards, floods, rainstorms, earthquakes, landslides, volcanic activity etc.)
- 7. Areas prone to bushfires.
- 8. Hilly areas with critical slopes.
- 9. Areas classified as prime agricultural lands.
- 10. Recharge areas of aquifers.
- 11. Water bodies characterized by one or any combination of the following conditions
 - a) water tapped for domestic purposes;
 - b) water within the controlled and/or protected areas;
 - c) water which support wildlife and fishery activities.
- 12. Mangrove areas characterised by one or any combination of the following conditions
 - a) areas with primary pristine and dense growth;
 - b) areas adjoining mouth of major river system;
 - c) areas near or adjacent to traditional fishing grounds;
 - d) areas which act as natural buffers against shore erosion, strong winds or storm floods.

CLETUS AVOKA

Minister Responsible for the Environment

Date of Gazette notification: 26th February, 1999.

EIA IN GHANA

Entry into force: 24th June, 1999

_____ 105

Final ESIA Report _REWARD Project _Nakpanzoo (Savelugu) October 2025

Annex 3: Sample Code of Conduct

All the employees of the Contractor and support staff of Supervising Consultant shall adhere to the following Code of Conduct during the execution of the project:

1. Compliance with Applicable Laws, Rules and Regulations

- a. All employees shall perform their duties in accordance with the Labour Act, 2003 and other applicable labour laws in Ghana.
- b. Employees/key experts will enjoy freedom of association and expression as defined in the Constitution of Ghana and expressed in Labour Act, 2003 (Act 651) and other labour laws in Ghana.
- c. The Organization will not condone the activities of employees who achieve results through violation of the law or unethical business dealings. This includes any payments for illegal acts, indirect contributions, rebates, and bribery.
- d. The Organization shall not permit any activity that fails to stand the closest possible public scrutiny.
- e. Employees uncertain about the application or interpretation of any legal requirements should refer the matter to appropriate line supervisor
- f. Workers/employees who falsify their ages will be summarily dismissed as the company does not tolerate child and forced labour.
- g. The company will not tolerate any form of child or forced labour from any subcontractor/employee who practice forced or child labour
- h. Employees are required to report suspected cases of child or forced labour on site to REWARD Environmental and Social Specialist, DOVVSU or Municipal Assembly.

2. Compliance with Applicable Health and Safety Requirements

- a. All employees' have the right and duty to ensure safe working conditions to the extent of exercising control over tools, equipment, machinery and processes and to express their views on working conditions that may affect their safety and health. Subcontractors will do same for their employees
- b. Employees of the Contractor shall be responsible for removing themselves from danger as much as possible whenever they have good reason to believe that there is an imminent and serious danger to their safety or health. They should have the duty so to inform their supervisor immediately.
- c. Employees/key experts will be provided with the appropriate protective gear for the operations or activities and request for same before engaging in any activity associated with the works.
- d. No worker shall be allowed to undertake any work without wearing approved protective clothing/gear.
- e. Workers shall use and take care of personal protective equipment, protective clothing and facilities placed at their disposal and not misuse anything provided for their own protection or the protection of others
- f. First time offenders who are not in the appropriate protective gear will receive a verbal caution, second time offenders will receive a formal written caution, while multiple offenders will receive sanctions ranging from suspensions to dismissal.
- g. Except in an emergency, employees, unless duly authorised, should not interfere with, remove, alter or displace any safety device or other appliance furnished for their protection or the protection of others, or interfere with any method or process adopted with a view to avoiding accidents and injury to health.

- h. Every employee shall take reasonable care for their own safety and health and that of other persons who may be affected by their acts or omissions at work;
- Workers shall report to their immediate supervisor, and Health and Safety Officer, any situation which they believe presents a risk and which they cannot properly deal with themselves;
- j. Damaged or faulty electrical equipment such as power sockets, leads and appliances are removed from service.
- k. Damaged or faulty equipment should be replaced, or repaired by a qualified person as soon as possible.
- I. Power points should be protected by safety-shutters, or all vacant power points be covered by plastic plug protectors.
- m. Electrical appliances and leads should be kept away from water.
- n. All machines and vehicles should be turned off when not in use
- o. All employees shall comply with all the safety and health measures prescribed by the employer. Employees should not operate or interfere with plant and equipment that they have not been duly authorised to operate, maintain or use.
- p. Employees should not sleep or rest in dangerous places such as scaffolds, , garages, or in the vicinity of fires, dangerous or toxic substances, running machines or vehicles and heavy equipment.
- q. Supervisors should not assign employees to undertake activities that the later do not have necessary competence, training or certification or that has not been stated in their contract with the Company.
- r. Employees should not undertake any assigned activity for which you do not have necessary competence, training or certification or that has not been stated in their contract with the Company.
- s. Every employee is encouraged to contribute by integrating environmental sustainability issues as they relate to our industry into our business planning, strategies and decision-making.
- t. Employees shall avail themselves for all OHS, HIV/AIDS Gender Based Violence, Emergency Preparedness Training/Sensitization Programmes organized under the project.
- u. All Company employees should strive to conserve resources and reduce waste through re-use and other energy conservation measures.

3. Use of Illegal Substances

- a. No employee/key expert/sub-contractor shall report to work under the influence of alcohol or any substance considered as illegal under the laws of Ghana including marijuana.
- b. No employee shall smoke, consume alcohol or illegal substances while on duty, including lunches and during overtime meals, or on company property.
- a. Officers and directors <u>may</u> authorize, in advance, the consumption of alcohol for special occasions or for certain business meetings as long as such use is limited and does not violate other legal requirements.
- b. No employee shall under any circumstance engage in any work related to the organization under the influence of Alcohol or illegal substances even if consumption is permitted under the exception described above.
- c. Employees who violate this smoking and alcohol conduct standard may have their contract terminated.

4. Non- Discrimination

- a. Discrimination against any job applicant or employee on the grounds of colour, race, religion, age, nationality, sex, marital or family status, ethnic affiliation, pregnancy, sexual orientation, disability or other reason is prohibited.
- b. In certain cases, however, the requirements of safety regulations relating to specific positions/activities within a construction business will take precedence over clause 4(a).
- c. We do not employ any person below the legal minimum age (18 years) and will require commitments from suppliers and subcontractors to refrain from such practices
- d. Workers are not to undertake any assigned activity for which they do not have necessary competence, training or certification or that has not been stated in their contract with the Company.
- e. Recruitment, job transfer and progression, remuneration and training and award of discretionary bonuses when applicable are determined solely by the application of objective criteria, fair and unprejudiced opinion, personal performance and merit.
- d. Recruitments, transfers, training, maternity leave and standard terms and conditions will be done in accordance within line Ghana Labour laws.
- e. Employees who perceive that they have been discriminated against can seek redress through their supervisor, Environmental, Health and Safety Officer, management and/or the Ministry of Labour and Social Welfare.

5. Interaction with Community

- a. The Company strives to cultivate a local identity in each of its host communities by setting good corporate citizenship standards, while respecting local sensitivities.
- b. The Company will regularly contribute to the economic and social development of communities, and expects all employees to promote human rights and respectful community involvement anywhere it operates.
- c. Employees should comply with the norms, laws, rules and regulations applicable to the host communities except in cases where they are in conflict with that of Ghanaian laws.
- d. In a case where an employee perceives that the laws, rules and regulations of host communities are in conflict with that of the company, employees are to refer such cases to their supervisor, Environment, Health and Safety Officer or manager for further clarification at the Ministry of Labour and Social Security

6. Sexual Harassment

Sexual Harassment would be considered as unwelcome conduct of a sexual nature which makes a person feel offended, humiliated and/or intimidated. It includes situations where a person is asked to engage in sexual activity as a condition of that person's employment, as well as situations which create an environment which is hostile, intimidating or humiliating for the survivor

- a. Sexual harassment is unlawful.
- b. This company does not tolerate sexual harassment in any form.
- c. Every employee has a responsibility to ensure that sexual harassment does not occur.
- d. No employee shall under any circumstance sexually engage another either by the use of words or actions. Some acts that may be considered as sexual include;
 - an unwelcome sexual advance
 - a request for sexual favours
 - unwelcome comments about someone's sex life or physical appearance
 - sexually offensive comments, stories or jokes
 - displaying sexually offensive photos, pinups or calendars, reading matter or objects
 - sexual propositions or continued requests for dates

- physical contact such as touching or fondling, or unnecessary brushing up against someone
 - Indecent assault, defilement or rape (these are criminal offences).
- e. Any employee who believes he or she has been a target/survivor of sexual harassment is encouraged to inform the offending person orally or in writing that such conduct is unwelcome and offensive and must stop or to report the unwelcome conduct as soon as possible to a supervisor, management or the environmental and social officer of GASSLP representative on the Project Grievance Redress Committee or the nearest DOVVSU or Police Station
- f. Reports of sexual harassment will be treated promptly, seriously and confidentially.
- g. Complainants have the right to determine how a complaint will be treated and knowledge of the outcome of investigations.
- h. Anyone found to have sexually harassed another person will be handed over to the Family Support Unit of the Ghana Police Force.
- i. No employee will be treated unfairly as a result of making a complaint of sexual harassment. Immediate disciplinary action will be taken against anyone who victimizes or retaliates against someone who has made a complaint of sexual harassment.
- j. For the purposes of reporting and dealing with sexual harassment and crimes, the Company will provide a hot line to a management level personnel for reporting cases of sexual abuse and harassment.
- k. Rape, defilement and assault cases shall be reported to FSU of the Ghana Police Force by survivor or other employees'

7. Violence or Exploitation

- a. No employee shall bear any weapon on site unless he/she has been authorized and have a legitimate business reason to do so. Even so, this will have to be with the permission of the appropriate supervisor, manager and conformity with the laws of Ghana.
- b. The company is committed to maintaining a safe and secure workplace and working environment. Acts or threats of physical violence, intimidation, harassment or coercion, stalking, sabotage, and similar activities are not tolerated.
- c. Employees who engage in acts or threats of violence, outside of self-defense, shall be dismissed and handed over to the Police Station.
- d. Employees are expected to treat all individuals with respect, tolerance, dignity and without prejudice to create a mutually respectful and positive working environment.

8. Protection of Children

- a. As much as possible, employees' are to avoid bringing any person under 18 to work on the project site) unless with permission from Environment, Health and Safety Officer.
- b. Every employee shall himself be responsible for the safety and wellbeing of any person under age 18 years brought to work by them. *Physical contact with children can be misconstrued both by the recipient and by those who observe it, and should occur only when completely nonsexual and* otherwise appropriate, and never in private.
- c. One-on-one meetings with a child or young person are best held in a public area; in a room where the interaction can be (or is being) observed; or in a room with the door left open, and another employee or supervisor is notified about the meeting.
- d. Avoid any covert or overt sexual behaviors with children on site. This includes seductive speech or gestures as well as physical contact that exploits, abuses, or harasses.
- Employees are to provide safe environments for children and youth at all times on site

9. Sanitation Requirement

- a. The company shall provide and maintain sanitary facilities (according to building regulations) for all employees to ensure their total health and safety. All such facilities shall be labelled with inscription in English for the understanding of every employee.
- b. Every employee/key expert shall be responsible for the appropriate use of sanitary facilities including toilets, bathrooms and refuse bins/skip containers where provided.
- c. No employee shall resort to other inappropriate means of defecation or urination (open defecation or indiscriminate disposal of refuse or urination on the company's compound or project site) apart from what has been prescribed by the company.
- d. Any act of indecency with respect to the use of sanitary facilities shall attract punitive actions including suspensions or even dismissals.

10. Avoidance of Conflict of Interest

- a. The Company expects that employees will perform their duties conscientiously, honestly, and in accordance with the best interests of the Organization.
- b. Employees/key experts must not use their positions or the knowledge gained as a result of their positions for private or personal advantage.
- c. Regardless of the circumstances, if employees sense that a course of action they have been pursued, or are presently pursuing, or are contemplating pursuing may make it difficult to perform the work objectively, they should immediately communicate all the facts to their supervisor.
- d. An Employee or a member of his or her immediate family shall not receive improper personal benefits as a result of his or her position in the Company.
- e. Any situation that involves, or may reasonably be expected to involve, a conflict of interest with the Company should be disclosed promptly to supervisors/ managers.

11. Protection and Proper Use of Property

- a. All employees unless otherwise directed are responsible for the proper acquisition, use, maintenance and disposal of company assets (e.g., materials, equipment, tools, real property, information, data, intellectual property and funds) and services. Acquisition of assets should be in compliance with procurement standards of the company.
- b. Any act of theft, carelessness, and waste on the part of an employee shall attract sanctions including the termination of one's work contract.
- c. Every employee shall do their part to protect the company's assets and ensure their efficient use.
- d. Unless otherwise permitted by management, Company guidelines and procedures, the appropriation of Company property by employees for personal use, or for resale is strictly prohibited.
- e. Similarly, you are not permitted to use your authority over other employees to use Company resources for personal benefit.
- f. On termination of and at any other time during your employment when requested you must hand over Company's assets and records stored in whatever format or medium.
- g. The Company strictly prohibits any access, usage or disclosure of employees' personal data without legitimate authorization. Employees should note that the Company reserves the right to retrieve their e-mails transmitted via the Company e-mail accounts and to monitor your use of the Internet.
- h. Every employee shall use company assets only for legal and ethical activities.

12. Report of Violation of Code of Conduct

- a. Employees should promote ethical behavior and encourage other employees to talk to supervisors, managers or other appropriate personnel when in doubt about the best course of action in a particular situation.
- b. In order to protect our organization from unethical or illegal activity, it is your duty and obligation at all times to be watchful of the practices that you see occurring around you, to take reasonable steps to prevent or detect improper conduct, and to report any suspicion of fraudulent, abusive, unethical or illegal activity.
- c. All reports of misconduct or unethical behavior, conflict of interest, or illegal activity are to be handled as confidential and be treated seriously and discreetly.
- d. Employees may report anonymously should that be their preference.
- e. In the event of a grievance being raised to a manager relating to discriminatory behaviour or harassment, the manager must notify Human Resources immediately, irrespective of how trivial the complaint may appear.

13. Non-Retaliation

- a. The company will not tolerate any act of retaliation against anyone who, in good faith, reports known or suspected unethical or illegal misconduct, seeks advice, raises a concern, or provides information in an internal or external investigation or legal proceeding pertaining to the company.
- b. Allegations of retaliation will be investigated, as appropriate.
- c. Acts of retaliation (which may include firing or laying off, demoting, denying overtime or promotion, disciplining, denying benefits, failing to hire or rehire, intimidation or making threats) may lead to disciplinary action against the person responsible for the retaliation, up to and including termination of contract.
- d. Any employee who believes he/she has experienced retaliation, should report to his/her supervisor, manager or the REWARD Environmental and Social Officer.
- e. Any false accusation of retaliation would attract disciplinary actions even to the extent of termination of contract.

Implementation of Code of Conduct

- a. The Environment, Health and Safety Officer of the Contractor will be responsible for implementing and enforcing the Code of Conduct, while monitoring
- b. The following measures will be adopted to implement the Code of Conduct:
 - The Consultant will ensure that all employees/key experts and sub-contractors are given copies of the Code of Conduct for reference.
 - All employees on the assignment will be made to sign the Code of Conduct.

Annex 4: Sample Grievance Form

GRIEVANCE REGISTRATION FORM (FORM A) - For Complainant

Confidentiality Required: Yes No:
Name (Complainant) Optional:
Contact Information (house number/ mobile phone):
Nature of Grievance or Complaint:
Details of Grievance:
Name (Receiver):
Name (Filer):
Relationship of Filer to Complainant (if different from Complainant):

Annex 5: Details of Stakeholder Engagement

Stakeholder/	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Institution/ Location						
Government Institutio	ns – Category A	,				
Ministry of Food and Agriculture – Savelugu		Management Information System Officer	0242808705	2025-04-14	 Resolution of land-related conflicts – The project should collaborate with chiefs and traditional leaders in order to resolve land-related issues before commencing the project. Bush fire education – Farmers should be educated to on the effect of bush fire and its prevention especially as this is a major issue especially after harvest. Municipal Agriculture Production - About 68,345 people are into agriculture. Maize, Rice, Soya, groundnut, cowpea are the common crops grown. Adequate agriculture inputs are not available to farmers to increase production. The farmers are mostly engaged in peasant agriculture making their production levels low. The farmers generally are engaged in rain-fed agriculture which is making production difficult. Project Implementation - The project is a welcomed development as it will boost rice production. The municipal economy is dominated by agriculture, therefore any project in agriculture has a high probability of been successful. The project will be beneficial to the people economically and help alleviate poverty in the area. Project should deeply involve the Municipal Dept. of Agriculture for sustainability. The municipal MOFA office will offer the needed support for the successful implementation of the project. Land in the municipality are largely owned by stools. Employment of competent personnel – The project should ensure that experienced and dedicated technical staff are employed on the field to ensure project efficiency. Agricultural conservation practices – In order to maintain good soil texture and fertility all year round appropriate conservation practises should be followed. Marketing of produce and post-harvest management – Produce marketing can be difficu	
Environmental Protection Authority	Abdul karim Jato	Programme Officer	0201224235	2025-04-22	 Compensation - Compensation issues will arise if there are PAPs in the valley. Compensation should be addressed through comprehensive RAP. 	
(EPA) – Tamale					 There must be valuation of properties if any, as well as compensation for any form of displacement. Project Implementation - Environmental permit is required for the project. Biodiversity conservation should be a consideration in the project implementation. If there are RAP issues, it should be handled properly in order not to impoverish persons involved. There will be field visits by the EPA team to monitor environmental compliance during implementation. Farmers should be educated on the use and handling of agro-chemicals. 	

Stakeholder/	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Institution/ Location						
					 The project has the potential to transform livelihoods of beneficiaries if it is implemented effectively. Recommendations - There should be environmental monitoring during implementation to check results against established baseline conditions. There should be good water management practices. There should be a flood control plan in the valley. EPA Monitoring – the project should include EPA staff in the implementation phase of the project to monitor the compliance of the farmers with environmental standards. 	
Lands Commission	Mohammed Alhassan	Assistant Secretary	0242081543	2025-04-14	 Compensation - Land acquisition will warrant some form of compensation to right owners. There must compensation for physical and economic displacement if any. Capturing of PAPs data must be done comprehensively. Project Implementation - The land in the area is owned by stools. Land for this kind of project are normally acquired from the traditional authorities. The project will help to improve livelihoods and food security. Assistance in the farm of farm inputs should be provided to the farmers. The project will lead to effective land utilization. Recommendation - Need more community engagement for on the project for enhanced participation. 	
Water Resource Commission (WRC)	Yussif Abdul -Razak Gunu	Accountant	0249768120	2025-04-15	Concerns/Recommendations: - Farmers should form fire fighter groups. Education on agrochemicals use for farmers There should be timely harvest of crops by farmers. community education on disaster management	

Stakeholder/ Institution/ Location	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
NADMO, Savelugu Municipal Assembly, Savelugu	Abukari Abdul Rahim Yahuza Saibu	Accountant Stores Planning and Coordination	0247667079 0245745493 0242808705	2025-04-15	 Floods – Seasonal floods occur in the municipality between September to October and should be taken into consideration by the project as this could be a potential risk to the project. Windstorm – Windstorms are experienced between April and May when the wet season is beginning. Bush fires – Bush Fires occur between November and January during the dry season and this has caused low productivity. NADMO will liaise with the Ghana Fire Service to train fire fighters and community volunteers to handle bush fires as well provide education on the effects of bush fires on the project. Disaster Impact: There have been loss of lives and properties as a result of floods, bush burning and windstorms. This has also in some instance caused food scarcity. Sensitization: NADMO sensitizes the communities twice a year. Operations: They provide Relief items, evacuation and collaborate with fire service. Concerns/Recommendations: NADMO appeals for means (transport) and fuel to support Nakpanzoo. Communities should form volunteers who are trained in disaster management to help manage disasters. Support from the Municipal Assembly – The assembly is willing to provide support to any project that will improve the production of farmers in the community. Compensation - If people are identified to be impacted by the project, compensation plan must be undertaken and implemented. Land acquisition must be properly done from the traditional authorities and compensation paid before start of project if requested. There must be compensation of individuals lands will be acquired for the project. Project Implementation - The municipality's population is heavily dependent on agriculture; therefore, the project will offer strategic partnership to boost food security.	
Ghana National Fire Service, Tamale Private Sector – Catego	Isaac Ofei Dodoo	Administrative Officer	0249829629	2025-04-14	 Farm inputs and machinery should be made available to the farmers regularly to make the project successful. Preservation of water bodies – The project should put measures in place to preserve existing water bodies as this serves as farm boundaries and also helps to curb bush fires. Training of fire volunteers – Fire volunteers from the farming communities should be trained to provide immediate assistance in the case of fire outbreaks. Soil tests – The project should conduct water logging as well as fertility tests to determine the suitability of soil for maximum crop production. Inadequate logistics – The Fire Service department should be provided with adequate logistics like vehicles to facilitate project monitoring and training of fire volunteers. 	

Stakeholder/ Institution/ Location	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Commercial Farmer, Savelugu	Iddrisu Issah Alhassan Abukari	Farmer Farmer Member	0547856198 0553985174	2025-04-15	 Project Implementation - Bunding of the field is needed for the project. Seeds and fertilizer will be required as support for the farmers. If peoples land will be taken, compensation should be paid accordingly. The farmers are happy about the project and are eager to be part. Irrigation and machinery will be required to make the project successful. Recommendations - Improved seeds should regularly be supplied to farmers as well as fertilizer and pesticides. Government support for the project must be consistent. There should be processing and storage facilities after harvesting. There should be ready market to sell produce. Lack of storage facilities — The project should provide adequate storage facilities and warehouses to store produce after harvest since they are kept in the open and in homes. Inadequate machinery — There's not enough agricultural tractors to plough fields, for example, delaying planting at the start of the season, and the ones that are available are broken. The project should procure such machinery as harvesters and tractors etc. to facilitate farming. Bush fire awareness — There is the need for farmers to be educated on fire belt creation and other preventive measures during farming to help curb bush fires. Political interference — To ensure that the project is implemented successfully, the project	
Aggregator	Abukari Adam	Member	024/400156	2025-04-15	 should be devoid of all political interference. Procurement of quality seeds – The project should procure quality seeds for farmers in order to increase the yield of farm produce. Storage facilities – The Busaka warehouse in Savelugu for example should be reconstructed and new facilities provided to prevent post-harvest losses. Availability of food – The project will help provide adequate food in the community as production will be increased. Income generation – The increase in farm yield will generate income as farm produce is supplied to consumers. 	
Agro Input Dealers Community and Focus	Adam Ibrahim Group, Nankpazoo – C	Salesman Category C	0246239295	2025-04-15	 Activities – They sell fertilizers, seeds (hybrid/OPV), crop protection chemicals, tools/equipment for Rice, Maize, Soybean, and Vegetables. There are no peak season for them as they are busy all year round. Source – They Source their products from local distributors. Other roles – Aside selling, they offer technical advice/training to farmers. Concerns/Recommendations - They need easier means of connecting to suppliers and accessing credit/financial services. NGO Partnership - They are open to partnering with NGOs and other private organizations. Technical Training – The programme should consider more technical training for farmers. Challenges – High transportation costs and limited access to capital has been a challenge for them. Opinion - They believe the project is going to have a Positive impact and increase yield for farmers. 	

Stakeholder/	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Institution/ Location						
Traditional Elders	Adama Abdul Malik	Chief	0249517241	2025-04-14	Land Ownership – All the land are stool lands.	
	Yakubu Issahaka	Zagyuri na	055 359 5731		 Land Use – The land is mainly used for farming and rearing of livestock. Land Related Conflicts – Community members have not experienced any land-related 	
	Issahaka Abdulai	Wulan bla	0599302119		conflicts.	
	Mahamadu Ntoli	Kpana lana	0547907685		 Ethnic Groups – Members of the community belong to the Dagomba ethnic group. Compensation - Every Project Affected Person if determined must be captured for the 	
	Abukaru Adam	Community Member	0249249715		 payment of appropriate compensation. Land acquisition must be properly done from the traditional authorities who are incharge of the land. Any form of compensation payment must be fair. Project Implementation - Farming is what most people are engaged into, therefore the project is welcomed as it will help to boost food security and livelihoods in the area. There is abundant of land in the area for the project which belong to the traditional authority. The youth and the women should be encouraged to part of the project. Adequate support should be given to farmers on the project. Irrigation and machinery support should be part of the project. Buying of farm inputs is a major challenge for the people in the area, therefore, these inputs should be covered by the project. Recommendations - Processing and storage should be a vital project component 	
					 Ready market with competitive produce pricing should be arranged for farmers. The roads in the area should be improved to facilitate easy movement of goods and persons. 	
Womens' Group	Muminatu Isaac	Secretary	0535289624	2025-04-14	Project Implementation - The project will help the people in the area especially the	
Womens Group	Shaba Abibata	Chairperson	0245234041	2025 04 14	women to have sustainable income.	
	Abudulai Mariya	Box Keeper VSLA	0246557417		 Women should be given the opportunity to be part of the project. Women usually do not have money to buy farm inputs, so support in that regard will 	
	Abudulai Sanatu	Key Holder VSLA	0555200251		be required Irrigation should be considered for the project so that there can be all-year round	
	mohammed Safuri	Vice Chairperson	0539589570		farming There is enough land in the area to use for the project.	
	Ali Abu	Treasurer	0534213470		 Recommendations - Adequate support to women will be required to make the project impactful. There should not be discrimination is selecting beneficiaries There should be training on modern rice production methods and use of agro-inputs for beneficiaries. Project Impact on Community – They feel the initiative will benefit them by increasing the output of their produce and, as a result, providing income. Vulnerable Groups – There are vulnerable persons in the community as well as disabled persons in the community. Indigenous people – There are indigenous people in the community. Support for Less Privileged – There is support for the less privileged in the community through the LEAP project. The months of April through July are the most difficult in terms of having money. Women in leadership – Women are involved in decision making through the unit committee and the women representatives Local groups – Local groups present include: VSLA group, providing financial support to members, farm groups, and youth groups providing assistance to each other. 	
Mens' group	Adama Abdul Malik	Chief	0249517241	2025-04-14	Project Implementation - The project will go a long way to boost the livelihoods of the	
	Yakubu Issahaka	Zagyuri na	055 359 5731		men in the area. - There is considerable interest in rice production in the area among the men.	
	Issahaka Abdulai	Wulan bla	0599302119		- The necessary support should be given to those who will be on the project.	

Stakeholder/	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Institution/ Location						
	Mahamadu Ntoli	Kpana lana	0547907685		- Rain-fed agriculture is not improving livelihoods; therefore, irrigation should be considered.	
	Abukaru Adam	Community Member	0249249715		- Land preparation support should be part of the project.	
	Alhassan Saibu	Member	0547486747		Recommendations - The road network in the area should be improved to make transport of goods easy.	
	Mohammed Issah	Member	0245374424		 Support for people on the project should not be delayed. 	
	Mohammed Issahaka	Member	0248404961		- If people's lands are taken for the project, the right compensation should be paid to	
	Mohammed Yahaya	Member	0249249715		the right owners.	
Youth group	Alhassan Abdul	Member	0539062573	2025-04-14	Project Implementation - The youth are interested in the project.	
	Karim Abdulai Safianu	Member	0248868307		 Adequate input support should be given for production. The youth are mostly engaged in agriculture; therefore, the project will help to boost 	
		Member	0533651601		their production. The project will boost income if implemented well with the people.	
	Fuseini Ibrahim	Member	0249414684		 Irrigation, agro-inputs and machinery support should be extended to beneficiaries. Recommendations - There should be processing and storage facilities after harvesting. 	
	Alhassan Sualey Alhassan	Member	0595344744		 There should be ready market to sell produce. Support is to farmers is key if the project is to succeed. 	
	Mohammed	Member	0557300778		Community needs/priorities – Healthcare, potable water and Farm machinery, are the	
	Iddrisu Yakubu				three topmost needs of the community.	
Cattle Herders	Ziblida Haruna	Herdsman	0535759377	2025-04-15	 Origin – The cattle herders originate from Burkina Faso and have been herding for about 25 years. They have a cordial and friendly relationship with nearby communities. Conflict Resolution - They manage crop intrusion by paying affected farmers as compensation for crops destroyed or settling conflicts at chief's palace. They mostly check on their cattle regularly to prevent intrusion when grazing. Herding Activities - They can travel about 10 km with their cattle to graze mostly setting off in the morning around and there are no specific spot to graze. Their cattle mostly feed on waste/plants in dry season. Most of them own the cattle and also farms as well. They have no association. Challenges - One of their challenges is accessing water for their cattle. 	

Annex 6: Stakeholder Engagement Attendance Sheets

la.	Name		Organization/District/Community	Position		Phone No.	Protection Authority
AS	dul Karim	Jato	EP4	Programme Of	ficer	0201224285	
+	10						
	,						
-							
					-		
			,		-		
+							
-					-		
					+		
-							1 2
-							

lo. Mame	Organization/District/Community		Phone No.	Email/Sign
Ziblida Harung	Cattle Herder	Herdomon	0535759377	anniy agii
			1	
۸ .				
			-	

io.	Name		/District/Community		Savelugy		
	Adam Horahim			Position	Piseme Mo.	Ernell / Sign	
		Haro I	mout Jeafer	Jealer Salerma	0246237295		
1							
1							
+			,				
H	1						
H							
	-						
_							
_							
-							
		-					
				-			
		-					

Name	Organization/District/Community	Position	Phone No.	Ernall / Sign
Iddian Issah	Commodel Farmer	Farmer	6547856198	
Alhasen Asyken		former	0113682124	
	,			
١				
		3		

No.	Name Ac D tt 4	Organication/District/Community	1.00	Phone No.	limell/Sign
•	Abdullah Shiraz	Municipal Assense	Econotidation of	0242808705	
+					
t				1	
İ	¥.				
1					
-					
_					
_					
-					
					-
				-	

- 1	Abukari Abdul Ration	Organization/District/Community NAAMO		extrent	#Hone No.	Ernali / Sign
1	Yahuza Saibu	~	Stores	Manager	0245745493	
	Ł .					
_						
			*		-	
_						

Va.	Name	Organization/District/Community	Position	Phone No.	Es Commission,
	Turing Holul-Razak Guny	DRC	Accountment	0249768120	
-					
-					
+					
			-		
-					
1					

No.	Mamo	Organization/District/Community	Position	Phone No.	Email / Sign
	Alhaban Asolul Karim	Youth Group	Member	0539062573	
,	Abdulai Stranu Fuscini Ibrahin		V	0248868307	
+	Alhavan Sualey			0533651601	
- 1	Alharran Mohammed	7 7		0249 414684	
1	Udvisa "Yakubu			0191344744	
T	- Torons	V -	Member	0557300778	
T					
		-			
_					
_					
_					
_					
					-
_	•				
-					

io. Mama	Organization/District/Community	Position	Phone No.	Email / Sign
Muminahu Isaac Shasa Abibata	Womenu Group	Secretary	0535289624	
Abdulai Manya		Chairperson	0245284041	
Abdulai Sarahi		Box Keeper Vola	102465574417	
Mohammed Sapiri		Key Holder Vocat	0111200221	
Ali Aby !	-	Vice Chairpenson	0139389570	
		Treasurer	0534213470	
				-
+				

Name	Organization/District/Community	Position	Phone No.	Email / Sign
Adams Abdul Matik	Menst Group	Clices	0249517241	and a second
Yakubu Israhak Mahamadu Utili	More Group	Zagyun Ha	18725730	
Abukary Adam		Wulan Bla	0547907685	
Alharran Saibu		Kørna Lana		
Mohammed Israh	1	Tommwitz Mense	0547486747	
Mohammed Lowbaka	7	Member	0241314424	
Mohammed Yahaya			02404961	
101094			0219249715	

No.	flame	Organization/Distr		14.00.0000	Phone No.	Ernsil / Sign	
	Islama Asolul Matik	Tradition	Elden	Clief	0249517241		
_	Takuby Israhaka	~	~	Zagymi Ha	0173575731		
_	srahaka Asdulai	~		Wylan Bla	0599302119		
	Mahamady HIDLI Buka-v Adam			Kpang Lan	9 0042907685		
77	Suka-v Adam	~,	-	Tomorristy Men	4 0249249715		
+							
\dagger							
T							
L							
_				4	,		
_							
_							
_							

SAL CONSULT LIMITED STAKEHOLDER MEETING ATTENDANCE SHEET Title of hoject: Obste: 14 104 1 2025 Time: 12:05 pm Venue: Gharia Haboral Fre terrieg Trimale. No. Name Organization/District/Community Position Phone No. Emill / Sign I I Israec Office Dodob GNF-S Hehrin. Officer 0247827629

Name	Organization/District/Community	Position	Phone No.	Email / Sign
. Adam Adul Somed		Cheipason	0840347921	
Abdul Rahim Yakubu		Key holder	0733251028	
3. Acdul Kainm Asacs		Member	0142644629	
for Yaxubu Amin		Menuser	0040658186	
· Nasifa Alhaman			024801489	
S. Azimpaga Alhavan			754284250	
Abubakan Safura			0598134306	
- Asarah Yakubu			059812660-6	
			-	
-				
		48	1	

SAL CONSULT LIMITED STAKEHOLDER MEETING ATTENDANCE SHEET Title of Project: Date: 141012025 Time: 9:00 PM Venue: Lands Commission

Vo.	Name	Organization/District/Community	Position	Phone No.	Email / Sign
	Mohammed Alhason	Lande Commission	Assistant Secretary	0242081543	
	(2)			1	
	1				
1					
1			10		
1					
1					