

TABLE OF CONTENT

OF CONTENT	
F FIGURES	III
F TABLES	ıv
NYMS AND ABBREVIATIONS	VI
TIVE SUMMARY	VII
OBJECTIVES	VII
COMPONENTS AND MAIN ACTIVITIES	VII
PROJECT ACTIVITIES IN THE TINDUATUA VALLEY (MION DISTRICT)	VIII
ANALYSIS OF ALTERNATIVE PROJECT OPTIONS	x
INSTITUTIONAL AND LEGAL FRAMEWORK FOR IMPLEMENTATION OF THE PROJECT	XIV
BRIEF DESCRIPTION OF THE PROJECT LOCATION IN MION DISTRICT	XIX
INTRODUCTION	1
BACKGROUND OF THE PROJECT	1
THE ESIA REPORT CONTENT AND STRUCTURE	3
PROJECT DESCRIPTION	4
Project Location	4
Project Components	7
Project Activities	10
ANALYSIS OF ALTERNATIVES	13
POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK	19
	10
NATIONAL POLICIES AND PLANS	19
	F TABLES IVMS AND ABBREVIATIONS TIVE SUMMARY

4.2.	1 Agriculture Sector Legislation and Related Requirements	26
4.2	2 Local Governance and Planning Requirements	26
4.2	National Labour, Environmental Quality, Health, Safety and Social Guidelines	28
4.3	National Institutional Framework	31
4.4	International Policies and Conventions	34
4.4.	1 African Development Bank Operational Safeguards	34
4.4.	2 International Conventions	39
5.0 E	NVIRONMENTAL AND SOCIAL BASELINE CONDITIONS	41
5.1	MION DISTRICT BASELINE CONDITIONS	41
5.1.	1 Physical Environment	41
5.1	2 Biological Environment	52
5.1	3 Socio-economic Environment	54
5.2	CHARACTERISTICS OF THE PROJECT SITE (TINDANTUA VALLEY)	58
5.2.	1 Air Quality	59
5.2	2 Ambient Noise	63
5.2	3 Water Resources	65
5.2.	4 Soil, Vegetation and Biodiversity	70
5.2.	5 Socio-economic Environment – Project site (Tindantua Community)	82
6.0 S	TAKEHOLDER CONSULTATIONS	86
6.1	OBJECTIVES OF THE CONSULTATIONS	86
6.2	STAKEHOLDERS CONSULTED AND CONCERNS RAISED	86
6.3	Public disclosure	95
6.4	GRIEVANCE REDRESS MECHANISM	95
7.0 P	OTENTIAL ENVIRONMENTAL AND SOCIAL ISSUES AND IMPACTS	100
7.1	IMPACT ASSESSMENT	101
7.1.	1 Identification of Potential Environmental and Social Issues and Impacts	101
7.1	2 Evaluation and Interpretation of Impacts	101
7.1	3 Mitigation and Control	106
7.2	POTENTIAL ENVIRONMENTAL RISKS AND SOCIAL ISSUES	106
7.3	PROJECT AREA OF INFLUENCE (AOI)	106
7.3.	1 Environmental Area of Influence	107
7.3	2 Social Area of Influence	107
7.4	COMMUNITY INFLUENCE AND VULNERABLE GROUPS	107
7.5	INSTITUTIONAL INFLUENCE	108
7.6	POTENTIAL POSITIVE IMPACTS	108
7.6.	1 Creation of job opportunities	108
7.6.	2 Increased commerce and boost to local economy	108
7.6.	3 Food security	109
7.6.	4 Adoption of good agricultural practices	109
7.6.	5 Technology transfer	109
7.7	Moderate and Major Negative Impacts	109
7.7.	1 Preparatory Phase: Moderate and Major adverse impacts	113
7.7	2 Construction Phase: Moderate and major adverse impacts	116

	7.3 Operation Phase: Moderate and Major adverse impacts	122
	7.4 Decommissioning Phase: Moderate and major adverse impacts and specific measures	129
	7.5 Cumulative Negative Impacts of the Project	131
8.0	MITIGATION MEASURES	134
8.3	RECOMMENDED MITIGATION MEASURES FOR IDENTIFIED IMPACTS	134
9.0	ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN	150
9.:	ESMP Implementation	
	1.1 Institutional Arrangement and Responsibilities	
9.2	MONITORING AND REPORTING	
9.3	ANNUAL E&S COMPLIANCE AUDITS OF THE PROJECT AND COST	
9.4	NEEDS ASSESSMENT OF THE IMPLEMENTING INSTITUTIONS	
	4.1 Key Institutions	
	4.2 Institutional Roles, Capacity Gaps and Recommendation	
	4.3 Capacity Building Approach and Training Needs	
	4.4 Environmental and Social Monitoring Approaches	
	4.5 Technical and Operational Capacity	
	4.6 Coordination and Accountability	
	ESTIMATED BUDGET TO	
9.!	IMPLEMENT ESMP	
10.0	DECOMMISSIONING	179
10	Pre-Decommissioning Assessment	179
10	DECOMMISSIONING PHASE ACTIVITIES	179
	0.2.1 Dismantling and Removal of Structures and Equipment	179
	0.2.2 Solid Waste Management	180
10	Post-Decommissioning Assessment	180
11.0	CONCLUSION	181
12.0	BIBLIOGRAPHY	182
13.0	ANNEXES	183
LIST	FIGURES	
Eicus	-1: Map of Ghana showing the beneficiary districts including Mion	-
	-2: LOCATION MAP OF MION DISTRICT SHOWING THE TINDANTUA VALLEY	
	-1: UNIMODAL RAINFALL REGIME OF NORTHERN GHANA, REPRESENTED BY TAMALE, 1960–2010.	
	-2: Mean annual rainfall total and standard deviation for northern Ghana	
	-3: AVERAGE MONTHLY RAINFALL	
	-4: AVERAGE MONTHLY MINIMUM AND MAXIMUM TEMPERATURE	
	-5: AVERAGE MONTHLY RELATIVE HUMIDITY	
	-6: AVERAGE TOTAL SUNSHINE HOURS	
	-7: AVERAGE MONTHLY WIND SPEED	

FIGURE 5-8: GROUND WATER POTENTIAL ZONES IN THE NORTHERN PART OF GHANA	46
FIGURE 5-9: ELEVATION MAP OF THE MION DISTRICT	48
FIGURE 5-10: DRAINAGE MAP OF THE MION DISTRICT	49
FIGURE 5-11: SOIL MAP OF THE MION DISTRICT	51
FIGURE 5-12: VEGETATION MAP OF THE MION DISTRICT	53
FIGURE 5-13: GRAPH SHOWING COMPLIANCE AND OR EXCEEDANCE OF PARTICULATES TO GSA/WHO STANDARDS	61
FIGURE 5-14: DAYTIME AMBIENT NOISE LEVELS MEASURED AT THE VALLEY	65
FIGURE 5-15: GRAPH SHOWING IN-SITU MEASUREMENT OF TEMPERATURE	67
FIGURE 5-16: GRAPH SHOWING IN-SITU MEASUREMENT OF PH	67
FIGURE 5-17: GRAPH SHOWING IN-SITU MEASUREMENT OF ELECTRICAL CONDUCTIVITY	68
FIGURE 5-18: GRAPH SHOWING IN-SITU MEASUREMENT OF TOTAL DISSOLVED SOLIDS	68
FIGURE 5-19: GRAPH SHOWING IN-SITU MEASUREMENT OF DISSOLVED OXYGEN	69
FIGURE 5-20: GRAPH SHOWING IN-SITU MEASUREMENT OF TURBIDITY	70
Figure 5-21: Age range of respondents	82
FIGURE 5-22: A PIE CHART SHOWING DISABILITY STATUS OF HOUSEHOLDS	83
FIGURE 5-23: SECONDARY SOURCE OF INCOME FOR RESPONDENTS	84
FIGURE 6-1: PROCEDURE FOR GRIEVANCE REDRESS	98
FIGURE 7-1: EIA PROCESS	100
Figure 7-2: Mitigation Hierarchy	106
LIST OF TABLES	
Table 2-1: Project Beneficiaries	4
TABLE 2-2: PROPOSED RICE VALLEYS FOR DEVELOPMENT	10
Table 3-1: Analysis of Alternative Project Options	
Table 4-1: National Policies and Plans	
Table 4-2: National Legal Framework	24
Table 4-3: Agriculture Sector Legislation and Related Requirements	26
Table 4-4: Local Governance and Planning Requirements	27
Table 4-5: National Labour, Environmental Quality, Health, Safety and Social Guidelines	28
Table 4-6: National Institutional Framework	31
Table 4-7: Operational Safeguards of AfDB	34
Table 4-8: International Policies and Framework	39
Table 5-1: List of Health Facilities in Mion District	57
Table 5-2: Environment and Health Protection- Requirements for Ambient Air Quality and Point Sources/S	
EMISSIONS (GS 1236:2019).	59
Table 5-3: NO_2 , SO_2 and CO results measured at the valley compared to GSA and WHO standards	63
TABLE 5-4: CHEMICAL AND PHYSICAL ANALYSIS OF SOIL SAMPLES	
Table 5-5: Coordinates of sampling locations and associated vegetation types	
Table 5-6: Star Rating system	
Table 5-7: IUCN Red List categories	74
TABLE 5-8: SAMPLE PROFILES AND SPECIES COMPOSITION OF TINDANTUA VALLEY	
TABLE 5-9: FLORISTIC ANALYSIS OF TINDANTUA VALLEY	
Table 5-10: Life Form Composition of the Flora	77

TABLE 5-11:ECOLOGICAL GUILDS OF THE FLORA	//
TABLE 5-12: IUCN RED LIST STATUS COMPOSITION OF THE FLORA	78
Table 5-13: Fauna of the Project Area	79
TABLE 6-1: DETAILS OF STAKEHOLDERS IDENTIFIED AND CONSULTED	88
Table 6-2 : Composition of Grievance Redress Committees / Structures	96
TABLE 6-3: GRM IMPLEMENTATION BUDGET SUMMARY	99
Table 7-1: Impact Characteristics	101
Table 7-2: Sensitivity Criteria	103
TABLE 7-3: IMPACT SIGNIFICANCE	105
TABLE 7-4: IMPACT SIGNIFICANCE DEFINITIONS	105
TABLE 7-5: PREPARATORY PHASE POTENTIAL ADVERSE IMPACTS	113
TABLE 7-6: CONSTRUCTION PHASE POTENTIAL ADVERSE IMPACTS	116
TABLE 7-7: OPERATION PHASE POTENTIAL ADVERSE IMPACTS	122
Table 7-8: Decommissioning Phase Potential Adverse Impacts	129
TABLE 8-1: PROPOSED MITIGATION AND MANAGEMENT MEASURES FOR IDENTIFIED IMPACTS	135
TABLE 8-2: BENEFICIAL IMPACTS OF THE PROJECT	149
TABLE 9-1: ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN	151
TABLE 9-2: ROLES AND RESPONSIBILITIES OF KEY ACTORS	163
TABLE 9-3:ENVIRONMENTAL AND SOCIAL MONITORING PLAN	166
TABLE 9-4: INSTITUTIONAL ROLES, CAPACITY GAPS AND RECOMMENDATIONS	172
TABLE 9-5: ESTIMATED BUDGET TO IMPLEMENT ESMP	176
LIST OF PLATES	
PLATE 5-1: THE TINDANTUA VALLEY	59
PLATE 5-2: ARA N-FRM SETUP FOR PM _{2.5} AND PM ₁₀ SAMPLING	60
PLATE 5-3: GASES MONITORING AT THE TINDANTUA VALLEY	62
PLATE 5-4: AMBIENT NOISE MONITORING AT THE PROPOSED TINDANTUA RICE VALLEY	64
PLATE 5-5: SAMPLING AND IN-SITU TESTING AT THE DAKA RIVER	66
PLATE 5-6: TINDANTUA VALLEY – FOREGROUND, LARGELY BARE; ISOLATED TREES IN THE BACKGROUND	72
PLATE 5-7: DEGRADED GALLERY FOREST ALONG DAKA RIVER. TINDANTHA VALLEY, MION	73

ACRONYMS AND ABBREVIATIONS

AEZ Agro-Ecological Zones
AfDB African Development Bank
CBD Central Business District

CITES Convention on International Trade in Endangered Species of Wild

Fauna and Flora

CSIR Council for Scientific and Industrial Research
DCP Decommissioning and Site Closure Plan

DEMC District Environmental Management Committees

EA Environmental Assessment EHU Environmental Health Unit

EIS Environmental Impact Statements
EPA Environmental Protection Authority

ERO ECOWAS Rice Observatory

ESIA Environmental Impact Assessment

ESMP Environmental and Social Management Plan
FASDEP Food and Agriculture Sector Development Policy

FAW Fall Army Worm
FBGs Farmer Based Groups
FBOs Farmer Based Organizations
FID Factories Inspectorate Division

FROGGIE Forest Reserves of Ghana Information Exhibitor

GAP Gender Action Plan

GIDA Ghana Irrigation Development Authority
GMMB Ghana Museum and Monument Board

GNFS Ghana National Fire Service
GRC Grievance Redress Committee
ISS Integrated Safeguards System

LEAP Livelihood Empowerment Against Poverty

MED Metro Education Directorate

METASIP Medium Term Agriculture Sector Investment Plan

MoFA Ministry of Food and Agriculture
MSME Micro Small and Medium Scale Enterprises
NADMO National Disaster Management Organization

NRDS National Rice Development Strategy

OSs Operational Safeguards
PAFs Project Affected Framers
PAPs Project Affected Persons

PCR Project Completion/Technical Review

PIU Project Implementation Unit
PSC Project Steering Committee
RAP Resettlement Action Plan
RCC Regional Coordinating Council

REWARD Resilient Rice Regional Value Chains In West Africa

SDHMT Sub-district Health Management Team SIP Savannah Investment Programme

UNFCCC United Nations Framework Convention on Climate Change

VLD Voluntary Land Donation

VSLA Village Savings and Loans Associations WRC Water Resources Commission

EXECUTIVE SUMMARY

The Resilient Rice Regional Value Chains in West Africa (REWARD) Project is being implemented by the Government of Ghana through the Ministry of Food and Agriculture with the support of the African Development Bank (AfDB) aimed at addressing disruptions in food systems in Ghana.

Specific activities to be undertaken in selected Inland Valleys include but not limited to: development of water control and conveyance systems; construction of drainage systems to collect water out of command areas; construction of access roads into the valleys; and land development for crop cultivation. The programme will also seek to address issues with women and youth drawn from the Gender Action Plan (GAP).

0.1 Objectives

The overall goal of the project is to increase rice production in order to contribute to industrialization, youth employment and food security. The specific objectives of the project are to:

- Increase rice productivity and production thus increased incomes for farmers, particularly women and young people;
- Increase the resilience and adaptive capacities of rice farms and production systems; and
- Increase the marketing and intra-regional trade of rice.

0.2 Components and main activities

The project components and activities comprise:

No	Component	Sub-Component and Activities		
	Name			
1	Production	Sub-component 1.1: Sustainable climate-resilient infrastructure and		
	and	management services in rice production systems		
	Productivity	Key interventions will include:		
		Development of Agricultural Zones		
		Sustainable Land and Water Management (SLWM)		
		Form and build capacity of Water Users Association		
		Social infrastructure development		
		Sub-component 1.2: Improved availability and access to climate-resilient inputs,		
		mechanization services and knowledge		
		Key interventions will include:		
		Seed Delivery Systems		
		Fertilizers and Pest Control Management Systems		
		Agricultural Mechanization Services Delivery		
		Extension Delivery		

No	Component Name	Sub-Component and Activities	
2	Processing and Marketing	 Sub-component 2.1: Modernized processing infrastructure and strengthening capacities of value chain actors This component will focus on: The construction and installation of processing and storage infrastructure to minimise post-harvest losses and enhance value addition. Development of information systems using innovative technologies (incl. digital) and consumer-oriented branding to improve access to market. 	
3	Policy and Governance	 Key activities under this component will include: Support to policy reforms and harmonization at regional/national levels Finalize the National Rice Development Strategy II (NRDS). Organise policy dialogues and workshops to discuss issues relevant to the rice sub-sector. Coordinate activities to ensure synergies among rice value chain stakeholders and projects to boost production, processing, marketing and consumption of locally-produced rice. Enhance control and regulations for agricultural inputs at regional/national levels. 	
4	Programme Coordination and Management	 This component will be responsible for: Day-to-day management of project activities to ensure harmony and coherence. Establishment or nesting of Project Implementation Unit (PIU) under existing PIU to support the coordination and management of the project. Development of Regional and National Management and monitoring systems based on digital technologies to ensure tracking of results at Regional and National levels, and in line with ECOWAS Rice Observatory (ERO). 	

0.3 Project Activities in the Tinduatua Valley (Mion District)

The specific project activities to be implemented in the Tinduatua Rice Valley in the Mion District at the preparatory, construction and operation phases of the project implementation are:

0.3.1 Preparatory Phase

The preparatory phase activities include:

- Identification of beneficiary community and farmers for rice production;
- Conduct of relevant studies, including socio-economic surveys and resettlement related studies;
- Development and Implementation of Environmental and Social Management Plan (ESMP);
- Request for applications and screening of applicant farmers; and
- Assessment of soil suitability and GIS mapping of commercial farms using ICT.

0.3.2 Construction Phase

The construction phase activities will include the following:

• Rehabilitation of existing access routes;

- Construction of mini work camp;
- Vegetation clearance and land preparation;
- Winning of construction materials from borrow pits (site yet to be determined);
- Transportation of materials to and from project site;
- Construction of drainage channels and flood protection works;
- Provision and installation of farm infrastructure such as farm houses and storage facilities;
- Waste disposal (cleared vegetation, construction waste etc.); and
- Decommissioning of mini work camp.

The vegetation will be cleared using suitable machinery for land development to ensure that top soils are not unduly disturbed. Some activities to be undertaken will involve land levelling and In-field bunding. Bunds which are earthen embankments will be created to retain rainfall runoff. The plots will be formed to conform to the direction of the contours, in this way reducing the earth movement during bunding and levelling to the minimum. The levels of the plots will be set to balance cut and fill. Bunding and land levelling will form the major activities in plot formation. Pegging out of plots boundaries to the standard size of plots will be required during the levelling. All levelled plots would be portioned and bunded by in-field contour bunds into plots.

Roads linking valleys to towns which are mostly in deplorable states will be maintained to reduce postharvest losses which has been a major problem confronting farmers. Access roads will be maintained to permit the use of agricultural machinery in the cropping zone to do tillage, deliver inputs and send out produce.

0.3.3 Operation Phase

The operation phase activities include:

- Production and promotion of rice;
- Support for out-grower contractual arrangements;
- Conduct surveillance and collect data on pests attacking the Rice in the project zones with specific reference to FAW;
- Community sensitization, Establishment of fire belts and enforcement of community fire by-laws to deal with the impact of bush fires;
- Promotion of quality standards for rice, maize and soybean production, storage and processing;
- Support business development, including improvements in business processes of existing commercial farmers;
- Enhance access to market information (e.g. quantity, quality, timing and pricing);
- Promote the development of allied services (packaging, new distribution networks for rice products, transport services, new agro-input delivery systems, etc.);
- Support to feed millers to improve feed stock and expand processing capacity;
- Promote the sustainable use of agro-chemicals;
- Enhance investment facilitation and promotion to increase the number of commercial producers and processors in the Savannah regions; and
- Capacity building for women and youth in small-scale commercial rice business management and entrepreneurship, including mentorship.

0.4 Analysis of Alternative Project Options

The proposed project considered some feasible options including:

- Site selection;
- Resettlement related options
- Power supply;
- Sources of water;
- Water Management Systems;
- Waste management; and
- Project implementation versus No Project implementation.

These are further discussed in the table below.

Op	Option/ Method of Potential Environmental, Social, Technological and Economic				
	Deployment	Implica	ations	Preferred Option	
Site Selection					
1.	Tindantua	Advantages Disadvantages		Tindantua was	
	Valley	1. Size of the valley	1. Underdeveloped rice	selected as the	
		2. Potential benefit to farming	fields	preferred valley	
		communities with limited		because of its	
		access to developed rice		potential benefit	
		fields		to many more	
		3. Not a flood prone area		communities. The	
		4. Sparsely vegetated fields		large size of the	
2.	Other Valleys	Advantages	Disadvantages	valley also makes	
		1. Already developed rice fields	1. Relatively small valleys in	it the preferred	
		serving nearby communities	size	choice.	
			2. Valleys susceptible to		
			flooding		
			3. Relatively dense		
			vegetation		
			4. Potential displacement		
			issues		
Res	settlement relate	ed options			
Tin	dantua	Advantages	Disadvantage	The preferred	
		Chief is willing to donate	1. The livelihood of four (4)	option is the	
		land for the project.	farmers will be disrupted.	Tindantua site	
		2. The affected farmers are	2. The affected farmers will	due to more	
		relatively few (4 farmers).	have to trek longer	favourable	
		3. The chief is willing to	distances to access	resettlement	
		provide alternate land for	alternate farmlands	related	
		the affected farmers.	provided by the chief.	conditions.	
		4. There will be no temporary	·		
		or permanent physical			

Op	tion/ Method of	Potential Environmental, Social,	, Technological and Economic	
_	Deployment	Implica	Preferred Option	
		structures to be removed or		
		destroyed.		
Pov	wer supply			
1.	National grid	Advantages	Disadvantages	Solar energy
		1. The cost of electricity is low	1. Unreliable power supply	installations
		decreasing production cost	from frequent power cuts	(Option 2) such as
2.	Solar energy	Advantages	Disadvantages	solar powered
	installations	1. Presents a clean and	Expensive capital cost	pumps are
		sustainable source of		preferred for the
		electricity		pump irrigation.
		2. Low operational costs		
		3. Meets the objective of		
		Technology transfer and		
		climate friendliness		
Sou	urces of Water			
1.	Groundwater	Advantages	Disadvantages	Option 3, which is
		1. Relatively reliable source all	1. Expensive to access and	the use of rain
		year round	abstract	water appears to
		2. Seasonal variations are	2. Challenges of over-	be the most
		minimal	exploitation to meet high	preferred option
		3. Relatively stable water	demands and associated	as it will be easier
		quality	threat of land subsidence	to implement
			3. May require farms of	water
			boreholes to meet	management
			demand	plans
			4. Threat of high iron and	
			fluoride concentration in	
			aquifers in the northern	
			parts of the country	
2.	Surface	Advantages	Disadvantages	
	water	1. Easier to abstract and use	1. Seasonal variations in	
			flow	
			2. Vulnerable to pollution	
3.	Rain	Advantages	Disadvantages	
	harvesting	1. Easy to trap and store	Source is unreliable	
			2. Evaporation losses are	
			high in the dry months of	
			the year	
Wa	iter Managemen	t Systems		
1.	The head-	Advantages	Disadvantages	The preferred
	bund system	1. Water stored in the ponds is	1. Developing of bunds can	option is the
		conserved and can be used	be laborious and may	head-bund

Op	tion/ Method of	Potential Environmental, Social		
	Deployment	, Implica	-	Preferred Option
2.	The central-drain system	for additional irrigation during dry spells because of the small nature of the storage ponds. 2. The technique allows for deep water infiltration into the soil by trapping the water, thereby enhancing the soil's water retention capacity. 3. This system also help to prevent soil erosion and gully formation by reducing the speed and volume of surface runoff. Advantages 1. The water levels in the rice fields, especially those near the central drain, can be controlled to mitigate	demand more manpower if size of farm is huge. 2. Having head-bund system in areas with adequate rainfall or irrigation may cause waterlogging which may affect crop growth. Disadvantages 1. This system is only suitable for areas with high rainfall and not arid conditions.	system as it is ideal for small to medium-sized farms. It also allows for deep water infiltration into the soil by trapping water, thereby enhancing the soil's water retention capacity which is very essential in rice production.
		controlled to mitigate against excessive flooding of the fields. 2. Help reduce soil salinity. 3. With water levels being controlled, crops receive optimal water amounts leading to better growth and yield.	conditions. 2. The central drain can be a conduit for soil erosion if not maintained properly.	
3.	The	Advantages	Disadvantages	
	interceptor- canal system	 In periods of high rainfall, the fields are better protected from any rapid overflow of water from the stream and from the lateral runoff from the uplands. The interceptor-canal system can be used to irrigate the rice fields during dry spells in the rainy season. 	 Water can be lost from the canals through seepage into the ground and evaporation, reducing the overall efficiency of the irrigation system. It can be challenging to distribute water evenly across large areas with this system, as some parts of the irrigated land can receive more water than others. 	

Opt	tion/ Method of	Potential Environmental, Social	, Tecl	nnological and Economic	Buofarrad Oution
	Deployment	Implica	Implications		Preferred Option
			3.	Canals require regular maintenance, such as desilting and repairing leaks, which can be expensive and laborintensive.	
4.	The contour-	Advantages	Dis	advantages	
	bund system	The stream used for irrigation is effectively obliterated and water is allowed to cascade from one levelled area to the next by way of built outlets or spillways to the next field.	1.	Contour bunds are not suitable for uneven or eroded land as overtopping of excess water with subsequent breakage may occur at low spots.	
Wa	ste Managemen	t Option	Ţ		
1.	Composting	Advantages	Dis	advantages	Option 1,
	plant	 Improvements in soil quality. Enhances the structure of the soil. Eco-friendly. Fully organic fertilizer. Higher yields. 	 1. 2. 3. 4. 5. 	Requires initial investment. Efficiency depends on the amount of organic waste May attract rats, snakes, and bugs. Requires space Unpleasant smell	composting is a better option as it is ecofriendly and could be used to improve soil quality on farms. It will also keep waste away from
2.	District	Advantages	Dis	advantages	landfill, which
	Waste Dump/ landfill sites	 Straightforward concept to deal with waste. Filled land can be reused for other community purposes. Landfills can prevent environmental dumping. Good for waste that is non-recyclable. 	1. 2. 3. 4.	Completed landfill areas can settle and requires maintenance. Requires proper planning, design, and operation. Can contribute to groundwater pollution. Landfills can be a breeding ground for bacteria.	already have limited space.
Pro	ject Implementa	tion versus No Project Implementa	tion		
1.	Project Implementati on	 Advantages Enhancing rice production, Strengthening market systems, Improving farmer livelihoods. 	1. 2.	Potential displacement issues Depriving other projects from accessing scarce resources	Project implementation is the preferred option as the benefits outweigh that of the no

Opt	tion/ Method of	f Potential Environmental, Social, Technological and Economic		Preferred Option		
	Deployment		Implicat	tions		Preferred Option
		4.	Supporting research to			project
			produce breeder seeds,			implementation
		5.	Ensuring widespread access			option
			to seed of improved rice			
			varieties.			
		6.	Facilitate the supply of key			
			inputs such as fertilizers and			
			pesticides			
2.	No Project	Ad	vantages	Dis	advantages	
	Implementati	1.	Project resources can be	1.	Food security challenges	
	on		channeled into other	2.	High Cost of Land	
			development programs		Development:	
				3.	Inadequate Irrigation and	
					Poor Water	
					Management.	
				4.	Limited availability of	
					quality breeder,	
					foundation and certified	
					seeds:	
				5.	Inadequate use of	
					Improved Agro Inputs:	
				6.	Inadequate access to	
					mechanized services	
				7.	Poor knowledge of good	
					agronomic practices	
				8.	Poor quality of processing	
					and storage facilities	

0.5 Institutional and legal framework for implementation of the project

0.5.1 Institutional roles and responsibilities

The key stakeholder institutions identified include:

- Ministry of Food and Agriculture;
- Water Resources Commission;
- Lands Commission;
- Environmental Protection Authority;
- Local Government Authority; and
- Traditional Authorities.

Their roles and mandates as well as relevance to the project are summarised as follows:

Institution	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
Ministry of Food and Agriculture (MOFA)	MOFA promotes sustainable agriculture and agribusiness through research and technology development, effective extension and other support services to farmers, processors, and traders for improved human livelihood. The Food and Agriculture Sector Development Policy (FASDEP II) and the Medium-Term Agricultural Sector Investment Plan (METASIP) seeks to guide development and interventions in the agriculture sector. The Resilient Rice Regional Value Chains in West Africa Project (REWARD) of MoFA also seeks to develop agriculture in Ghana in line with the country's efforts at poverty reduction and ensuring food security by promoting inclusive commercial farming along selected commodity value chains.	Regional and District Departments of Agriculture have the mandate of offering extension services and support to ensure sustainability and the successful implementation of the project
Water Resources Commission (WRC)	WRC was established by an Act of Parliament (Act 522 of 1996) with the mandate to regulate and manage Ghana's Water Resources and co-ordinate government policies in relation to them. The Act stipulates that ownership and control of all water resources are vested in the President on behalf of the people, and clearly defines the WRC as the overall body responsible for water resources management in Ghana. The functions of the WRC as established under Act 522 among other things are to: Formulate and enforce policies in water resources conservation, development and management in the country; Coordinate the activities of the various agencies (public and private) in the development and conservation of water resources; Enforce, in collaboration with relevant agencies, measures to control water pollution; and Be responsible for appraising water resources development project proposals, both public and private, before implementation.	The REWARD Project will collaborate with the WRC for the protection of water bodies

Institution	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
Local Government Authority	The Regional Coordinating Council (RCC) and the Metropolitan /Municipal/District Assemblies (MMDAs) are responsible for the overall development of the region and metropolis/municipality/district respectively. Acts 462 and 480, which established the current district assembly structure, designate the District/Municipal/Metropolitan Assembly as the planning authority, charged with the overall development of the district. With regard to environmental management at the district level, the District Environmental Management Committees (DEMC) has been set up by law (Act 462) to among other things: Promote and provide guidelines for the establishment of community-level environmental committees to put	The project is located in the Mion District and will be influenced by decisions and plans of the Northern Regional Coordinating Council and the identified Assembly. The Assembly will play key roles in the successful implementation and related activities of the project.
	 into effect the environmental programmes of the Assembly in the community; and Plan and recommend to the DA, strategies and activities for the improvement and protection of the environment with emphasis on fragile and sensitive areas, river courses etc. 	
Lands Commission	 The Lands Commission was established by Article 258 of the 1992 Constitution and the Lands Commission Act, 2008 (Act 767). The functions of the Lands Commission include amongst others; Advise the Government, local authorities and traditional authorities on the policy framework for the development of particular areas of the country to ensure that the development of individual pieces of land is coordinated with the relevant development plan for the area concerned; Ensure that through sound, sustainable land use planning, socio-economic activities are consistent with sound land use through sustainable land use planning in the long-term national development goals; and Promote community participation and public awareness at all levels in sustainable land management and development practices to ensure the highest and best use of land. 	The REWARD Project will be implemented in line with the objectives of the Commission for sustainable development of land and conform to the development goals of the MMDAs.

Institution	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
Environmental Protection Authority	The EPA is the body responsible for regulating the environment and ensuring the implementation of government policies on the environment. The functions of the Authority include:	The REWARD Project will obtain environmental permit from the EPA and will follow all EPA
	 Ensuring compliance with any laid down environmental impact assessment procedures in the planning and execution of development projects, including compliance in the respect of existing projects; Promoting effective planning in the management of the environment; Imposing and collecting environmental protection levies in accordance with the Environmental Protection Act 2025, Act 1124 or regulations made under the Act; and Acting in liaison and co-operation with government agencies, District Assemblies and other bodies and institutions to control pollution and generally protect the environment. 	procedures in the implementation of the project.
Traditional Authorities	In Ghana, people of common descent owe allegiance to a symbol of collective authority, such as the 'stool' for the Akans of southern Ghana or the 'skin' for the northern peoples. Traditional authorities play a role in the administration of the area. At the village level, family and land disputes and development issues are also traditionally dealt with by the village chief and elders. In addition to providing an important leadership role, especially in the more rural areas, chiefs act as custodians of stool/skin land, can mobilise their people for developmental efforts and arbitrate in the resolution of local disputes. Although chiefs have no direct political authority, some are appointed by the Government or District Assemblies.	The proposed project site falls under the Mamprusi Traditional Council and the Tindantua community that is a key stakeholders in the project.

0.5.2 Policies, Legislative and regulatory requirements for the implementation of the ESMP

The relevant policies and legal frameworks include:

Policies and Plans

- Ghana Shared Growth and Development Agenda, 2010;
- National Environmental Policy, 2012;
- National Land Policy, 1999;
- National Water Policy, 2024;
- National Climate Change Policy, 2013;
- National Gender Policy, 2015;

- Riparian Buffer Zone Policy, 2014;
- Food and Agriculture Sector Development Policy, FASDEPII (MOFA);
- National Environmental Action Plan/Policy, 1994; and
- National Employment Policy, 2012.

National legal framework

- The Constitution of the Republic of Ghana, 1992;
- Ghana Investment Promotion Centre Act 1994, Act 478;
- Environmental Protection Act 2025, Act 1124;
- Environmental Assessment Regulations 2025, LI 2504
- Fees and Charges (Miscellaneous Provisions) Act, 2022 (Act 1080);
- Water Resources Commission Act 1996, Act 522;
- The Water Use Regulations 2001, LI 1692;
- Ghana Meteorological Agency Act 2004, Act 687.

Agriculture sector legislation and related requirements

Plants and Fertilizer Act 2010 (Act 803).

Local governance, planning and other institutional requirements

- Local Governance Act, 2016 (Act 936);
- National Building Regulations, 1996 (LI 1630);
- The State Lands Act, 1962 (Act 125);
- Lands Commission (LC) Act 2008, Act 767;
- Land Use and Spatial Planning Act, 2016 (Act 925)

Labour, Health, Safety, Security and Social Protection

- Labour Act, 2003 (Act 651);
- Occupational Safety and Health Policy of Ghana (Draft, 2004);
- Workmen's Compensation Law, 1987 (PNDCL 187);
- National Workplace HIV/AIDS Policy.

Environmental regulations


- Ghana Standards for Drinking Water (GS 175:2017 5th);
- Ghana Standard for Environmental Protection Requirements for Effluent Discharge (GS1212, 2019);
- Ghana Standards for Environment and Health Protection Requirements for Ambient Air Quality and Point Source/Stack Emissions (GS 1236, 2019);
- Ghana Standards for Health Protection Requirements for Ambient Noise Control (GS 1222, 2018);
- Ghana Standards for Environment and Health Protection Requirements for Motor Vehicle Emissions (GS1219, 2018);
- Factories, Offices and Shops Act, 1970 (Act 328);
- Water Resources Commission (WRC) Act 1996, Act 522;
- Ghana National Fire Service Act, 1997 (Act 537);
- Fire Precaution (Premises) Regulations, 2003 (LI1724).

0.6 Brief Description of the Project location in Mion District

The Tindantua Valley in the Mion District is located in the eastern corridor of the Northern Region of the Republic of Ghana between Latitude $9^{\circ}-35^{\circ}$ North and $0^{\circ}-30^{\circ}$ West and $0^{\circ}-15^{\circ}$ East. The district covers an area of 2714.1 sq.km. and shares boundaries with Yendi Municipal to the East, Tamale Metropolitan and Mion Municipal to the West, Gushegu and Karaga to the North and Nanumba North and East Gonja to the South. The distance from the district capital Sang, to the regional capital, Tamale is about 63km.



Map of Ghana showing the beneficiary districts including Mion



Location map of Mion District showing the Tindantua valley

0.6.1 Environmental and Social Baseline Conditions for the Tindantua Valley (Mion)

Physical Environment

The topography of the Mion is basically undulating with few hills, which provide a good flow for runoff water. Mion is underlain by Voltaian rocks normally suitable for rural water supply - boreholes. During the raining season, water normally drains into rivers, dams and streams present in Mion although there are incidences of large quantities of water collecting on road sides, washing roads out or pooling to prevent proper transportation.

The area is underlain basically by sedimentary rocks of predominantly voltaian sandstone, shales and mudstones. The soils derived from the above parent materials range from laterite, ochrosols, sandy soils, alluvial soils and clay. The organic content is low and is increasingly worsened by the extensive bush burning and bad agricultural practices.

The climate of the district is relatively dry, with a single rainy season that begins in March/April and ends in October. The amount of rainfall recorded annually varies between 750 mm and 1050 mm. The dry season starts in October/November and ends in March/April with maximum temperatures occurring towards the end of the dry season and minimum temperatures in December and January. The Harmattan winds, which occur during the months of December to early February, have considerable effect on the temperatures in the district, which may vary between 14°C at night and 40°C during the day. Humidity, which is very low, mitigates the effect of the daytime heat.

Biological Environment

The area is in the interior Guinea savannah woodland belt and characterized by common grass vegetation with tussocks reaching a height of 3m or more and drought-resistant trees like sheanut (*Vitellaria paradoxa*), baobab (*Adansonia digitata*), dawadawa (*Parkia biglobosa*) and acacia.

The vegetation changes markedly with change in the season and climatic conditions. Many of the rivers flow throughout the year which can support irrigation farming, particularly in the dry season. The sheanut, which is the main export product of the area, still grows in the wild with vegetation largely affected by bush fires, indiscriminate felling of trees for fuel wood, charcoal burning and housing development.

Socio-economic Environment

Administratively, the Mion District is divided into three (3) Area Councils-Sang, Sambu and Kpabia and Twenty (20) electoral areas. Politically the District has one constituency namely Mion Constituency. The District Chief Executive heads the Office of the District Assembly. The District Assembly comprises the District Chief Executive, twenty (20) elected members, nine (9) appointed members and a Member of Parliament who has no voting rights. The Assembly is chaired by a Presiding Member elected from among the assembly members. Out of the twenty-nine (29) Assembly members only one is a female. There is the need to sensitize women to involve in leadership positions and decision making. The Assembly performs its functions through the Executive Committee and a network of sub-committees. The district population, according to the 2021 Population and Housing Census, is 94,930 made up of 47,162 (49%) males and 47,769 (51%) females. This is about 4% and less than 1% of the regional and national population respectively. The population density is 37 persons per sqkm with a total of 15,399 households and an average household size of 6 persons per household which is higher than the regional average of 5.

According to the 2021 Population and Housing Census, the district is predominantly rural with 90% rural population and 11% living in urban areas. With a literate population of only 29%, the district clearly has a very high illiteracy rate.

The economy of the people is largely subsistence with agriculture being their main occupation. Over 95% of the people depend on agriculture for their livelihood. Other economic activities, which are mostly small to medium scale, include weaving, agro-processing (Shea butter extraction), meat processing, fish mongering, wholesale and retail of general goods, transport and many others.

The agricultural potential is enormous as there is suitable land for cultivation of cereals, tubers and rearing of animals such cattle, sheep, goats, pigs and poultry birds for domestic and commercial purposes. Both males and females engage in agriculture but females have no land ownership rights. A good number of the populace is engaged in small scale manufacturing business. They include smock weavers, blacksmiths, bakers, mechanics, shea butter extraction and groundnut oil extraction.

The district has a total of 386 kilometers of road network. 45 kilometers of this is tarred road, which is part of the primary road that connects Tamale, the regional capital, to Yendi, the mother district. The rest of the road network is untarred. Farmers find it difficult to access markets in Yendi, Sang, Tamale, Sambu, Salaga, and Bimbilla, especially during the rainy season, due to the poor condition of the roads.

Land ownership follows a patrilineal system with regards to land inheritance. Accordingly, inheritances can go to the male's sons or brothers. However, a person or a group of people can buy land for construction, farming and other purposes from chiefs and family leaders.

0.6.2 Site Specific Conditions within Tindantua Valley

In addition to the above description, the site specific measurements and observations are summarised below:

Physical Characteristics

Particulate Matter and Gases

Active air quality monitoring was carried out between 7th and 10th April 2025 at the proposed project site, that is within the Tindantua valley. Sampling was done in compliance with the requirements of GS 1236:2019 as shown in the Table below.

Environment and Health Protection- Requirements for Ambient Air Quality and Point Sources/Stack Emissions (GS 1236:2019).

S/N	Air Quality Parameter	Maximum Limits	Averaging Time
1	Carbon monoxide, mg/m ³	10	8 hours
2	Sulphur dioxide (SO ₂), μg/m ³	50	24hours
3	Nitrogen oxides (measured as NO ₂), μg/m ³	150	24hours
4	PM_{10} , $\mu g/m^3$	70	24hours
5	PM _{2.5} , μg/m ³	35	24hours

The sampling and analysis of ambient particulate matter concentrations was done according to the ASTM Test Method D4096-17. Particulate matter ($PM_{2.5}$ and PM_{10}) was sampled at the Tindantua

valley for 24 hours using ARA N-FRM Air Sampler set to a flow rate of 16.7 L/min drawing air through the inlet onto a 47mm quartz filter for analysis.

The Particulate Matter (PM_{2.5}) concentrations monitored at the proposed Tindantua Rice Valley site was 10.0 μ g/m³ which was within both the Ghana Standard (GS 1239:2019) permissible value of 35 μ g/m³ and the WHO 2021 limit of 15 μ g/m³.

The Particulate Matter (PM_{10}) concentration of 16.0 $\mu g/m^3$ recorded at the Rice valley was significantly within both the national ($70~\mu g/m^3$) and international ($45~\mu g/m^3$) thresholds. This suggests that the area experiences limited dust-generating activities. There was no physical activity such as land preparation at the time of sampling. The calm weather and a recent rainfall prior to the sampling day may have also contributed to the low readings. However, the lack of extensive natural vegetative cover and sparse shrubs on the site would contribute to wind induced soil erosion during harsh weather conditions.

Sampling of gases including SO₂, NO₂ and CO was done at the Tindantua site using the Aeroqual A-S500 meter. For SO₂ and NO₂ 24 hour averages were used and 8 hours for CO.

The concentration of nitrogen dioxide (NO₂) recorded at the proposed Tindantua Rice Valley was 0.20 $\mu g/m^3$, which was far below both the Ghanaian standard of 150 $\mu g/m^3$ and the more stringent WHO limit of 25 $\mu g/m^3$. The SO₂ concentration measured at the site was 0.10 $\mu g/m^3$, which is far below the WHO guideline value of 40 $\mu g/m^3$ and the Ghana standard threshold. Carbon monoxide measured at the valley was below the minimum equipment detection limit of 0.06 mg/m³ at the time of sampling. This was well below both the WHO guideline of 4 mg/m³ and the Ghanaian maximum of 10 mg/m³.

Ambient Noise

For the purposes of establishing the ambient noise levels in the proposed project area, a noise assessment was undertaken between 7^{th} and 10^{th} April 2025. Measurements were done with a High Precision TSI Quest Sound Level Meter, Model Type 1 which was calibrated at 114 dB (A) before each measurement. Statistical indices computed include L_{Aeq} , L_{max} , L_{min} and L_{peak} .

Noise level (L_{Aeq}) recorded at the project site (Tindantua valley) is 52.5 dB(A), with a maximum noise level (L_{max}) of 73.3 dB(A), a minimum noise level (L_{min}) of 45.1 dB(A) and a peak (L_{peak}) of 80.6 dB(A).

When compared with the Ghana Standard (GS 1222:2018) and the IFC Environmental, Health and Safety (EHS) Guidelines, which both prescribe a maximum L_{Aeq} of 70 dB for commercial/agricultural zones (Zone E), the measured L_{Aeq} level was well below the permissible threshold. However, the slightly elevated L_{max} and L_{peak} values of 73.3 dB(A) and 80.6 dB(A), respectively are likely caused by intermittent noise events such as passing motorcycles, livestock vocalizations etc. The low L_{min} of 45.1 dB further supports that the background noise level remains undisturbed during most of the day.

Water Quality

The neighbouring water body is the Daka River which was tested for water quality. Parameters measured were temperature, Electrical conductivity (EC), Total dissolved solids (TDS), Dissolved oxygen (DO) and Turbidity and the results compared with the GS 175:2017 and the WHO guidelines

for drinking water. The water is used by the local community for domestic activities like cooking, bathing, washing of clothes and cleaning when there are challenges with the local borehole. Some farmers also use it to water their crops on small plots.

The temperature of the river was measured to be 34.2°C. The in- situ measurement of pH was 6.92 units, which falls within the acceptable range of 6.5 to 8.5 as set by both GS 175:2017 and WHO.

Electrical conductivity (EC) measured was 70.5 μ S/cm, which is lower than the GS 175:2017 limit of 2000 μ S/cm. WHO does not provide a numerical standard for EC but recognizes it as a general indicator of water salinity and dissolved ionic content. The low EC value suggests minimal levels of dissolved salts, indicating good water quality in terms of mineral content.

Total dissolved solids (TDS) measured in the Daka River was 35.1 mg/L, this is well below the GS 175:2017 maximum permissible limit of 500 mg/L.

Dissolved oxygen (DO) concentration in the river was 4.0 mg/L. Although neither GS 175:2017 nor WHO provides a specific guideline for DO in drinking water, levels below 5 mg/L are generally considered inadequate for the survival of many aquatic organisms. A DO level of 4.0 mg/L may indicate moderate organic pollution, possibly due to wastewater discharge or decaying biomass that increases the biological oxygen demand (BOD).

Turbidity recorded was 62.6 NTU, which greatly exceeds both the GS 175:2017 and WHO guideline limits of 5 NTU. This high turbidity level is indicative of a significant presence of suspended particles, likely due to soil erosion, surface runoff, or unregulated waste disposal likely from upstream into the river.

Soil

The project site has marginal, with shallow soil depth as the major limitation with a soil depth <50 cm. The soil texture may be sandy with clay content <6%. The topsoil tend to be droughty, while the subsoil have a high level of gravel and concretions (hard, compact masses). The soils are therefore prone to erosion and have low moisture and nutrient-holding capacity. The status of exchangeable calcium and magnesium may be low and declining.

Biological Characteristics

Flora

The Tindantua valley generally has a flat or gently undulating topography and is subject to seasonal inundation. The two (2) habitat types recognized at the project site are the Seasonally flooded Grassland with isolated trees and the Gallery Forest along the Daka River.

The Seasonally flooded grassland is a tree savannah habitat characterised by isolated trees with open canopy. Crops such as yam and rice are being intensively cultivated in this area in addition cattle grazing. It has been intensively cultivated, with yam and rice being the main crops. Some of the tree species found in this area are *Vitellaria paradoxa*, *Combretum adenogonium*, *Tamarindus indica and Anogeissus leiocarpa*.

The Gallery Forest that is characterised by a broken canopy with a narrow belt of largely degraded gallery forest found along the Daka river bank. This site has farms that extend to other places of the river bank. Some of the trees found in the gallery are *Daniellia oliveri, Diospyros abyssinica and Mitragyna inermis.*

Fauna

Most of the large mammals which were common in the area have moved away due to human activities such as farming and cattle grazing as well as wildfires.

Notable among these are the elephant, lion, leopard, warthog, several parrots, terns, songbirds (passerines), land tortoises, pythons other snakes, lizards, bats, birds of prey, mongooses, bovids (e.g. the African buffalo and several duikers), egrets, ducks, pigeons. A number of the species known to occur in the area are of both national and global (IUCN, CITES) conservation significance.

Conclusion

The results of the survey indicate that none of the floral and faunal species recorded are of conservation concern due to the project area being an extensively modified habitat. The project will therefore have no significant impact on the existing vegetation and fauna as well as their habitat. Few *Vitellaria paradoxa* (shea tree) were observed on the project site. These are commonly found in many other parts of the district.

Socio-economic Characteristics

Farming is the dominant primary source of income for the Tindantua community, with an overwhelming 100% of the thirty- nine (39no.) sampled respondents relying on it. All respondents interviewed identified their ethnicity as Dagomba. This indicates complete ethnic homogeneity within the surveyed sample from the Tindantua community. All respondents (100%) interviewed identified themselves as Moslems. This uniformity suggests that Islam is the predominant religion among those surveyed in the Tindantua community. The majority of the community members rely on borehole as their primary source of water otherwise would resort to the river. Majority of the respondents (95%) report that their household use "No facility/Bush" for sanitation. One household reported having a Flush Toilet (3%). This indicates very low access to improved sanitation.

0.7 Potential Moderate and Major Impacts

The process of determining an impact's significance involves two main steps:

- Assessing Impact Magnitude This is based on extent, duration, scale, and frequency. Magnitude
 is rated as negligible, small, medium, or large for negative impacts, while positive impacts are
 simply noted as beneficial. Judgement and experience guide this evaluation.
- Assessing Receptor Sensitivity This is determined by legal standards, the importance of the receptor, its capacity to absorb change, and its ability to recover.

Once both magnitude and sensitivity are established, a significance rating is assigned using a standard matrix (see Table below), then refined through professional judgement. Significance is classified as negligible, *minor*, *moderate* or *major*.

	Sensitivity			
Magnitude	Low [1]	Medium [2]	High [3]	
Negligible [0]	Negligible [0]	Negligible [0]	Negligible [0]	
Small [1]	Negligible [1]	Minor [2]	Moderate [3]	
Medium [2]	Minor [2]	Moderate [4]	Major [6]	
Large [3]	Moderate [3]	Major [6]	Major [9]	

Key: Negligible – 0 to 1, Minor – 2, Moderate – 3 to 4, Major – 6 to 9

The table below outlines the potential environmental and social issues and their significant impacts associated with the REWARD Project.

Potential Impacts and their significant impact

AfDB No.	Applicable Operational Safeguard	Risk/Impact Description	Magnitude	Sensitivity	Significance		
Preparato	Preparatory Phase						
OS 1	Environmental and Social Assessment	Risk of Poor assessment of environmental and social risks and impacts	Large [3]	High [3]	Major [9]		
OS 5	Involuntary Resettlement, Land Acquisition, Population Displacement and Compensation	Risk of Land related disputes	Medium [2]	Medium [2]	Moderate [4]		
	una compensation	Impact on livelihoods (economic displacement)	Medium [2]	Medium [2]	Moderate [4]		
		Physical Displacement	Small [0]	Medium [3]	Negligible [0]		
OS 6	Biodiversity, renewable resources and ecosystem services	Destruction of vegetation and displacement of wildlife	Small [1]	Medium [2]	Minor [2]		
Constructi	ion Phase						
OS2	Labour conditions, health and safety	Risk of Project site accidents/incidents and animal/insect threat/bites	Medium [2]	High [3]	Major [6]		
		Risk of Poor labour working conditions	Medium [2]	High [3]	Major [6]		
		Risk of Sexual Harassment (SH) and Gender Based Violence (GBV)	Medium [2]	High [3]	Major [6]		
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and Contamination	Medium [2]	Medium [2]	Moderate [4]		
		Air Pollution	Medium [2]	Medium [2]	Moderate [4]		
		Water Pollution	Medium [2]	Medium [2]	Moderate [4]		
		Noise and Vibration	Medium [2]	Medium [2]	Moderate [4]		
		Waste generation and Disposal	Medium [2]	Medium [2]	Moderate [4]		
0S4	Community Health Safety and Security	Risk of poor Traffic Management	Medium [2]	Medium [2]	Moderate [4]		

AfDB No.	Applicable Operational Safeguard	Risk/Impact Description	Magnitude	Sensitivity	Significance
		Risk of Fire outbreak	Medium [2]	Medium [2]	Moderate [4]
		Visual/ Aesthetic Impacts	Medium [2]	Medium [2]	Moderate [4]
		Risk of Public health	Small [1]	High [3]	Moderate [3]
		issues			
		Risk of Security concerns	Small [1]	Medium [2]	Minor [2]
		Risk of Drowning	Medium [2]	Medium [2]	Moderate [4]
Operation	stage				
OS2	Labour conditions, health and safety	Risk of Farm incidents/accidents	Medium [2]	High [3]	Major [6]
		Risk of Poor labour working conditions	Medium [2]	High [3]	Major [6]
		Risk of Sexual Harassment (SH) and Gender Based Violence (GBV)	Medium [2]	High [3]	Major [6]
		Child Labour risk	Medium [2]	High [3]	Major [6]
OS3	Resource Efficiency and Pollution	Soil erosion and	Medium [2]	Medium [2]	Moderate [4]
	Prevention and Management	degradation			
		Air Pollution	Medium [2]	Medium [2]	Moderate [4]
		Water Pollution	Medium [2]	Medium [2]	Moderate [4]
		Noise and Vibration	Medium [2]	Medium [2]	Moderate [4]
		Solid waste generation and disposal	Medium [2]	Medium [2]	Moderate [4]
0S4	Community Health Safety and	Fire Outbreak risk	Medium [2]	Medium [2]	Moderate [4]
	Security	Polluted Waterbodies	Medium [2]	Medium [2]	Moderate [4]
		Sexual Transmitted	Medium [2]	Medium [2]	Moderate [4]
		Diseases risk			
		Risk of Security concerns	Small [1]	Medium [2]	Minor [2]
		Risk of Flooding	Medium [2]	High [3]	Major [6]
		Risk of poor Traffic	Small [1]	Medium [2]	Minor [2]
		management			
		Risk of Drowning	Medium [2]	Medium [2]	Moderate [4]

0.8 Stakeholder Consultations

0.8.1 Stakeholders consulted

Stakeholder institutions and affected communities identified and consulted include the Ministry of Food and Agriculture, Ministry of Lands, PIU, EPA, Fire Service, Mion District Assembly, Commercial farmers, Input Suppliers, Traditional Authorities and Focus Groups (including women and youth) within the project communities.

All stakeholders consulted expressed enthusiasm about the project and indicated their readiness to lend their support for its successful implementation. Below are the key environmental and social issues discussed with the stakeholders.

Employment and Livelihoods

- The project will generate short- and long-term job opportunities for skilled and unskilled local labour, including women. However, unmet expectations regarding opportunities could result in social agitation or unrest.
- Labour and employment issues such as delayed wages, discriminatory practices, or exclusion of women and youth could undermine project credibility.
- Transparent, inclusive recruitment and training plans must be clearly communicated and coordinated with local stakeholders.
- Food Security, Economic Growth and Market Development
 - Project benefits such as food security, and improved access to mechanization and input services which will raise agricultural productivity and income for value chain actors must be shared with stakeholders to obtain their buy-in for a smooth project implementation.
 - The project will stimulate local commerce and attract new investments in processing, marketing, and quality control services.
 - Increased agricultural output will reduce rice imports and help Ghana conserve foreign exchange.
- Knowledge, Capacity Building, and Technology Transfer
 - Training of farmers and stakeholders in good agricultural practices will promote climatesmart farming, reduce losses, and improve resilience.
 - Introduction of modern technologies and digital tools (e.g. RiceAdvice, pest control methods)
 will enhance productivity and efficiency in farming.
- Land Access, Tenure, and Use
 - Farmers and landowners may be either physically or economically displaced by the project and should be engaged extensively on the impacts and mitigation measures including compensation.
 - Improper land acquisition or voluntary land donations which are not transparent and inclusive may lead to disputes and restrict access to traditional lands and resources.
 - Tenant farmers and informal land users may be overlooked in consultation or compensation processes if stakeholder mapping is not comprehensive.
- Water Use and Resource Consumption
 - Water-intensive rice cultivation may increase pressure on local water resources, especially during dry periods.
 - o Inclusive planning and monitoring involving local communities and water user associations are essential to ensure fair and sustainable water use.

Environmental Degradation

- Site clearing and infrastructure development may result in loss of vegetation and some trees.
- Soil degradation and erosion may occur due to land preparation, bare farmlands, and construction activities.
- Dust, emissions, and fumes from construction and operations may degrade local air quality, especially on untarred roads.
- Runoff, domestic waste, chemicals, and effluent may pollute surface and groundwater, affecting aquatic life and users.
- Operation of machinery and vehicle movement will generate noise and vibration, causing nuisance to nearby communities.

Pesticide and Agrochemical Use

- The application of synthetic fertilizers and pesticides poses risks of water pollution, biodiversity loss, and adverse health impacts on farmers and surrounding communities.
- Capacity building is needed for smallholder farmers on Integrated Pest Management (IPM),
 safe handling practices, and the use of environmentally safer alternatives.

Health, Safety, and Labour Conditions

- Workers face risks of injuries, accidents, insect/animal bites, agrochemical exposure, dust-inhalation and equipment-related injuries during construction and operation.
- Poor labour conditions, including lack of contracts and inadequate welfare facilities, may expose workers to exploitation and health risks.
- Fires from negligence or improper burning could cause property loss and injuries.

Social Risks and Community Impacts

- Presence of workers may increase incidents of gender-based violence, rape, and defilement in host communities.
- Pollution and unsafe practices may lead to spread of communicable diseases, including HIV/AIDS and cholera.
- Rising social tensions, theft, confrontations, and conflicts may emerge between workers and locals over cultural, financial, or sexual issues.
- Increased road traffic may cause congestion and accidents due to broken-down or poorly parked haulage vehicles.
- Local communities must be made aware of potential risks and emergency response protocols must be clearly established.

• Gender-Based Violence, Sexual Exploitation and Abuse, and Child Labour

- Labour influx during construction and agro-industrial operations may increase the risk of GBV,
 SEA, and child labour.
- Without strong safeguards, women, girls, and persons with disabilities may face heightened vulnerabilities.
- Community engagement is crucial to raise awareness, strengthen prevention mechanisms, and ensure access to referral and support services.

• Grievance Redress

- The project must implement a well-functioning and accessible Grievance Redress Mechanism (GRM) that all stakeholders can use.
- Existing community grievance structures should be formally recognized and integrated into the broader project-level redress system.

0.8.2 Concerns raised by stakeholders consulted and proposed solutions

Some specific major issues and concerns and their proposed solutions and suggestions/ responses include:

Group of stakeholders	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
Project Implementer	Ministry of Food and Agriculture (Mion District)	 The district MOFA is aware that land has been donated by the chief of Dabogni for the project. The local farmers rely on rainfed agriculture which makes farming less reliable and profitable. The District MOFA must be well-resourced in terms of (finance/logistics) for their extension/ monitoring/ supervisory role. Farmers should be educated and resourced with appropriate farm inputs and machinery to reduce post-harvest losses. Lack of irrigation facilities is a handicap to agricultural productivity There should be ready markets for the rice that will be produced. The road network in the area should be improved to enhance mobility of people and goods. 	The issues raised by the District MOFA were acknowledged and were advised to familiarize themselves adequately with the project documents such as the SEP, PMP, ESMP The project is expected to have a positive impact on community members by creating jobs in the rice value chain and thereby reduce rural migration to non- existent jobs in towns and cities.
Regulatory Institution	Environmental Protection Authority	 Compensation issues should be at the forefront for farmers who may suffer livelihood challenges and this should be addressed in a comprehensive RAP report. There must be valuation of properties if any, as well as compensation for any form of displacement. Environmental permit is required for the project. Biodiversity conservation should be a consideration in the project implementation. There will be periodic field visits by the EPA team to monitor environmental 	The regional EPA was assured that the project will follow all EPA guidelines and that the EPA will be involved in providing monitoring support. Additionally, budgetary provisions will be made for their role.

Group of stakeholders	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
Other	Water Resources	compliance during implementation. • Education on agrochemicals	Concerns of the WRC were
Government Institutions	Commission	use for farmers to avoid pollution of local water bodies.	noted and that Commission will be consulted when/ if the need arises.
	Mion District Assembly	 The Assembly is willing to provide support to any project that will improve the productivity of farmers in the community. Compensation issues are important to the Assembly and must be comprehensively addressed. A grievance mechanism should be established to assist the PIU to resolve complaints and grievances in a timely, effective and efficient manner. Main agricultural challenges in the area are the lack of mechanization and the high cost of agricultural input. There is concern about the inadequate road network and the roads are mostly in poor condition. Assembly members and the beneficiary community leadership should be particularly well sensitized about the project to ensure 	All the relevant stakeholders will be engaged and the ESIA will provide mitigation measures especially for farmers who will be adversely affected by the project implementation. The Assembly will be required to assist in any grievance mechanism measures implemented by the project.
	National Disaster Management Organization, Mion	 effective implementation. Seasonal floods occur regularly during the rainy season leading to loss of farmlands and creating food insecurity concerns. Drought is also experienced during the dry season leading to bushfires. NADMO is concerned that communities farm close to waterways. Project should ensure improved drainage and proper location of facilities 	The challenges of NADMO were noted as well as their importance to the project. Budget will be allocated for the training of fire fighters and community volunteers to handle bush fires as well provide education on the effects of bush fires on the project.

Group of stakeholders	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
stakeholders	Ghana National Fire Service	within the valley to avoid flooding. The project should put measures in place to preserve existing water bodies as this serves as farm boundaries and also help to curb bush fires. The GNFS should be adequately resourced to train fire volunteers from the farming communities. Fire incidents have minimized in recent times due to continuous community education. Main causes of fire include the indiscriminate burning of bushes (i.e. deliberate, postharvest). Most fires occur between the months of November and January leading to loss of income, lives and properties and soil fertility. The local Fire station will be on hand to assist the project when/ if required including involvement in community	The challenges of GNFS were noted as well as their importance to the project. As part of the ESMP, resources will be provided to support the training of community volunteers.
Community based business entities	Small Holder Farmer	 education Common crops cultivated include soybean, maize, rice, sorghum, yam, cassava and groundnut. Urgent needs include tractor service, access to agrochemicals including fertilizers. Concerns about the poor road network need to be addressed. Inputs and credit support will be required for the beneficiaries on the project. Drought and pest resistant seed varieties should be provided for production. Ready market for produce is key to encourage more people to get involved. 	 They group was assured of the benefits that the project offers. Project affected farmers' fears were allayed as an effective RAP will be prepared and implemented Roads leading to project sites will be improved to enhance transportation.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
stakeholders		 Land preparation support is required before planting. Existing farmers on the proposed project site must be compensated if they are to move out. Gender bias/political influences should be avoided in the project implementation. Farmers should be trained on sustainable farm practices by MOFA extension officers. The road in the project area should be improved especially during the rainy season. 	
	Aggregators	 Low purchasing power of farmers. High transportation cost due to poor road network. Lack of access to finance. Inadequate storage infrastructure. There are no formal agreements between aggregators and farmers. Aggregators carry out limited processing of the rice such as cleaning and drying prior to transporting to local markets. 	Concerns were well noted and the group was assured of benefits that the project will bring to their businesses
	Agro Input Dealers	 Main business activities include trading of fertilizers, seeds, chemicals, tools and equipment, sourced from local distributors. Customers are mostly small-holder farmers. Peak season is between March and June of the year. They offer technical advice/training to farmers. Some concerns include difficulty in connecting to suppliers, inadequate storage facilities, high transport cost and lack of access to finance. The agro input dealers mostly source their goods from local distributors on 	The group was advised to intensify their efforts in educating the farmers including the proper disposal of empty agrochemical containers and fertilizers through licensed waste management companies.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
Group of stakeholders Civil Society Organizations (CSO)	Farmer Based Organization (FBO)	cash and carry basis. They are hardly out of stock. All transactions are manual. The project should avoid political biases. Vulnerable groups should be given special consideration during project implementation Traditional authorities are important for the success of the project. Agricultural inputs should be subsidized to ensure	The group was assured that the REWARD project is non-partisan and will require their support in providing advocacy and training.
		 affordability to farmers. Extensive consultation should be conducted to comprehensively address any land reallocation issues. The use of agro-chemicals and the management of waste from organic fertilizers should be properly managed to prevent the contamination of water bodies flowing through the valleys. Farmers are in urgent need of easy access to affordable 	
		finance. • A close cooperation is required between farmers and suppliers, credit/financial services etc. A cooperative arrangement among farmers facilitated by CSOs/ NGOs will be useful • Initiatives by the Rural Enterprise Programme to provide financial support to farmers is a good one which includes business advisory services.	
Community stakeholders	Traditional Authority, Tindantua	 The REP is challenged by high illiteracy levels, difficulty in loan repayment by programme beneficiaries and inadequate finance. Land is predominantly owned by the traditional authorities and mostly used for farming and livestock. 	The project was explained to the leaders to understand the benefits of the project to the project communities.

Group of stakeholders	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
		 Some concerns include conflicts with herdsmen, compensation for displaced farmers, fairness in selection of project beneficiary farmers. They recommend timely supply of seeds and agrochemicals, and improvement in the road network. Incidences of gender-based violence, sexual exploitation or abuse cases are uncommon in the project area. There are usual petty quarrels between members of the opposite sex but these are settled amicably by family heads/parents or traditional authority depending on which is readily available and accessible. 	 The assistance of the leaders were sought to ensure cooperation from affected farmers. The leaders were thanked for donating their lands for the project. The LEAP will be implemented to support vulnerable persons who may be affected by the project e.g. bicycles will be given to farmers to aide in transportation to their farms. The Grievance redress mechanism will be put in place to ensure farmers benefit and no one suffers from the project implementation.
	Womens' Group	 Women are mostly vulnerable and will require special assistance from the project. Concerns include difficulty in accessing ready market for farm produce, lack of processing facilities. Local groups include VSLA which provide some financial support to the women. Vulnerable households mostly receive support from Livelihood Empowerment Against Poverty (LEAP). 	 The womens' value to the community was acknowledged and as such, the project has been designed to benefit women and encourage their full participation. There will be no room for sexual harassment and in the unlikely event of that happening, the case should be reported to the relevant authorities.
	Men's Group	 Main source of livelihood is farming and rearing of livestock. Deforestation has contributed to unreliable rainfall patterns and has affected the planting (June – December). Their top concerns are the poor road network, lack of access to potable drinking water and financial support. 	 The group's concerns were acknowledged and they were assured of job opportunities from the project. In addition, local persons will be considered first for any job opportunities. The group was advised to follow the grievance redress process to address any concerns.

Group of stakeholders	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
		 They have confidence in the extension support service and that must be made more effective. Processing facilities are needed to support their farming activities. 	
	Youth group	 The youth are willing and available to participate in the project as this will help to reduce unemployment and alleviate poverty. Ready markets for the rice produce will be required to ensure reliable flow of income. Irrigation is necessary to make the project more effective and sustainable. Extension officers should play a major role in the implementation of the project. 	 The youth were assured of job opportunities that may arise from the project. Local community members will be considered first for any job opportunity provided there is the capability The group was advised to be conversant with the grievance redress process to address any concerns.

0.9 Environmental and Social Management Plan (ESMP)

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
Prepa	ratory Phase											
OS1	Environmental and Social Assessment	Risk of Poor assessment of environmental and social risks and impacts	Unidentified risks and impacts could prevent or stall project implementation. Selection of unqualified persons for assessment studies	Project proponent (MoFA), environment, community	Major [9]	 Detailed and high quality assessment of environmental and social risks Selection of qualified ESIA consultant Environmental permit acquisition 	• PIU	358,000/33,966 35,000/3,321	Lender	Project E&S Instrument s (ESIA, RAP, SEP, PMP)	E&S Report Permit	Apr – Sep 2025 31 st Oct 2025
OS5	Involuntary resettlement, land acquisition, population displacement and compensation	Risk of Land related disputes	Proposed site is owned by the chief of Tindantua.	Farmers; Community	Moderate [4]	 Acquire signed Voluntary Land Donation (VLD) forms Provide training on completion of VLD forms 	PIU ESIA Consultant	2,000/190 2,500/237	Lender	Signed VLD	Signed VLD	Sep 2025
		Impact on livelihoods (economic displacement)	The project activities could restrict four (4) farmers access to lands that were otherwise used for farming.	Project affected Farmers	Moderate [4]	 Develop a Resettlement Action Plan (RAP)/ Livelihood Restoration Plan Implement the Resettlement Action Plan (RAP) 	RAP ConsultantPIU	80,000/7,590 39,520/3,750	PIU/Lender Lender	RAP Report RAP Implement ation report	RAP Report RAP Implement ation audit	Sep 2025 Qtr 1, 2026
						Build PIU's capacity for RAP implementation	RAP Consultant	20,000/190	PIU/Lender	Training for RAP implement ation team	Training reports	Qtr 1, 2026
OS6	Biodiversity, renewable resources and ecosystem services	Removal of vegetation and displacement of wildlife	The project site is an already disturbed area due to previous human activities such as farming. The floristic analysis conducted indicates that none of the species identified at the site are of conservation concern according to the Forest Reserves of Ghana Information Exhibitor (FROGGIE) data base. Site clearing will not lead to any major destruction of biodiversity of significant importance, only a few trees and destruction of the habitats of some animals.	Flora and Fauna	Minor [2]	Restrict vegetation clearance to the required area only and prohibit hunting of animals which may stray to the project area by providing temporary fences. This must be included in the contractor's bill of quantities and code of Conduct. Train contractor's E&S Officer on ESMP requirements	• Contractor • PIU	20,000/1,900	PIU	Installation of Fence Training for	Physical inspection Training reports	Before construction Before construction

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
Const	ruction Phase											
OS 2	Labour conditions, health and safety	Risk of Project Site incidents/accidents	Project site accidents/incidents and animal/insect threat/bites	All Project workforce, Vulnerable categories of workers, Women	Major [6]	Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training	Project Contractor	50,000/4,744	PIU	Records and purchase of PPEs, training on PPE use, house- keeping, emergency response etc.	Review of CESMP OHS audits	Before construction During construction
		Risk of Poor labour working conditions	Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions. Workers could face issues of discrimination, forced labour, child labour, freedom of association and collective bargaining, lack of or ineffective worker grievance redress mechanisms	workforce,	Major [6]	 Adhere to national labour laws as provided in the Labour Act of 2003 (Act 651) and international best practice such as provisions of AfDB ISS (2023) OS 2 on Labour and Working Conditions Specific considerations should include the following: Provide all workers with signed contracts Provide welfare facilities as required. Encourage frequent breaks and job-rotation to reduce impact of the hot weather on workers. Require workers to sign Code of Conduct Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. Provide adequate training for workers on safety, GBV, SEA/SH, child labour/human rights, social norms. Establish an effective worker grievance redress mechanism 	Project Contractor	120,000/11,385	PIU	Signed contract, welfare facilities, Grievance redress mechanism / records	E&S audits	During construction
		Risk of Sexual Harassment (SH) and Gender Based Violence (GBV)	Presence of workers and increase in incidents of rape, defilement, child molestation and GBV.	Women, Children	Major [6]	 Include the requirements of policies on GBV, SEA/SH, Child Labour and Human Rights in the contractor's Code of Conduct Provide training for workers on required lawful conduct and legal consequences for failure to comply 	Project Contractor	80,000/7,590	PIU	Clauses on GBV, SEA/SH, Child Labour and Human Rights in the	Review of contractor' s code of conduct	During construction

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
						with laws on non-discrimination and GBV Insert clause requiring contractors and consultants to cooperate with law enforcement agencies investigating cases of gender-based violence A minimum requirement of female employment should be indicated in contract documents Contact numbers of representative on the Grievance Redress Committee and GBV Service Providers should be pasted around the project site and within the immediate project zone Discuss issues of Gender Based Violence at daily Toolbox meetings Display on site posters prohibiting sexual exploitation and harassment.				contractor's Code of Conduct		
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and Contamination	Excavation for foundation of structures could lead to soil erosion and creation of gullies through runoff	Soil	Moderate [4]	Develop an Erosion Management Plan	Contractor	50,000/4,744	PIU/Lender	Erosion Manage- ment Plan	Inspection/ review	Before construction
			especially in the rainy season Soil contamination could also occur from			Implement the Erosion Management Plan	Contractor	100,000/9,488		Sediment traps	Inspection	During construction
			inappropriate disposal of waste oil, spilled oil during machinery operation and maintenance as well as fuel storage sites and leaks from vehicle refuelling			 Train contractor's E&S Officer on ESMP requirements 	PIU	20,000/1,898		Training on erosion manageme nt	Training records	During construction
		Air Pollution	Emission of fumes and dust from transport of materials especially on untarred routes to project site. Baseline air quality data (PM _{2.5} – 10µg/m³, PM ₁₀ – 16µg/m³, NO ₂ – 0.2µg/m³, SO ₂ – 0.1µg/m³) shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds hence emissions from project activities such as transportation of materials must not result in	workers and members of the surrounding	Moderate [4]	 Trucks and heavy machinery with a valid emission test pass certificate should only be allowed on the project site. Dust pollution must be reduced by ensuring that drivers do not speed especially on untarred roads. Suppress dust by watering dusty construction areas. Ensure the use of nose mask in dusty environment. 	Project Contractor	60,000/5,693	PIU/ Supervising Engineer	Valid emission test certificate Speed limit signage Wet road surfaces Complaints /grievances	Inspection	During construction

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			significant air quality deterioration									
		Water Pollution	Sediment and waste oil transport into nearby water bodies. Domestic waste from the construction workers and food vendors providing	The Daka river water quality and pools of water in the valley.	Moderate [4]	 Undertake construction in the dry season Carry out maintenance activities away from water bodies Install sediment traps Educate workers on the 	Project Contractor	60,000/5,693 10,000/949	PIU/ Supervising Engineer	Sediment traps	Inspection	During construction
			services to the construction crew.			importance of waste management.				Toolbox exercises	Toolbox records	
		Noise and Vibration	equipment, movement of	Health of project workforce and members of the surrounding communities	Moderate [4]	 Ensure construction activities are carried out during the day. Provide and enforce wearing of hearing protection by workers Sensitize workers on effects of 	Project Contractor	20,000/1,898	PIU/ Supervising Engineer	Noise emission levels	Noise monitoring report	During construction
						 noise pollution Ensure the use of well serviced/maintained vehicles and other equipment with acceptable noise emission levels. 				Complaints /grievances	Records of complaints /grievances	
		Waste generation and Disposal	steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog drains and facilitate the outbreak of sanitary related diseases such as cholera.	workforce and members of the Local communities within the project area	Moderate [4]	 Ensure that contractor develops and implements a detailed Construction Waste Management Plan. Ensure efficiency in the use of materials. Reuse materials such as pieces of wood, and metals. Recycle scrap metal Ensure collection and proper disposal of construction debris Provide adequate waste bins for waste collection and segregation Sensitize workers on waste management Develop SOPs for managing hazardous and non-hazardous waste. 	Project Contractor	100,000/9,488	PIU/ Supervising Engineer	Inventory of waste generated/ Disposed of	records/ inventory	During construction
OS4	Community Health, Safety and Security	Risk of poor Traffic Management	Transport of materials and equipment to and from the project site through communities and townships raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage/construction		Moderate [4]	 Avoid transportation of materials and workers during peak hours Train drivers on and ensure adherence to the Highway Code Ensure regular maintenance of vehicles Use flagmen and designated parking areas for safety onsite 	Project Contractor	50,000/4,744	PIU/ Supervising Engineer	Records of traffic incident and accidents Community complaints /grievances	Review/ inspection of records	During construction

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			trucks could lead to road accidents and traffic congestion especially on busy roads.									
		Risk of Fire Outbreak	Fire outbreaks from negligence of workers or the community burning refuse, game hunting and workers not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property.	Local communities near the project	Moderate [4]	 Create fire belts to prevent spread of fire into the active working areas. Sensitize workers and community on the dangers of bushfires Store flammable materials away from fire sources Designate cooking and smoking areas onsite . Provide fire-fighting equipment onsite. Train workers on fire fighting and where applicable include community fire volunteers 	Project Contractor	50,000/4,744	PIU/ Supervising Engineer	Records of fire incidence Training in fire safety and risk	Review/ inspection of records	During construction
		Visual / Aesthetic Impacts	Presence of construction machinery, material stockpiles, temporary work camps; Vegetation clearance, earthworks (bare ground); Dust plumes.	Local communities (Tindantua), commuters.	Moderate [4]	 Maintain tidy construction sites (good housekeeping). Minimize area of land clearance beyond essential footprint. Locate temporary facilities at unobtrusive areas to reduce visibility. Promptly rehabilitate disturbed areas post-construction. (grading, seeding). Ensure permanent structures (patios, sheds) use materials/colours that blend reasonably with the surroundings. 	• Contractor • PIU	20,000/1898	PIU Lender	Site tidiness. Area cleared. Community feedback (via GRM).	Site Inspections , Photograp hic records	During construction
		Risk of Public Health Issues	Pollution of local water bodies (River Daka) will adversely affect the health of users. Sexual relations between workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	Local communities near the project area of influence	Moderate [3]	 Potable water tanks or containers could be used on the project site to keep water for drinking. Sexual harassment or violence on the project site will not be tolerated and project contractor should be made aware of such incidences to ensure that any complaints are addressed in accordance with the law. Undertake sexual health education programs for workers and also ensure they desist from 	Project Contractor	60,000/5,693	PIU/ Supervising Engineer	Potable water tanks on site Records of sensitizatio n of workers on GBV/SH Availability of condoms in washrooms	Physical inspection Review of records Inspection	During construction

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
		Risk of Security Concerns	Violent behaviour and confrontations between workers and locals. Workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over illicit sexual affairs, child labour, drunk driving, accidents and destruction of property.	Local communities near the project area of influence	Minor [2]	irresponsible sexual behaviour during project implementation. Encourage handwashing after work and if possible provide hand sanitizers to workers. Encourage workers to get vaccinated. Provide information, instructions and trainings on STDs, drug abuse etc. to the workers to create awareness. Provide female and male condoms to the community and workers. Sensitize local community on cultural tolerance and grievance mechanisms to prevent confrontations Migrant workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. The contractor should prioritize employing locals especially the youth who may be unemployed which can ultimately lead to unrest or other social vices.	Project Contractor	30,000/2,846	PIU	Availability of hand washing sinks/basin s and sanitizers on site Community meetings Toolbox exercises Number of locally employed workers	Inspection of community meeting minutes Review of toolbox records Inspection of records of locally	During construction
											employed workers	
Onorsti	on Stage	Risk of Drowning	Any borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for workers especially contract staff who are not familiar with the local terrain. Children who may play around the sites and unsuspecting community members may also be at risk of drowning especially when it rains and the place get flooded.	workforce and Local communities near the project	Moderate [4]	 Fence dug outs or borrow pits to prevent drowning. Provide warning signage at borrow pit sites. Sensitize community members on risk of drowning 	Project Contractor	100,000/9,488	PIU	Presence of fence and signage Records of drowning incidents/ accidents Records of community sensitization programmes	Review/ audits of records	During construction

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
OS2	Labour conditions, health and safety	Risk of Farm incidents/accidents	Farm accidents/incidents and animal/insect threat/bites	All Farm workers, Vulnerable categories of workers, Women	Moderate [4]	 Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training Training and sensitization of farmers on the use of PPE, farm implements and agro-chemicals 	•	300,000/28,463	Regional MoFA	Records of training on PPE use, house- keeping, emergency response etc.	Review of ESMP OHS audits	During operation
		Risk of Poor labour working conditions	Lack of employment contracts could lead to farm workers being paid rates below the stipulated national minimum wage or work under poor conditions. Farm workers could be exposed to discrimination, forced and child labour, restriction of freedom of association and collective bargaining, non-existent or ineffective farm worker grievance redress mechanism.	workforce, Vulnerable	Moderate [4]	 Adhere to national labour laws as provided in the Labour Act of 2003 (Act 651) and international best practice such as provisions of AfDB ISS (2023) OS 2 on Labour and Working Conditions Specific considerations should include the following: Provide all workers with signed contracts Provide welfare facilities as required. Encourage frequent breaks and job-rotation to reduce impact of the hot weather on workers. Require workers to sign Code of Conduct Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. Provide adequate training for farm workers on safety, GBV, SEA/SH, child labour/human rights, social norms. Establish an effective grievance redress mechanism for farm 	Community Development	200,000/18,975	Regional MoFA	Number of labour related complaints and grievances	Review of the records	During operation
		Risk of Sexual Harassment (SH) and Gender Based Violence (GBV)	Presence of migrant farm workers could increase incidents of rape, defilement and GBV.	Women	Moderate [4]	workers Provide sensitization and training for farm workers on required lawful conduct, access to GBV service providers and legal consequences for failure to comply with laws on non-discrimination and GBV Farm owners to be encouraged to employ females as farm workers.	Department of Community Development	100,000/9,488	Regional MoFA	Number of recorded incidents of GBV/SH cases	Review of records	During operation

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
		Risk of Child Labour	Employment and deployment of Children under the working age at the expense of their education and exposure to hazards that endanger their health and wellbeing.	Children	Moderate [4]	 Prohibit the employment of children under age 15 on farms. Ensure children who spend time with their parents on the farm do not do so at the expense of their education and well-being. 	District MoFA/ Department of Community Development	50,000/4,744	Regional MoFA	Number of recorded incidents of child labour cases	Review of records	During operation
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and degradation	Abuse of fertilizer use could lead to soil degradation. Leaving farmlands bare especially after harvesting could expose the soil to erosion.	Soil	Moderate [4]	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management.	District MoFA	100,000/9,488	Regional MoFA	Training of farmers on soil, water and nutrient management	-	During operation
		Air Pollution	Use of farm machinery, clearing of dry lands and emission of fumes/dust from tricycles or motorcycles conveying farmers and farm produce especially on untarred routes from farms are some of the activities that have the potential of affecting the air quality within the project area. Stubble burning to prepare the field for the next planting season can also affect the air quality within the project area. Baseline air quality data (PM2.5 – 10µg/m³, PM10 – 16µg/m³, NO2 – 0.2µg/m³, SO2 – 0.1µg/m3) shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds. Hence, emissions from farming activities such as tilling, threshing and transportation of farm produce are not expected to result in significant air quality deterioration.	surrounding community	Moderate [4]	 Practicing No-till or Low-till methods where crop residues are retained on the field or incorporated into the soil can help decompose the stubble naturally, reducing the need for stubble burning. Mobile, small-scale threshers can be used in place of manual threshing so as to reduce the amount of dust or rice chuff emitted into the atmosphere. Minimizing dust generation activities as much as possible especially during windy periods. Vehicle speed, particularly on untarred roads transporting farm produce and agric inputs to and from the farm will be strictly controlled to minimize dust generation. 	District MoFA	100,000/9,488	Regional	Training of farmers on good farming practices	•	During Operation
		Water Pollution	Sediment laden with excess fertilizers and other agrochemicals and waste oil transport into nearby	water quality and other water	Moderate [4]	 Provide education to farmers on the MoFA extension guide on soil, water and nutrient management. There will be proper timing in the 	District MoFA	300,000/28,463	Regional MoFA	Training of farmers on good farming	Inspection	During operation

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			Pollution of watercourses caused by wastes generated by farm workers as well as runoff from land used for growing rice (containing fertilisers, pesticides and herbicides etc.).			 and other agrochemicals considering the crop's nutrient needs and soil conditions in order to maximize fertilizer uptake and minimize leaching and runoff. Implement Pest Management Plan (PMP) Provision of on-site sanitation facilities and encourage the farm workers to use it. Educate farm workers to avoid open defecation. Sediments traps will be designed and constructed within the farm lands to contain contaminated sediments which will later be harvested for producing blocks for building. 						
		Noise and Vibration	Noise from activities like tilling the land for the next planting season, threshing the rice after cultivating and screaming sounds from farmers or labourers to scare away birds can all generate noise. Tricycles and motorbikes conveying farmers and farm produce to the milling factories or markets could generate some noise including the sounds from tooting horns.	and members of communities close to the project area	Moderate [4]	 Scare crows should be encouraged instead of the screaming sounds from farmers or labourers to scare away birds. Use threshing machines with soundproofing devices 	District MoFA	50,000/4,744	Regional MoFA	Sensitization of farmers	MoFA participatio n in community engagemen t meetings	Throughout the operational phase
		Solid waste generation and disposal	Improper disposal of waste, i.e. empty containers of agrochemicals and fertilizers which can serve as breeding grounds for mosquitoes. Threshing will produce rice husk that may pile up to form heaps of waste.	Health of farm workers and the Local community.	Moderate [4]	 Provide education to farmers on the MoFA extension guide on compost production using rice husk, straw, and other organic waste. Provide adequate waste skips to collect empty containers of agrochemicals and fertilizers for disposal by a licenced waste management company. Good housekeeping should be encouraged on farms. Implement Pest Management Plan (PMP) 	District MoFA	75,000/7,116	Regional MoFA	Sensitization of farmers	MoFA participatio n in community engagemen t meetings	operational
OS4	Community Health Safety and Security	Fire Outbreak Risk	Fire outbreaks from negligence of farm workers and community members, burning refuse, game hunting, cooking and not properly extinguishing	nearby vegetation, farm workers and	Moderate [4]	 Create fire belts to prevent spread of fire into the active working areas. Sensitize farm workers and community on the dangers of bushfires 	District MoFA/GNFS/NADMO	100,000/9,488	Regional MoFA	Sensitizatio n of farmers	1	the operational

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
			stubs of cigarette. These fires could spread to adjoining farms causing injuries to persons and destruction of property.			 Store flammable materials away from fire sources Designate cooking and smoking areas on farms. Provide fire-fighting equipment onsite Train farm workers on fire fighting and where applicable include community fire volunteers 					MoFA/GNF S and NADMO.	
		Poor Traffic Management risk	Transportation of farmers and farm produce through communities raises traffic/public safety concerns.	Local communities	Minor [2]	 Drivers should exercise caution when driving through crowded areas such as markets. Installation of speed rumps to check speeding vehicles. Identify safe parking areas off main roads to allow for unloading and long-term parking of vehicles. 	MoFA/Assembly	50,000/4,744	PIU/Supervisi ng Engineer	Records of traffic incident and accidents Community complaints /grievances	MoFA and Assembly participatio n in community engagemen t meetings	Throughout the operational phase
		Risk of Security Concern	Violent behaviour and confrontations between migrant farm workers and locals. Farm workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over sexual affairs, child labour, drunk driving, accidents and destruction of property.	Farm workers and Local communities	Minor [2]	 Sensitize local community on cultural tolerance and grievance mechanisms at community durbars to prevent confrontations Migrant farm workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. Farm owners should prioritize employing locals into their farms especially the youth who may be unemployed which can ultimately lead to unrest or other social vices. 	MoFA/Assembly	30,000/2,846	PIU/Supervisi ng Engineer	Records of traffic incident and accidents Community complaints /grievances	MoFA and Assembly participatio n in community engagemen t meetings	Throughout the operational phase
		Polluted Waterbodies	Pollution of local water bodies from contaminated sediments and run-off will adversely affect the health of community members.		Moderate [4]	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management. Educate farm workers to avoid open defecation.	District MoFA	50,000/4,744	Regional MoFA	Sensitizatio n of farmers	MoFA participatio n in community engagemen t meetings	operational phase
		Risk of project induced Sexual Transmitted Diseases	Sexual relations between migrant farm workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	and Local	Moderate [4]	Undertake sexual health education programs for farm workers to desist from irresponsible sexual behaviour.	District MoFA/ District Health Directorate	50,000/4,744	Regional MoFA	Sensitizatio n of farmers		operational

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
		Risk of Flooding	The project implementation could be adversely affected by events of flood from torrential rainfall in the wet season especially in low-lying areas affecting properties and lives.	Farmers, Local community, Flora and Fauna	Major [6]	 Educate farmers and community on early warning signs of flood. Discourage the siting of farms within or close to river beds. Collaborate with spatial planning and disaster management agencies, using disaster maps and systems, to stay away from flood-prone areas. Infrastructure for agricultural establishments should be constructed preferably on high grounds. Sensitive farmers on the benefits of insurance cover for equipment and personnel. 	MoFA/Assembly/NA DMO	150,000/14,231	Regional MoFA	Sensitizatio n of farmers	Participatio n in community engagemen t by MoFA, the Assembly and NADMO.	the
		Risk of Drowning	Any burrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for communities in the project area especially children.	1	Moderate [4]	 Maintenance of dug outs or borrow pits fence to prevent drowning. Provide and replace warning signage at borrow pit sites when necessary. Sensitize community members on risk of drowning 	District MoFA	50,000/4,744	Regional MoFA	Sensitizatio n of community members/f armers	Participatio n in community engagemen t by MoFA.	
Decor	nmissioning Phase		<u> </u>									
OS2	Occupational health and safety (OHS) impacts and risks	Risk of Project Site incidents/accidents	animal/insect threat/bites	workforce, Vulnerable categories of workers, Women		Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training	Project Contractor	50,000/4,744	PIU	Records and purchase of PPEs, training on PPE use, housekeepi ng, emergency response etc.		after construction
OS3	Resource Efficiency and Pollution Prevention and Management	Waste generation and Disposal	' ' '	workforce and members of the Local communities within the	Moderate [4]	 Ensure efficiency in the use of materials. Reuse materials such as pieces of wood, and metals. Recycle scrap metal Ensure collection and proper disposal of construction debris Provide adequate waste bins for waste collection and segregation Sensitize workers on waste management 	Project Contractor	120,000/11,385	PIU	Inventory of waste generated/ Disposed of	Inspection/ review of records/ inventory	Immediately after construction

AfDB No.	AfDB OS Description	Risk/Potential Impact	Risk/ Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verification	Timetable for Implementati on
OS4	Community Health and Safety	Poor Traffic Management risk	Transport of materials and equipment to and from the project site through communities and townships raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage/construction trucks could lead to road accidents and traffic congestion especially on busy roads.	communities	Moderate [4]	Develop SOPs for managing hazardous and non-hazardous waste. Develop and ensure implementation of Pest Management Plan (PMP) Avoid transportation of materials and workers during peak hours Train drivers on and ensure adherence to the Highway Code Ensure regular maintenance of vehicles Use flagmen and designated parking areas for safety onsite.	Project Contractor	50,000/4,744	PIU	Records of traffic incident and accidents Community complaints /grievances	Review/ inspection of records	Immediately after construction

0.10 Environmental Monitoring

No.	Potential Environmental and Social Impacts/Risks	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
CONS	STRUCTION PHASE					
1	Project site accidents/incidents risk	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Tindantua valley	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
2	Poor labour working conditions risk	 Availability of copies of signed contracts Human Resource Management Plan/Recruitment Policy Complaints lodged by workers 	• Tindantua valley construction site	Quarterly	PIU Environmental and Social Safeguards Specialists	31,620 (3,000)
3	Soil impacts and sediment transport	 Observable change in turbidity of water in drains or water bodies Observable oil sheen in drain Observation of rills/gullies 	• Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental Safeguards Specialist	42,160 (4,000)
4	Air and Noise Pollution	Number of complaints by community members/workers	• Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental Safeguards Specialist	52,700 (5,000)
5	Waste generation and inefficient management	 Number of mobile toilets and dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site 	Tindantua valley construction site and Immediate environs	Weekly	PIU Environmental Safeguards Specialist	26,245 (2,490)

No.	Potential Environmental and Social Impacts/Risks	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
		Complaints by workers/community members				
6	Traffic accident risks/Public safety concerns	 Grievance records Traffic related incidents/accidents Records of accidents, incidents and near misses. 	Tindantua valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
7	Risk of Fire outbreaks	 Fire related incidents/accidents Records of fire incidents and near misses. Number of functional fire extinguishers onsite 	Tindantua valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
8	Visual / Aesthetic Impacts	Site tidiness.Area cleared.Community feedback (via GRM).	Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	5,375 (510)
9	Risk of Public health issues	 Number of sensitization campaigns Number of condoms distributed to Contractor's staff in a month Number of STD cases reported to local health facilities involving encounters with Contractor's staff 	Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	47,430 (4,500)
10	Security and SH/GBV concerns risks	Number of conflicts/cases reported to the Grievance Redress Committee/Community Liaison Officer	Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	36,890 (3,500)

No.	Potential Environmental and Social Impacts/Risks	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)	
		 Number of conflicts/cases dealt with by the Grievance Redress Committee Number of crimes such as theft, defilement and rape reported, investigated, and concluded by the police involving the Contractor's workers 					
Sub Total							
OPER	ATIONAL PHASE						
1	Farm accidents/incidents risk	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Tindantua valley Farm	Monthly	District MoFA Extension officers/ Regional MoFA	31,620 (3,000)	
2	Poor labour working conditions risk	 Availability of copies of signed contracts Complaints lodged by farm hands and other workers 	Tindantua valley Farm	Monthly	District MoFA Extension officers/ Regional MoFA	42,160 (4000)	
3	Soil impacts and sediment transport	 Observable change in turbidity of water in Daka river Observable oil sheen in Daka river Observation of rills/gullies 	Tindantua valley Farm and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	52,700 (5,000)	
4	Air and Noise Pollution	Number of complaints by community members/farmhands	Tindantua valley Farm and community	Monthly	District MoFA Extension officers/ Regional MoFA	31,620 (3,000)	

No.	Potential Environmental and Social Impacts/Risks	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
5	Waste generation and inefficient management	 Presence of toilet facilities and number dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site Complaints by farm workers/community members 	Tindantua valley Farm and immediate environs	Weekly	District MoFA Extension officers/ Regional MoFA	52,700 (5,000)
6	Traffic accident risks/Community safety concerns	 Grievance records Traffic related incidents/accidents Records of all accidents, incidents and near misses. 	Tindantua valley Farm/ community and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	52,700 (5,000)
7	Risk of Fire outbreaks	 Fire related incidents/accidents Records of fire incidents and near misses. Number of functional fire extinguishers onsite 	Tindantua valley Farm and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	31,620 (3,000)
8	Risk of Community health issues	 Number of sensitization campaigns Number of condoms distributed to farm workers or placed at convenient places in a month Prevalence of STD cases reported to local health facilities 	Tindantua valley Farm/ Tindantua community and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	47,430 (4,500)
9	Security and SH/GBV concerns risks	 Number of conflicts/cases reported to the Grievance Redress Committee/Community Liaison Officer Number of conflicts/cases dealt with by the Grievance Redress Committee 	Tindantua valley Farm/ Tindantua community and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	36,890 (3,500)

No.	Potential Environmental and Social Impacts/Risks	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year GHS (USD)
		 Number of crimes such as theft, defilement and rape reported, investigated, and concluded by the police involving workers or patrons 				
10	Risk of Drowning	Number of drowning cases reported and investigated involving unsuspecting community members and animals.	Dugout (from the previous sand winning site now used as water source)	Weekly	District MoFA Extension Officers, District Assembly/ Regional MoFA	31,620 (3,000)
Sub-t	411,060 (39,000)					
DECC	MMISSIONING PHASE					
1	Risk of Project site accidents/incidents	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Tindantua valley	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
2	Waste generation and inefficient management	 Number of mobile toilets and dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site Complaints by workers/community members 	Tindantua valley construction site and Immediate environs	Weekly	PIU Environmental Safeguards Specialist	31,620 (3,000)
3	Traffic accident risks/Public safety concerns	Grievance records Traffic related incidents/accidents Records of accidents, incidents and near misses.	Tindantua valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700 (5,000)
Sub-t	otal	1	1		<u>'</u>	137,020 (13,000)

N	lo.	Potential	Monitoring Indicators/Means of	Monitoring Site	Frequency	Responsibility	Cost Estimate/ Year	
		Environmental and	verification			(Implementation/	GHS (USD)	
		Social Impacts/Risks				Monitoring)		
T	TOTAL COST FOR MONITORING							

0.11 Institutional capacity to implement ESMP

The capacity assessment presented in the table provides a description of institutional roles, their existing capacities, the gaps that may hinder performance, and actionable recommendations to close these gaps. The responsibility and budget to implement the recommendations have been included in the ESMP budget.

Institutional Roles, Capacity Gaps and Recommendations

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
MoFA (District &	Lead	Regional/district	Weak safeguards	Provide intensive
Regional)	implementer;	offices have limited	integration at	training on safeguards
	coordination,	environmental and	local level; and	compliance;
	extension,	social safeguards	limited tools for	Supply digital data
	safeguards	knowledge.	monitoring	collection tools;
	compliance	However, national		Integrate ESMP
		divisional office has		indicators into MoFA
		stronger capacity		M&E systems
Project	Safeguards	Adequately staffed	Limited	Strengthen
Implementation	oversight and	with environmental	operational	coordination
Unit (PIU)	project	and social	linkages with	platforms with MoFA,
	management	safeguards officers	district	EPA, and District
			institutions	Assembly; and
				formalize reporting
				schedules
EPA (Regional	Regulatory	Strong technical	Inability to	Engage EPA to
Office)	oversight; and	expertise, but	conduct regular	improve support at
	participation in	logistics	field inspections	regional level such as
	joint inspections	constrained (e.g.,	due to lack of	vehicles, field logistics,
		transport, field	resources	and budget for regular
		equipment)		compliance
				monitoring
Mion District	Local governance;	Some competence	Weak capacity in	Provide structured
Assembly	grievance	in grievance	grievance redress	training on grievance
	redress;	handling, but	aligned with	mechanisms and
	community	limited awareness	ESMP	safeguards at
	mobilization	of safeguards		district/regional levels
CSIR – Water	Technical	Adequate technical	Underutilized in	Formalize role in ESMP
Research Institute	monitoring of	competence and	field	monitoring with
	water quality	facilities	implementation	budget and data-
				sharing mandate
CSIR – Soil	Technical	Adequate technical	Underutilized in	Formalize role in ESMP
Research Institute	monitoring of soil	competence and	project-specific	monitoring with
	quality	facilities	monitoring	

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
				budget and data-
				sharing mandate
GNFS	Fire education,	Strong institutional	Limited	Engage GNFS to
(Regional/District)	prevention, and	mandate, but	firefighting	improve fire-fighting
	response	inadequate fire	equipment;	equipment resources
		hydrants, tenders,	inadequate	at the district level;
		and trained	training capacity	build capacity on
		personnel		prevention and
				community training
				methods
NADMO (District	Disaster risk	Active but under-	Staffing and	Engage district
Office)	education,	resourced with	logistical deficits	NADMO to recruit
	preparedness,	limited staff and	constrain rapid	additional staff;
	and response	logistics	response	provide disaster
				response logistics
				(vehicles, equipment);
				and build staff
				capacity
NGOs/CSOs	Community	Active presence but	Weak technical	Provide training in
	engagement and	limited technical	understanding of	safeguards,
	sensitization	expertise on	ESMP safeguards	participatory
		safeguards		monitoring, and
				technical engagement

MoFA should establish formal coordination mechanisms, including joint monitoring schedules and shared reporting platforms to enhance accountability and synergy across agencies.

0.12 Grievance Redress Mechanism

The activities of the project may generate grievances arising from the interaction between project and local authorities/community, workers and the host community. Some potential grievances identified and likely to occur during project implementation include:

- Complaints from the local community on the conduct of workers, especially sexual harassment and other gender-based offenses;
- Complaints related to noise, dust, traffic incidents;
- Restriction of access to persons who otherwise were using portions of land e.g. for grazing
- Failure to consider the recruitment of local man-labour;
- Non-respect of the habits and customs of the host community by the contractor/ consultants/ MoFA personnel etc;
- Non-compliance with the measures or provisions contained in the ESMP.

In managing grievances, the REWARD project proposed measures for resolution of grievances that may arise due to project implementation. This is a three-tier grievance redress structure which are;

- Community level structures (1st Tier) These includes; a Grievance Redress Committee and Sitelevel Grievance Redress Mechanism.
- District level structure (2nd Tier) District Grievance Redress Committee
- Project-wide level structure (3rd Tier) Project Grievance Redress Committee

Community Level (1st Tier):

- Includes Community Grievance Redress Committees (GRCs) and site-level Grievance Redress Mechanisms (GRMs).
- Handles initial complaints from individuals or communities related to agricultural or infrastructure activities.
- Site-level GRMs are managed by contractors and report monthly to the project team; oversight is provided by the PIU Environmental and Social Safeguard Specialists.

<u>District Level (2nd Tier):</u>

- District Grievance Redress Committees (District GRCs) address unresolved complaints from the community level or cases where community GRCs fail to act within 30 days.
- They meet quarterly or as needed for urgent matters.

Project Level (3rd Tier):

- Project Grievance Redress Committee led by the Project Coordinator or Social Safeguard Specialist.
- Handles cases escalated from the district level, especially if not resolved in 30 days or if the complainant is dissatisfied with the resolution.

0.13 ESMP Implementation Budget

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
		Cost (USD)	Cost (GHS)
Preconstruction	- E & S assessment and permit acquisition.	37,287	393,000
(Preparatory) Phase	- Training and completion of VLD forms.	427	4,500
	- RAP/LRP Implementation and capacity building for PIU.	13,237	139,520
	Fencing of site to restrict vegetation clearanceTraining of E&S officers on ESMP.	2,841	30,000
- Sub Total		53,792	567,020
Construction Phase	 Development and implementation of an Occupational, Health and safety management plan. 	4,735	50,000
	- Labour force management and training on safety, discrimination, GBV, SEA/SH, child labour/human rights and ethical conduct.	18,939	200,000
	- Erosion management and ESMP training for contractor's E&S team	16,098	170,000
	- Air quality deterioration abatement measures and PPE provision	5,682	60,000
	- Water pollution abatement measures	6,629	70,000

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
,		Cost (USD)	Cost (GHS)
	- Noise abatement measures implementation	1,894	20,000
	and PPE provision	,	,
	- Waste management including hazardous and	11,364	120,000
	non-hazardous waste		
	- Traffic management and road safety training for	4,735	50,000
	drivers - Implementation of fire prevention/fighting	4.705	50.000
	measures and training for workers and	4,735	50,000
	community		
	- Management of grievances including GBV,	5,682	60,000
	SEA/SH, child labour/human rights	3,002	00,000
	- Sensitization of workers and community on	2,841	30,000
	cultural tolerance and conflict management	,-	
	- Management and community sensitization on	9,470	100,000
	drowning risks		
Sub-Total		92,804	980,000
Operation Phase	- Development and implementation of	28,463	300,000
	occupational health and safety plan/measures	,	,
	- Sensitization on good labour practices, rights	18,975	200,000
	and ethical conduct.		
	- GBV sensitization for farm owners/workers	9,569	100,000
	- Child labour sensitization for farm owners	4,744	50,000
	- Education on soil, water and nutrient	9,488	100,000
	management for farmers.		
	- Education of farmers on air quality	9,488	100,000
	deterioration abatement measures		
	- Education on soil, water, and nutrient management, waste management, pollution	28,463	300,000
	prevention and PMP Implementation		
	- Sensitization of farmers on noise abatement	4,744	50,000
	measures	4,744	30,000
	- Waste management including provision of	7,116	75,000
	skips, collection/disposal and education on	- /	
	composting		
	- Fire risk management and sensitization of	9,488	100,000
	farmers on fire-fighting techniques.		
	- Education of farmers on soil, water and nutrient	4,744	50,000
	management.Sexual health education programs for farm	4.744	50.000
	workers to promote public health	4,744	50,000
	- Flood risk assessment and management	14,231	150,000
	- Sensitization of workers and community on		
	cultural tolerance, and conflict management	2,841	30,000
	Traffic management and road safety training for	4,744	50,000
	drivers	7,777	
	- Management and community sensitization on	4,744	50,000
	drowning risks	,	·
Sub Total		166,508	1,755,000
	- Development and implementation of an	4,735	50,000
	Occupational, Health and safety plan.		

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
		Cost (USD)	Cost (GHS)
Decommissioning Phase	 Waste management including hazardous and non-hazardous waste 	11,364	120,000
riiase	 Traffic management and road safety training for drivers 	4,735	50,000
Sub Total		20,834	220,000
Grievance Redress Mechanism (GRM)		79,000	832,660
Resettlement Action Plan Implementation		3,750	39,520
Environmental & Social Performance Audit		25,000	263,500
RAP Completion Audit		7,000	73,780
Sub Total		114,750	1,209,460
Total		448,688	4,731,480

0.14 Decommissioning

A Decommissioning and Site Closure Plan (DCP) is required to guard against the remote possibility of abandoning temporary constructed structures. Should such a circumstance arise, the potential would exist for impacts from abandonment of the facility such as aesthetic impacts and potential trespassing and safety concerns.

The specific objectives in managing the decommissioning process will be:

- To ensure that rehabilitation and decommissioning are carried out in a planned sequential manner, consistent with best practice;
- To ensure that agreed post-project land-use outcomes are achieved; and
- To avoid on-going liability.

A Full Decommissioning Report is expected to be prepared in the event of any such activity for approval by the EPA and any other requisite state agencies.

Pre-Decommissioning Assessment

Prior to any decommissioning, the EPA will be notified and an assessment will be carried out to identify any potential environmental impacts that need to be addressed and mitigated in the decommissioning process.

Decommissioning Phase Activities

Some of the activities that will be undertaken during the decommissioning phase will mostly be the dismantling and removal of structures and equipment.

Dismantling and Removal of Structures and Equipment

All decommissioning and restoration activities will be in accordance with all applicable state and local permits and requirements and will include the following specific activities:

- Hardware retirement: All power sources would be disconnected from structures and equipment
 before dismantling commences. Cranes and/or other machinery will be used for the disassembly
 and removal of structures and associated installations. These will either be transported whole for
 reconditioning and reuse or dissembled into salvageable, recyclable, or disposable components;
- Foundation removal: All foundation materials will be removed as per EPA guidelines or requirements. The remaining excavation will be filled with clean sub-grade material, compacted to a density similar to surrounding sub-grade material, and finished with topsoil;
- Monitoring: A monitoring and remediation period of two years immediately following the
 completion of any decommissioning and restoration activities will be undertaken. If agricultural
 impacts are identified during this period, follow-up restoration efforts will be implemented; and
- Area restoration: Areas where subsurface components are removed will be graded to match
 adjacent contours, stabilized with an appropriate seed mix, and allowed to re-vegetate naturally.
 All community roads, impacted by Project decommissioning activity, if any, will be restored to
 original condition upon completion of decommissioning.

Solid Waste Management

All solid waste resulting from the decommissioning process will be evacuated by handlers commissioned by the District Solid Waste Department.

Post-Decommissioning Assessment

Removal of machinery, equipment and all other materials related to the project will be completed within one year of decommissioning. At the end of the decommissioning exercise, the EPA will be invited to carry out a post-decommissioning assessment to establish compliance with all regulatory requirements and issue a certificate to that effect. The Decommissioning and Closure Plan will be finalized and submitted to the relevant authorities for approval at least six months prior to closure of the site.

A report describing the performance of the final DCP in working towards its objectives, based on monitoring results, and the extent to which it has been complied with, will be submitted to the EPA. The report will be provided to documented stakeholders and will otherwise be publicly available on request. Files and documents used to collate information regarding closure commitments, licenses, approvals and other information concerning closure will be catalogued and maintained in accordance with standard practices.

0.15 Conclusion

The proposed project will be implemented in accordance with relevant national laws and best international practices provided by the applicable Operational Safeguards of the AfDB 2023 Integrated Safeguard System.

Stakeholders have been identified and their suggestions and concerns obtained through the consultation and engagement process have been highlighted in the report and addressed. A Stakeholder Engagement Plan (SEP) has been proposed to ensure continued engagement of all stakeholders and the implementation of a grievance redress mechanism to ensure harmony in the project implementation.

The potential adverse impacts of the project have been identified. Adequate mitigation measures have been proposed to manage the moderate to major adverse impacts. Also, management and monitoring plans have been designed to ensure that the proposed mitigation measures are adequately implemented. The institutional capacities have been assessed and gaps identified with recommendations.

The assessments have shown that the project generally has moderate impacts on the environment and the impacts could be further mitigated with the adoption of good environmental, health and safety practices. A Pest Management Plan (PMP) is required to ensure judicious and safe use of agrochemicals as well as safe disposal of obsolete chemicals and empty containers.

The Chief of the Tindantua community has donated the land for the project. A Resettlement Action Plan has been proposed to mitigate the livelihood impacts on four (4) farmers who will temporarily vacate their farm lands for use by the project.

The project holds immense benefit for the Tindantua community, the district and region regarding food security, job creation, growth of MSMEs, etc. The entire country will benefit from improved food security, increased knowledge and adoption of best agricultural practices for rice production, etc.

1.0 INTRODUCTION

1.1 Background of the Project

The Government of Ghana (GoG) through the Ministry of Food and Agriculture (MoFA), in collaboration with the African Development Bank (AfDB) is undertaking the Resilient Rice Regional Value Chains in West Africa (REWARD) Project.

The Project seeks to develop some selected inland valleys to promote rice production in the Northern part of Ghana specifically, the Northern, Upper West, North-East and Savannah Regions to boost preparedness against food insecurity and improve the resilience of food systems in Ghana.

Specific activities to be undertaken in these selected Inland valleys include but not limited to: development of water control and conveyance systems; construction of drainage system to collect water out of command areas; construction of access roads into the valleys; and land development for crop cultivation. The programme will also seek to address issues with women and youth drawn from the Gender Action Plan (GAP).

This development objective will be achieved through improving farmers' access to usable weather, climate and advisory services; improving access to local climate information services through digital information platforms; facilitating the co-production of services between private and public sector; increasing farmers' access to agricultural and nutrition sensitive technologies developed by a consortium of National Centers of Specialization (NCoS), Consultative Group for International Agricultural Research (CGIAR) and other international research institutes; establishing spatial information system to design and plan climate resilience land management practices; promoting private sector involvement in regional agricultural trade; and supporting women farmers to access services to improve marketing along target commodity value chain.

In line with environmental permitting requirements as provided under the Environmental Protection Act, 2025 (Act 1124), the Environmental Assessment Regulations of 2025 (LI 2504), this assessment has been carried out by SAL Consult Limited to help understand the likely implications of the proposal in order to inform the environmental permitting decision-making prior to project implementation in the Mion District area. Also, the ESIA will ensure the project and subprojects comply with the requirements of the Bank's Operational Safeguards System (OSS). The main objective of REWARD-Ghana is to reduce importation of rice by increasing competitive local rice production, processing, income, and job creation, which will lead to improved nutrition and food security in a sustainable manner and contribute to reducing poverty through a private-public sector driven interventions along the rice value chain. The specific objectives of the project are;

- To increase rice productivity and production thus increased incomes for farmers, particularly women and young people;
- To increase the resilience and adaptive capacities of rice farms and production systems; and
- To increase the marketing and intra-regional trade of rice.

1.2 Purpose of the ESIA

The scope of work for the ESIA study is to among other things:

- Provide technical description of the proposed project and identify all activities of environmental/social concerns;
- Analyse project alternative and investigate options to the project development in relation to the
 project site, design, and the "no action alternative" which assumes that the Project is not
 implemented.
- Establish the existing environmental and socio-economic baseline conditions of the project area of influence:
- Predict and examine all the significant environmental impacts on the surrounding communities and the general environment during implementation of the proposed project and advise on appropriate mitigation and abatement measures against potential adverse impacts;
- Provide a monitoring program for predicted impacts and mitigation measures;
- Provide an Environmental and Social Management Plan (ESMP) integrating Grievance Redress Mechanism (GRM);
- Document the socio-economic and cultural advantages and disadvantages associated with the proposed project for stakeholders and interested groups to make an informed decision on the level of environmental compromise and permitting.
- Provide a plan to guide the development of an emergency response plan for the project;
- Provide guidelines to be followed in the event of decommissioning; and
- Carry out public consultations and include the outcome in the ESIA report with arrangements to address stakeholder concerns.

1.3 Methodology for the Assessment Process

This report has been prepared in accordance with applicable African Development Bank and Ghanaian environmental assessment guidelines and involves the following activities:

- Data gathering; The Consultant assembled and evaluated relevant baseline data relating to the biophysical and socio-economic environment to be influenced by the project. The baseline data include climate, topography and relief, geology and soil, vegetation, demography, access to basic services and socio-economic conditions. In addition, this report has scoped out the issues and provided general assessment of the impacts.
- Stakeholder identification and consultations; Key stakeholders identified include Ministry of Food and Agriculture (Department of Agriculture, Mion District), Environmental Protection Authority (EPA) of Ghana, Mion District Assembly, Lands Commission, Ghana National Fire Service, Produce Suppliers, Commercial Farmers, Farmer Based Organizations, Assembly Representatives, Community Focus Groups including Traditional Authority, Youth Groups, Women Groups etc. Stakeholders were engaged in April 2025 and the outcome of engagements with key stakeholders have been reviewed and incorporated in the study (See Details in Section 6 and Annex 5).
- **Data collation and analysis;** The report preparation involved review of project documents, related Environmental Impact Statements (EIS), as well as EPA, and AfDB reference documents as follows:
 - Project Documents (Project Implementation Document);
 - District Profile for the Mion District;
 - Medium Term Development Plan;

- o Population and Housing Census Report, 2021;
- Technical sheets for project development;
- Ghana EPA Guidelines;
- o GoG and AfDB Reference Documents;
- Sector policy documents and regulations; and
- Relevant international conventions.

1.4 The ESIA Report Content and Structure

EPA guidelines for preparation of ESIA and the AfDB Operational Safeguards System (OSS) guided the preparation of this ESIA report. The outline of the report includes the following:

- A non-technical executive summary;
- An introduction describing the ESIA purpose, objectives, approach and methodology;
- A description of the project, with an emphasis on subproject scope;
- Analysis of alternatives;
- Policy, legal and administrative framework;
- Baseline environmental and social conditions of the Mion District;
- Stakeholder Engagement and public consultations and disclosure;
- Potential environmental and social issues and impacts;
- Proposed mitigation measures;
- Environmental and social management plan requirements;
- Decommissioning;
- Capacity building and training required to implement the ESMP;
- ESMP implementation budget;
- Conclusion; and
- Annexes.

2.0 PROJECT DESCRIPTION

This section provides a detailed description of the Project in relation to its location, the key project components and an overview of the proposed activities that are to take place during the planning/preparatory, operation, and implementation phase.

2.1 Project Location

The programme will cover generally the Savannah Ecological Zone of Ghana and specifically focus on 7 Districts within four (4) administrative regions thus Northern, Upper West, North-East and Savannah Regions, that have the potential for rice production.

The Mion District where the project site is situated is located in the Northern Region of Ghana. The Northern Region makes up one of the sixteen political regions of Ghana and it is located in the Northern belt between longitude 0.1495° W and Latitude 9.3673° N. The region shares boundary with the North East Region and Savannah Region to the north, Oti Region to the south, and neighbouring country, i.e. the Republic of Togo to the east (see **Figure 2-1**). The Northern Region of Ghana administratively consist of 1 Metropolitan Assembly, 4 Municipal Assemblies and 11 District Assemblies.

The Mion District which has a total land area of about 2,714 sq. km is located at the central part of the Northern Region of Ghana. To the north, it borders Gushegu and Karaga districts. To the south, it shares boundaries with Nanumba North and East Gonja districts. On the western side, it is adjacent to the Tamale Metropolitan Assembly and Savelugu/Nanton. To the east, it borders the Yendi Municipal District. The District has a total of about 171 communities.

The proposed Project will be implemented in the selected site (shown in **Table 2-1** and **Figure 2-2** below) which have been identified by the Ministry of Food and Agriculture (MOFA) for Environmental and Social Impact Assessment Studies and subsequent development (if found suitable) for improved rice production.

Table 2-1: Project Beneficiaries

NO.	REGION	DISTRICT	VALLEY
1.	Northern	Mion	Tindantua




Figure 2-1: Map of Ghana showing the beneficiary districts including Mion




Figure 2-2: Location map of Mion District showing the Tindantua valley

2.2 Project Components

The Project has four (4) main components namely; production and productivity, processing and marketing, policy and governance, and project coordination and management.

Component 1: Development of sustainable and climate-resilient rice production systems

Sub-component 1.1: Sustainable climate-resilient infrastructure and management services in rice production systems. Key interventions will include:

i. Development of Agricultural Zones

This sub-component will seek to develop new lands and rehabilitate existing water regulatory infrastructure to increase area under rice production. This will leverage on Agricultural Zones being established by Government to address the issue of access to large tracts of land, to drive sustainable and commercially oriented agriculture with the aim to significantly expand Ghana's rice productive capacity.

Under each Agricultural Zone large contiguous tract of arable land of not less than 300 hectares will be designed and developed within which a modern agricultural economic enclave will be located with the intention to create a viable ecosystem for the community to engage in commercial farming. Government will partner with the community for this project. Key activities will include land clearing, bunding of fields, construction of boreholes and small offices, construction of drying patios, farm access tracks, machinery and equipment.

The Ministry of Food and Agriculture (MoFA) has identified various locations across the country which has the potentials of being the food baskets for the country. Some of the potential locations identified for establishment of the Agricultural Zones include the Mamprugu Moagduri district in the North-East region, Mion, Tamale Metro and Savelugu Municipal in the Northern Region, West Gonja in the Savannah Region, Wa and Nandom Municipal in the Upper West Region.

The African Development Bank and other Development Partners since 2015 have supported the development of about 1,700 ha of various valleys for rice production. These valleys will be upgraded with the necessary infrastructure (drying patios etc), including setting up of an agricultural mechanization services centers into an Agricultural Economic Enclave.

ii. Sustainable Land and Water Management (SLWM)

This intervention seeks to enhance environmental resilience and agricultural productivity, to address productivity barriers and opportunities in agriculture and environmental services. These SLM and CSA technologies are being incorporated to address the interplay between agriculture, biodiversity loss, and climate change.

Climate variability and change affects rice production, and may result in increased cost of production, low yields, increased post-harvest losses, low farm income, food insecurity among others if appropriate mitigation and adaptation measures are not put in place.

The Ministry of Food and Agriculture (MoFA) developed a National Climate-Smart Agriculture and Food Security Action Plan (2016-2020), with the aim to facilitate and operationalize the national climate change policy for effective integration of climate change into food and agricultural sector development policies and programmes. In line with the CSA Action Plan, the following CSA technologies would be mainstreamed into all activities of the REWARD Project:

- a) Real-time climate and weather information system:
- b) Climate resilient seeds
- c) Soil Nutrient Management
- d) Ecological Organic Agriculture (EOA)
- e) Water Conservation and Management
- f) Alternative Wetting and Drying (AWD)
- g) Build capacity on SLM technologies

iii. Form and build capacity of Water Users Association:

According to the legislative instrument (L.I. 2230) passed on 12th February 2016, Water Users Association (WUA) is to be formed on all public irrigation infrastructures constructed by government and other parties on behalf of or in concert with the government. By this L.I. 2230, the Water User Associations are responsible for the Organisation, Maintenance and Management of the Irrigation infrastructure in their service area. The process of formation involved sensitisation, formation and capacity building of the farmers.

The capacities of the existing Water Users' Associations (WUAs) would be strengthened and new one's formed at the newly constructed sites, to function properly.

iv. Social infrastructure development:

This will support development of rural feeder roads, to enhance transportation of inputs, produce and mobility of humans within the Agricultural Economic Enclaves. It will also support development of water and sanitation facilities and services within the enclaves.

Sub-component 1.2: Improved availability and access to climate-resilient inputs, mechanization services and knowledge

Key interventions will include:

i. Seed Delivery Systems

This will support production of improved seeds in collaboration with Research Institutions (Council for Scientific and Industrial Research - Crop Research Institute and Savannah Agricultural Research Institute), Universities and Grains and Legumes Development Board (GLDB). Identified research institutes will be supported with funding to produce adequate quantities of breeder and foundation seeds, for the production of certified seeds by trained and certified seed growers at the targeted irrigation schemes. Resilient varieties like CSIR-Banse Rice (83 days) would be promoted.

Adequate support would also be provided to seed regulatory institutions for monitoring and certification of all classes of seeds. About 244 kg of breeder seeds and 12.2 MT of foundation seeds will be required for project period. The seed unit in Tamale will be rehabilitated and renovated and equipped with modern seed processing facility.

ii. Fertilizers and Pest Control Management Systems

Improve access to agro chemicals (fertilizers and pesticides) through input credits: The proposed project will facilitate access to agro-inputs through input credit system. This will be done through payment guarantee for identified commissioned aggregators to supply/provide agro-inputs to farmers, who will in turn repay in kind at the end of every cropping season.

Optimizing the use of quality agro-inputs are essential for sustainable agriculture production, ensuring optimal crop yields, minimizing environmental impact and meeting food production demands. Capacities of the value-chain actors would be enhanced to provide efficient utilization which would translate to quality and higher yields for better incomes.

iii. Agricultural Mechanization Services Delivery

One key feature of Government Policy on Agriculture is the comprehensive utilization of mechanization services for land preparation, seeding/planting, fertilizer application, crop maintenance/protection, harvesting and post-harvest management to increase productivity of rice. In the same vein, Agricultural Mechanization Service Providers or Agricultural Mechanization Services Centers (AMSECs) would be supported to offer dedicated mechanized services to farmers in the selected Agricultural Economic Enclaves.

iv. Extension Delivery

The role and importance of agricultural extension delivery in Ghana's overall agricultural growth and development like in many other jurisdictions cannot be over emphasized. Agricultural Extension plays a key interface between agricultural research and the farmer and other agricultural value chain actors by packaging technologies into suitable transmittable forms, interventions and innovations that could be utilized by farmers and other value chain. This will be achieved through:

- Promote increased and sustained programme participation
- Incremental adoption of inputs and technologies leading to an increased on-site productivity
- Improved post-production activities
- Capacity building and monitoring of operations of extension officers
- Building and promotion of synergies between extension and research
- Build Skill and Capacity of Machinery Operators and AMSEC managers

<u>Component 2: Development of rice processing clusters, agro-industry and commercial linkages for trade</u> facilitation

Sub-component 2.1: Modernized processing infrastructure and strengthening capacities of value chain actors

This component will focus on construction and installation of processing and storage infrastructure to minimise post-harvest losses and enhance value addition. It will develop information systems using innovative technologies (incl. digital) and consumer-oriented branding to improve access to market.

Additionally, this component will promote private sector investment by supporting business, with special focus on women and youth, and improve availability of financial services across the value chain to facilitate lending to processors, farmers, and other actors.

Promote the consumption of Ghana Rice: Events and promotional activities would as well be organized to encourage the consumption of Ghana rice.

Component 3: Policy/regulatory reforms at the national and regional levels and innovation-oriented regional technical support, for competitive rice value chains in the face of imports

Key activities under this component will include:

- Support to policy reforms and harmonization at regional/national levels
- Finalize the National Rice Development Strategy II (NRDS).
- Organise policy dialogues and workshops to discuss issues relevant to the rice sub-sector.
- Coordinate activities to ensure synergies among rice value chain stakeholders and projects to boost production, processing, marketing and consumption of locally-produced rice.
- Enhance control and regulations for agricultural inputs at regional/national levels.

Component 4: Programme Coordination and Management

This component will be responsible for day-to-day management of project activities to ensure harmony and coherence. A Project Implementation Unit (PIU) will be established or nested under existing PIU to support the coordination and management of the project. Regional and National Management and monitoring systems based on digital technologies will be developed to ensure tracking of results Regional and National levels, and in line with ECOWAS Rice Observatory (ERO).

2.3 Project Activities

The proposed Project will be implemented in seven (7) Districts within four (4) administrative regions thus Northern, Upper West, Savannah and North-East Regions, as indicated in the **Table 2-2**. The valleys will be upgraded with necessary infrastructure, such as water conservation bunds and drains, drying patios and farm access tracks.

Table 2-2: Proposed Rice Valleys for Development

No	Region	District	Community	Valleys	Area (ha)	Project Activities
1	Northern	Mion	Tindantua	Sakoya, Bogni	350	New land development with machinery support, drying patios, farm roads etc
2		Tamale Metro	Nyankpala	SARI	50	Construct bunds and drains of existing area for SARI for seed production
3		Savelugu	Napanzo	Nanpanzo	300	Rehabilitation of existing valley, reshaped bunds and spot improvement of farm tracks
4	North East	Mamprugu Moagduri	Kubori/ Zanwara	Kubori	250	Land development packaged (bunds, drying patios and site office)

No	Region	District	Community	Valleys	Area (ha)	Project Activities
5	Upper West	Nandom	Nandom- Kpee	-	200	Machinery support with drying patios and land development
			Ко	Gbafin	150	Machinery support with drying patios and land development
6		Wa Municipal	Charia	Kolivege Bor	350	Land development with drying patios inclusive
			Sing	-	200	Reshaping of bunds, drying patios and drainage construction to convey excess water out of the fields
7	Savannah	West Gonja	Busunu	-	200	Land development and bunds
	TOTAL				2,050	-

Source: Department of Agriculture, 2024

The specific project activities to be expected within the Mion District during the REWARD Project will be:

Preparatory Phase

The preparatory phase activities include:

- Identification of beneficiary farmers for rice production
- Conduct of relevant studies, including socio-economic surveys and resettlement related issues
- Development and Implementation of Environmental and Social Management Plan (ESMP)
- Request for applications and screening of applicant farmers
- Assessment of soil suitability and GIS mapping of commercial farms using ICT.

Construction Phase

The construction phase activities will include the following:

- Rehabilitation of existing access routes
- Construction of mini work camp
- Vegetation clearance and land preparation
- Winning of construction materials from borrow pits (site yet to be determined)
- Transportation of materials to and from project site
- · Construction of drainage channels and flood protection works
- Provision and installation of farm infrastructure such as farm houses and storage facilities
- Waste disposal (cleared vegetation, construction waste etc.)
- Decommissioning of mini work camp

The vegetation will be cleared using suitable machinery for land development to ensure that top soils are not unduly disturbed. Some activities to be undertaken will involve land levelling and In-field bunding. Bunds which are earthen embankments will be created to retain rainfall runoff. The plots will be formed

to conform to the direction of the contours, in this way reducing the earth movement during bunding and levelling to the minimum. The levels of the plots will be set to balance cut and fill. Bunding and land levelling will form the major activities in plot formation. Pegging out of plots boundaries to the standard size of plots will be required during the levelling. All levelled plots would be portioned and bunded by infield contour bunds into plots.

Roads linking valleys to towns which are mostly in deplorable states will be maintained to reduce postharvest losses which has been a major problem confronting farmers. Access roads will be maintained to permit the use of agricultural machinery in the cropping zone to do tillage, deliver inputs and send out produce.

Operation Phase

The operation phase activities include:

- Production and promotion of rice.
- Support for out-grower contractual arrangements.
- Conduct surveillance and collect data on pests attacking the Rice in the project zones with specific reference to FAW.
- Community sensitization, Establishment of fire belts and enforcement of community fire by-laws to deal with the impact of bush fires.
- Promotion of quality standards for rice, maize and soybean production, storage and processing
- Support business development, including improvements in business processes of existing commercial farmers
- Enhance access to market information (e.g. quantity, quality, timing and pricing)
- Promote the development of allied services (packaging, new distribution networks for rice products, transport services, new agro-input delivery systems, etc.)
- Support to feed millers to improve feed stock and expand processing capacity
- Promote the sustainable use of agro-chemicals;
- Enhance investment facilitation and promotion to increase the number of commercial producers and processors in the Savannah regions
- Capacity building for women and youth in small-scale commercial rice business management and entrepreneurship, including mentorship.

3.0 ANALYSIS OF ALTERNATIVES

This chapter investigates options to the Project development in relation to the Project site, design, and the "no action alternative" – which assumes that the Project is not implemented.

The consideration of Project alternatives is in compliance with Environmental Assessment Regulation LI 2504, which states that an EIA development for any project should outline the main alternatives for the proposed undertaking, taking into account the main technology, equipment, and location.

The proposed project considered some feasible options in respect of their potential environmental and social impacts. These are analysed in **Table 3-1** and include:

- Site selection;
- Resettlement related options
- Power supply;
- Sources of water;
- Water Management Systems;
- Waste management; and
- Project implementation versus No Project implementation.

Table 3-1: Analysis of Alternative Project Options

Option/ Method of Potential Environmental, Social, Deployment Implicat		_	Preferred Option	
Site	e Selection			
1.	Tindantua	Advantages	Disadvantages	Tindantua was
	Valley	1. Size of the valley	1. Underdeveloped rice	selected as the
		2. Potential benefit to farming	fields	preferred valley
		communities with limited		because of its
		access to developed rice		potential benefit to
		fields		many more
		3. Not a flood prone area		communities. The
		4. Sparsely vegetated fields		large size of the
2.	Other Sites	Advantages	Disadvantages	valley also made it
	(Bofoyili,	1. Already developed rice fields	1. Relatively smaller valleys	the preferred
	Jagbni)	serving nearby communities	in size	choice.
			2. Valleys susceptible to	
			flooding	
			3. Relatively dense	
			vegetation	
			4. Potential displacement	
			issues	
Res	settlement related	lissues		
1.	Tindantua	Advantages	Disadvantage	The preferred
		5. Chief is willing to donate land	3. The livelihood of four (4)	option is the
		for the project.	farmers will be disrupted.	Tindantua site due

Ор	otion/ Method of	Potential Environmental, Social, Technological and Economic		
-	Deployment	Implication		Preferred Option
2.	Other Sites (Bofoyili, Jagbni)	 The affected farmers are relatively few (4 farmers). The chief is willing to provide alternate land for the affected farmers. There will be no temporary or permanent physical structures to be removed or destroyed. Advantages Vast lands available for the project. Alternative lands to be provided for any affected farmers may be closer to the community. 	 4. The affected farmers will have to trek longer distances to access alternate farmlands provided by the chief. Disadvantages 1. Land is owned by individuals who may not be easily willing to donate for the project. 2. There may not be alternative land for the affected farmers. 3. There will be more farmers affected (in excess of 20). 	to more favourable resettlement related conditions.
Pov	wer supply			
1.	National grid	Advantages 1. The cost of electricity is low decreasing production cost	Disadvantages 1. Unreliable power supply from frequent power cuts	Solar energy installations (Option 2) such as
2.	Solar energy installations	 Advantages Presents a clean and sustainable source of electricity Low operational costs Meets the objective of technology transfer and climate friendliness 	Disadvantages 2. Expensive capital cost	solar powered pumps are preferred for the pump irrigation.
Sou	urces of Water			
1.	Groundwater	Advantages 1. Relatively reliable source all year round 2. Seasonal variations are minimal 3. Relatively stable water quality	Disadvantages 1. Expensive to access and abstract 2. Challenges of overexploitation to meet high demands and associated threat of land subsidence	Option 3, which is the use of rain water appears to be the most preferred option as it will be easier to implement water management plans

Op	otion/ Method of	Potential Environmental, Social,	, Technological and Economic
-	Deployment	Implicat	Preferred Option
			 3. May require farms of boreholes to meet demand 4. Threat of high iron and fluoride concentration in aquifers in the northern parts of the country
2.	Surface water	Advantages	Disadvantages
		Easier to abstract and use	 Seasonal variations in flow Vulnerable to pollution
3.	Rain	Advantages	Disadvantages
	harvesting	1. Easy to trap and store	 Source is unreliable Evaporation losses are high in the dry months of the year
Wa	iter Management	Systems	the year
			Dicadvantages The most preferred
1.	The head- bund system	 Water stored in the ponds is conserved and can be used for additional irrigation during dry spells because of the small nature of the storage ponds. The technique allows for deep water infiltration into the soil by trapping the water, thereby enhancing the soil's water retention capacity. This system also help to prevent soil erosion and gully formation by reducing the speed and volume of surface 	1. Developing of bunds can be laborious and may demand more manpower if size of farm is huge. 2. Having head-bund system in areas with adequate rainfall or irrigation may cause waterlogging which may affect crop growth. The most preferred is the Head Bund system. The Head bund is ideal for small to mediumsized farms.
2.	The central-	runoff. Advantages	Disadvantages
	drain system	 The water levels in the rice fields, especially those near the central drain, can be controlled to mitigate against excessive flooding of the fields. Help reduce soil salinity. 	This system is only suitable for areas with high rainfall and not arid

Op	otion/ Method of	Potential Environmental, Social	, Technological and Economic Preferred Option
	Deployment	Implica	tions
3.	The interceptor-	 With water levels being controlled, crops receive optimal water amounts leading to better growth and yield. Advantages In periods of high rainfall, the 	Disadvantages 1. Water can be lost from
	canal system	fields are better protected from any rapid overflow of water from the stream and from the lateral runoff from the uplands. 2. The interceptor-canal system can be used to irrigate the rice fields during dry spells in the rainy season.	the canals through seepage into the ground and evaporation, reducing the overall efficiency of the irrigation system. 2. It can be challenging to distribute water evenly across large areas with this system, as some parts of the irrigated land can receive more water than others. 3. Canals require regular maintenance, such as desilting and repairing leaks, which can be expensive and labor- intensive.
4.	The contour-	Advantages	Disadvantages
	bund system	1. The stream used for irrigation is effectively obliterated and water is allowed to cascade from one levelled area to the next by way of built outlets or spillways to the next field.	1. Contour bunds are not suitable for uneven or eroded land as overtopping of excess water with subsequent breakage may occur at low spots.
	ste Management	<u> </u>	1
1.	Composting plant	 Advantages Improvements in soil quality. Enhances the structure of the soil. Eco-friendly. Fully organic fertilizer. 	Disadvantages 1. Requires initial composting is a investment. 2. Efficiency depends on the amount of organic waste 3. May attract rats, snakes, improve soil quality
		5. Higher yields.	and bugs. on farms. It will 4. Requires space also keep waste

Or	otion/ Method of		Potential Environmental, Social,	Tech	nnological and Economic	
•	Deployment		Implicat		_	Preferred Option
			-	5.	Unpleasant smell	away from landfill,
						which already have
2.	District Waste	Ad	vantages	Dis	advantages	limited space.
	Dump/ landfill	1.	Straightforward concept to	1.	Completed landfill areas	
	sites		deal with waste.		can settle and requires	
		2.	Filled land can be reused for		maintenance.	
			other community purposes.	2.	Requires proper planning,	
		3.	Landfills can prevent		design, and operation.	
			environmental dumping.	3.	Can contribute to	
		4.	Good for waste that is non-		groundwater pollution.	
			recyclable.	4.	Landfills can be a	
					breeding ground for	
					bacteria.	
Pro	ject Implementati	ion v	ersus No Project Implementation	n		
1.	Project	Ad	vantages	Dis	advantages	Project
	Implementation	1.	Enhancing rice production,	1.	Potential displacement	implementation is
		2.	Strengthening market		issues	the preferred
			systems,	2.	Depriving other projects	option as the
		3.	Improving farmer livelihoods.		from accessing scarce	benefits outweigh
		4.	Supporting research to		resources	that of the no
			produce breeder seeds,			project
		5.	Ensuring widespread access			implementation
			to seed of improved rice			option
			varieties.			
		6.	Facilitate the supply of key			
			inputs such as fertilizers and			
			pesticides			
2.	No Project	Ad	vantages	Dis	advantages	
	Implementation	1.	Project resources can be	1.	Food security challenges	
			channeled into other	2.	High Cost of Land	
			development programs		Development:	
				3.	Inadequate Irrigation and	
					Poor Water	
					Management.	
				4.	Limited availability of	
					quality breeder,	
					foundation and certified	
					seeds:	
				5.	Inadequate use of	
					Improved Agro Inputs:	
				6.	Inadequate access to	
					mechanized services	

Option/ Method of Deployment	Potential Environmental, Social, Technological and Economic Implications			Preferred Option
		7.	Poor knowledge of good agronomic practices	
		8.	Poor quality of processing and storage facilities	

4.0 POLICY, LEGAL AND INSTITUTIONAL FRAMEWORK

National and sector legislation and policies relevant to the agriculture sector have been reviewed in this section. Also, institutional requirements, international conventions, AfDB safeguard policies, and national environmental quality guidelines for the management of environmental and social issues have been considered. These have been summarized in **Table 4-1 to Table 4-6** under the following themes:

- National Policies and Plans
- National legal framework;
 - Agriculture sector legislation and related requirements;
 - Local governance, planning and other institutional requirements;
 - Public Health, Safety, Security and Social Protection;
 - Environmental legislation in Ghana;
- National Institutional Framework;
- International Policies and Conventions
 - o African Development Bank safeguard policies; and
 - o International conventions.

4.1 National Policies and Plans

The policies and plans reviewed and applied in the assessment include:

- Ghana Shared Growth and Development Agenda, 2010;
- National Environmental Policy, 2012;
- National Land Policy, 1999;
- National Water Policy, June 2024;
- National Climate Change Policy, 2013;
- National Gender Policy, 2015;
- Hazardous Child Labour Activity Framework, 2016;
- National Plan of Action Phase II for the Elimination of the Worst Forms of Child Labour in Ghana, 2017-2021;
- Riparian Buffer Zone Policy, 2014;
- Food and Agriculture Sector Development Policy, FASDEPII (MOFA);
- National Environmental Action Plan/Policy, 1994; and
- National Employment Policy, 2012

Table 4-1: National Policies and Plans

No.	Policies and Plans	Applicability to Proposed Project
1.	Ghana Shared Growth and Development Agenda, 2010	The REWARD Project is in accord
	It provides for the Vision for the Agricultural, Environment and Natural	with the focus of the policy.
	Resource Sectors in Chapter four. The main focus of the agricultural sector is	
	to accelerate the modernization of agriculture and ensure its linkage with	
	industry through the application of science, technology and innovation.	
	The modernized agriculture sector is expected to underpin the transformation of the economy through job creation, increased export earnings, food security, and supply of raw materials for value addition and	

No.	Policies and Plans	Applicability to Proposed Project
	rural development as well as significant reduction in the incidence of	
	poverty.	
2.	National Environmental Policy, 2012	The proposed project seeks to
	The ultimate aim of the Policy is to improve the surroundings, living	promote sustainable
	conditions and the quality of life of the entire citizenry, both present and	development by including
	future. It seeks to promote sustainable development through ensuring a	economic, social and
	balance between economic development and natural resource conservation.	environmental considerations.
	The policy thus makes a high-quality environment a key element supporting	
	the country's economic and social development.	
3.	National Land Policy, 1999	The project sites will not be in
	The key aspects of the policy relevant to the project include:	protected areas, forests or
	• The use of any land in Ghana for sustainable development, the protection	wildlife estate.
	of water bodies and the environment and any other socioeconomic activity	The implementation of the
	will be determined through national land use planning guidelines based on	project will conform to the
	sustainable principles in the long-term national interest.	environmental laws of the
	Land categories outside Ghana's permanent forest and wildlife estates are	country which includes,
	available for such uses as agriculture, timber, mining and other extractive	registration with EPA, Preliminary
	industries, and human settlement within the context of a national land use	Environmental and Social
	plan.	Assessment and obtaining an
	All land and water resources development activities must conform to the	environmental permit prior to
	·	commencement.
	environmental laws in the country and where Environmental Impact	
	Assessment report is required this must be provided. Environmental	
4	protection within the 'polluter pays' principle will be enforced.	The prejectle Conjugate and
4.	National Water Policy, 2024 The National Water Policy (revised 2024) is a framework formulated to guide	The project's Environmental and Social Management Plan (ESMP)
	the sustainable use, management and planning of water resources for	must include mitigation measures
	drinking and other domestic uses. It is targeted at water users, water	against over-exploitation of water
	managers and practitioners, investors, decision makers and policy makers	resources and also against water
	within central and local government structures, non-governmental	pollution which emanate from
	organisations (NGOs) and international development agencies. The revised	agrochemicals and unsustainable
	policy (2024) also recognises the various cross-sectoral opportunities and	agricultural practices. The
	challenges related to water use and its links with other relevant sectoral	irrigation designs must include
	policies such as those on sanitation, agriculture, transport and energy.	water use efficiency techniques especially for the chosen crops".
	The objective of Section 2.3.5 Focus Area 4 –Water for Food Security is to ensure availability of water in sufficient quantity and quality for the	
	cultivation of food crops, water in sufficient quantity and quality for the	
	fisheries to achieve sustainable food security for the country. The relevant	
	policy measures and/or actions to be undertaken include:	
	(i) encouraging efficient use of fertilizers to reduce pollution of water	
	bodies and ensure conservation of water, and	
	(ii) promoting and encouraging water use efficiency techniques in	
	agriculture and reducing transmission losses of water in irrigation	
	Systems. National Environmental Action Plan / Policy 1994	The design and implementation of
5.	National Environmental Action Plan/Policy, 1994	The design and implementation of
		the proposed project will take into

No.	Policies and Plans	Applicability to Proposed Project
	The National Environmental Action Plan was initiated to define a set of policy actions, related investments and institutional strengthening activities that would make Ghana's development strategy more environmentally sustainable. The Plan formulated a national environmental policy as the framework for implementing the Action Plan.	consideration measures to promote the sustainable use of natural resources and ensure environmental management.
	The Policy aims at ensuring a sound management of resources and the environment and to avoid any exploitation of these resources in a manner that might cause irreparable damage to the environment. Specifically, it provides for maintenance of ecosystems and ecological processes essential for the functioning of the biosphere, sound management of natural resources and the environment, and protection of humans, animals and plants and their habitats.	
6.	National Employment Policy, 2012 The National Employment Policy indicates that poverty is still high at about 28.5 percent and that there is a strong correlation between the employment situation and poverty. The policy states that the key source of demand for labour emanates from the productive sectors of the economy, namely, agriculture, industry and service. One of the key strategies of the employment policy is to promote farm and non-farm rural employment through modernization of agriculture, improving the productivity of farmers and contract farming arrangements, promoting effective linkages between farm and non-farm activities among others.	The proposed project is consistent with the strategy of the employment policy to promote farm and non-farm rural employment.
7.	National Gender Policy, 2015 The National Gender Policy aims at mainstreaming gender equality concerns into the national development processes by improving the social, legal, civic, political, economic and socio-cultural conditions of the people of Ghana. It also seeks to empower the vulnerable groups particularly women, children, and people with special needs such as persons with disabilities and the marginalized.	The project will not discriminate against women and the vulnerable in the local communities. The criteria for selecting beneficiary farmers will consider gender and disability
8.	Hazardous Child Labour Activity Framework (HAF), 2016 The overall objective of the Hazardous Child Labour Activity Framework (HAF) project enacted in 2016 is to develop a comprehensive, age-appropriate contextually relevant and acceptable hazardous child labour framework to drive research, intervention, monitoring and enforcement. The framework was formed to facilitate identification, quantification and evaluation of hazardous child labour and raise evidence for future studies. It will also provide the best options for intervention and evaluation to safeguard the health, safety, development and education of children. This framework, guided by ILO Convention 182 (which requires each country through tripartite arrangements to develop a list of hazardous sectors and activities) and its recommendations, addresses the limitations of existing lists	The proposed project is consistent with the Hazardous Child Labour Activity Framework and will not involve any child in a hazardous activity.

No.	Policies and Plans	Applicability to Proposed Project
	and focuses on child-centred strategies that consider both risks and beneficial child work.	
9.	National Plan of Action Phase II for the Elimination of the Worst Forms of Child Labour in Ghana, 2017-2021 The Ghana National Plan of Action for the elimination of the worst forms of child labour phase II (2017-2021) was launched in 2017 to address the identified gaps of the National Plan of Action Phase I (NPA1). The Ghana's National Plan of Action Phase I (NPA1) for the Elimination of the Worst Forms of Child Labour (2009-2015) was enacted to address child labour through various interventions, including strengthening technical capacity, enhancing public awareness and empowering communities.	The design and implementation of the proposed project will take into consideration the measures of the National Plan of Action Phase II for the elimination of the worst forms of child labour in Ghana.
	The NPA2 aims to build on the gains made subsequent to the implementation of the NPA1 (2009–2015) with the view to utilise the good practices and lessons learned to address the challenges of child labour in a more effective and sustainable way. The main objective of the NPA 2 is to reduce the worst forms of child labour to the barest minimum (<10%) by 2021 while laying strong social, policy and institutional foundations for the elimination and prevention of all forms of child labour in the longer term. The Plan is composed of upstream strategies designed to reinforce awareness creation on child labour, leading to social mobilization and advocacy for improved policy implementation in the areas of education and technical/vocational training, social protection, law enforcement, labour inspection and youth employment; coupled with improvements in coordination and resource mobilization. The upstream strategies will underpin sets of downstream interventions formulated to address child labour directly at the district and community levels. These sets of interventions will aim at effective provision and monitoring of social services and economic empowerment programmes by local government administrations and promoting community empowerment	
10.	and sustainable action against child labour. National Climate Change Policy, 2013	The climate-resilient technology
10.	The Policy is built on seven (7no.) systematic pillars and the objective of the Policy is to mitigate and ensure an effective adaptation in key sectors of the economy, such as agriculture and food security, natural resources management, energy, industry and infrastructure among others. Under the Agriculture and Food Security area, the key objectives are: Develop climate-resilient agriculture and food systems for all agroecological zones; and Develop human resource capacity for climate-resilience. The key actions to achieve these objectives which are related to the	to be adopted for the proposed project includes use of improved seed varieties and irrigation systems. The project will develop human resource capacity to adapt to changing climate as part of the modernisation of the scheme. and improve post-harvest management through the
	 Develop climate-resilient cropping and livestock systems as well as crop varieties and livestock breeds tolerant to flooding, drought and salinity; 	provision of storage and processing facilities and infrastructure

No.	Policies and Plans	Applicability to Proposed Project
	■ Promote appropriate technologies for small-scale irrigation, water re-use	
	and water harvesting; and	
	■ Improve post-harvest capacity, e.g., storage and processing facilities and	
	infrastructure.	
11.	Buffer Zone Policy, 2011	The project will maintain a 100-
	The policy aims at providing comprehensive measures and actions that	meter buffer to the Daka River.
	would guide the creation of vegetative buffers for the preservation and	The setback distances provided
	functioning of the nation's water bodies and vital ecosystems. The	for the water pollution hazards is
	recommended buffer widths provided in the Policy include:	factored in the 100 meter buffer
	Minor perennial streams: 10 to 20 meters; and	distance observed by the project
	Important seasonal streams: 10 to 15 meters.	for the siting of storage facilities
	The Policy also designates the following as water pollution hazards and must	for agrochemicals, septic systems
	be setback from any stream or water body by the following distances:	and waste bins.
	, , ,	
	 Storage of hazardous substances – 45 meters 	
	■ Raised septic systems – 75 meters	
	■ Solid waste landfills – 90 meters	
12.		The project will significantly
	The revised FASDEP of 2006 (FASDEP II) emphasizes the sustainable	advance the achievement of the
	utilization of all resources and commercialization of activities in the sector	FASDEP objectives through
	with market-driven growth in mind and with emphasis on environmental	improved efficiency and
	sustainability.	management of the scheme. The project will ensure sustainable
	The Medium Term Agriculture Sector Investment Plan (METASIP) developed	utilization of resources and
	to implement FASDEP II over the medium term 2011-2015 includes the	sustainable land and
	following programmes:	environmental management
		including through the use of a
	■ Food security and emergency preparedness;	more efficient irrigation system.
	■ Improved growth in incomes;	
	Increased competitiveness and enhanced integration into domestic and	
	international markets;	
	Sustainable management of land and environment; and	
	 Science and technology applied in food and agriculture development 	

4.2 National Legal Framework

The regulatory areas reviewed and applied in the assessment in compliance with national requirements include:

- The Constitution of the Republic of Ghana, 1992;
- Ghana Investment Promotion Centre Act 1994, Act 478;
- Environmental Protection Act 2025;(Act 1124);
- Environmental Assessment Regulations 2025, LI 2504
- Fees and Charges (Miscellaneous Provisions) Act, 2022 (Act 1080);
- Water Resources Commission Act 1996, Act 522;
- The Water Use Regulations 2001, LI 1692;
- Ghana Meteorological Agency Act 2004, Act 687.

Table 4-2: National Legal Framework

		Applicability to Proposed
No.	Legal Framework and Key Compliance Requirements	Project
1.	The Constitution of the Republic of Ghana, 1992	This is the overarching
	The Constitution includes some provisions to protect the right of individuals to private property and also sets principles under which citizens may be deprived of their property in the public interest (described in Articles 18 and 20).	legislative framework of Ghana. Articles 18 and 20 provides conditions for the acquisition of property (in this case land) for development projects and
	Article 18 provides that "Every person has the right to own property either alone or in association with others."	compensation
	In Article 20, the Constitution describes the circumstances under which compulsory acquisition of immovable properties in the public interest can be done. It includes: • the development or utilization of property for public benefit • reasonable justification is provided for acquisition • the prompt payment of fair and adequate compensation • resettlement of displaced persons on suitable alternative land with due regard for their economic well-being, social and cultural values.	
2.	Ghana Investment Promotion Centre Act 1994, Act 478	The proposed project has
	The Ghana Investment Promotion Centre Act 1994 (Act 478) requires that every investor wishing to invest in the country must in its appraisal of proposed investment projects or enterprises, "have regard to any effect the enterprise is likely to have on the environment and measures proposed for the prevention and control of any harmful effects to the environment".	environmental impacts and measures have been proposed in the ESIA/ESMP to address the impacts.
3.	Environmental Protection Act 2025, Act 1124	The project will be in
	The Environmental Protection Act 2025 (Act 1124) amends the name of the regulator from the Environmental Protection Agency to the Environmental Protection Authority and confers additional powers on the Authority beyond the issue of environmental permits. Act 1124	compliance with the Environmental Assessment (EA) procedures for approval of the EPA.
	consolidates the various legislations that regulate environmental protection in the country, such as the Hazardous and Electronic Waste Control and Management Act, 2016 (Act 917) and the Pesticides Control and Management Act, 1996 (Act 528). Act 1124 also establishes	The proposed project will involve the clearing of vegetation and generation and disposal of waste. Also,
	the Environmental Protection Authority to regulate, protect, co-	considering that the project
	ordinate, and exercise general oversight over climate change and environmental matters.	area is over 40 hectares and according to the EPA
	Part II of the Act 1124 specifically deals with pesticides control and management. This section of the Act provides the rules for registration,	classification, a permit has to be obtained.

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	pesticides classification, approval, clearance, using, disposing of and non- disclosure of confidential information, the granting of license, labelling and pesticides inspections.	The Pest Management Plan (PMP) will address concerns of relevant stakeholders with regards to pests and pesticides.
4.	Environmental Assessment Regulations 2025, LI 2504 The Environmental Assessment Regulations 2025 (LI 2504) enjoins any proponent or person to register an undertaking with the Authority and obtain an Environmental Permit prior to the commencement of the project. This regulation allows the EPA to place proposed undertakings at the appropriate level of environmental assessment. The LI 2504 seeks to ensure that development is undertaken in a sustainable environment.	The Project will be guided by LI 2504 including registering with the EPA and obtaining an environmental permit.
5.	Fees and Charges (Miscellaneous Provisions) Act, 2022 (Act 1080) The Fees and Charges (Miscellaneous Provisions) 2022 (Act 1080) sets out the fee regime for processing and environmental permits, associated with the Environmental Assessment Regulations. This Act replaces the 2019 Amendment. Processing and permit fees are required for initial registration, and upon submission and approval of Preliminary Environmental Report (PER).	Processing and permit fees are required for initial registration, submission of ESIA report and registration of sub-projects.
6.	Water Resources Commission (WRC) Act 1996, Act 522 The Water Resources Commission Act, 1996 (Act 522) establishes and mandates the Water Resources Commission (WRC) as the sole agency responsible for the regulation and management of the utilisation of water resources and for the co-ordination of any policy in relation to them. The Act states under Section 24 that any person who pollutes or fouls a water resource beyond the level that the EPA may prescribe commits an offence and is liable on conviction to a fine or a term of imprisonment or both.	The project will put in place measures to prevent the pollution of the Daka river.
7.	Water Use Regulations 2001, LI 1692 The Water Use Regulations 2001, LI 1692 prohibits the use of water resources without authority from the Water Resources Commission. It provides procedures for allocating permits for various water uses including domestic, commercial, municipal, industrial, agricultural, power generation, water transportation, fisheries (aquaculture), environmental, recreational and underwater (wood) harvesting. The Act provides under section 16 for any person to apply to the	Project managers will ensure the continuous renewal of water use permits through the appropriate tariff setting and compliance with permit requirements

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	Commission in writing for the grant of water right. The Regulations also prescribe the raw water charges and processing fees to be paid by prospective water users with respect to the water use permits. The Commission is also mandated to request for evidence that an environmental impact assessment or an environmental management plan has been approved by the EPA before issuance of the Water Use Permit.	
8.	Ghana Meteorological Agency 2004, Act 687 This Act establishes the Ghana Meteorological Agency, which replaces the Meteorological Services Department. The Agency is to provide meteorological information, advice, and warnings for the benefit of agriculture, civil and military aviation among others to mitigate the effects of natural disasters such as floods, storms and droughts on socio-economic development and projects. The Agency is to provide the accurate data on climatic which are relevant for establishing climate change trends.	The project managers will liaise with the Ghana Meteorological Agency regularly especially in seeking meteorological information and advice

4.2.1 Agriculture Sector Legislation and Related Requirements

The agriculture sector legislation reviewed include:

• Plants and Fertilizer Act 2010 (Act 803);

Table 4-3: Agriculture Sector Legislation and Related Requirements

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	Plants and Fertilizer Act 2010 (Act 803) The Act provides for the efficient conduct of plant protection to prevent the introduction and spread of pests and diseases, to regulate imports and exports of plants and planting materials; the regulation and monitoring of the exports, imports and commercial transaction in seeds and related matters; and control and regulation of fertilizer trade.	The Plant Protection Regulatory Services Division (PPRSD) of MoFA will ensure that all seeds/plant materials are safe and also put in monitoring mechanism to prevent the spread of pests and diseases from the project site to other parts of the country.

4.2.2 Local Governance and Planning Requirements

The relevant legislation reviewed include:

- Local Governance Act, 2016 (Act 936);
- National Building Regulations, 1996 (LI 1630);

- The State Lands Act, 1962 (Act 125);
- Lands Commission (LC) Act 2008, Act 767; and
- Land Use and Spatial Planning Act, 2016 (Act 925).

Table 4-4: Local Governance and Planning Requirements

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
1.	Local Governance Act, 2016 (Act 936)	The input of the Physical
	This Act establishes and regulates the local government system and	Planning and Roads
	gives authority to the RCC and the District Assembly to exercise political	Departments of the District
	and administrative power in the regions and districts respectively. This	Assemblies will be sought in
	includes initiation of development programmes as well as development,	designing water distribution
	improvement and management of human settlements and the	networks
	environment through departments such as the Urban/Feeder Roads	
	and Physical Planning Departments.	
2.	National Building Regulations, 1996 (LI 1630)	The project will involve
	The National Building Regulations, 1996 (LI 1630) make it an offence for	development of agricultural
	any individual to undertake any development without the acquisition of	infrastructure such as sheds,
	a Building Permit from the appropriate authority. This ensures that	storage etc. and the necessary
	buildings are well planned and are in conformity with the Assembly's	building permit will be
	plan designs of an area. The LI 1630 ensures that buildings are well	acquired.
	planned, consistent with the Assembly's spatial plan for an area.	
3.	The State Lands Act, 1962 (Act 125)	The project implementation
	The Act 125 vests the authority to acquire land for the public interest in	will result in some form of
	the President of the Republic. It also gives responsibility for registering	displacement or disturbance,
	a claim on the affected person or group of persons, and provides details	and due process will be
	of the procedure to do this. The State Lands Act, 1962 provides some	followed in accordance with
	details to be taken into consideration when calculating compensation	the relevant provisions of this
	such as definitions for cost of disturbance, market value, replacement	Act
	value, and so on.	
4.	Lands Commission (LC) Act, 2008 (Act 767)	The Project will be
	The Lands Commission Act 2008 re-establishes the Lands Commission	implemented in line with the
	to integrate the operations of public service land institutions in order to	objectives of the Commission
	secure effective and efficient land administration to provide for related	for sustainable development
	matters. The objectives of the Commission are to (i) promote the	of land and conform to the
	judicious use of land by the society and (ii) ensure that land	development goals of the
	development is in conformity with the nation's development goals.	MMDAs.
5.	Land Use and Spatial Planning Act, 2016 (Act 925)	The project design will be
	The Land Use and Spatial Planning Act, 2016 (Act 925) regulates land	guided by planning schemes
	use through a decentralised planning system to ensure judicious use of	and local plan guides
	land in order to improve quality of life, promote health and safety in	developed by the Land Use
	respect of human settlements and generally provide for spatial aspects	and Spatial Planning
	of socio-economic development and related matters.	Departments/District
		Assemblies

4.2.3 National Labour, Environmental Quality, Health, Safety and Social Guidelines

The reviewed legislation includes:

- Labour Act, 2003 (Act 651);
- Occupational Safety and Health Policy of Ghana (Draft, 2004);
- Workmen's Compensation Law, 1987 (PNDCL 187);
- National Workplace HIV/AIDS Policy;
- Environmental Impact Assessment Guideline for the agricultural Sector (EPA, 2010);
- Ghana Standard for Environmental Protection Requirements for Effluent Discharge (GS1212, 2019);
- Ghana Standards for Environment and Health Protection Requirements for Ambient Air Quality and Point Source/Stack Emissions (GS 1236, 2019);
- Ghana Standards for Health Protection Requirements for Ambient Noise Control (GS 1222, 2018);
- Ghana Standards for Environment and Health Protection Requirements for Motor Vehicle Emissions (GS1219, 2018);
- Ghana National Fire Service Act, 1997 (Act 537);
- Fire Precaution (Premises) Regulations, 2003 (LI1724);
- Control of bush fires law of 1983 (PNDC L 46)
- Control and Prevention of Bush Fire Law (PNDC L 229);
- Children's Act 1998, Act 560; and
- Alternative Dispute Resolution Act 2010 (Act 798).

Table 4-5: National Labour, Environmental Quality, Health, Safety and Social Guidelines

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
1.	Labour Act, 2003 (Act 651) The Labour Act 2003 (Act 651) Section 118(1) stipulates that it is the duty of an employer to ensure that satisfactory, safe and healthy conditions are provided for every worker. Under these provisions, a worker is required to report situations that he believes may pose "an imminent and serious danger to his or her life, safety or health".	Construction activities could result in injuries and fatalities. HSE issues have been duly assessed and provided for in the proposed ESMP for the project
2.	Occupational Safety and Health Policy of Ghana (Draft, 2004) The statement of the Occupational Safety and Health Policy of Ghana (Draft, 2004) is: 'to prevent accidents and injuries arising out of or linked with or occurring in the course of work, by minimising as far as reasonably practicable the cause of the hazards in the working environment and, therefore the risk to which employees and the public may be exposed'. The policy is derived from provisions of the International Labour Organisation (ILO) Conventions 155 and 161. The policy document highlights specific strategies, activities promotion and awareness creation which ensure that workers engaged at the construction and operation stages of the project are protected.	Potential sources of accidents and injuries that could occur in the course of work, have been identified and incorporated into safeguards for minimising safety and health risks and hazards as required by the draft OSH Policy.
3.	Workmen's Compensation Law, 1987 (PNDCL 187)	The Labour policy and employment contracts will provide for workmen

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	It is to provide for the payment of compensation to workmen for personal injuries caused by accidents arising out and in the course of their employment. The tenets of the law place a large share of the burden of supporting workers injured at the workplace on the shoulders of the employers.	compensation in the event of injury.
4.	National Workplace HIV/AIDS Policy The broad objectives of the National Workplace HIV/AIDS Policy, among others, are to provide protection from discrimination in the workplace to people living with HIV and AIDS; prevent HIV and AIDS spread among workers; and provide care, support and counselling for those infected and affected. The project will institute a plan of action to prevent HIV/AIDS spread through awareness creation.	The project duration will be short-term and use just a few migrant workers. This will reduce the potential for HIV spread but an HIV policy will be provided as required by the national policy
5.	Environmental Impact Assessment Guidelines for the Agricultural Sector (EPA, 2010) The Agriculture Sector Guidelines is meant to assist the Environmental Protection Authority (EPA) in the implementation of its Environmental Impact Assessment procedures in Ghana. The document is in two parts. Part I deals with the background and methodology. Areas covered include overview of the agricultural sector, environmental assessment processes, environmental management programme and project decommissioning. Part II covers information and tools used in the environmental impact assessment. This includes the legal framework for EIA procedures in agriculture, general screening criteria, environmentally sensitive areas in agriculture and impact identification, evaluation and mitigation measures. It is intended to provide guidelines that will be used through all stages of an Agricultural Project Cycle; i.e. identification, preparation, appraisal, implementation and post-implementation monitoring.	These guidelines were taken into consideration in preparing this ESIA report. Also, all other project activities will follow these guidelines
6.	Ghana Standard for Environmental Protection - Requirements for Effluent Discharge (GS1212, 2019) Ghana Standard for Environmental Protection - Requirements for Effluent Discharge (GS1212, 2019); specifies requirements for sector specific effluent quality and also gives guideline discharge into the environment.	Effluent from both construction and operation phases will be managed as specified in the proposed ESMP
7.	Ghana Standards for Environment and Health Protection - Requirements for Ambient Air Quality and Point Source/Stack Emissions (GS 1236, 2019) Ghana Standards for Environment and Health Protection - Requirements for Ambient Air Quality and Point Source/Stack Emissions (GS 1236, 2019) specifies the requirements and methods of analysis for ambient air. It also	Dust and vehicular emissions will be controlled as specified in the proposed ESMP

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	specifies the requirements and test methods for point source or stack emissions based on the sources of energy.	
8.	Ghana Standards for Health Protection - Requirements for Ambient Noise	Noise generated at both the
	Control (GS 1222, 2018)	construction and operation
	Ghana Standards for Health Protection - Requirements for Ambient Noise Control (GS 1222, 2018) specifies the requirements for acceptable ambient noise levels within categorized locations. According to the Standards, the test method should be in accordance with the relevant test methods given in GS 1253:2018 (Acoustics- Guide for the measurement of outdoor Aweighted sound levels	stages will be monitored as stated in the proposed ESMP to ensure it does not exceed acceptable limits
9.	Ghana Standards for Environment and Health Protection - Requirements	Vehicles for transportation
	for Motor Vehicle Emissions (GS1219, 2018) Ghana Standards for Environment and Health Protection - Requirements for Motor Vehicle Emissions specifies the requirements for exhaust emissions of motor vehicles as well as tractors, farm equipment (such as combine harvester, etc.), mobile industrial / construction machines (such as excavators).	of materials and workers will produce fumes but will be managed with regular maintenance as stipulated in the proposed ESMP
10.	Ghana National Fire Service Act, 1997 (Act 537)	The project area is prone to
	The Ghana National Fire Service (GNFS) Act, 1997 (Act 537) re-established the National Fire Service to provide for the management of undesired fires and to make provision for related matters. The objective of the Service is to prevent and manage undesired fire. For the purpose of achieving its objective, the Service shall organise public fire education programmes to create and sustain awareness of the hazards of fire, heighten the role of the individual in the prevention of fire and provide technical advice for building plans in respect of machinery and structural layouts to facilitate escape from fire, rescue operations and fire management.	bushfires so the Fire Service will be engaged to provide education/sensitization on fire prevention and fighting.
11.	The Fire Precaution (Premises) Regulations 2003, LI 1724 The Fire Precaution (Premises) Regulations 2003 (LI 1724) requires all premises intended for use as workplaces to have Fire Certificates and confers enforcement powers on the Ghana National Fire Service (GNFS) to demand a fire certificate for premises that are put to use as a place of work.	Fire certificates will be obtained for warehouses and project offices.
12.	Control of Bush Fires Law of 1983 (PNDCL 46)	Bushfire is a risk to the
	It seeks to control the setting of bushfires by criminalizing the intentional, reckless, or negligent causing of such fires and holding the offender liable for all consequences of the fire.	proposed project and will be guided by these Laws to take lawful action against any such offender.
13.	Control and Prevention of Bushfire law, PNDCL 229	The project area has been designated as an environmentally sensitive

No.	Legal Framework and Key Compliance Requirements	Applicability to Proposed Project
	Section 2 defines "starting of a bushfire". A person starts a bushfire if an action of that person results in the uncontrolled burning of a farm, forest or grassland. The Chief Conservator of Forests or the Chief Game and Wildlife Officer may authorize starting of fires by authorized officers in Conservation Areas under section 4.	area as climatic conditions make it prone to bushfires. Measures have been proposed in this report to deal with fire risks.
14.	The Children's Act 1998, Act 560 The Act spells out the rights of the child, quasi-judicial/judicial child adjudication, parentage /custody/access/maintenance, fosterage/adoption and employment of children issues. The Act defines a child as a person below the age of 18 years. The minimum age for admission of a child to employment is fifteen years and the minimum age for the engagement of a person in hazardous work is eighteen years. No person shall engage a child in exploitative labour and labour is exploitative of a child if it deprives the child of its health, education or development.	The Project will be guided by this Act in the employment of labour for the proposed project and will ensure all labour engaged by the Contractors are not below the minimum age.
15.	Alternative Dispute Resolution Act 2010 (Act 798) The purpose of the Act is to "provide for the settlement of disputes by arbitration, mediation and customary arbitration, to establish an Alternative Dispute Resolution Centre and to provide for related matters." The Act further defines Alternative Dispute Resolution "as the collective description of methods of resolving disputes otherwise than through the normal trial process" (Section 135). The ADR Act covers both domestic and international arbitration in Ghana and the enforcement of both domestic and foreign arbitral awards within the jurisdiction.	The REWARD Project will ensure that the alternative dispute resolution option is used to address disputes and conflicts instead of the more expensive and time-consuming legal court system under this project.

4.3 National Institutional Framework

The stakeholder institutions identified include:

- Ministry of Food and Agriculture;
- Water Resources Commission;
- Lands Commission;
- Environmental Protection Authority;
- Local Government Authority; and
- Traditional Authorities.

The roles and responsibilities of the Project Implementation Unit (PIU), implementing agencies and other stakeholders, legislative and regulatory requirements for the implementation of the ESMP are provided under **section 9** of this report.

Table 4-6: National Institutional Framework

No.	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
1.	Ministry of Food and Agriculture (MOFA) MOFA promotes sustainable agriculture and agribusiness through research and technology development, effective extension and other support services to farmers, processors, and traders for improved human livelihood. The Food and Agriculture Sector Development Policy (FASDEP II) and the Medium-Term Agricultural Sector Investment Plan (METASIP) seeks to guide development and interventions in the agriculture sector. The Resilient Rice Regional Value Chains in West Africa Project (REWARD) of MoFA also seeks to develop agriculture in Ghana in line with the country's efforts at poverty reduction and ensuring food security by promoting inclusive commercial farming along selected commodity value chains.	Regional and District Departments of Agriculture have the mandate of offering extension services and support to ensure sustainability and the successful implementation of the project
2.	Water Resources Commission (WRC) WRC was established by an Act of Parliament (Act 522 of 1996) with the mandate to regulate and manage Ghana's Water Resources and co-ordinate government policies in relation to them. The Act stipulates that ownership and control of all water resources are vested in the President on behalf of the people, and clearly defines the WRC as the overall body responsible for water resources management in Ghana. The functions of the WRC as established under Act 522 among other things are to: Formulate and enforce policies in water resources conservation, development and management in the country; Coordinate the activities of the various agencies (public and private) in the development and conservation of water resources; Enforce, in collaboration with relevant agencies, measures to control water pollution; and Be responsible for appraising water resources development project proposals, both public and private, before implementation.	The REWARD Project will collaborate with the WRC for the protection of the Daka River.

No.	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project
3.	The Regional Coordinating Council (RCC) and the Metropolitan /Municipal/District Assemblies (MMDAs) are responsible for the overall development of the region and metropolis/municipality/district respectively. Acts 462 and 480, which established the current district assembly structure, designate the District/Municipal/Metropolitan Assembly as the planning authority, charged with the overall development of the district. With regard to environmental management at the district level, the District Environmental Management Committees (DEMC) has been set up by law (Act 462) to among other things: promote and provide guidelines for the establishment of community-level environmental committees to put into effect the environmental programmes of the Assembly in the community; and plan and recommend to the DA, strategies and activities for the improvement and protection of the environment with emphasis on fragile and sensitive areas, river courses etc.	The project is located in the Mion District and will be influenced by decisions and plans of the Northern Regional Coordinating Council and the identified Assembly. The Assembly will play key roles in the successful implementation and related activities of the project.
4.	Lands Commission The Lands Commission was established by Article 258 of the 1992 Constitution and the Lands Commission Act, 2008 (Act 767). The functions of the Lands Commission include amongst others; advise the Government, local authorities and traditional authorities on the policy framework for the development of particular areas of the country to ensure that the development of individual pieces of land is coordinated with the relevant development plan for the area concerned; ensure that through sound, sustainable land use planning, socio-economic activities are consistent with sound land use through sustainable land use planning in the long-term national development goals; and promote community participation and public awareness at all levels in sustainable land management and development practices to ensure the highest and best use of land.	The REWARD Project will be implemented in line with the objectives of the Commission for sustainable development of land and conform to the development goals of the MMDAs.

No.	Institutional Framework and Key Implementation Responsibilities	Applicability to Proposed Project	
5.	Environmental Protection Authority	The REWARD Project	
	The EPA is the body responsible for regulating the environment and ensuring the implementation of government policies on the environment. The functions of the Authority include:	will follow and abide by all EPA procedures in the implementation of the project.	
	 ensuring compliance with any laid down environmental impact assessment procedures in the planning and execution of development projects, including compliance in the respect of existing projects; promoting effective planning in the management of the environment; imposing and collecting environmental protection levies in accordance with the Environmental Protection Act 2025, Act 1124 or regulations made under the Act; and 		
	 acting in liaison and co-operation with government agencies, District Assemblies and other bodies and institutions to control pollution and generally protect the environment. 		
6.	In Ghana, people of common descent owe allegiance to a symbol of collective authority, such as the 'stool' for the Akans of southern Ghana or the 'skin' for the northern peoples. Traditional authorities play a role in the administration of the area. At the village level, family and land disputes and development issues are also traditionally dealt with by the village chief and elders.	The proposed project site falls under the Mamprusi Traditional Council that is a key stakeholder in the project.	
	In addition to providing an important leadership role, especially in the more rural areas, chiefs act as custodians of stool/skin land, can mobilise their people for developmental efforts and arbitrate in the resolution of local disputes. Although chiefs have no direct political authority, some are appointed by the Government or District Assemblies.		

4.4 International Policies and Conventions

Some international requirements, standards and guidelines reviewed include the African Development Bank Operational Safeguards and other International Conventions which are further discussed in this section.

4.4.1 African Development Bank Operational Safeguards

The African Development Bank (AfDB) has an updated Integrated Safeguards System (ISS), published in 2023, which contains published Operational Safeguards (OSs) to guide the safe development of projects it funds. The applicable Operational Safeguards are described in the **Table 4-7** below. The AfDB requirements are not inconsistent with the national requirements and therefore no implementation conflicts are foreseen.

Table 4-7: Operational Safeguards of AfDB

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
1.	OS1– Environmental and social assessment	Borrowers or clients are responsible for conducting the environmental and social assessment (Strategic Environmental and Social Assessment, or SESA, or Environmental and Social Impact Assessment, or ESIA) and for developing, as an integral part of project documentation, an appropriate plan for managing possible impacts. It categorises proposed projects into categories 1, 2, 3, 4 and 5 based on the extent of adverse impacts anticipated from the project.	Applicable	OS1 is applicable because the REWARD Project will be based on the development and rehabilitation of agriculture infrastructures, which may pose adverse environmental and social risks. The REWARD Project risks will be managed throughout the implementation of mitigation measures prescribed in the site specific ESMPs. The project will prepare an ESIA and conduct extensive stakeholder engagements.
2.	OS2- Labour and Working Conditions	This OS outlines the main requirements for borrowers or clients to protect the rights of workers and provide for their basic needs. When the borrower or client intends to employ a workforce for a project, it develops and implements a human resources policy and procedures appropriate to the nature and size of the project, with the scale of the workforce in alignment with this OS and with applicable national laws. The OS requires the protection of the workforce through the institution of appropriate health and safety measures taking into account risks inherent in the particular sector and specific classes of hazards in the borrower's work and does not	Applicable	The Contractor shall comply with the Labour laws and Occupational Health and Safety Best Practice. Preparation of an occupational health and safety plan. Develop a worker grievance redress mechanism. Training of workers on OHS procedures.

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
		support the use of child labour and forced labour.		
3.	OS3- Resource Efficiency and Pollution Prevention and Management	This OS outlines the main pollution prevention and control requirements for borrowers or clients to achieve high quality environmental performance, and efficient and sustainable use of natural resources, over the life of a project. It draws on and aligns Bank operations with existing international conventions and standards related to pollution, hazardous materials and waste, and related issues.	Applicable	OS3 is applicable because potential environment and social impact due to emissions of pollutants and waste is anticipated during the construction phase. Likewise, agriculture development activities will involve the use of improved application of fertilizers and agrochemicals, as well as result in the production of agriculture wastes. These will be managed as per measures prescribed in the ESMP. The project will prepare and implement a Pest Management Plan (PMP).
4.	OS 4– Community Health, Safety and Security	This OS outlines the risks and impacts of the project to the health and safety of the Affected Communities during the project lifecycle and establish preventive and control measures consistent with Best International Practices and commensurate with their nature and magnitude of impacts.	Applicable	OS4 is applicable because the implementation of the project will have some impact on beneficiary communities as well as those close to the project site. The communities have been engaged on the project and there will be continuous engagement of all nearby communities.
5.	OS5— Land Acquisition, Restrictions on Access to Land and Land Use, and Involuntary Resettlement	It relates to Bank-financed projects that cause the involuntary resettlement of people. It seeks to ensure that when people must be displaced they are treated fairly, equitably, and in a socially and culturally sensitive manner; that they receive compensation and resettlement assistance so that their standards of living,	Applicable	OS5 is applicable because there will be loss of livelihood due to restriction on access to land use since some community members may be restricted from accessing farm lands. The project will develop a process to minimize the impact of the project affected persons through the preparation and implementation of Resettlement Action Plan (RAP) which will include

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
		income-earning capacity, production levels and overall means of livelihood are improved; and that they share in the benefits of the project that involves their resettlement.		Livelihood Restoration Plan (LRP) and a Voluntarily Land Donation (VLD) process.
6.	OS6 – Habitat and Biodiversity Conservation and Sustainable Management of Living Natural Resources	This Operational Safeguard (OS) outlines the requirements for borrowers or clients to (i) identify and implement opportunities to conserve and sustainably use biodiversity and natural habitats, and (ii) observe, implement, and respond to requirements for the conservation and sustainable management of priority ecosystem services	Applicable	OS6 is applicable since the proposed interventions will involve the clearing of vegetation and possible impact of local flora and fauna.
7.	OS 7 – Vulnerable Groups	The client will identify, through an environmental and social risks and impacts assessment process, all communities of Indigenous peoples within the project area of influence who may be affected by the project. Also the client will ensure that vulnerable groups and individuals are identified as early as possible in Bank Group operations and that engagement is meaningful, taking into account individuals' and communities' specificities and delivered in an appropriate form, manner and language. The client will adopt a gender-responsive approach to the management of E&S impacts, which takes into account the rights and interests of women	Applicable	Although there are no indigenous people on the project site or within the project communities of influence, a Resettlement Action Plan (RAP) has been prepared with due cognizance of the interests of vulnerable persons especially women, the elderly, People with disabilities (PWDs) etc. The engagement will be meaningful, taking into account individuals' and communities' specificities and delivered in an appropriate form, manner and language.

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
		and girls, men, and boys, including paying specific attention to the differentiated burden of impacts that women and girls might face.		
8.	OS8 – Cultural Heritage	This OS outlines the need of the client must protect cultural heritage from the adverse impacts of project activities and support its preservation. Clients should also promote the equitable sharing of benefits from the use of cultural heritage.	Applicable	There are no sensitive sites like shrines and cemeteries within the proposed project areas. However, water bodies in many Ghanaian societies are believed to house deities. These cultural/traditional beliefs and norms will be documented and respected as part of project implementation.
9.	OS9 - Financial Intermediaries	FIs are required to monitor and manage the environmental and social risks and impacts of their portfolio and FI subprojects, and monitor portfolio risk, as appropriate to the nature of intermediated financing. The way in which the FI will manage its portfolio will take various forms, depending on a number of considerations, including the capacity of the FI and the nature and scope of the funding to be provided by the FI.	Not Applicable	The project design does not foresee the need for a financial intermediary during project implementation.
10.	OS 10 - Stakeholder Engagement and Information Disclosure	Stakeholder Engagement and Information Disclosure recognizes the importance of open and transparent engagement between the Client and project stakeholders as an essential element of good international practice. Effective stakeholder engagement can improve the environmental and social sustainability of projects,	Applicable	All Stakeholders relevant to the project will be engaged according to the prepared stakeholder engagement plan. The stakeholder engagement plan will be updated as required and implemented together with a functional grievance redress mechanism.

No.	AfDB Operational Safeguard Policy	Summary of core requirements	Potential for Trigger under proposed project	Applicability to proposed project
		enhance project acceptance, and make a significant contribution to successful project design and implementation.		

4.4.2 International Conventions

Ghana is a signatory to some of the international conventions that are relevant to the proposed project and it is imperative to analyse the project in light of the commitments made under such conventions. The relevant international conventions are summarised **Table 4-8** below.

Table 4-8: International Policies and Framework

No.	Legal Framework and Key Compliance Requirements	Ratification Date	Applicability to Proposed Project
1.	United Nations Convention on Biological Diversity The three goals of the CBD are to promote the conservation of biodiversity, the sustainable use of its components, and the fair and equitable sharing of benefits arising out of the utilization of genetic resources. The convention calls for the adoption of national strategies, plans and programmes for the conservation and sustainable use of biological diversity into their relevant sectoral and cross-sectional plans, programmes and policies. One of the tools that are prescribed for the management of biodiversity is an environmental assessment. Article 14 of the convention deals with impact assessment and minimization of adverse impacts.	29 August 1994	Ghana is a signatory to these international conventions which are also are relevant to the proposed project. The proposed project has potential impacts on biodiversity and will have to implement appropriate climate change adaptation measures. Ghana, being a signatory of these conventions, will work towards the achievement of the respective goals of these conventions. The ESIA will identify endangered species in the project area and recommend appropriate mitigation measures for their protection and conservation.
2.	Convention on International Trade in Endangered Species of Wild Fauna and Flora (CITES) The objective of the Convention is to conserve wildlife and prevent international trade from threatening species with extinction.	14 November 1975	The Project has not identified any endangered species listed on the CITES on the project farmlands.

No.	Legal Framework and Key Compliance	Ratification Date	Applicability to Proposed
3.	Legal Framework and Key Compliance Requirements United Nations Framework Convention on Climate Change (UNFCCC) The UNFCCC provides the basis for global action to protect the climate system for present and future generations. The ultimate objective of this Convention and any related legal instruments that the Conference of the Parties may adopt is to achieve, in accordance with the relevant provisions of the Convention, stabilization of greenhouse gas concentrations in the atmosphere at a level that would prevent dangerous anthropogenic interference with the climate system. Such a level should be achieved within a time frame sufficient to allow ecosystems to adapt naturally to climate change, to ensure that food production is not threatened and to enable economic development to proceed in a sustainable manner.	06 September 1995	Applicability to Proposed Project The REWARD Project is a government agricultural initiative and is therefore bound by the requirements of the regulation.

5.0 ENVIRONMENTAL AND SOCIAL BASELINE CONDITIONS

Baseline conditions give the existing status of the environment in the proposed project area of influence before the commencement of the project activities. The information serves the purpose of a base reference against which the changes due to the implementation of the project can be measured. The description which is informed by relevant literature available/documents from stakeholders, presents a general understanding of the conditions within Mion District which is the host district and where necessary, the Northern Region of Ghana. The site-specific context describes the prevailing conditions at the project sites based on field observation and assessments.

5.1 Mion District Baseline Conditions

5.1.1 Physical Environment

The physical environment encompasses all natural and built factors in the locality. This section gives a description of the characteristics of physical environment of the Mion District.

Climate

The climate of the district is relatively dry, with a single rainy season that begins in March/April and ends in October. The amount of rainfall recorded annually varies between 750 mm and 1050 mm. The dry season starts in October/November and ends in March/April with maximum temperatures occurring towards the end of the dry season and minimum temperatures in December and January. The Harmattan winds, which occur during the months of December to early February, have considerable effect on the temperatures in the district, which may vary between 14°C at night and 40°C during the day. Humidity, which is very low, mitigates the effect of the daytime heat.

Rainfall

Owusu (2018) carried out a detailed study on rainfall changes in the savannah zone of northern Ghana from 1961 to 2010. The study examined rainfall variability, trends, and impacts on agriculture and water resource management in the region.

The zone experiences a unimodal rainfall regime that lasts between 5 and 6 months, as shown in **Figure 5-1**. Rainfall is influenced by the Inter-Tropical Discontinuity (ITD) and other atmospheric systems. The mean annual rainfall total is around 1000mm and 90% of the rain occurs from May to October. Rainfall in the region is highly variable, both at the annual and multi-decadal scale (CARE International, 2013). Rain onset is erratic, making forecasting for agricultural applications very difficult.




Figure 5-1: Unimodal rainfall regime of northern Ghana, represented by Tamale, 1960–2010.

The trend analysis of rainfall data from four stations (Navrongo, Tamale, Wa, Yendi) showed a decline in rainfall during the 1970s and 1980s, with minimal recovery post-2000. However, the recovery is insufficient to match the wetter periods of the 1950s and 1960s.

The region also experiences high inter-annual and multi-decadal variability, alternating between dry and wet phases every 20–30 years. The 1950s and 1960s were wetter, followed by droughts in the 1970s and 1980s, and a slight recovery post-2000 (see **Figure 5-2**).




Figure 5-2: Mean annual rainfall total and standard deviation for northern Ghana.

The average monthly total rainfall data from the year 2015 to 2024 for Yendi (the nearest meteorological station) is described in **Figure 5-3** below. The figure shows a distinct difference between wet season and dry season. The dry season is between November and March and wet season between April and October, peaking in September.

The highest average total monthly rainfall was recorded in September with a value of 240 mm making it the wettest month and the lowest was recorded in January (8.4 mm).




Figure 5-3: Average Monthly rainfall

(Ghana Meteorological Agency, 2025)

Temperature

Figure 5-4 shows the average monthly maximum and minimum temperatures. The hottest months mostly fall between February and April (35–36°C) which is the peak of the dry season. The minimum temperature was recorded in January (20°C) which usually coincide with the Harmattan, accompanied by cooler mornings and cooler nights.




Figure 5-4: Average monthly Minimum and Maximum temperature

(Ghana Meteorological Agency, 2025)

Relative Humidity

The month of January recorded the lowest average monthly relative humidity while the highest was recorded in August. There is a steady decline in humidity levels between October and December with December marking the return to dry season conditions. The pattern indicated is typical for a tropical savanna climate with distinct wet and dry seasons. (**Figure 5-5**).




Figure 5-5: Average Monthly Relative Humidity

(Ghana Meteorological Agency, 2025)

Sunshine

High values of sunshine were recorded in January and November, with a gradual decline from January to August. Sunshine hours begin to increase again from September, peaking in November. This rise marks the end of the rainy season and return to drier, sunnier conditions. (Figure 5-6)




Figure 5-6: Average Total Sunshine Hours

(Ghana Meteorological Agency, 2025)

Wind Speed

As shown in **Figure 5-7**, the general trend indicate that the wind speed fluctuates over the years with two broad periods i.e. high winds from January to July, peaking in April and low winds from September to November. December marks a return to higher wind speeds.

Wind speed variation is generally described as moderate ranging roughly from 1.3 m/s to 2.6 m/s. The difference between the highest and lowest months is significant enough to impact activities dependent on wind including farming.




Figure 5-7: Average Monthly Wind Speed

(Ghana Meteorological Agency, 2025)

Water Resources

Ground Water

The occurrence of groundwater in Ghana is associated with 3 main geological formations. These are the basement complex, comprising crystalline igneous and metamorphic rocks; the consolidated sedimentary formations underlying the Volta basin (including the limestone horizon); and the mesozoic and cenozoic sedimentary rocks. The basement complex and the Voltaian formation cover 54 percent and 45 percent of the country respectively. The remaining 1 percent consists of mesozoic and cenozoic sediments.

Groundwater occurrence in the basement complex is associated with the development of secondary porosity as a result of jointing, shearing, fracturing and weathering. The depths of aquifers are normally between 10m and 60m, and yields rarely exceed 6 m³/hr. In the mesozoic and cenozoic formations occurring in the extreme south eastern and western part of the country, the aquifer depths vary from 6 m to 120 m. There are also limestone aquifers, some of which are 120 m to 300 m in depth. The average yield in the limestone aquifers is as high as 180 m³/hr. In all, the total actual renewable water resources are estimated to be 53.2 billion m³ per year. All recharge to water resources is precipitation.

The quality of groundwater resources in Ghana is generally good except for some cases of localised pollution and areas with high levels of iron, fluoride and other minerals. Salinity in certain groundwater occurrences is also found especially in some coastal aquifers. **Figure 5-8** shows a map of the Ground Water Potential Zones in Ghana (Murali Krishna Gumma & Paul Pavelic, 2012) .




Figure 5-8: Ground Water Potential Zones in the Northern part of Ghana (Source: Murali Krishna Gumma & Paul Pavelic, 2012)

Surface Water

The topography of the district is basically undulating with few hills, which provide a good flow for run-off water. The district is underlain by Voltaian rocks normally suitable for rural water supply – boreholes (see **Figure 5-9**).

During the raining season, water normally drains into rivers, dams and streams present in the district although there are incidences of large quantities of water collecting on road sides, washing roads out or pooling to prevent proper transportation. **Figure 5-10** shows the drainage map of the Mion district.




Figure 5-9: Elevation Map of the Mion District

(Source: SAL Consult, 2025)




Figure 5-10: Drainage Map of the Mion District

(Source: SAL Consult, 2025)

Geology and Soils

The area is underlain basically by sedimentary rocks of predominantly voltaian sandstone, shales and mudstones (see **Figure 5-11**). The soils derived from the above parent materials range from laterite, ochrosols, sandy soils, alluvial soils and clay. The organic content is low and is increasingly worsened by the extensive bush burning and bad agricultural practices. This to a large extent accounts for the low yield per acre and its consequent food shortage during the dry or lean season in the area.




Figure 5-11: Soil Map of the Mion District

(Source: SAL Consult, 2025)

5.1.2 Biological Environment

Vegetation

The area is in the interior Guinea savannah woodland belt and characterized by common grass vegetation with tussocks reaching a height of 3m or more and drought-resistant trees like sheanut (Vitellaria paradoxa), baobab (Adansonia digitata), dawadawa (Parkia biglobosa) and acacia (see **Figure 5-12**). The vegetation changes markedly with change in the season and climatic conditions. Many of the rivers flow throughout the year which can support irrigation farming, particularly in the dry season. The sheanut, which is the main export product of the area, still grows in the wild with vegetation largely affected by human activities such as farming and bush fire.




Figure 5-12: Vegetation Map of the Mion District (Source: SAL Consult, 2025)

5.1.3 Socio-economic Environment

Governance Structure

Governance comprises the interaction between the formal institutions and those in civil society. It also refers to a process whereby elements in society wield power, authority, resources and influence and enact policies and decisions concerning public life and social uplift.

The political structure of the Assembly places the District Assembly as the main institution about which every other institution revolves. The current local government system has a three (3) tier structure at the district level, which is made up of the following:

- (i) District Assembly;
- (ii) Town / Area Councils; and
- (iii) Unit Committees

Administratively, the District is divided into three (3) Area Councils-Sang, Sambu and Kpabia and Twenty (20) electoral areas. Politically the District has one constituency namely Mion Constituency. The District Chief Executive heads the Office of the District Assembly. The District Assembly comprises the District Chief Executive, twenty (20) elected members, nine (9) appointed members and a Member of Parliament who has no voting rights. The Assembly is chaired by a Presiding Member elected from among the assembly members. Out of the 29 Assembly members only one is a female. There is the need to sensitize women to involve in leadership positions and decision making. The Assembly performs its functions through the Executive Committee and a network of sub-committees. The executive functions are performed by the Executive Committee which is presided over by the District Chief Executive (DCE) and consists of not more than one-third of the total number of members of the Assembly, excluding the Presiding Member. It exercises its executive and co-coordinating functions of the Assembly through the five sub-committees that collate and deliberate on issues relevant to their functional areas. The sub-committees are as follow:

- Development Planning sub-committee
- Social Services sub-committee
- Works sub-committee
- Finance and Administration sub-committee
- Justice and Security sub-committee

To ensure effective administration of the Assembly, the DCE is supported by a secretariat or central administration which is headed by the District Coordinating Director (DCD) who reports to the DCE and is in-charge of the day-to-day administration of the Assembly.

Demography

The district population, according to the 2021 Population and Housing Census, is 94,930 made up of 47,162 (49%) males and 47,769 (51%) females. This is about 4% and less than 1% of the regional and national population respectively. The population density is 37 persons per sqkm with a total of 15,399 households and an average household size of 6 persons per household which is higher than the regional average of 5.

Majority (64%) of households live in compound houses, followed by huts/buildings (20%), separate house (10%). Up to 2% of households are accommodated in semi-detached houses with flats, huts in different compounds, tents and uncompleted building accommodating the least households in all cases.

According to the 2021 Population and Housing Census, the district is predominantly rural with 89% rural population and 11% living in urban areas.

The district is multi-ethnic in nature with the Dagombas as the dominant ethnic group. They speak the Dagbani language which belongs to the Mole-Dagbani sub-group of Gur languages. Other ethnic groups include the Konkombas, Hausas, Chokosis, Akans, Ewes, Basares and Moshies. The Konkombas are the second biggest group in the district.

Majority (62%) of the district population professes Islam, followed by Christians (17%) and Traditionalist (17%) with a small proportion of the district population belonging to the Pentecostal/charismatic (2%) churches and other religions (1%).

Education and Literacy

According to the 2010 Population and Housing Census, there are 71 schools in the district comprising 64 Early Childhood Centers and Primary Schools and 7 Junior High Schools. There is no Senior High School and therefore students from the district have to attend Senior High School (SHS) education in places outside the district.

With a literate population of only 29%, the district clearly has a very high illiteracy rate. A little above two-thirds (71%) of the literate population could read and write English and Ghanaian language. Less than one-third (22%) could read and write English only and 7% could read and write Ghanaian language only.

Economic Activities

The economy of the people is largely subsistence with agriculture being their main occupation. Over 95% of the people depend on agriculture for their livelihood. Other economic activities, which are mostly small to medium scale, include weaving, agro-processing (Shea butter extraction), meat processing, fish mongering, wholesale and retail of general goods, transport and many others.

The agricultural potential is enormous as there is suitable land for cultivation of cereals, tubers and rearing of animals such cattle, sheep, goats, pigs and poultry birds for domestic and commercial purposes. Both males and females engage in agriculture but females have no land ownership rights. A good number of the populace is engaged in small scale manufacturing business. They include smock weavers, blacksmiths, bakers, mechanics, shea butter extraction and groundnut oil extraction.

Utilities and Services

Energy

Most part of the district is not connected to the National Electricity Grid. Only 20% of dwelling units within Sang (the District Capital), Sambu, Zakpalsi and Jimle have been connected to the National Electricity Grid (2020 Composite Budget, Mion District). Kerosene is the dominant source of lighting in the district, with 68% of the total dwelling units relying on kerosene. Other sources of lighting include; Gas lamp (<1%),

solar energy (<1%), flash light/torch (19%), firewood (1%), and crop residue (<1%) with candle and others representing (<1%) (Population and Housing Census, 2010). With regards to cooking fuel, 96% depend on wood, followed by charcoal (2%) and saw dust, animal waste and others (<1%).

Water

The main sources of drinking water in the district include the small-town water systems, boreholes and surface water (Stream, Dam, and Rivers) which are used for domestic, animal drinking and irrigation purposes. The district has four small town water systems located in Sang, Kpabia, Gunsi and Zakpalsi and a total of 120 water facilities comprising 98 boreholes, 8 dug outs and 14 dams. The commonest sources of drinking water are bore-hole/Pump/Tube well (50%) followed by river and stream (28%) and pipe-borne water (5%). Access to potable water sources, in terms of the number of facilities, is highly inadequate considering the population of the district.

Sanitation and Waste Management

The number of sanitation facilities in the Mion District is quite adequate. There are a total of 6,793 toilet facilities in the district comprising 6,784 household pit latrines, 1 KVIP and 8 public latrines. The dominance of the household pit latrines was due to the prioritization of household latrine construction to achieve open defecation-free status by the district. These facilities aid in reducing the sanitation and environmental-related diseases in the district. However, those who do not have access to toilet facilities practice open defecation by using the bushes and fields.

Majority (46%) of households dispose of their solid waste in open space at public dumps and 6% dispose of their solid waste into public containers. Significant numbers of households either have their solid waste dumped indiscriminately (34%) or burned (1%). In addition, 65% of households throw their liquid waste onto the street/outside. Another 22% throw their liquid waste either onto the compound, while 2% throw their liquid waste into gutters. Only 1% of households dispose of their liquid waste through plumbing systems into gutters. Overall, rural households appear to be better urban households in terms of both solid (rubbish) and liquid waste disposal.

Communication

Out of the population 12 years and older, 48% (28% males and 21% females) own mobile phones. Also, 13% of the population has access to the internet and the proportion of males (9%) among users of the internet facility is more than females (4%).

Health

The district has a total of Thirteen (13) Health Facilities comprising Five (5) Health Centres and Eight (8) CHPS Compounds. The district also has Four (4) CHPS Compounds completed but not operational, Two CHPS Compounds under construction and Nine Demarcated CHPS Zones. **Table 5-1** shows the list of Health Facilities in Mion District.

Table 5-1: List of Health Facilities in Mion District

Sub-District	S/N	Facility	Status of Facility
	1	Jimle Health Centre	Operational
2		Tidjo CHPS Compound	Operational
	3	Nanvili CHPS Compound	Completed but not Operational
Jimle	4	Chegu CHPS Compound	Under Construction
	5	Kpabia Health centre	Operational
	6	Bofoyili CHPS Compound	Operational
	7	Tanado CHPS Compound	Operational
	8	Dabogni CHPS Compound	Operational
	9	Buli CHPS Zone	No Compound
	10	Nsojah CHPS Zone	No Compound
	11	Nyentou CHPS Zone	No Compound
Kpabia	12	Afayili CHPS Zone	No Compound
	13	Kukpalgu Health Centre	Operational
	14	Tinsung CHPS Compound	Completed but not Operational
Kukpalgu	15	Dombini CHPs Zone	No Compound
	16	Sambu Health Centre	Operational
	17	Kpunkpuno CHPS Compound	Operational
	18	Nadundo CHPS Compound	Operational
	19	Bachaborido CHPS Compound	Operational
	20	Warivi CHPS Compound	Completed but not Operational
Sambu	21	Manyini CHPS Compound	Completed but not Operational
	22	Sang Health Centre	Operational
	23	Sakpei CHPS Compound	Operational
	24	Zakpalsi CHPS Compound	Under Construction
	25	Salankpang CHPS Zone	No Compound
Sang	26	Kulinkpegu CHPS Zone	No Compound
	27	Sanzee CHPS Zone	No Compound
	28	Kayoung CHPS Zone	No Compound

(Source: Mion District Medium Term Development Plan, 2021)

Transportation

The district has a total of 386 kilometers of road network. 45 kilometers of this is tarred road, which is part of the primary road that connects Tamale, the regional capital, to Yendi, the mother district. The rest of the road network is untarred. Farmers find it difficult to access markets in Yendi, Sang, Tamale, Sambu, Salaga, and Bimbilla, especially during the rainy season, due to the poor condition of the roads.

Land Ownership/Tenure

Land ownership follows a patrilineal system with regards to land inheritance. Accordingly, inheritances can go to the male's sons or brothers. Where royal land is involved, as in the case of chieftains, land and right to chieftaincy may be passed on from a father to his sons, who are wards of the father's brother on the understanding that the right to the land and chieftaincy should rotate among the sons of the father and the father's brother. Whoever has control over the land has right to the land and any resources it produces.

Land ownership in traditional society tends to be acknowledged by communal recognition and observation, or that of the ruling traditional elder. Deeds or papers are not usually involved, nor are lawyers. The existence of deeds or papers usually indicates a previous dispute over the land which was taken to the court system. When a conflict emerges the traditional avenue for resolution is to have the traditional elder arbitrate. However, this process usually only works when both parties respect the traditional elder. If one or both parties lack confidence in the traditional elder, local politicians are frequently asked to arbitrate.

Land disputes may be taken to the court system, but these are costly and, in the case of royal land, they can drag on as each party seeks to appeal every judgement that goes against it. In some areas, recourse to the courts is less likely because of the costs involved and less acceptance of that system as a dispute settling mechanism.

Nevertheless, even if a case goes before the courts, the land may still be used and/or occupied by the disputants since it often is the source of livelihood of the disputants. Force may be used to settle cases where traditional authority is ineffective.

A person or a group of people can buy land for construction, farming and other purposes from chiefs and family leaders.

5.2 Characteristics of the Project site (Tindantua valley)

The immediate beneficiary community, i.e. the Tindantua community has been identified based on the availability of land for commercial farming. This section describes the environmental and social conditions in the community and project vicinity. **Plate 5-1** below shows a photo of the Tindantua valley.



Plate 5-1: The Tindantua Valley (SAL Consult, 2025)

5.2.1 Air Quality

Active air quality monitoring was carried out between 7th and 10th April 2025 at the proposed project site, that is within the Tindantua valley and the sampling was done in compliance with the requirements of GS 1236:2019 as shown in **Table 5-2**.

Table 5-2: Environment and Health Protection- Requirements for Ambient Air Quality and Point Sources/Stack Emissions (GS 1236:2019).

S/N	Air Quality Parameter	Maximum Limits	Averaging Time
1	Carbon monoxide, mg/m ³	10	8 hours
2	Sulphur dioxide (SO ₂), μg/m ³	50	24hours
3	Nitrogen oxides (measured as NO ₂), μg/m ³	150	24hours
4	PM ₁₀ , μg/m ³	70	24hours
5	PM _{2.5} , μg/m ³	35	24hours

Particulate Matter

The sampling and analysis of ambient particulate matter concentrations was done according to the ASTM Test Method D4096-17. Particulate matter ($PM_{2.5}$ and PM_{10}) was sampled at the Tindantua valley for 24 hours using ARA N-FRM Air Sampler set to a flow rate of 16.7 L/min drawing air through the inlet onto a 47mm quartz filter for analysis. **Plate 5-2** below show the mounted equipment at the Tindantua valley.



Plate 5-2: ARA N-FRM Setup for PM_{2.5} and PM₁₀ sampling (SAL Consult, 2025)

Results

The Particulate Matter (PM_{2.5}) concentrations monitored at the proposed Tindantua Rice Valley was 10.0 $\mu g/m^3$ which was within both the Ghana Standard (GS 1239:2019) permissible value of 35 ($\mu g/m^3$) and WHO 2021 limit of 15 $\mu g/m^3$.

The low concentration observed at the proposed site is a confirmation of minimal anthropogenic activities with little impact on PM_{2.5} levels in the area. Additionally, the prevailing meteorological conditions (e.g., low wind speeds) may have influenced the low readings.

Likewise, the Particulate Matter (PM₁₀) concentration of 16.0 μ g/m³ which was also lower than the WHO limit of 45 μ g/m³ and Ghana's permissible threshold of 70 μ g/m³.

Figure 5-13 shows a graphical presentation of compliance and/or exceedance of particulates to GSA/WHO Standards.




Figure 5-13: Graph showing compliance and or exceedance of particulates to GSA/WHO Standards (SAL Consult, 2025)

Gases (NO₂, SO₂ and CO)

The Aeroqual Series 500(A-S500) Gas Meter, a high rated device that enables accurate real time surveying of common indoor and outdoor air pollutants, was used to determine the concentration levels of NO_2 , SO_2 and CO (Plate 5-3). The ambient concentrations were recorded for every minute, from which hourly concentrations were calculated and mean concentrations determined.



Plate 5-3: Gases monitoring at the Tindantua valley (SAL Consult, 2025)

Results

The concentration of nitrogen dioxide recorded at the Tindantua Rice Valley was $0.20~\mu g/m^3$, which is far below both the Ghanaian standard of 150 $\mu g/m^3$ and the more stringent WHO limit of 25 $\mu g/m^3$. NO₂ primarily originates from vehicular emissions, fossil fuel combustion, and biomass burning and such a low level confirms that the surrounding environment is largely free from major anthropogenic sources of NO₂ as at the time of the monitoring exercise.

Likewise, the SO_2 level measured at the site was 0.10 $\mu g/m^3$ which is well below the WHO guideline value of 40 $\mu g/m^3$ and also the Ghana standard threshold.

The CO concentration measured at the site was below the minimum detection limit of 0.06 mg/m³ and therefore well below both the WHO guideline of 4 mg/m³ and the Ghanaian maximum of 10 mg/m³.

Table 5-3 below shows the results of each gas monitored at the proposed Tindantua rice valley.

Table 5-3: NO₂, SO₂ and CO results measured at the valley compared to GSA and WHO standards.

		Geocoor	Concentration				
S/N	Sampling Point	Latitude	Longitude	NO ₂	SO ₂	СО	
				(μg/m³)	(μg/m³)	(mg/m³)	
1	Tindantua Rice valley	9.13081° N	0.15218° W	0.20	0.10	< 0.06	
Ghar	na Standards (GS 1236:2019)	150	50	10			
WHC	0 (2021)	25	40	4			

^{*}Values in red shows exceedance whiles values in green shows compliance with standards

NB: Readings reported as "< (value)" indicate the concentration was below the instrument's Minimum Detection Limit (MDL). The MDLs are based on manufacturer specifications for the Aeroqual sensor heads used: 9.4 μ g/m³ for Nitrogen Dioxide (NO₂), 26.2 μ g/m³ for Sulfur Dioxide (SO₂), and 0.06 mg/m³ for Carbon Monoxide (CO).

5.2.2 Ambient Noise

For the purposes of establishing the existing ambient noise levels in the proposed project area, a noise assessment was undertaken between 7th and 10th April 2025.

Noise measurements/recordings were taken with a High Precision TSI Quest Sound Level Meter, Model Type 1. The sound level meter has an in-built calibrator and was calibrated before each measurement/recordings were taken. The noise meter was calibrated at 114 dB (A) prior to the measurement. The following statistical indices was computed L_{Aeq}, L_{max}, L_{min} and L_{peak}.

The ambient noise levels (LEQ values) recorded at the Tindantua rice valley was compared to the Ghana Standard (GS 1222:2018) and IFC guideline values. **Plate 5-4** below shows a photograph of the daytime noise monitoring at the project site.



Plate 5-4: Ambient Noise monitoring at the proposed Tindantua Rice Valley (SAL Consult, 2025)

Results

The equivalent continuous sound level (L_{Aeq}) recorded at the project site (Tindantua valley) is 52.5 dB(A), with a maximum noise level (L_{max}) of 73.3 dB(A), a minimum noise level (L_{min}) of 45.1 dB(A) and a peak (L_{peak}) of 80.6 dB(A) (see **Figure 5-14**).

When compared with the Ghana Standard (GS 1222:2018) and the IFC Environmental, Health and Safety (EHS) Guidelines, which both prescribe a maximum L_{Aeq} of 70 dB for commercial/agricultural zones (Zone E), the measured L_{Aeq} level was well below the permissible threshold. This is a confirmation of the relatively quiet rural setting of the project area.

The slightly elevated L_{max} and L_{peak} values of 73.3 dB(A) and 80.6 dB(A) respectively suggest intermittent noise events. These are likely caused by passing motorcycles, livestock vocalizations, small-scale machinery etc. The low L_{min} of 45.1 dB further confirms that the background noise level remains undisturbed during most of the day.




Figure 5-14: Daytime Ambient noise levels measured at the Valley (SAL Consult, 2025)

5.2.3 Water Resources

The Northern Region is located within the Volta Basin. The major sub-basins of the Volta include the Black and White Volta Rivers, the Oti River and the Lower Volta, including Lake Volta.

Surface Water

The Daka River, a tributary of the Volta River which drains the project area is a vital water source for many communities who use it for drinking, washing, cooking, and farming.

Water Quality

The Daka river water was tested in situ for pH, Conductivity, TSS, TDS, Turbidity and Chloride using the Hanna multipara meter and compared with the Ghana Standards Authority (GS 175:2017) and the World Health Organization (WHO, 2011) guidelines for drinking water quality.

Plate 5-5 shows the sampling and in-situ testing at the Daka River.









Plate 5-5: Sampling and in-situ testing at the Daka River (SAL Consult, 2025)

Results

Temperature

The temperature of the Daka River was 34.2°C. The temperature range for drinking water quality set by the Ghana Standards Authority (GS 175:2017) is 25°C to 30°C. It has to be understood that the temperature measured relates to the natural environment and not strictly comparable to the guidelines.

However, elevated river temperatures can lower dissolved oxygen levels and hinder aquatic life. Riparian vegetation may be useful to provide shade. **Figure 5-15** shows a graphical presentation of the temperature.




Figure 5-15: Graph showing In-situ measurement of temperature (SAL Consult, 2025)

рН

The pH of the river at the time of in-situ testing was 6.92, which falls within the acceptable range of 6.5 to 8.5 as set by both GS 175:2017 and WHO. This indicates that the Daka River is slightly acidic but chemically stable and safe for most domestic and ecological purposes as shown in **Figure 5-16**.




Figure 5-16: Graph showing In-situ measurement of pH

Electrical Conductivity

Electrical conductivity (EC) measured was 70.5 μ S/cm, which is far lower than the GS 175:2017 limit of 2000 μ S/cm (see **Figure 5-17**). WHO does not provide a numerical standard for EC but recognizes it as a

general indicator of water salinity and dissolved ionic content. The low EC value suggests soft water with minimal levels of dissolved salts, indicating good water quality in terms of mineral content.



Figure 5-17: Graph showing In-situ measurement of electrical conductivity (SAL Consult, 2025)

Total Dissolved Solids

Total dissolved solids (TDS) measured in the Daka River was 35.13 mg/L, this is well below the GS 175:2017 maximum permissible limit of 500 mg/L (see **Figure 5-18**). While WHO does not impose a health-based limit, it notes that TDS values above 600 mg/L can affect the taste and palatability of water. The low TDS observed is consistent with the low EC value and reflects low mineral and pollutant loading.




Figure 5-18: Graph showing In-situ measurement of total dissolved solids (SAL Consult, 2025)

Dissolved Oxygen

Dissolved oxygen (DO) concentration in the river was 4.03 mg/L (see **Figure 5-19**). Although neither GS 175:2017 nor WHO provides a specific guideline for DO in drinking water, levels below 5 mg/L are generally considered inadequate for the survival of many aquatic organisms. A DO level of 4.03 mg/L may indicate moderate organic pollution, possibly due to wastewater discharge or decaying biomass that increases the biological oxygen demand (BOD).




Figure 5-19: Graph showing In-situ measurement of dissolved oxygen (SAL Consult, 2025)

Turbidity

Turbidity recorded was 62.61 NTU (see **Figure 5-20**), which greatly exceeds both the GS 175:2017 and WHO guideline limits of 5 NTU. This high turbidity level is indicative of a significant presence of suspended particles, likely due to soil erosion, surface runoff, or unregulated waste disposal likely from upstream into the river. Measures such as catchment management, erosion control, reforestation, and enforcement of waste discharge regulations are recommended to reduce turbidity levels and protect water quality.




Figure 5-20: Graph showing In-situ measurement of Turbidity (SAL Consult, 2025)

Water Use

Water is mainly used for domestic activities like cooking, bathing, washing of clothes and cleaning. Small scale farmers also use it to water their crops.

5.2.4 Soil, Vegetation and Biodiversity

Soil

Generally, the soils in the Northern region are suitable for cereal crop production including rice. The project site is expected to have marginal, with shallow soil depth as the major limitation with a soil depth <50 cm. The soil texture may be sandy with clay content <6%. The topsoil may tend to be droughty, while the subsoil may have a high level of gravel and concretions (hard, compact masses). The soils are therefore prone to erosion and have low moisture and nutrient-holding capacity. The status of exchangeable calcium and magnesium may be low and declining. The chemical and physical analysis of soil samples taken from Yendi, the closest sampling location is presented in **Table 5-4.**

Table 5-4: Chemical and physical analysis of soil samples

Location	cation Depth		Site pH OCa TNb			200 Sept. 100 Se	Bray's a	vailable		Exc	hangeal	ole catio	ons (cmol	(+)/kg)		Base	Particl	e size a	nalysis	Texture
				(g/kg)	(g/kg)	(g/kg)	P (mg/kg)	K (mg/kg)	Ca	Mg	К	Na	TEB	Exch. Acidity	ECEC	sat. (%)	Sand (%)	Silt (%)	Clay (%)	
Yendi	0-20	Zakoli	6.54	108	10	186	5.74	68.31	2.14	1.34	0.31	0.09	3.88	0.08	3.96	98.0	47.7	50.2	4.1	Si loam
		Malzeri	6.98	67	6	116	9.97	113.29	2.94	1.07	0.26	0.08	4.35	0.07	4.42	98.4	41.4	56.5	2.1	Si loam
		Piong	6.33	71	6	122	6.7	47	2.94	0.8	0.18	0.08	4	0.1	4.1	97.6	45.6	52.4	2	Si loam
		Zang	6.59	82	7	141	3.35	53.77	2.4	0.8	0.26	0.08	3.54	0.08	3.62	97.8	50.7	47.2	2.1	S. Ioam
		Adibo	5.91	60	5	103	4.86	56.13	2.27	2.14	0.19	0.06	4.66	0.25	4.91	94.9	25.3	70.5	4.2	Si loam
	20-40	Zakoli	6.6	67	6	116	3.67	40.92	3.74	1.07	0.29	0.09	5.19	0.08	5.27	98.5	44.8	51.1	4.05	Si loam
		Malzeri	6.59	49	4	84	5.02	36.52	4.01	0.53	0.21	0.07	4.82	0.08	4.9	98.4	29.6	66.1	4.3	Si loam
		Piong	6.27	49	4	84	4.15	36.52	2.67	1.47	0.18	0.08	4.4	0.12	4.52	97.3	48.6	49.1	2.3	Si loam
		Zang	6.2	75	6	129	1.83	43.62	2.94	1.87	0.2	0.11	5.12	0.12	5.24	97.7	47.1	48.8	4.05	S. loam
		Adibo	5.94	38	3	65	1.75	25.02	1.87	1.34	0.53	0.16	3.9	0.2	4.1	95.1	29.6	68.4	2	Si loam

(Source: Tetteh et.al, 2016)

Vegetation

The Tindantua Valley generally has a flat or gently undulating topography and is subject to seasonal inundation. The two (2) habitat types recognized at the project site are the Seasonally flooded Grassland with isolated trees and the Gallery Forest along the Daka River.

Seasonally flooded Grassland with Isolated Trees

The Seasonally flooded grassland with isolated trees habitat is a tree savanna with open canopy. It has been intensively cultivated, with yam and rice being the main crops which has led to a loss of the typical tree and shrub strata of the Guinea savanna vegetation (see **Plates 5-6**). Some of the tree species found on the site are *Vitellaria paradoxa*, *Combretum adenogonium*, *Tamarindus indica and Anogeissus leiocarpa*. Some of the common shrub and herbaceous species are *Ziziphus mucronata and Lepidium africanum*.



Plate 5-6: Tindantua Valley – foreground, largely bare; isolated trees in the background (Sal Consult, 2025)

The Gallery Forest habitat

The Gallery Forest habitat is the section of the valley that is drained by the Daka River, which has a narrow belt of largely degraded gallery forest along its bank. The forest has broken canopy and farms extend to the river bank in many places. Some of the trees in the gallery are *Daniellia oliveri*, *Diospyros abyssinica* and *Mitragyna inermis* (see **Plate 5-7**).



Plate 5-7: Degraded Gallery Forest along Daka River, Tindantua valley, Mion (Sal Consult, 2025)

Floral Survey

A flora survey was conducted in April 2025 with an initial reconnaissance survey done within the project site and external boundaries to obtain an overview of the extent, topography and complexity of the vegetation. Sample quadrats of size 20 m x 20 m were studied in the proposed site and a total of 3 vegetation samples were taken during the survey. The locations of the samples were recorded with a Garmin 64s GPS. **Table 5-5** shows the sample location coordinates and their associated vegetation types.

The ecological significance and national conservation status of the species encountered were defined using the ecological guild and star rating system (see **Table 5-6**) adopted in the Forest of Ghana Geographic Information Exhibitor manual (Hawthorne, 1993). The Global conservation status **(Table 5-7)** of each species was determined using the International Union of Conservation of Nature (IUCN) red list of threatened species (IUCN, 2024).

Table 5-5: Coordinates of sampling locations and associated vegetation types

Site	Lat (N)	Long (W)	Description
Mion Tindantua (Site A)	N 09.13486	W 000.15037	Farmland/isolated trees; seasonally flooded grassland/ yam
Mion Daka River	N 09.12931	W 000.15082	Gallery forest
Mion Tindantua Valley (Site B)	N 09.15079	W 000.15500	Seasonally flooded grassland with isolated trees and shrubs (tree savanna)

(SAL Consult, 2025)

Table 5-6: Star Rating system

Rating	Description
Black Star species	Species rare internationally and at least uncommon in Ghana; urgent attention to
	conservation of populations needed
Gold Star species	Fairly rare internationally and/or locally
Blue star species	Widespread internationally but rare in Ghana or vice-versa
Scarlet star species	Common, but under serious pressure from heavy exploitation
Red Star species	Common, but under pressure from exploitation
Pink Star species	Common and moderately exploited. Also, non-abundant species of high potential value
Green Star species	No particular conservation concern, common in Ghana

Table 5-7: IUCN Red List categories

Category	Description
Extinct (EX)	A taxon is Extinct when there is no reasonable doubt that the last individual has died. A
	taxon is presumed Extinct when exhaustive surveys in known and/or expected habitat,
	at appropriate times (diurnal, seasonal, annual), throughout its historic range have failed
	to record an individual. Surveys should be over a time frame appropriate to the taxon's
	life cycle and life form.
Extinct in the Wild	A taxon is Extinct in the Wild when it is known only to survive in cultivation, in captivity
(EW)	or as a naturalized population (or populations) well outside the past range. A taxon is
	presumed Extinct in the Wild when exhaustive surveys in known and/or expected
	habitat, at appropriate times (diurnal, seasonal, annual), throughout its historic range
	have failed to record an individual. Surveys should be over a time frame appropriate to
	the taxon's life cycle and life form.
Critically Endangered	A taxon is Critically Endangered when the best available evidence indicates that it meets
(CR)	any of the criteria A to E for Critically Endangered, and it is therefore considered to be
	facing an extremely high risk of extinction in the wild.
Endangered (EN)	A taxon is endangered when the best available evidence indicates that it meets any of
	the criteria for Endangered, and it is therefore considered to be facing a very high risk of
	extinction in the wild.
Vulnerable (VU)	A taxon is Vulnerable when the best available evidence indicates that it meets any of the
	criteria for Vulnerable, and it is therefore considered to be facing a high risk of extinction
	in the wild.
Near Threatened	A taxon is Near Threatened when it has been evaluated against the criteria but does not
(NT)	qualify for Critically Endangered, Endangered or Vulnerable now, but is close to qualifying
	for or is likely to qualify for a threatened category in the near future.
Least Concern (LC)	A taxon is Least Concern when it has been evaluated against the criteria and does not
	qualify for Critically Endangered, Endangered, Vulnerable or Near Threatened.
	Widespread and abundant taxa are included in this category
Data Deficient (DD)	A taxon is Data Deficient when there is inadequate information to make a direct, or
	indirect, assessment of its risk of extinction based on its distribution and/or population
	status. A taxon in this category may be well studied, and its biology well known, but
	appropriate data on abundance and/or distribution are lacking.
Not Assessed (NA)	A taxon is Not yet Assessed when it is has not yet been evaluated against the criteria

(IUCN, 2024)

Results and Floral Analysis

The species lists for the 3 samples analysed are presented in **Table 5-8** while the floristic analysis of the project site is presented in **Table 5-9**. The sampling recorded a total of 24 species in 20 genera belonging to 12 flowering plant families. The families with high species representation were the *Fabaceae* (5) and the *Combretaceae* (5). These 2 families (out of total of 12) accounted for 40% of the species recorded. The rest of the families were poorly represented with less than 5 species each. The diversity of species on the site is low. This is not surprising since most of the herbs and shrubs have been destroyed by bush fires and cattle grazing.

Table 5-8: Sample profiles and species composition of Tindantua Valley

Mion Tindantua Valley (Site A)	Mion Tindantua valley (Site B), Seasonally flooded grassland with isolated trees	Daka River Gallery, Tindantua valley
N 09.13486	N 09.15079	N 09.12931
W 000.15037	W 000.15500	W 000.15082
Elev. 138m	Elev. 142m	Elev. 134m
Species	Species	Species
Capparis erythrocarpos	Acacia gourmaensis	Diospyros abyssinica
Icacina senegalensis	Albuca nigritana	Mitragyna inermis
Vitellaria paradoxa	Balanites aegyptiaca	Daniellia oliveri
Ziziphus mucronata	Combretum adenogonium	Cassia mimosoides
Tamarindus indica	Acacia senegal	Ziziphus Spina-christi
Balanites aegyptiaca	Anogeissus leiocarpus	Combretum nigricans
Lannea kerstingii	Tamarindus indica	
Acacia gourmaensis	Lannea acida	
Lepidium africanum		
Sterculia setigera		
Anogeissus leiocarpus		
Gardenia ternifolia		
Combretum adenogonium		
Combretum nigricans		
Crossopteryx febrifuga		
Terminalia avicennioides		
Piliostigma thonningii		
Combretum nigricans		
Asparagus africanus		
Lannea acida		
Adansonia digitate		
Terminalia laxiflora		
Detarium microcarpum		

(SAL Consult, 2025)

Table 5-9: Floristic Analysis of Tindantua Valley

Table 5-9: Floristic Analysis Species	Family	Life Form	Guild	Star Rating	IUCN
Acacia gourmaensis	Fabaceae	Tree	Non forest Savana/planted	NE	LC
Acacia Senegal	Fabaceae	Tree	Non forest Savana/planted	NE	LC
Adansonia digitate	Malvaceae	Tree	Non forest Savana/planted	NE	NE
Albuca nigritana	Asparagaceae	Herb	NE	NE	NE
Anogeissus leiocarpus	Combretaceae	Tree	NE	Green	LC
Asparagus africanus	Asparagaceae	Climber	Non forest Savana/planted	NE	NE
Balanites aegyptiaca	Zygophyllaceae	Tree	Non forest Savana/planted	NE	LC
Capparis erythrocarpos	Capparaceae	Climber	NE	Green	NE
Combretum adenogonium	Combretaceae	Tree	Non forest Savana/planted	NE	LC
Combretum nigricans	Combretaceae	Tree	NE	NE	NE
Crossopteryx febrifuga	Rubiaceae	Tree	Non forest Savana/planted	NE	LC
Detarium microcarpum	Fabaceae	Tree	Non forest Savana/planted	NE	LC
Gardenia ternifolia	Rubiaceae	Shrub	Non forest Savana/planted	NE	LC
Icacina senegalensis	Icacinaceae	Shrub	Non forest Savana/planted	NE	NE
Lannea acida	Anacardiaceae	Tree	Non forest Savana/planted	NE	LC
Lannea kerstingii	Anacardiaceae	Tree	Non forest Savana/planted	NE	LC
Lepidium africanum	Brassicaceae	Herb	NE	NE	NE
Piliostigma thonningii	Fabaceae	Tree	Non forest Savana/planted	NE	LC
Sterculia setigera	Malvaceae	Tree	Non forest Savana/planted	NE	LC
Tamarindus indica	Fabaceae	Tree	Non forest Savana/planted	NE	LC
Terminalia avicennioides	Combretaceae	Tree	Non forest Savana/planted	NE	LC
Terminalia laxiflora	Combretaceae	Tree	Non forest Savana/planted	NE	LC
Vitellaria paradoxa	Sapotaceae	Tree	Non forest Savana/planted	NE	VU

Species	Family	Life Form	Guild	Star Rating	IUCN
Ziziphus mucronata	Rhamnaceae	Tree	Non forest Savana/planted	NE	LC

(SAL Consult, 2025)

The Life form composition of the flora (**Table 5-10**) showed a dominance of the Tree Life form (about 75%) followed by the Climber, Herb and Shrub life forms with equal representation (about 8.3% each) in the flora. The open nature of the vegetation, due to land cultivation, wildfires and grazing, could explain the observed low diversity of life forms.

Table 5-10: Life Form Composition of the Flora

Life form	No.	%
Climber	2	8.3
Herb	2	8.3
Shrub	2	8.3
Tree	18	75
Total	24	99.9

(SAL Consult, 2025)

The ecological guilds of the species, which gives an indication of the developmental/successional stage of the vegetation, shows a complete absence of pioneers and other guilds (e.g shade bearers and non-pioneer light demanders) typical of forest or woodland vegetation, which is undergoing regeneration after disturbance as seen in **Table 5-11**. The regeneration here is actually a regrowth of the plants left behind by cultivation.

Table 5-11: Ecological Guilds of the Flora

Guild	No.	%
NE	5	20.8
Non Forest Savanna/Planted	19	79.2
Total	24	100

Legend: NE: Not evaluated; NFS/P: Non-Forest Savanna/Planted species; NPLD: Non-Pioneer Light Demander (SAL Consult, 2025)

Species of National Conservation Concern

Inspection of **Table 5-9** reveals that none of the species recorded on the site are of conservation concern according to the Froggie data base. However, it must be noted that *Vitellaria paradoxa* (Shea tree) is a tree of economic importance to the local people in the project area.

Species of Global Conservation Concern

Table 5-12 shows that only 1 Vulnerable species (*Vitellaria paradoxa*) were recorded on the project site. The rest of the species (95%) were either Least Concern or Not Evaluated and do not merit conservation action globally.

Table 5-12: IUCN Red List Status Composition of the Flora

IUCN Red list Status	Number (No.)	Percentage (%)
LC	15	63
NE	8	33
VU	1	4
Total	24	100

(SAL Consult, 2025)

Fauna of the project site

The faunal list of the project (see **Table 5-13**) was based on the information gathered through interviews and observation which involved recording any animal sightings while driving or walking along the main road or animal trails to the areas bordering the proposed project site and identification of animal spoors. General walks through the project sites to spot animal spoors (any sign left by a living animal, such as feeding sites, regular pathways, tracks, footprints, faecal pellets, nests, etc.) were also undertaken. The animals identified were classified as either Schedule 1 (S.1) or Schedule 1 (S.2) depending on the degree of protection they enjoy under the national wildlife conservation regulation (Schedules, 1995) as follows:

- S.1. (Schedule 1) The hunting, capturing or destroying of these species is prohibited at all times.
- S.2. (Schedule 2) The hunting capturing or destroying of these species is absolutely prohibited between 1st August and 1st December of any season. The hunting, capturing or destroying of any young animal, or adult accompanied by its young, of these species is absolutely prohibited at all times.

According to the hunters interviewed, most of the large mammals which were common in the area have moved away due to human activities such as farming and cattle grazing as well as wildfires. Notable among these are the elephant, lion, leopard, warthog, several parrots, terns, songbirds (passerines), land tortoises, pythons other snakes, lizards, bats, birds of prey, mongooses, bovids (e.g. the African buffalo and several duikers), egrets, ducks, pigeons. A number of the species known to occur in the area are of both national and global (IUCN, CITES) conservation significance.

Table 5-13: Fauna of the Project Area

	Name		Conservat	Conservation Significance	
Order	Common	Species	IUCN	National	Abundance Status
Artiodactyla (Even-toed ungulates)	Bushbuck	Tragelaphus scriptus	LC	II	Rare
	Common Duiker	Sylvicapra grimmia	LC	II	Rare
	Oribi	Ourebia ourebi	LC	II	Rare
	Red River Hog	Potamochoerus porcus	LC	II	Rare
	African Civet	Civettictis civetta	LC	II	Rare
Carrierana (Carreitana)	Common Slender Mongoose	Herpestes sanguineus	LC	II	Common
Canivora (Carnivores)	Common Kusimanse	Crossarchus obscurus	LC	II	Common
	Marsh Mongoose	Atilax paludinosus	LC	II	Common
Lagomorpha	African Savanna Hare	Lepus microtis	LC	Not Listed	Common
	Gambian Pouched Rat	Cricetomys gambianus	LC	Not Listed	Common
	Grasscutter	Thryonomys swinderianus	LC	Not Listed	Common
Rodentia	Gambian sun squirrel	Heliosciurus gambianus	LC	Not Listed	
	Guinea multimammate mouse	Mastomys erythroleucus	LC	Not Listed	
	Stripped Ground Squirrel	Euxerus erythropus	LC	Not Listed	Abundant
	Common Frog	Amnirana galamensis	LC	Not listed	
Anura (Frogs and Toads)	Common Toad	Sclerophrys regularis	LC	Not listed	
	Crowned Bull Frog	Hoplobatrachus occipitalis	LC	Not listed	
Squamata	Agama Lizard	Agama agama	LC	Not listed	
(Snakes and Lizards)	African Rock Python	Python sebae	NT	II	
	Boomslang	Dispholidus typus	LC	Not listed	
	Forest Cobra	Naja melanoleuca	LC	Not listed	
	Gaboon Viper	Bitis gabonica	LC	Not listed	
	Hissing Sandsnake	Psammophis sibilans	LC	Not listed	
	Night Adder	Causus rhombeatus	LC	Not listed	
	Nile Monitor	Varanus niloticus	LC	1	

Order	Name	Name		Conservation Significance	
	Common	Species	IUCN	National	Status
	Puff Adder	Night Adder	LC	Not listed	
	Savanna Monitor	Varanus exanthematicus	LC	Not listed	
	Spitting cobra	Naja nigricollis	LC	Not listed	
Accipitriformes	Black Kite	Milvus migrans	LC	1	
	Shikra	Accipiter badius	LC	1	
	Lizard Buzzard	Kaupifalco monogrammicus	LC	1	
	African Grey Hornbill	Lophoceros nasutus	LC	Not listed	
Bucerotiformes	West African Pied Hornbill	Lophoceros semifasciatus	LC	Not listed	
	Spur-winged lapwing	Vanellus spinosus	LC	Not listed	
Columbiformes	Laughing Dove	Spilopelia senegalensis	LC	П	
	Red-Eyed Dove	Streptopelia semitorquata	LC	П	
C life was a s	Levaillant's cuckoo	Clamator levaillantii	LC	Not listed	
Cuculiformes	Senegal Coucal	Centropus senegalensis	LC	Not listed	
	Double-spurred Spurfowl	Pternistis bicalcaratus	LC	П	
Galliformes	Stone Partridge	Ptilopachus petrosus	LC	П	
	Western Grey Plantain-eater	Crinifer piscator	LC	Not listed	
Passeriformes	African Blue Flycatcher	Elminia longicauda	LC	Not listed	
	African Pied Wagtail	Motacilla aguimp	LC	Not listed	
	Black-crowned Tchagra	Tchagra senegalus	LC	Not listed	
	Bronze Mannikin	Permestes cucullata	LC	Not listed	
	Common Bulbul	Pycnonotus barbatus	LC	Not listed	
	Long-tailed Glossy Starling	Lamprotornis caudatus			
	Long-tailed nightjar	Caprimulgus climacurus	LC	Not listed	
	Melodious Warbler	Hippolais polyglotta			
	Northern Grey-headed Sparrow	Passer griseus	LC	Not listed	

Order	Name		Conservation Significance		Abundance
	Common	Species	IUCN	National	Status
	Orange-Cheeked Waxbill	Estrilda melpoda	LC	Not listed	
	Red-breasted swallow	Cecropis semirufa	LC	Not listed	
	Village Weaver	Ploceus cucullatus	LC	Not listed	
	White-fronted Black Chat	Oenanthe albifrons	LC	Not listed	
Pelecaniformes	Cattle Egret	Bubulcus ibis	LC	1	

(SAL Consult, 2025)

Conclusions

The results of the survey indicate that none of the floral and faunal species recorded are of conservation concern due to the project area being an extensively modified habitat. The project will therefore have no significant impact on flora and fauna as well as their habitat.

Isolated cases of *Vitellaria paradoxa* (shea tree) were recorded on the project site which are not of biodiversity and economic significance because they are commonly found in many other areas of the district.

5.2.5 Socio-economic Environment – Project site (Tindantua Community)

<u>Demography</u>

Thirty- nine (39) households were randomly sampled for the survey in the Tindantua community of which thirty six (36) were male (92%) and 3 female (8%).

The ages of the respondents ranged from 23 to 87 years, with an average age of approximately 49.6 years. All respondents reported being married with majority of respondents (49%) being in the 31-50 years' age bracket, with a significant proportion (36%) aged 51 years and above. Younger adults (18-30 years) constitute 15% of the sample. No respondent was below 18 years (see **Figure 5-21**).




Figure 5-21: Age range of respondents

These 39 households sampled comprise a total of about 431 individual members, that is an average household size of approximately 11 persons. Household sizes however range from a minimum of 4 to a maximum of 59 members. Within these 39 households, there were 209 males (48%) and 222 females (52%), indicating a slightly higher proportion of females.

Households with 13 or more members constitute the largest group (36%) and contain nearly 60% of all individuals covered in the survey. Households with 7-9 members are the next most common size category (28%). 8 out of 39 households (21%) (see **Figure 5-22**) reported having at least one member with a form of disability. The types mentioned include both mental and physical disabilities.




Figure 5-22: A pie chart Showing Disability status of households

Ethnicity and Religion

All 39 respondents (100%) identified their ethnicity as Dagomba. This indicates complete ethnic homogeneity within the surveyed sample from the Tindantua community. All 39 respondents (100%) identified their religion as Moslem.

Education and Literacy

A very high proportion of respondents, 31 out of 39 (80%), have no formal education. Five respondents (13%) completed Primary School, while three respondents (5%) completed SHS. One respondent (3%) reported having a University education. No respondents were reported as SHS dropouts in this dataset.

Educational Level	Count	Percentage (%)
None (No formal Ed.)	31	80
Completed Primary School	5	13
Completed SHS	2	5
University	1	3

Economic Activities

Farming is the dominant primary source of income, with an overwhelming 100% of households relying on it. This underscores the agrarian nature of the community's economy. All 39 respondents (100%) stated that farming is the primary source of income for their household.

Livestock rearing was the most common secondary income source, reported by 9 respondents (23%). Farming (as a secondary activity, perhaps different type or scale) was mentioned by 15 respondents (39%). Small Business/Trade was mentioned by 4 respondents (10%). One respondent mentioned "Mechanic" (3%) and one mentioned "Other" (Nothing else) (3%). Nine respondents (23.1%) did not specify a secondary income source or indicated none. **Figure 5-23** gives a graphical representation of the secondary source of income for respondents.

The vast majority of respondents, 34 out of 39 (87%), identified as self-employed. Five respondents (13%) reported being unemployed.




Figure 5-23: Secondary source of income for respondents

Utilities and Services

Source of Drinking Water

The primary source of drinking water for 35 (90%) of the respondents is a Borehole. A smaller number (2 households, 5%) use dug out /Dam whiles 1 household (3%) uses sachet water. Distances to water sources vary, with many boreholes located very close (e.g., 0.01km to 1km), while dugout/dams can be further (3-5km).

Sanitation Facility

Almost all household respondents (37 out of 39, or 94%) report using "No facility/Bush" for sanitation. One household reported having a Flush Toilet (3%). This indicates very low access to improved sanitation.

Sanitation Facility	Count	Percentage (%)
No facility/Bush	37	94
Flush Toilet	1	3
Not Specified	1	3

Main Source of Energy for Cooking

Firewood is the universal source of energy for cooking, with all households (100%) relying on it. This complete dependence on firewood can contribute to deforestation and indoor air pollution.

Main Source of Energy for Lighting

Firewood is the predominant source of energy for cooking, used by 37 out of 39 households (95%). One household reported using Charcoal (3%).

Main Source of Energy for Lighting

Electricity (NEDCO) is the main source of lighting for 35 out of 39 households (90%). Two households use Solar Power (5%), and one uses Candles (3%).

Main Source of Energy for Lighting	Count	Percentage (%)
Electricity (NEDCO)	35	90
Solar Power	2	5
Candles	1	3
Not Specified	1	2

Health

Malaria was the most frequently reported health condition, affecting 32 out of 39 households (82%). High blood pressure was also common (62%), followed by Fever (49%), Ulcer (36%), Diarrhoea (28%), and Acute Respiratory Infection (21%).

Common Health Condition	Households Reporting	Percentage (%)
Malaria	32	82
High blood pressure	24	62
Fever	19	49
Ulcer	14	36
Diarrhoea	11	28
Acute Respiratory Infect.	8	21

Public hospitals are the most preferred medical service provider, chosen by 35 out of 39 respondents (90%). Traditional medicine is also a significant option for 24 respondents (62%). Private hospitals were chosen by 5 (13%), Pharmacist/Chemist by 2 (5%), and Community Health Centre/Post by 3 (8%). Respondents could select multiple providers.

Preferred Medical Service Provider	Count	Percentage (%)
Public Hospital	35	90
Traditional Medicine	24	62
Private hospital	5	13
Pharmacist/Chemist	2	5
Community health center/post	3	8

6.0 STAKEHOLDER CONSULTATIONS

The ESIA preparation included preliminary stakeholder identification, some initial consultations and analysis of the requirements with key stakeholders. The key project stakeholders identified for consultations included government and non-governmental organizations. Stakeholder consultation is a process and should continue through the design stage of the project implementation phase.

6.1 Objectives of the consultations

The main objective of consultations with stakeholders is to discuss and provide relevant information on the project. Specifically, to achieve the following objectives:

- Provide some information about the proposed project;
- Provide opportunities for stakeholders to discuss their opinions and concerns;
- Provide and discuss with stakeholders, alternatives considered to reduce anticipated impacts;
- Identify and verify significance of environmental, social and health impacts; and
- Inform the process of developing appropriate mitigation and management guidelines.

6.2 Stakeholders consulted and concerns raised

The project was presented and explained to all stakeholders and were encouraged to share their concerns and perceived risks. The stakeholders were generally enthused about the project and indicated their readiness to lend their support for the successful implementation of the project.

Below are the key environmental and social issues discussed with the stakeholders.

- Employment and Livelihoods
 - The project will generate short- and long-term job opportunities for skilled and unskilled local labour, including women. However, unmet expectations regarding opportunities could result in social agitation or unrest.
 - Labour and employment issues such as delayed wages, discriminatory practices, or exclusion of women and youth could undermine project credibility.
 - Transparent, inclusive recruitment and training plans must be clearly communicated and coordinated with local stakeholders.
- Food Security, Economic Growth and Market Development
 - Project benefits such as food security, and improved access to mechanization and input services which will raise agricultural productivity and income for value chain actors must be shared with stakeholders to obtain their buy-in for a smooth project implementation.
 - The project will stimulate local commerce and attract new investments in processing, marketing, and quality control services.
 - o Increased agricultural output will reduce rice imports and help Ghana conserve foreign exchange.
- Knowledge, Capacity Building, and Technology Transfer
 - Training of farmers and stakeholders in good agricultural practices will promote climate-smart farming, reduce losses, and improve resilience.
 - Introduction of modern technologies and digital tools (e.g. RiceAdvice, pest control methods) will enhance productivity and efficiency in farming.

Land Access, Tenure, and Use

- o Farmers and landowners may be either physically or economically displaced by the project and should be engaged extensively on the impacts and mitigation measures including compensation.
- Improper land acquisition or voluntary land donations which are not transparent and inclusive may lead to disputes and restrict access to traditional lands and resources.
- Tenant farmers and informal land users may be overlooked in consultation or compensation processes if stakeholder mapping is not comprehensive.

Water Use and Resource Consumption

- Water-intensive rice cultivation may increase pressure on local water resources, especially during dry periods.
- o Inclusive planning and monitoring involving local communities and water user associations are essential to ensure fair and sustainable water use.

Environmental Degradation

- o Site clearing and infrastructure development may result in loss of vegetation and some trees.
- Soil degradation and erosion may occur due to land preparation, bare farmlands, and construction activities.
- Dust, emissions, and fumes from construction and operations may degrade local air quality, especially on untarred roads.
- Runoff, domestic waste, chemicals, and effluent may pollute surface and groundwater, affecting aquatic life and users.
- Operation of machinery and vehicle movement will generate noise and vibration, causing nuisance to nearby communities.

• Pesticide and Agrochemical Use

- The application of synthetic fertilizers and pesticides poses risks of water pollution, biodiversity loss, and adverse health impacts on farmers and surrounding communities.
- Capacity building is needed for smallholder farmers on Integrated Pest Management (IPM), safe handling practices, and the use of environmentally safer alternatives.

Health, Safety, and Labour Conditions

- Workers face risks of injuries, accidents, insect/animal bites, agrochemical exposure, dustinhalation and equipment-related injuries during construction and operation.
- Poor labour conditions, including lack of contracts and inadequate welfare facilities, may expose workers to exploitation and health risks.
- Fires from negligence or improper burning could cause property loss and injuries.

Social Risks and Community Impacts

- Presence of workers may increase incidents of gender-based violence, rape, and defilement in host communities.
- Pollution and unsafe practices may lead to spread of communicable diseases, including HIV/AIDS and cholera.
- Rising social tensions, theft, confrontations, and conflicts may emerge between workers and locals over cultural, financial, or sexual issues.
- Increased road traffic may cause congestion and accidents due to broken-down or poorly parked haulage vehicles.
- Local communities must be made aware of potential risks and emergency response protocols must be clearly established.
- Gender-Based Violence, Sexual Exploitation and Abuse, and Child Labour

- Labour influx during construction and agro-industrial operations may increase the risk of GBV,
 SEA. and child labour.
- Without strong safeguards, women, girls, and persons with disabilities may face heightened vulnerabilities.
- Community engagement is crucial to raise awareness, strengthen prevention mechanisms, and ensure access to referral and support services.

Grievance Redress

- The project must implement a well-functioning and accessible Grievance Redress Mechanism (GRM) that all stakeholders can use.
- Existing community grievance structures should be formally recognized and integrated into the broader project-level redress system.

The stakeholders identified and consulted are given in **Annex 5** which provides details of the engagement including locations, dates, stakeholders who participated, pictures, the main concerns raised by participants, responses and commitments of MOFA. **Annex 6** gives the attendance sheet of the stakeholders engaged.

A summary of the outcome of the consultations for key stakeholders is provided in **Table 6-1**. These are mostly concerns and suggestions/interventions from government institutions, community based business entities, farmer-based organizations, and affected communities.

Table 6-1: Details of stakeholders identified and consulted

Group of stakeholders	Stakeholders	Issues/Concerns	Proposed Solution/ Responses
Project Implementer	Ministry of Food and Agriculture (Mion District)	 The district MOFA is aware that land has been donated by the chief of Dabogni for the project. The local farmers rely on rain-fed agriculture which makes farming less reliable and profitable. The District MOFA must be well-resourced in terms of (finance/logistics) for their extension/ monitoring/ supervisory role. Farmers should be educated and resourced with appropriate farm inputs and machinery to reduce post-harvest losses. Lack of irrigation facilities is a handicap to agricultural productivity There should be ready markets for the rice that will be produced. 	 The issues raised by the District MOFA were acknowledged and were advised to familiarize themselves adequately with the project documents such as the SEP, PMP, ESMP The project is expected to have a positive impact on community members by creating jobs in the rice value chain and thereby reduce rural migration to non- existent jobs in towns and cities.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		 The road network in the area should be improved to enhance mobility of people and goods. 	
Regulatory Institution	Environmental Protection Authority	 Compensation issues should be at the forefront for farmers who may suffer livelihood challenges and this should be addressed in a comprehensive RAP report. There must be valuation of properties if any, as well as compensation for any form of displacement. Environmental permit is required for the project. Biodiversity conservation should be a consideration in the project implementation. There will be periodic field visits by the EPA team to monitor environmental compliance during implementation. 	The regional EPA was assured that the project will follow all EPA guidelines and that the EPA will be involved in providing monitoring support. Additionally, budgetary provisions will be made for their role.
Other Government Institutions	Water Resources Commission	Education on agrochemicals use for farmers to avoid pollution of local water bodies.	 Concerns of the WRC were noted and that Commission will be consulted when/ if the need arises.
	Mion District Assembly	 The Assembly is willing to provide support to any project that will improve the productivity of farmers in the community. Compensation issues are important to the Assembly and must be comprehensively addressed. A grievance mechanism should be established to assist the PIU to resolve complaints and grievances in a timely, effective and efficient manner. Main agricultural challenges in the area are the lack of 	 All the relevant stakeholders will be engaged and the ESIA will provide mitigation measures especially for farmers who will be adversely affected by the project implementation. The Assembly will be required to assist in any grievance mechanism measures implemented by the project.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
	National Disaster	 mechanization and the high cost of agricultural input. There is concern about the inadequate road network and the roads are mostly in poor condition. Assembly members and the beneficiary community leadership should be particularly well sensitized about the project to ensure effective implementation. Seasonal floods occur regularly during the rainy 	• The challenges of NADMO were noted as
	Management Organization, Mion	season leading to loss of farmlands and creating food insecurity concerns. Drought is also experienced during the dry season leading to bushfires. NADMO is concerned that communities farm close to waterways. Project should ensure improved drainage and proper location of facilities within the valley to avoid flooding.	well as their importance to the project. • Budget will be allocated for the training of fire fighters and community volunteers to handle bush fires as well provide education on the effects of bush fires on the project.
	Ghana National Fire Service	 The project should put measures in place to preserve existing water bodies as this serves as farm boundaries and also help to curb bush fires. The GNFS should be adequately resourced to train fire volunteers from the farming communities. Fire incidents have minimized in recent times due to continuous community education. Main causes of fire include the indiscriminate burning 	 The challenges of GNFS were noted as well as their importance to the project. As part of the ESMP, resources will be provided to support the training of community volunteers.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		of bushes (i.e. deliberate, post-harvest). Most fires occur between the months of November and January leading to loss of income, lives and properties and soil fertility. The local Fire station will be on hand to assist the project when/ if required including involvement in community education	
Community based business entities	Small Holder Farmer	 Common crops cultivated include soybean, maize, rice, sorghum, yam, cassava and groundnut. Urgent needs include tractor service, access to agrochemicals including fertilizers. Concerns about the poor road network need to be addressed. Inputs and credit support will be required for the beneficiaries on the project. Drought and pest resistant seed varieties should be provided for production. Ready market for produce is key to encourage more people to get involved. Land preparation support is required before planting. Existing farmers on the proposed project site must be compensated if they are to move out. Gender bias/political influences should be avoided in the project implementation. Farmers should be trained on sustainable farm practices by MOFA extension officers. 	 They group was assured of the benefits that the project offers. Project affected farmers' fears were allayed as an effective RAP will be prepared and implemented Roads leading to project sites will be improved to enhance transportation.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		The road in the project area	
		should be improved	
		especially during the rainy	
		season.	
	Aggregators	• Low purchasing power of	Concerns were well noted
		farmers.	and the group was
		High transportation cost	assured of benefits that
		due to poor road network.	the project will bring to
		Lack of access to finance.	their businesses
		• Inadequate storage	
		infrastructure.	
		• There are no formal	
		agreements between	
		aggregators and farmers.	
		Aggregators carry out	
		limited processing of the	
		rice such as cleaning and	
		drying prior to transporting to local markets.	
	Agro Input	Main business activities	The group was advised to
	Dealers	include trading of fertilizers,	intensify their efforts in
	Dedicis	seeds, chemicals, tools and	educating the farmers
		equipment, sourced from	including the proper
		local distributors.	disposal of empty
		Customers are mostly small-	agrochemical containers
		holder farmers.	and fertilizers through
		Peak season is between	licensed waste
		March and June of the year.	management companies.
		• They offer technical	
		advice/training to farmers.	
		Some concerns include	
		difficulty in connecting to	
		suppliers, inadequate	
		storage facilities, high	
		transport cost and lack of	
		access to finance.	
		The agro input dealers	
		mostly source their goods	
		from local distributors on	
		cash and carry basis. They	
		are hardly out of stock. All	
Civil Society	Farmer Based	transactions are manual.	• The group was assured
Civil Society Organizations	Organization	The project should avoid political biases	The group was assured that the REWARD project
(CSO)	(FBO)	political biases.	that the REWARD project
()	\ \ /	Vulnerable groups should be given special	is non-partisan and will require their support in
]	be given special	require their support in

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		consideration during project	providing advocacy and
		implementation	training.
		Traditional authorities are	
		important for the success of	
		the project.	
		Agricultural inputs should	
		be subsidized to ensure	
		affordability to farmers.Extensive consultation	
		should be conducted to	
		comprehensively address	
		any land reallocation issues.	
		The use of agro-chemicals	
		and the management of	
		waste from organic	
		fertilizers should be	
		properly managed to	
		prevent the contamination	
		of water bodies flowing through the valleys.	
		Farmers are in urgent need	
		of easy access to affordable	
		finance.	
		• A close cooperation is	
		required between farmers	
		and suppliers,	
		credit/financial services etc.	
		A cooperative arrangement among farmers facilitated	
		by CSOs/ NGOs will be	
		useful	
		• Initiatives by the Rural	
		Enterprise Programme to	
		provide financial support to	
		farmers is a good one which	
		includes business advisory services.	
		The REP is challenged by	
		high illiteracy levels,	
		difficulty in loan repayment	
		by programme beneficiaries	
_		and inadequate finance.	
Community	Traditional	Land is predominantly	The project was explained
stakeholders	Authority, Tindantua	owned by the traditional	to the leaders to
	Tillualitua	authorities and mostly used	understand the benefits
		for farming and livestock.	of the project to the
			project communities.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/
stakeholders			Responses
		 Some concerns include conflicts with herdsmen, compensation for displaced farmers, fairness in selection of project beneficiary farmers. They recommend timely supply of seeds and agrochemicals, and improvement in the road network. Incidences of gender-based violence, sexual exploitation or abuse cases are uncommon in the project area. There are usual petty quarrels between members of the opposite sex but these are settled amicably by family heads/parents or traditional authority depending on which is readily available and accessible. 	 The assistance of the leaders were sought to ensure cooperation from affected farmers. The leaders were thanked for donating their lands for the project. The LEAP will be implemented to support vulnerable persons who may be affected by the project e.g. bicycles will be given to farmers to aide in transportation to their farms. The Grievance redress mechanism will be put in place to ensure farmers benefit and no one suffers from the project implementation.
	Womens' Group	 Women are mostly vulnerable and will require special assistance from the project. Concerns include difficulty in accessing ready market for farm produce, lack of processing facilities. Local groups include VSLA which provide some financial support to the women. Vulnerable households mostly receive support from Livelihood Empowerment Against Poverty (LEAP). Main source of livelihood is farming and rearing of livestock. Deforestation has contributed to unreliable 	 The womens' value to the community was acknowledged and as such, the project has been designed to benefit women and encourage their full participation. There will be no room for sexual harassment and in the unlikely event of that happening, the case should be reported to the relevant authorities. The group's concerns were acknowledged and they were assured of job opportunities from the project.

Group of	Stakeholders	Issues/Concerns	Proposed Solution/		
stakeholders			Responses		
		rainfall patterns and has affected the planting (June – December). Their top concerns are the poor road network, lack of access to potable drinking water and financial support. They have confidence in the extension support service and that must be made more effective. Processing facilities are needed to support their farming activities.	 In addition, local persons will be considered first for any job opportunities. The group was advised to follow the grievance redress process to address any concerns. 		
	Youth group	 The youth are willing and available to participate in the project as this will help to reduce unemployment and alleviate poverty. Ready markets for the rice produce will be required to ensure reliable flow of income. Irrigation is necessary to make the project more effective and sustainable. Extension officers should play a major role in the implementation of the project. 	 The youth were assured of job opportunities that may arise from the project. Local community members will be considered first for any job opportunity provided there is the capability The group was advised to be conversant with the grievance redress process to address any concerns. 		

6.3 Public disclosure

AfDB requires that environmental reports for projects are made available to project affected groups, local NGOs, and the public at large. Public disclosure of EIA documents or environmental reports is also a requirement of the Ghana EIA procedures (Annex 1). The report should be disclosed to all relevant stakeholders to make inputs or comments. Public notice in the media should be served for that purpose.

6.4 Grievance Redress Mechanism

The activities of the project may generate grievances arising from the interaction between project and local authorities/community, workers and the host community etc. Some potential grievances identified and likely to occur during project implementation include:

- Complaints from the local community on the conduct of workers, especially sexual harassment and other gender-based offenses;
- Complaints related to noise, dust, traffic incidents; and
- Restriction of access to persons who otherwise were using portions of land e.g. for grazing
- Failure to consider the recruitment of local man-labour;
- Non-respect of the habits and customs of the host community by the actors of the site;
- Non-compliance with the measures or provisions contained in the ESMP.

In managing grievances, the REWARD project proposed measures for resolution of grievances that may arise due to project implementation. This is a three-tier grievance redress structure which are:

- Community level structures (1st Tier) These includes; a Grievance Redress Committee and Site-level Grievance Redress Mechanism.
- District level structure (2nd Tier) District Grievance Redress Committee
- Project-wide level structure (3rd Tier) Project Grievance Redress Committee

Community Level (1st Tier):

- Includes Community Grievance Redress Committees (GRCs) and site-level Grievance Redress Mechanisms (GRMs).
- Handles initial complaints from individuals or communities related to agricultural or infrastructure activities.
- Site-level GRMs are managed by contractors and report monthly to the project team; oversight is provided by Environmental and Social Safeguard Specialists.

District Level (2nd Tier):

- District Grievance Redress Committees (District GRCs) address unresolved complaints from the community level or cases where community GRCs fail to act within 30 days.
- They meet quarterly or as needed for urgent matters.

Project Level (3rd Tier):

- Project Grievance Redress Committee led by the Project Coordinator or Social Safeguard Specialist.
- Handles cases escalated from the district level, especially if not resolved in 30 days or if the complainant is dissatisfied with the resolution.

Each level functions progressively, allowing for escalation of unresolved or unsatisfactorily resolved issues. The composition of the Grievance Redress Committees/Structures at the various levels in the **Table 6-2** below.

Table 6-2 :Composition of Grievance Redress Committees / Structures

Membership of Committees / Structures							
Community Grievance Site-level Grievance District Grievance Project Grievance Redres							
Redress Committee		Redress Mechanism		Redress Committee		Committee	

Assembly member for the community	Site Environmental Officer	District Director of Agriculture / Rep	Project Coordinator		
Chief	Representatives of site workers	District Planning Officer	Social Safeguard Specialist		
Agriculture Extension Agent (AEA) in charge of the community	PAP representative	District Land Officer	Environmental Safeguard Specialist		
PAP representative		District Community Development Officer (formerly Social Welfare Officer)	Any other project Specialist who would be required		

- Setting up of a Grievance Redress Committee (GRC) at the community level and the district level to receive and address grievances from stakeholders.
 - At the community level, the GRC will be made up of the Assemblyman, the Chief, Agriculture Extension Agent (AEA), and a representative of the project affected persons (PAPs). The Assemblyman will be responsible for receiving grievances and subsequently liaise with the other members of the GRC to have the issue resolved.
 - At the district level, the GRC will be made up of the District Director of Agriculture, the District Planning Officer, District Land Officer and the District Community Development Officer.
 - At the Project level, the GRC will be made up of the Project coordinator, Social Safeguard Specialist, Environmental Safeguard Specialist and any other project Specialist who would be required.
- The PIU will constantly engage project affected persons through its Stakeholder and Public Disclosure Plan. This will keep the communities informed of developments on the project, including planned activities, project impacts and mitigation measures, grievance mechanism, the right to submit complaints and the compensation process.
- Building capacity of the Assemblymen to ensure they can engage the communities, record and ensure grievances are resolved.

Grievances are expected to be communicated either verbally (in a language of choice) or in writing to the GRC. Upon receipt of complaints, timely responses are expected to be given. It is expected that if grievances cannot be resolved locally, then these will be referred quickly to the District Council GRC for resolution.

Actions to be taken to address the grievance will be agreed upon by the GRC, and progress of implementation of agreed measures reported to the Local community, District Assembly, PIU and Ministry of Food and Agriculture on a weekly and monthly basis.

A grievance management procedure indicating activities and timeframe for resolution of issues is shown in **Figure 6-1**.




Figure 6-1: Procedure for Grievance Redress

GRM operating budget

Table 6-3 presents the operating budget of the GRM. This budget is estimated at USD 79,000.

Table 6-3: GRM Implementation Budget Summary

Headings	Unit	Quantity	Unit cost (USD)	Total cost (USD)	
Reproduction and distribution of forms	Lump sum	1	5,000	5,000	
Organization of GRM awareness and public campaigns in local communities	Session	20	2,000	40,000	
Training of members of the two (02) committees on the GRM (community level and district level)	Session	2	2,000	4,000	
Support for the operating of complaints management committees (communities and district)	Monthly	60	500	30,000	
Total cost of the implementation of GRM				79,000	

7.0 POTENTIAL ENVIRONMENTAL AND SOCIAL ISSUES AND IMPACTS

The Impact Assessment methodology provided in this Chapter sets out the approach used to characterize and evaluate the potential environmental and social effects associated with the REWARD Project.

The entire EIA process can be described as a systematic approach to identifying, describing and evaluating the potential environmental and social effects, and developing measures that will be implemented to manage these effects. These measures include ones that avoid or reduce the significance of adverse effects to an acceptable level and enhancing beneficial effects of the project.

The typical EIA process, including Impact Assessment stages, is indicated in Figure 7-1 below.




Figure 7-1: EIA Process

7.1 Impact Assessment

In undertaking the assessment of impacts, the consultant has drawn upon, among others:

- Its knowledge of sources of potential impacts associated with the REWARD Project;
- An identification of the main environmental and social resources and receptors from the baseline data collection; and
- The results of the various stakeholder engagements.

The assessment methods described below present the criteria for determining receptor sensitivity, impact magnitude and impact significance. The impact assessment for this study includes:

- Identification of Potential Environmental and Social Issues and Impacts; and
- Evaluation and interpretation of impacts.

The Impact mitigation and control strategy is present in the ensuing chapter.

7.1.1 Identification of Potential Environmental and Social Issues and Impacts

The potential environmental and social impacts of the proposed project have been identified and assessed as positive/beneficial or negative/adverse comprehensively. These have been described for the various phases of the Project consisting of:

- 1. Construction phase activities;
- 2. Operational phase activities; and
- 3. Decommissioning phase activities

7.1.2 Evaluation and Interpretation of Impacts

The significance of each impact has been evaluated and compared with national, international as well as applicable industry standards. The methodology for evaluating an impact is outlined below:

Impact Identification and Characterization

Impacts are described in terms of their characteristics, including the impact's type and the impact's spatial and temporal features (namely extent, duration, scale and frequency). The definitions of the terms used are described in **Table 7-1**.

Table 7-1: Impact Characteristics

Characteristic	Definition	Terms
Туре	A descriptor indicating the relationship of the impact to the Project (in terms of cause and effect).	Direct - Impacts that result from a direct interaction between the Project and a resource/receptor (e.g., between occupation of a plot of land and the habitats which are affected). Indirect - Impacts that follow on from the direct interactions between the Project and its environment as a result of subsequent interactions within the environment (e.g., viability of a species population

Characteristic	Definition	Terms
		resulting from loss of part of a habitat as a result of the Project occupying a plot of land). Cumulative - Impacts that result from the incremental impacts of one action/activity when added to past, present, and reasonably foreseeable future actions/activities.
Duration	The time period over which a resource / receptor is affected.	Temporary - (associated with the notion of reversibility). Can be short, medium and long term: Short term – typically lasts from days to months. Medium-Long term – typically lasts from one to many years. Permanent – (i.e. irreversible)
Extent	The reach of the impact (i.e. physical distance an impact will extend to).	On-site - impacts that are limited to the Project site. Local - impacts that are limited to the Project site and adjacent area. Regional - impacts that are experienced at a regional scale, i.e. beyond adjacent properties, covering the metropolis and beyond National - impacts that are experienced at a national scale. Trans-boundary/International - impacts that are experienced outside of Ghana
Scale	Quantitative measure of the impact (e.g. the size of the area damaged or impacted, the fraction of a resource that is lost or affected, etc.). or the professional viewpoint of the measure of impact.	Quantitative measures as applicable for the feature or resources affected/ professional viewpoint of expert as applicable for the feature or resource in terms of severity of impact measure (i.e. minor, moderate, severe)
Frequency	Measure of the constancy or periodicity of the impact.	No fixed designations; intended to be a numerical value or a qualitative description.
Likelihood	Characteristic that pertains to unplanned events determined either qualitatively or quantitatively estimated on the basis of experience and/or evidence that such an outcome has previously occurred.	Unlikely – The event is unlikely but may occur at some time during normal operating conditions. Possible – The event is likely to occur at some time during normal operating conditions. Likely - The event will occur during normal operating conditions (i.e., it is essentially inevitable).

Determining Impact Magnitude

Once an impact's characteristics are defined, the next step is to estimate impact's "magnitude". Magnitude is typically a function of the following impact characteristics (as applicable):

- 1. extent;
- 2. duration;
- 3. scale; and
- 4. frequency.

Magnitude (from small to large) is in practice a continuum, and evaluation along the spectrum requires the exercise of professional judgement and experience. Each impact is evaluated on a case-by-case basis, and the rationale for each determination is noted. The universal magnitude designations, for negative effects, are: negligible, small, medium and large. The magnitude designations themselves are universally consistent, but the definition for the designations varies by issue. In the case of a positive impact, no magnitude designation has been assigned as it is considered sufficient for the purpose of the impact assessment to indicate that the Project is expected to result in a positive impact.

Determining Receptor Sensitivity

The other principal step necessary to assign significance for a given impact is to define the sensitivity of affected receptor. The importance and sensitivity of environmental (physical and biological) and socioeconomic receptors within will be determined based on:

- 1. Relevant legislative or policy standards or guidelines;
- 2. The relative importance/value assigned to existing socio-economic or environmental features/receptor;
- 3. The capacity of the receptor to absorb change; and
- 4. The recoverability of the receptor.

Table 7-2 provides a general definition of sensitivity ranking for environmental and socio-economic receptors, which are then tailored by technical subject matter experts.

Table 7-2: Sensitivity Criteria

	Low	Medium	High			
Biological and	l Physical Receptors - Sensitiv	vity Criteria				
Criteria	Ecosystem Value: An area or species which has local or no value Capacity for Change and Recovery: The receptor is not sensitive to changes in the surrounding environment and has a natural ability (i.e. without human enhancement) for a rapid rate of recovery to pre-impacted status within few days/months.	Ecosystem Value: An area or species which are recognized as being of regional importance; and/or Capacity for Change and Recovery: The receptor is relatively sensitive to changes in the surrounding environment and has moderate capacity to absorb change without significantly	Ecosystem Value: An area or species which is recognized as being of international and national importance and/or is legally protected; and/or Capacity for Change and Recovery: The receptor is highly sensitive to changes in the surrounding environment and has no / low capacity to absorb change without significantly altering its present			

	Low	Medium	High		
		altering its present character; natural recovery possible after one year.	character; no / slow natural recovery.		
Socio-Econom	nic Receptors - Sensitivity Crit	eria			
Criteria	Socioeconomic Value: A socio-economic activity of limited local or no value; and /or Capacity for Change and Recovery: The receptor is not sensitive to changes in the surrounding environment and has a natural ability (i.e. without human enhancement) for a rapid rate of recovery to pre-impacted status within days/weeks.	Socioeconomic Value: A socio-economic activity which is recognized as being of regional importance; and/or Capacity for Change and Recovery: A socio-economic activity which has the capacity to recover after one year.	Socioeconomic Value: A socio-economic activity which is recognized as being of international / national importance and/or a resource or area which is legally protected; and/or Capacity for Change and Recovery: The receptor has no / low capacity to absorb change without significantly altering its present character; no / slow natural recovery.		

Assessing Impact Significance

Once magnitude of impact and sensitivity of a receptor have been ranked, the significance can be determined for each impact. The impact significance rating was determined, using the matrix provided in **Table 7-3**, and impact significance definitions as presented in **Table 7-4**, which ensure a consistent approach throughout the impact assessment. The significance matrix provides basic guidance for the determination of impact significance. However, the resulting significance level is also interpreted based on professional judgement and expertise, and adjusted if necessary.

The impact ratings are categorised as follows:

- Minor significance;
- Moderate significance; and
- Major significance.

Table 7-3: Impact Significance

	Sensitivity						
Magnitude	Low [1]	Medium [2]	High [3]				
Negligible [0]	Negligible [0]	Negligible [0]	Negligible [0]				
Small [1]	Negligible [1]	Minor [2]	Moderate [3]				
Medium [2]	Minor [2]	Moderate [4]	Major [6]				
Large [3]	Moderate [3]	Major [6]	Major [9]				

Key: Negligible – 0 to 1, Minor – 2, Moderate – 3 to 4, Major – 6 to 9

Table 7-4: Impact significance definitions

Significance of Impact

Major	Significant . Impacts with a " Major " significance are likely to have damaging and lasting changes to the functioning of a receptor, and may have broader consequences (e.g. on function of the ecosystem or on community well-being). These impacts are a priority for mitigation in order to avoid or reduce their significance.
Moderate	Significant . Impacts with a " Moderate " significance are likely to be noticeable and result in lasting changes to baseline conditions, which may cause hardship to or degradation of the receptor. Broader consequences for the ecosystem or community are not anticipated. These impacts are a priority for mitigation in order to avoid or reduce their significance.
Minor	Detectable but Not Significant . Impacts with a " Minor " significance are expected to be noticeable changes to baseline conditions, beyond what would naturally occur, but are not expected to cause hardship or degradation. These impacts in most cases do not require mitigation and are not a concern of the decision-making process.
Negligible	Impacts with a "Negligible" significance are expected to be almost unnoticeable in terms of affecting the baseline conditions. These impacts do not require mitigation and are not a concern of the decision-making process.

The matrix and significance definitions will be used to assess adverse impacts of the Project. Significance rankings will not be determined for beneficial impacts; instead, these will be described in qualitative terms and, where applicable, measures to maximize benefits will also be described.

For all Significant impacts (Moderate or Major) identified by the assessment, additional mitigation measures will be proposed aimed at reducing their residual significance to as low as reasonably practicable (ALARP). For Not Significant impacts (Minor and Negligible), all design/control measures should be adhered to with monitoring and reporting implemented as required.

7.1.3 Mitigation and Control

All significant impacts identified will be subject to mitigation and control through preventive, reductive and offset measures as well as optimizing the viability and potential benefits that the project may generate. The selection of mitigation measures will consider a standard mitigation hierarchy, whereby preference is given to avoiding impacts altogether and subsequently to minimizing the impact, repairing its effects, and/ or offsetting the impact through actions in other areas as illustrated in **Figure 7-2**. Where the effectiveness of mitigation measures is uncertain, or depends on assumptions about operational procedures, monitoring programmes and/or operations/management procedures will define the required practice.




Figure 7-2: Mitigation Hierarchy

The environmental and social management plan (ESMP) framework will be developed for the project and its facilities in accordance with Environmental Assessment Regulations 2025, LI 2504 and the AfDB OS standards. The ESMP framework will present a programme for the implementation of mitigating measures and the identified impacts of the project during the construction and operation phases.

7.2 Potential Environmental Risks and Social Issues

Potential impacts of the REWARD Project on the physical, biological and social environments have been identified and are discussed below in this section.

7.3 Project Area of Influence (AoI)

The ESIA gives an identification, qualitative assessment and classification of potential environmental and social impacts and their respective management options based on the general project design concepts. The REWARD Project will have both positive and negative social, economic and environmental impacts at different levels.

There are two (2) AoIs: i.e. Area of Direct Influence (ADI) and Area of Indirect Influence (AII) for the REAWARD Project. These have been defined to properly identify environmental and social impacts and risks associated with the project in the sections below.

7.3.1 Environmental Area of Influence

The Area of Direct Influence (ADI) for the project includes the physical and biological components such as the vegetation, fauna, surface/groundwater resources, soils etc. at the project area and the community (i.e. Tindantua) around the project area.

The area of indirect influence (AII) is the territory where indirect or induced environmental impacts; i.e. those that occur at a different site from where the action causing the environmental impact occurs and at a different time compared with the time when the action causing the environmental impact occurred.

The All for the project includes 1-10 km zone around ADI (depending on the affected receptors, for example for groundwater it can be broader than for biodiversity), the transit routes for materials and personnel or workers.

7.3.2 Social Area of Influence

For social impacts, the ADI will include the households and the community that will be impacted by the Project due to:

- ✓ their location within or in close proximity to the Project footprint (including footprint of associated facilities);
- ✓ their location within the Area(s) of Influence for environmental resources, such as air or water quality, noise and vibration, visual and landscape, etc.;
- ✓ impacts on livelihood resources that will be affected by the Project (agricultural or grazing land, forest resources, fishing); or
- ✓ their connection to cultural, social or health resources that will be impacted by the Project.

The Area of Indirect Influence will also include populations that will experience indirect or induced impacts that may not be within the direct control of the Project, such as:

- ✓ economic opportunities associated with employment and economic spend;
- ✓ interaction with the workforce;
- ✓ use of services by the workforce; and
- ✓ in-migration.

7.4 Community influence and vulnerable groups

Construction activities may impact adversely on local communities especially those which are located in close proximity to these activities.

Vulnerable groups are those at risk of becoming more vulnerable due to impacts from project implementation. These vulnerable people include, but not limited to:

Disabled persons, whether mentally or physically challenged;

- Elderly, usually from 70 years and above;
- Very sick and or physically weak individuals;
- People without formal land rights;
- Migrants/settlers;
- Women; and
- Children.

7.5 Institutional Influence

The major institutions to be influenced or involved in the proposed project include:

- Ministry of Food and Agriculture;
- Project Implementation Unit;
- Water Resources Commission;
- Lands Commission;
- Forestry Commission
- Environmental Protection Authority;
- Regional Coordinating Council;
- District Assembly;
- Fire Service; and
- NADMO.

7.6 Potential Positive Impacts

The significant positive impacts of the proposed project are outlined as follows:

- Creation of job opportunities;
- Increased commerce and boost to local economy;
- Food security;
- Adoption of good agricultural practices;
- Technology transfer
- Save the Government of Ghana from importing rice and thereby save foreign exchange for Ghana

7.6.1 Creation of job opportunities

Job opportunities for skilled, semi-skilled and unskilled labour will be created at the construction and operation phases as locals, including women, will be recruited for short-term and long-term jobs. During construction of various agricultural value chain support infrastructure (assembly/construction of semi-industrial units, construction of warehouses etc.), labourers and piece workers will be engaged. The presence of workers will create an opportunity for food vendors, shop owners and other business operators in the communities to make some income. At the operation phase, there will be increase in the number of agricultural jobs leading to income generation and poverty reduction.

7.6.2 Increased commerce and boost to local economy

Agricultural productivity will increase quantitatively due to increased access to mechanization services by rice farmers. This will result in higher revenue for players within the value chain such as farmers, input suppliers, transport operators, feed millers etc. Also, the project will improve and facilitate establishment

of local services for marketing, processing, quality control services and development of new investment opportunities.

7.6.3 Food security

Increase in production capacity coupled with availability of storage facilities will make produce available all year round and improve reliance on local agricultural produce and product. This will reduce the importation of agricultural produce across borders and improve food security.

7.6.4 Adoption of good agricultural practices

The proposed project will involve the community and the local stakeholders throughout the project cycle equipping them with knowledge and skills in agricultural practices. The project will present the local stakeholders with a learning opportunity on good practices, such as climate smart agriculture, efficient water management, fertilizer application, among others leading to reduction in losses and better pest and disease management.

7.6.5 Technology transfer

Farmers will be exposed to new technologies for geomapping, crop management, pest and disease management, processing, etc. that were otherwise not known to them. For instance, applications such as the RiceAdvice decision support; will provide farmers guidelines for specific field conditions via smart phones. For pest and disease control, technologies that counter threats from parasitic striga, health-threatening aflatoxins and the invasion by Fall Army Worm will be made available to farmers. Facilitation of farmer access to mechanical and motorized shellers, threshers, improved seed variety and breeds will all increase productivity of farmers and increase their savings.

7.7 Moderate and Major Negative Impacts

The environmental impacts of the project have been grouped as moderate and major impacts based on their significance. Also, impacts have been considered at the various phases of the project, i.e., preparatory, construction and operation. The moderate and major adverse impacts are described below and in **Table 7-5**, **Table 7-6**, **Table 7-7** and **Table 7-8** for Preparatory, Construction, Operational and Decommissioning Phases respectively.

Preparatory phase

- Land related disputes Acquisition of lands by farmers without following due process could result in land-related disputes
- **Impact on livelihoods** The project activities could restrict locals access to lands that were otherwise used as pasture areas.
- **Destruction of vegetation -** Site clearing will lead to the destruction of some common vegetation and a few trees.

Construction phase

• Soil degradation – Levelling, as part of land preparation, and excavation for foundation of structures such as sheds and warehouses could lead to soil erosion and creation of gullies through runoff

- especially in the rainy season. Also, oil spillages from the maintenance of construction equipment and vehicles could contaminate soils and affect flora and soil fauna
- **Air pollution** Levelling of land and transport of materials on untarred roads will lead to emission of particulate matter i.e. dust and fumes and adversely affect air quality, especially in the dry season
- Water pollution Disposal of domestic waste from construction workers and food vendors and deposition of sediment, waste oil etc. via runoff into nearby water bodies .i.e. the Daka River will reduce the quality of water and could also smother some fishes and benthic organisms.
- **Noise and vibration** Generation of noise and vibration beyond acceptable limits from operation of construction equipment, movement of haulage vehicles and tooting of horns could be a nuisance to residents of nearby communities and other sensitize organisms.
- Waste generation and disposal Clearance of vegetation and levelling of land at project site will
 generate vegetative waste and excavated spoil. Other wastes such as construction debris, pieces of
 steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog
 drains, produce foul smell and facilitate the outbreak of sanitary related diseases such as cholera
- Inefficient waste management Inefficient waste management during construction, operation and maintenance leading to excess consumption of materials, generation of wastes/emissions, pollution of soils and water.
- Occupational health and safety Construction workers could be exposed to workplace and trafficrelated accidents/incidents as well as animal/insect threat/bites during land preparation, civil works and transportation of materials or persons.
- Poor labour working conditions Lack of employment contracts could lead to workers being paid
 rates below the stipulated national minimum wage or work under poor conditions. Also, the absence
 of welfare facilities like toilets, sheds could affect their health or lead to indiscriminate defecation.
- Traffic management Transport of materials and equipment to and from the project site through communities and towns raises traffic/public safety concerns. Broken-down, inappropriately parked or slow moving haulage/construction trucks could lead to road accidents and traffic congestion especially on busy roads.
- Visual intrusion Presence of construction machinery, material stockpiles, temporary work camps;
 Vegetation clearance, earthworks (bare ground); dust plumes, may intrude on the visual sensitivity of the Tindantua community.
- **Fire outbreak** Fire outbreaks from negligence of workers or the public burning refuse, game hunting and workers not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property.
- Gender based violence Presence of workers and increase in incidents of rape, defilement and GBV
- Public health issues Pollution of local water bodies will adversely affect the health of users. Sexual
 relations between workers and locals may bring about increase in sexually transmitted diseases
 including HIV/AIDs.
- **Risk of Drowning -** Borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains.
- **Security concerns** Violent behaviour and confrontations between workers and locals. Workers who are deemed to be financially sound could be victims of theft and burglary. Potential conflict over sexual affairs, child labour, drunk driving, accidents and destruction of property.

Operation phase

- **Soil erosion** Leaving farmlands bare especially after harvesting could expose the soil to wind erosion from the strong winds in the dry season
- **Air Pollution** Operation of equipment and vehicles will generate fumes that adversely affect the air quality. In addition, haulage of products and inputs such as fertilizers, pesticides, seeds especially on untarred routes to and from farms or agricultural establishments will generate dust and fumes.
- **Pollution of Soils and Water** Wastes, workforce sewage effluent, as well as runoff from cultivated land (containing fertilizers, pesticides and herbicides etc.) could pollute surface water, reduce its quality and make it unsuitable for use
- Odours Odours associated with waste may have nuisance value for nearby receptors.
- Noise and Vibration Noise and vibration from operation of processing equipment, equipment
 maintenance, movement of haulage vehicles, tooting of horns could be a nuisance to persons within
 the project community or nearby communities
- Waste generation and disposal Improper disposal of vegetative waste from weeding, harvests, domestic waste from workers and effluent from installations could create unsightly scenes and aid in the production of vermin. Also, it could serve as breeding grounds for disease causing vectors like mosquitoes, houseflies etc.
- Inefficient waste management Inefficient waste management during operation and maintenance leading to excess consumption of materials, generation of wastes/emissions, pollution of soils and water.
- Occupational health and safety Workplace and traffic accidents/incidents and animal/insect threat/bites.
- **Poor labour working conditions** Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions.
- Traffic management Haulage of produce, inputs and equipment to and from farms through communities raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage trucks could lead to road accidents and traffic congestion especially on busy roads.
- **Fire outbreak** Fire outbreaks from negligence of workers or the public burning refuse, game hunting and not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property.
- Gender based violence Presence of workers and increase in incidents of rape, defilement and GBV.
- **Risk of Drowning -** Burrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains.
- Public health issues Pollution of local water bodies will adversely affect the health of users. Sexual
 relations between workers and locals may bring about increase in sexually transmitted diseases
 including HIV/AIDs.
- Snake bite risks Farm workers on rice fields are likely to be exposed to snake bites which may result in hospitalization or fatality.
- Security concerns Violent behaviour and confrontations between workers and locals as a result of sexual affairs, child labour, drunk driving, accidents and destruction of property. Workers who are deemed to be financially sound could be victims of theft and burglary.
- **Flooding** The project implementation could be adversely affected by events of flood from torrential rainfall in the wet season especially in low-lying areas affecting properties and lives.

Decommissioning phase

- Occupational health and safety Workplace and traffic accidents/incidents and animal/insect threat/bites.
- Inefficient waste management Inefficient waste management during decommissioning leading to excess consumption of materials, generation of wastes/emissions, pollution of soils and water.
- Waste generation and disposal Improper disposal of waste from dismantling of machine parts could
 create unsightly scenes. Also, it could serve as breeding grounds for disease causing vectors like
 mosquitoes etc.
- Traffic management Transport of materials and equipment to and from the project site through
 communities and towns raises traffic/public safety concerns. Broken-down, inappropriately parked or
 slow-moving haulage/construction trucks could lead to road accidents and traffic congestion
 especially on busy roads.

7.7.1 Preparatory Phase: Moderate and Major adverse impacts

The preparatory phase moderate and major adverse impacts are provided in **Table 7-5.**

 Table 7-5:
 Preparatory Phase Potential Adverse Impacts

AfDB	AfDB OS	Risk/Potential			Sensitivity						
No.	Description	Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS1	Environmental and Social Assessment	Poor assessment study of environmental and social risks and impacts	Project proponent (MoFA), environment, community	Unidentified risks and impacts could prevent or stall project implementation. Selection of unqualified persons for assessment studies	Unikely	Direct	Permanent	Regional	High [3]	Large [3]	Major [9]
OS5	Involuntary resettlement, land acquisition, population displacement and	Land related disputes	Farmers	Proposed site which covers an area of 350 Ha is purportedly owned by the chief of the Tindantua community with no known land disputes over the land at the proposed site.	Unlikely	Direct	Temporary	Local	Medium [2]	Medium [2]	Moderate [4]
	compensation	Impact on livelihoods (Economic displacement)	Farmers	The project activities could restrict four (4) farmers access to lands that were	Likely	Direct	Permanent	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB OS	Risk/Potential					Sensitivity				
No.	Description	Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				otherwise used for farming.							
		Impact on livelihood (physical displacement)	N/A	There will be no physical movement of properties from the project site during project implementation.	Unlikely	Direct	Temporary	Local	High [3]	Negligible [0]	Negligible [0]
OS6	Biodiversity, renewable resources and ecosystem services	Destruction of vegetation and displacement of wildlife	Flora and Fauna	The project site is an already disturbed area due to previous human activities such as farming. The floristic analysis conducted indicates that none of the species identified at the site are of conservation concern according to the Forest Reserves of Ghana Information Exhibitor (FROGGIE) data base. It must be noted however, that Vitellaria paradoxa (Shea tree) is a tree of economic importance to	Likely	Direct	Permanent	Local	Small [1]	Medium [2]	Minor [2]

AfDB No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact							
					Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				the local people in the project area. Site clearing will not lead to any major destruction of biodiversity of significant importance, a few trees and destruction of the							
				habitats of some animals.							

7.7.2 Construction Phase: Moderate and major adverse impacts

The Construction phase moderate and major adverse impacts are provided in **Table 7-6** below.

Table 7-6: Construction Phase Potential Adverse Impacts

AfDD	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Sensitivity						
AfDB No.					Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS2	Labour conditions, health and safety	Workplace incidents/accidents	All Project workforce, Vulnerable categories of workers, Women	Project site accidents/incidents and animal/insect threat/bites. Ghana has recorded over 59,000 snake bite cases between 2015 and 2020 with an average 9,900 cases reported annually. The Savannah Region has a relatively high incidence of snakes bites as per the Ghana Health Service (2020).	Likely	Direct	Short- term	On- site	High [3]	Medium [2]	Major [6]
		Poor labour working conditions	All Project workforce, Vulnerable categories of workers, Women	Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions. Workers could face issues of discrimination, forced labour, child labour, freedom of association and collective bargaining, lack of or ineffective worker grievance redress mechanisms.	Likely	Direct	Short- term	On- site	High [3]	Medium [2]	Major [6]
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Women, Children	Presence of workers and increase in incidents of rape, defilement, child molestation and GBV. Culturally, women and children have limited rights compared to men in northern Ghana making GBV issues relatively pronounced in the project areas.	Likely	Direct	Short- term	Local	High [3]	Medium [2]	Major [6]

	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact			Sensitivity				
AfDB No.					Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS3	Pollution prevention and control, hazardous materials and resource efficiency	Soil erosion and contamination	Soil Health of	Excavation for foundation of structures could lead to soil erosion and creation of gullies through runoff especially in the rainy season. The project area due to its sparse vegetation cover is highly susceptible to erosion especially in low-lying areas like the valleys. Soil contamination could also occur from inappropriate disposal of waste oil, spilled oil during machinery operation and maintenance as well as fuel storage sites and leaks from vehicle refuelling.	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4] Moderate
			workers and members of the surrounding communities	materials especially on untarred routes to project site. Baseline air quality data ($PM_{2.5}-10\mu g/m^3$, $PM_{10}-16\mu g/m^3$, $NO_2-0.2\mu g/m^3$, $SO_2-0.1\mu g/m^3$) shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds hence emissions from project activities such as transportation of materials are not expected to result in significant air quality deterioration					[2]		[4]
		Water Pollution	Quality of water bodies – River Daka	Sediment and waste oil transport into the River Daka could exacerbate the already turbid conditions especially in the rainy season. The baseline turbidity reading of 62.6 NTU is about 12 times higher than the threshold of 5 NTU.	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]

		-11/							Sensitivity				
AfDB No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)		Sources of Impac	rt .	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Noise and	Health of	construction we average of 20 w total of 10 kg/generated per d 0.5 kg/day Also, be generated as 40g/day.	orkers and food orkers at the cons day domestic so ay using a per cap a total BOD load ssuming a per cap	vendors. For an struction phase, a lid waste will be pita generation of of 0.8 kg/day will bita production of ent, movement of	Likely	Direct	Short- term	Local	Medium [2] Medium	Medium [2] Medium [2]	Moderate [4] Moderate
		Vibration	project workforce	*	and tooting of h	orns will generate	Likely	Direct	term	LOCAI	[2]	Medium [2]	[4]
			and members of	Equipment type	Sound pressure level at 15m (dB)	Sound pressure level at 600m (dB)							
			the	Backhoe	80	47.96							
			surrounding communities	Grader	85	52.96							
			Communicies	Loader	85	52.96							
				Truck	88	55.96							
				Source: Generated from	WKC Group Formula (2015	5)							
				Movement of h	aulage vehicles/t	rucks and tooting							
				Movement of haulage vehicles/trucks and tooting of horns will at all times expose receptors to noise,									
				albeit transient. However, at night, the impact of									
				noise is likely to be higher. Exposure to elevated									
				levels of noise can cause nuisance, disturbance and even lead to hearing impairment under certain									
				even lead to h	earing impairme								

							Sensitivity				
AfDB No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Waste generation and disposal	Health of project workforce and members of the Local communities within the project area	intermittent noise and vibration for the construction period which will be one dry season (approx. 4 months). The nearest community which is >1km from the site will not experience high noise levels as equipment noise reduces to acceptable limits at a distance of 600m. Clearance of vegetation at project site, construction debris, pieces of steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog drains and facilitate the outbreak of sanitary related diseases such as cholera. Domestic and waste from the construction workers and food vendors to the construction crew. For an average of 20 workers at the construction phase, a total of 10 kg/day domestic solid waste will be generated per day using a per capita generation of 0.5 kg/day Also, a total BOD load of 0.8 kg/day will be generated assuming a per capita production of 40g/day.	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]
OS4	Community Health, Safety and Security	Traffic management	Local communities near the project area of influence	Transport of materials and equipment through communities and townships raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage/construction trucks could lead to road accidents and traffic congestion especially on busy roads. Locals may not be used to	Likely	Direct	Short- term	Local	Medium [2]	Medium [2]	Moderate [4]

A (DD	AfDB OS	Disk /Data attal					Sensitivity				
AfDB No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				truck traffic as the popular mode of transportation is bicycles, motorcycles and tricycles.							
		Fire outbreak	Vegetation, Project workforce and Local communities near the project area of influence	Fire outbreaks from negligence of workers or the community burning refuse, game hunting and workers not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property. A major constraint faced by the people within the fragile Savannah ecology is the issue of bushfire. Most of the vegetation cover is consumed every year by wild fire. This menace does not only affect the density and diversity of the vegetation in the Savannah ecosystem but has lowered the productivity of the land and the general agricultural output.	Likely	Direct	Temporary	Local	Medium [2]	Medium [2]	Moderate [4]
		Visual / Aesthetic Impacts	Local community (Tindantua) and commuters	Presence of construction machinery, material stockpiles, temporary work camps; Vegetation clearance, earthworks (bare ground); Dust plumes. Landscape is already agricultural.	Likely	Direct	Temporary	Local	Medium [2]	Medium [2]	Moderate [4]
		Public health issues	Local communities	Pollution of local water bodies (River Daka) will adversely affect the health of users	Likely	Direct	Short- term	Local	High [3]	Small [1]	Moderate [3]

AfDD	AfDD OC	Diele/Detemble					Sensitivity				
AfDB No.	AfDB OS Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
			near the project area of influence	Sexual relations between workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	Likely	Local	Long-term	Local	High [3]	Small [1]	Moderate [3]
		Security concerns		Violent behaviour and confrontations between workers and locals. Workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over illicit sexual affairs, child labour, drunk driving, accidents and destruction of property.	Likely	Local	Temporary	Local	Medium [2]	Small [1]	Minor [2]
		Risk of Drowning	Project Workforce and Local community members	Borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for workers especially contract staff who aren't use to the terrain. Children who may play around the sites and unsuspecting community members may also be at risk of drowning especially when it rains and the place get flooded.	Likely	Local	Long-Term	Local	Medium [2]	Medium [2]	Moderate [4]

7.7.3 Operation Phase: Moderate and Major adverse impacts

The Operation phase moderate and major adverse impacts are provided in **Table 7-7.**

Table 7-7: Operation Phase Potential Adverse Impacts

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS2	Labour conditions, health and safety	Occupational health and safety	Farm workers including Vulnerable categories .e.g Women	Farm accidents/incidents and animal/insect threat/bites. Ghana has recorded over 59,000 snake bite cases between 2015 and 2020 with an average 9,900 cases reported annually. The Savannah Region has a relatively high incidence of snakes bites as per the Ghana Health Service (2020). Exposure of workers/farmers to agrochemicals could lead to health challenges such as chemical burns, respiratory diseases from inhalation, and poisoning.	Likely	Direct	Long-term	On-site	High [3]	Medium [2]	Major [6]
		Poor labour working conditions	Farm workers including Vulnerable categories .e.g Women	Lack of employment contracts could lead to farm workers being paid rates below the stipulated national minimum wage or work under poor conditions. Farm workers could face issues of discrimination, forced and child labour, restriction of freedom of	Likely	Direct	Long-term	On-site	High [3]	Medium [2]	Major [6]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				association and collective bargaining, non- existent or ineffective farm worker grievance redress mechanism.							
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Women and Children	Presence of migrant farm workers could lead to increase in incidents of rape, defilement, child molestation and GBV. Culturally, women and children have limited rights compared to men in northern Ghana making GBV issues relatively pronounced in the project areas.	Likely	Direct	Long-term	Local	High [3]	Medium [2]	Major [6]
		Child Labour	Children	Employment and deployment of Children under the working age at the expense of their education and their exposure to hazards that endanger their health and well-being. In Ghana, children's work is mostly split between the three main areas: the agriculture, services, and industry sectors. The agricultural sector has the highest percentage of working children in the country, with 79.2% of working children between ages 5 and 14 employed in this sector (Child Labour and Forced Labour Reports, 2021). The Northern parts of Ghana has the lowest level of school attendance of children of primary school age at just 59.4 per cent of children due to	Likely	Direct	Long-term	Local	High [3]	Medium [2]	Major [6]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				child labour with most found in the agriculture and forestry sector. Children are vulnerable to snake and scorpion bites and suffer frequent accidents with poorly handled machetes while they are engaged in work in the bush. Boys tend cattle and girls collect water and firewood. (Child Protection Baseline Research Report, 2015).							
OS3	Pollution prevention and control, hazardous materials and resource efficiency	Soil erosion and degradation	Soil	Abuse of fertilizer use could lead to soil degradation. Leaving farmlands bare especially after harvesting could expose the soil to erosion. Soil degradation could also occur from inappropriate application of fertilizers and other agro-chemicals.	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]
		Air Pollution	Health of farm workers and surrounding community members.	Use of farm machinery, clearing of dry lands and emission of fumes/dust from tricycles or motorcycles conveying farmers and farm produce especially on untarred routes from farms are some of the activities that have the potential of affecting the air quality within the project area. Stubble burning to prepare the field for the next planting season can also affect	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Water Pollution	River water quality including water which has gathered as ponds in the valley.	the air quality within the project area. Baseline air quality data ($PM_{2.5}-10\mu g/m^3$, $PM_{10}-16\mu g/m^3$, $NO^2-0.2\mu g/m^3$, $SO^2-0.1\mu g/m^3$) shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds. Hence, emissions from farming activities such as tilling, threshing and transportation of farm produce are not expected to result in significant air quality deterioration. Sediment laden with excess fertilizers and other agrochemicals and waste oil transport into nearby water bodies especially in the rainy season. Pollution of watercourses caused by wastes generated by farm workers as well as runoff from land used for growing rice (containing fertilisers, pesticides and herbicides etc.). The baseline turbidity reading of 62.6 NTU is about 12 times higher than the threshold of 5 NTU.	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]
		Noise and Vibration	Health and wellbeing of farm workers	Farm workers are expected to be exposed to intermittent noise from activities like tilling of the land for the next planting	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
			and members of communities close to the project area	season, threshing the rice after cultivating and screaming sounds from farmers or labourers to scare away birds can all generate noise. Tricycles and motorbikes conveying farmers and farm produce to the milling factories or markets could also generate some noise including the sounds from tooting horns. The nearest community which is >1km from the site will not experience high noise levels as equipment noise reduces to acceptable limits at a distance of 600m.							
		Solid waste generation and disposal	Health of farm workers and members of the Local communities within the project area	Improper disposal of waste, i.e. empty containers of agrochemicals and fertilizers which can serve as breeding grounds for mosquitoes. Threshing will produce rice husk that may pile up to form heaps of waste. Domestic waste can also be generated from farm workers. For an average of 10 workers at the construction phase, a total of 5 kg/day domestic solid waste will be generated per day using a per capita generation of 0.5 kg/day. Also, a total BOD load of 0.4 kg/day will be generated	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
				assuming a per capita production of 20g/day.							
OS4	Community Health, Safety and Security	Polluted Waterbodies	Farm workers and Local communities	Pollution of River Daka from contaminated sediments generated by activities of farm workers as well as runoff from land used for growing rice (containing fertilisers, pesticides and herbicides etc.) run-off will adversely affect the health of community members. The baseline turbidity reading of 62.6 NTU is about 12 times higher than the threshold of 5 NTU.	Likely	Direct	Local	Local	Medium [2]	Medium [2]	Moderate [4]
		Sexual Transmitted Diseases		Sexual relations between migrant farm workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	Likely	Direct and Indirect	Long-term	Local and Regional	Medium [2]	Medium [2]	Moderate [4]
		Security concerns		Violent behaviour and confrontations between migrant farm workers and locals. Farm workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over sexual affairs, child labour, drunk driving, accidents and destruction of property.	Likely	Direct	Long-term	Local	Medium [2]	Small [1]	Minor [2]

AfDB	AfDB OS						Sensitivity				
No.	Description	Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Flooding	Community members, Farmers, Flora and Fauna	The project implementation could be adversely affected by events of flood from torrential rainfall in the wet season especially in low-lying areas affecting properties and lives.	Likely	Direct	Temporary	Regional	Major [3]	Medium [2]	Major [6]
		Traffic management	Local communities	Transportation of farmers and farm produce through communities raises traffic/public safety concerns.	Likely	Direct	Long-term	Local	Medium [2]	Small [1]	Minor [2]
		Fire outbreak	Rice farms, nearby vegetation, farm workers and local community.	Fire outbreaks from negligence of farm workers and community members, burning refuse, game hunting, cooking and not properly extinguishing stubs of cigarette. These fires could spread to adjoining farms causing injuries to persons and destruction of property. A major constraint faced by the people within the fragile Savannah ecology is the issue of bushfire. Most of the vegetation cover is consumed every year by wild fire. This menace does not only affect the density and diversity of the vegetation in the Savannah ecosystem but has lowered the productivity of the land and the general agricultural output.	Likely	Direct	Long-term	Local	Medium [2]	Medium [2]	Moderate [4]

ΔfΓ	AfDB AfDB OS	2.1/2					Sensitivity				
No		Risk/Potential Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
		Risk of Drowning	Farmers and Local community members	Borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. These pits may be left for communities as a water source and may pose the risk of drowning especially for children.	,	Local	Long-Term	Local	Medium [2]	Medium [2]	Moderate [4]

7.7.4 Decommissioning Phase: Moderate and major adverse impacts and specific measures

The Decommissioning phase moderate and major adverse impacts are provided in **Table 7-8.**

Table 7-8: Decommissioning Phase Potential Adverse Impacts

AfDB	AfDB OS	Risk/Potential			Sensitivity						
No.	Description	Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS2	Labour conditions, health and safety	Workplace incidents/accidents	All Project workforce, Vulnerable categories of workers, Women	Project site accidents/incidents and animal/insect threat/bites. Ghana has recorded over 59,000 snake bite cases between 2015 and 2020 with an average 9,900 cases reported annually. The Northern Region has a relatively high incidence of snakes bites as per the Ghana Health Service (2020).	Likely	Direct	Short-term	On-site	High [3]	Medium [2]	Major [6]

AfDB	AfDB OS	Risk/Potential					Sensitivity				
No.	Description	Impact	Receptor(s)	Sources of Impact	Likelihood	Nature	Duration	Extent	Sensitivity Score	Magnitude	Significance
OS3	Pollution prevention and control, hazardous materials and resource efficiency	Waste generation and disposal	Health of project workforce and members of the Local communities within the project area	Clearance of vegetation at project site, construction debris, pieces of steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog drains and facilitate the outbreak of sanitary related diseases such as cholera. Domestic and waste from the construction workers and food vendors to the construction crew. For an average of 20 workers at the construction phase, a total of 10 kg/day domestic solid waste will be generated per day using a per capita generation of 0.5 kg/day Also, a total BOD load of 0.8 kg/day will be generated assuming a per capita production of 40g/day.	Likely	Direct	Short-term	Local	Medium [2]	Medium [2]	Moderate [4]
OS4	Community Health, Safety and Security	Traffic management	Local communities near the project area of influence	Transport of materials and equipment through communities and townships raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage/construction trucks could lead to road accidents and traffic congestion especially on busy roads. Locals may not be used to truck traffic as the popular mode of transportation is bicycles, motorcycles and tricycles.	Likely	Direct	Short-term	Local	Medium [2]	Medium [2]	Moderate [4]

7.7.5 Cumulative Negative Impacts of the Project

The REWARD Project seeks to enhance climate resilience, agricultural productivity, and rural infrastructure within the Mion district. Given the area's agrarian economy and limited industrialization, interventions occur under low development pressure (Mion MTDP, 2022–2025). This cumulative impact assessment (CIA) examines combined environmental and social effects of REWARD alongside existing and planned developments, focusing on additive and synergistic interactions.

Natural resources such as soils, rivers, forests, and pasturelands experience moderate pressure from bush burning, overgrazing, and illegal tree felling. However, large-scale agriculture and infrastructure remain minimal, constrained by low urbanization and limited funding. The municipality's cumulative environmental footprint is modest, with localized land degradation but overall stable ecological conditions, providing a sound baseline for REWARD implementation.

Key Development Drivers and Interactions

Agriculture

Agriculture dominates livelihoods in the district. Expansion of cultivation, especially under projects promoting improved irrigation and mechanization, presents potential cumulative pressures on soils and water resources. However, the majority of farms remain small-scale with rain-fed systems, and existing agro-processing uses low-technology, small-scale operations. Planned interventions by the Assembly emphasize sustainable agri-business and capacity building of smallholder farmers, which align with REWARD's objectives. Consequently, the cumulative interaction between REWARD's agricultural support and ongoing local programs is expected to be positive, enhancing productivity while promoting soil conservation and climate-smart practices.

Infrastructure

Infrastructure remains basic, with unpaved, often impassable rural roads. The Medium-Term Development Plan highlights underinvestment in transport, education, and health infrastructure. Planned works focus on minor road upgrades, market improvements, and small-scale public facilities, as shown in the table below. REWARD's support for feeder roads will complement municipal efforts, enhancing connectivity and market access without adding significant ecological stress.

Community Issue	Policy Objective	Development Needs and Aspiration
Unpredictable rainfall pattern.	To ensure all year farming	Building and rehabilitating of irrigation infrastructure including formal schemes, dams and dugouts (SDG Targets 2.4, 17.17, Targets 1.1, 1.4, 1.5, 1.a, 2.a, 17.3)
Inadequate health infrastructure	Ensure accessible, and quality Universal Health Coverage (UHC) for all	Expand, upgrade and equip health facilities with private sector involvement (SDG Targets 3.8, 3.c) Rehabilitating of Sing health facility reservoir
Inadequate Infrastructure. school buildings, toilets, urinals Inadequate accommodation to keep teachers in deprived communities In adequate structure for security persons	Enhance equitable access to, and participation in quality education at all levels	Expand infrastructure and facilities at all levels (SDG Target 4.a, 4.c) by constructing classroom blocks with office and store, teachers' bungalows, KVIP and Urinals Construction of semi-detached bungalow for police officers
- Poor road network	Improve efficiency and effectiveness of road transport infrastructure and services	Expand and gravelling of selected road networks Support the routine maintenance, reshaping and creation of access roads
Lack of access to potable water	Improve access to safe and reliable water supply	Drilling of boreholes with hand pumps

Assessment of Cumulative Effects

Physical Environment

Potential cumulative effects on land, soil, and water are expected to be minor and localized. The district's limited industrial and infrastructural footprint reduces the risk of significant additive degradation. The introduction of REWARD's agricultural and water management interventions may lead to incremental land conversion and short-term sediment generation during construction. However, these are mitigated by the project's design emphasis on climate-smart practices and erosion control. Considering the absence of heavy industrial or mining activities, the cumulative impacts on air quality, hydrology, and noise environment are negligible.

Biological Environment

Cumulative effects on vegetation and biodiversity are minor. Although existing pressures include bush burning and charcoal production, these are diffused and community-driven. REWARD's interventions will likely reduce rather than exacerbate ecological strain by promoting sustainable land management under community-based planning. The incremental habitat modification from road and irrigation works is expected to be limited to disturbed lands and agricultural corridors.

Socio-economic Environment

At the social level, the additive impacts of REWARD and municipal initiatives are overwhelmingly beneficial. Improved agricultural productivity, employment during construction, and enhanced road access will raise local incomes and food security. Given that industrial activity remains low, competition for land and labour is minimal, reducing risks of social displacement. Potential negative cumulative effects,

such as increased migration, gender disparities, or localized resource conflicts, are expected to be minor and manageable through participatory planning and equitable benefit distribution.

Future Development Scenarios

Mion is unlikely to face rapid industrialization or urban expansion soon. Future projects remain small-scale, emphasizing basic infrastructure and agriculture rather than extractive industries. Consequently, cumulative development pressures will remain low. REWARD, aligned with municipal sustainability goals, contributes positively to the overall environmental profile and demonstrates integrated, climate-resilient rural development.

Conclusion

The cumulative impact of the REWARD Project is minor and not significant. With few large-scale developments in the area, REWARD's synergy with local initiatives will deliver net positive outcomes including stronger livelihoods, improved land management, and enhanced infrastructure without exceeding environmental thresholds. Overall, the project is environmentally sustainable and socially beneficial within Mion's developmental context.

8.0 MITIGATION MEASURES

Mitigation and enhancement measures for the potential adverse impacts have been proposed in this section to ensure that the project impacts are managed within reasonable and acceptable limits. The general rules followed in designing the mitigation measures are listed below:

- Avoidance of major impacts: major impacts are impacts where an accepted limit or standard may be exceeded, or large magnitude impacts occur to highly valued/sensitive resources/receptors;
- Reduction of major and moderate impacts: moderate impacts are impacts within accepted limits
 and standards. Moderate impacts may cover a broad range, from a threshold below which the
 impact is minor, up to a level that might be just short of breaching an established (legal) limit; and
- Minor impacts occur where effects are experienced, but the impact magnitudes are sufficiently small and well within accepted standards, and/or the receptors are of low sensitivity/value.

The potential adverse impacts associated with the project will be managed using the mitigation hierarchy (**Section 7.1.3**, **Figure 7-2**), giving priority to avoidance whenever possible before minimization, repair and offset. Some mitigation measures have been considered as part of the project design, however, risks and impacts not mitigated through design can be mitigated to the barest minimum using the proposed measures below. Residual impacts are expected to be low or negligible post-mitigation and monitoring programmes will be instituted for confirmation.

8.1 Recommended Mitigation Measures for Identified Impacts

Table 8-1 provides a summary of the significant impacts, as per the evaluation. The application of the mitigation measures is expected to reduce both moderate and major adverse impacts identified to either negligible or minor residual impacts.

Table 8-1: Proposed Mitigation and Management Measures for Identified Impacts

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures					
Prepara	Preparatory phase									
OS1	Environmental and Social Assessment	Poor assessment study of environmental and social risks and impacts	Project proponent (MoFA), environment, community	Major [9]	 The project will carry out detailed assessment of environmental and social risks and propose mitigation measures for identified moderate to major adverse impacts. The Project will select a qualified consultant to undertake the assessment studies. 					
OS5	Involuntary resettlement, land	Land related disputes	Farmers	Moderate [4]	 Land will not be acquired for the project as it is donated by the chief of the Tindantua community. The chief to sign the VLD forms 					
	acquisition, population displacement and compensation	Impact on livelihoods		Moderate [4]	 The Resettlement Action Plan (RAP) will provide an understanding of what impact subprojects will have on the four (4) project affected farmers. The RAP will propose changes that aim at avoiding or minimizing livelihood disruption and involuntary resettlement impacts for the affected farmers. The RAP will ensure the impacts are properly assessed and all Project-Affected-farmers (PAFs) are identified and their assets that are affected are recorded and valued for adequate compensation. The RAP will ensure identified PAFs and valued affected assets, are provided with adequate compensation packages whether in cash or kind based on the extent of displacement. The RAP will provide opportunity to address grievances, and provide support for resolution of grievances. 					
OS6	Biodiversity, renewable resources and ecosystem services	Destruction of vegetation and displacement of wildlife	Flora and Fauna	Moderate [4]	 Clear only area required for the project Stray animals that are observed at or around project sites should be given safe passage to nearby bush and not killed. Hunting and or killing of wildlife/animals in bushes around project site by construction/other workers should be prohibited and made punishable. 					

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures					
Constru	Construction phase									
OS2	Occupational health and safety (OHS) impacts and risks	Project Site incidents/accidents	All Project workforce, Vulnerable categories of workers, Women	Major [6]	 Good housekeeping around work area must be ensured to prevent slips, trips & falls. Only trained and competent workers should be allowed to carry out work and must be well briefed on safe working procedures. Appropriate work platforms and PPE must be used for specific tasks such as work at height. Mandatory and basic PPE including hardhat, hand gloves, safety goggles, HiVis and safety boots must be worn. Have accident and incident reporting form available to record accidents and near-misses The Project Contractor will implement and maintain an OHS management system taking into account specific risks associated with the project, legal requirements and duty of care. The Project Contractor will be responsible for ensuring that all affiliated sub-contractors comply with the OHS management system. The OHS management system will be in-line with recognized international best practice. 					
		Poor labour working conditions	All Project workforce, Vulnerable categories of workers, Women	Major [6]	 Provide all workers with signed contracted that are consistent with national labour laws Provide welfare facilities such as potable drinking water, shades, restrooms etc. for workers. Encourage frequent breaks and job-rotation to reduce impact of the weather on workers. Require workers to sign Code of Conduct and provide adequate training to both the workers and the communities Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. Establish an effective worker grievance redress mechanism. 					

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Women, Children	Major [6]	 Include in works contract clauses on mandatory and regular training for workers on required lawful conduct and legal consequences for failure to comply with laws on non-discrimination and GBV. Insert clause requiring contractors and consultants to cooperate with law enforcement agencies investigating cases of gender-based violence. A minimum requirement of female employment should be indicated in contract documents. Clauses prohibiting rape, defilement and other Gender based Violence as well as child and forced labour should be inserted into works contracts. Contact numbers of representative on the Grievance Redress Committee and GBV Service Providers should be pasted around the project site and within the immediate project zone Discuss issues of Gender Based Violence at daily Toolbox meetings Display on site posters prohibiting sexual exploitation and harassment.
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and contamination	Soil	Moderate [4]	 Landscape should be reinstated or regenerated to reflect its original general view before the project. All excavations and trenches should immediately be backfilled and compacted to its original state. Not undertake site clearance, piling, excavation and access road construction during the raining season to minimize erosion and runoff. Ensure that construction activities are restricted to designated work areas to avoid damage and disturbance outside of the site. In case of accidental/unintended spillage, immediately collect contaminated soil and stored as hazardous waste. Make available on site, all equipment and materials required to execute a clean-up. Utilize existing roads to access the site.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					Ensure that activities are confined to designated construction areas, limiting soil exposure and disturbance to the construction site only.
		Air Pollution	Health of workers and members of the surrounding communities	Moderate [4]	 Trucks and heavy machinery with a valid emission test pass certificate should only be allowed on the project site. Dust pollution must be reduced by ensuring that drivers do not speed especially on untarred roads. Suppress dust by watering dusty construction areas. Ensure the use of nose mask in dusty environment.
		Water Pollution	Water quality of Daka river water and water collected as ponds in the project area.	Moderate [4]	 Conduct regular maintenance on trucks to prevent oil leakages that could be washed together with sediment into nearby waterbodies Manage leaked oil by placing trays under trucks to collect leaked oil. Provide impervious storage area, especially for fuel and lubricant, hazardous waste, etc. Not store hazardous materials near natural drainage channels. Ensure that any temporary refuelling tanks are bunded. Have available on site, all equipment and materials necessary to execute clean up. Maintain logbook for water consumption. Progressively adopt less water consuming module cleaning methods. Adhere to agreed arrangements for the disposal of aqueous effluents. Proper handling of materials and wastes to prevent transport into water bodies. Avoid extensive land clearing, excavation, trenching etc. activities during heavy rainfall events to prevent runoff carrying contaminants to surface water (ponds in the project area) Obtaining water permits for ground water usage as required by Ghanaian law, WRC Act 522 (1996). Clean construction equipment away from surface waters. Monitor and record the volume of water used.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					 Ensure water usage and disposal align with national legislation and, where applicable, international best practices, and track any deviations from the estimated water use. Develop and implement a groundwater quality monitoring program to closely monitor changes in aquifer water levels, groundwater quality, and availability.
		Noise and Vibration	Health and wellbeing of workers and members of communities close to the project area	Moderate [4]	 Unnecessary tooting of horn by truck drivers must be avoided. A noise assessment must be carried out for all heavy machinery prior to use at the site to ensure noise levels are in compliance with EPA's guidelines values. Noise should be kept to a minimum with hearing protection used as deemed necessary for workers. Earmuffs or earplugs are recommended for ear protection. The level of noise must be continuously assessed to keep it within acceptable limits. All equipment and tools must be checked for suitability for the task. All construction equipment and hand tools should be operated by trained, experienced and competent persons, and where required persons must produce operator's license upon request. Ensure the use of well serviced/maintained vehicles and other equipment with acceptable noise emission levels. Provide silencers on all noise generating equipment.
		Waste generation and Disposal	Health of members of the Local communities within the project area	Moderate [4]	 Ensure that contractor develops and implements a detailed Construction Waste Management Plan. Ensure that construction debris are collected from work sites to avoid blocking of drains and waterways. Waste bins must be provided and well labelled for waste segregation and disposal. Only licensed waste management companies must be engaged to collect and dispose of waste collected from the site. Regular briefing or training on waste management must be provided to workers at the site.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
OS4	Community Health, Safety and Security	Traffic Management	Local communities near the project area of influence	Moderate [4]	 Have SOPs for managing hazardous and non-hazardous waste. The Highway Code must be strictly followed. Driver training must be provided as part of induction training and permit to drive and transportation of materials to project site issued. Trained flagmen (to slow down traffic) or trained stop-go men (to halt traffic) must be used to ensure safety when trucks are leaving the project site. Stop-go men and flagmen must also wear high visibility vests and use approved stop-go signs or flags. Vehicles to be used on the project must provide maintenance records, and must also be inspected by a competent person before allowed on the project. Have checklists available to manage vehicle and equipment maintenance and management Arrangements must be made for truck drivers to ensure peak times are avoided for haulage of materials to site. Ensure that all trucks used are serviced regularly to maintain optimal performance and ensure safety. Identify safe parking areas off main roads to allow for unloading and
		Fire Outbreak	Vegetation, Project workforce and Local communities near the project area of influence	Moderate [4]	 long-term parking of vehicles. Have accident and incident reporting form to record accidents and near-misses. Clear zones of land around the project site and other infrastructure should be created to prevent fires from spreading. These can be created by clearing vegetation or planting fire-resistant vegetation. There should be regular clearing of areas with dry vegetation to reduce the amount of flammable material available for a fire. Workers should designate areas for cooking and possible smoking to prevent fire from spreading in the likelihood of it happening.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Visual / Aesthetic Impacts	Local community	Moderate [4]	 Access to water and other fire suppression equipment should be ensured, and workers should be trained on effective fire suppression techniques. Local communities should be educated about the dangers of bushfires, the importance of safe disposal of debris, and the role of fire prevention in maintaining healthy ecosystem. Maintain tidy construction sites (good housekeeping).
		visual / Aestrietic impacts	(Tindantua) and commuters	iviouerate [4]	 Maintain tidy construction sites (good housekeeping). Minimize area of land clearance beyond essential footprint. Locate temporary facilities at unobtrusive areas to reduce visibility. Promptly rehabilitate disturbed areas post-construction. (grading, seeding). Ensure permanent structures (patios, sheds) use materials/colours that blend reasonably with the surroundings.
		Public health issues	Local communities near the project area of influence	Moderate [4]	 Potable water tanks or containers could be used on the project site to keep water for drinking. Sexual harassment or violence on the project site will not be tolerated and project contractor should be made aware of such incidences to ensure that any complaints are addressed in accordance with the law. Undertake sexual health education programs for workers and also ensure they desist from irresponsible sexual behaviour during project implementation. Encourage handwashing after work and if possible provide hand sanitizers to workers. Encourage workers to get vaccinated. Provide information, instructions and trainings on STDs, drug abuse etc. to the workers to create awareness. Provide female and male condoms to the community and workers.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Security Concerns	Local communities near the project area of influence	Minor [2]	 Sensitize local community on cultural tolerance and grievance mechanisms to prevent confrontations Migrant workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. The contractor should prioritize employing locals especially the youth who may be unemployed which can ultimately lead to unrest or other social vices.
Operation	on phase	Risk of Drowning	Project workforce and Local communities near the project area of influence.	Moderate [4]	 Dug out or borrowed pits should be fenced to prevent unsuspecting community members from falling and drowning in it. In situations where the burrowed pit will not be in use, it should be reclaimed. There will be pictorial signages mounted close to the pit to warn the community about the danger of drowning.
OS2	Occupational health and safety (OHS) impacts and risks	Workplace incidents/accidents	Farm workers, Vulnerable categories of workers, Women	Moderate [4]	 Good housekeeping around farm area must be ensured to prevent slips, trips & falls. Only trained and competent farm workers should be allowed to carry out work on the farm and must be well briefed on safe working procedures. Farm owners should ensure they and their farm workers are always in their PPE's when working on the farm. E.g. wellington boots etc. Potable water tanks or containers could be used on farms to keep water for drinking instead of using empty containers/gallons of fertilizers and agro-chemicals that can pose health risk to farmers. Develop and ensure implementation of Pest Management Plan (PMP)

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Poor labour working conditions	Farm workers, Vulnerable categories of workers, Women	Moderate [4]	 Safe, clean, and comfortable housing should be provided for migrant farm workers, either on-site or in nearby communities, with consideration for their needs and cultural sensitivities. Provide all farm workers with signed contracts that are consistent with national labour laws. Encourage frequent breaks and job-rotation to reduce the impact of the hot weather on farm workers. Establish an effective farm worker grievance redress mechanism. Fair wages, working conditions, and contracts that comply with labour laws should be implemented so that labourers can benefit from fair labour practices. Hiring of locals for labour, skills training for migrant workers, and support for local businesses to create broader economic opportunities should be prioritized.
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Women	Moderate [4]	 Educate farm workers on SH and GBV issues and make them sign code of conduct. Offenders will be reported to the local law enforcement agencies and if found guilty punished to serve as deterrent to potential offenders. No discrimination based on gender, marital status, nationality, age, religion, or sexual orientation will be tolerated toward employees or job applicants.
		Child Labour	Children	Moderate [4]	 Children who spend time with their parents on the farm should not be allowed to do so at the expense of their education and well-being. Children under the working age of 15 should not be engaged in hazardous work on the farms.
OS3	Resource Efficiency and Pollution	Soil erosion and degradation	Soil	Moderate [4]	Application of fertilizer will be controlled so that it does not lead to soil degradation.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
	Prevention and Management	Air Pollution	Health of farm workers and surrounding community members.	Minor [2]	 Education of farmers on proper application of fertilizer and pesticides to prevent abuse. Develop and ensure implementation of Pest Management Plan (PMP) After harvesting, crop residue comprising process residue (straw, husks, skins, trimmings, among others) and field residue (stalks and stubble/stems, leaves of crops) will be tilled into the soil to improve the soil structure and soil organic matter content. Farmers will be sensitised to adopt minimum tillage during planting seasons to reduce the susceptibility of the soil to erosion and hardpan formation associated with continuous ploughing at the same depth. Farmers will utilise cover crops at erosion-prone areas in sections. Practicing No-till or Low-till methods where crop residues are retained on the field or incorporated into the soil can help decompose the stubble naturally, reducing the need for stubble burning. Mobile, small-scale threshers can be used in place of manual threshing so as to reduce the amount of dust or rice chuff emitted into the atmosphere. Minimizing dust generation activities as much as possible especially during windy periods. Vehicle speed, particularly on untarred roads transporting farm produce and agric inputs to and from the farm will be strictly controlled to minimize dust generation.
		Water Pollution	Water quality of Daka river and other water which has gathered as ponds in the valley.	Moderate [4]	 There will be proper timing in the application of fertilizers/herbicides and other agrochemicals considering the crop's nutrient needs and soil conditions in order to maximize fertilizer uptake and minimize leaching and runoff.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
					 Develop and ensure implementation of Pest Management Plan (PMP) Provision of on-site sanitation facilities and encourage the farm workers to use it. Educate farm workers to avoid open defecation. Sediments traps will be designed and constructed within the farm lands to contain contaminated sediments which will later be harvested for producing blocks for building.
		Noise and Vibration	Health and wellbeing of workers and members of communities close to the project area	Moderate [4]	 Scare crows should be encouraged instead of the screaming sounds from farmers or labourers to scare away birds. The use of threshing machines with design specifications and operational adjustments that use soundproofing and vibration damping materials should be utilised during the harvesting periods in order to reduce noise and vibration to its barest minimum level. Ensure the use of well serviced/maintained vehicles and other equipment with acceptable noise emission levels when transporting farm produce and farmers from the farm. Provide silencers on all noise generating equipment.
		Solid waste generation and Disposal	Health of farm workers and the Local community.	Moderate [4]	 Rice husk has a high potential for the use as fuel. The project should take steps to identify potential investors that will process the husk to be used as fuel for boilers, in concrete production, or as a material for various industrial application. Farmers should be educated to use rice husk, straw, and other organic waste for composting which can eventually be used as fertilizer. There should be provision of adequate waste skips to collect empty containers of agrochemicals and fertilizers for disposal by licenced waste management company. Develop and ensure implementation of Pest Management Plan (PMP) Good housekeeping should be encouraged on farms.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
OS4	Community Health, Safety and Security	Traffic Management	Local communities	Minor [2]	 Drivers should exercise caution when driving through crowded areas such as markets. Installation of speed rumps to check speeding vehicles. Identify safe parking areas off main roads to allow for unloading and long-term parking of vehicles.
		Fire Outbreak	Rice farms, nearby vegetation, farm workers and local community.	Moderate [4]	 Clear zones of land around the rice fields and other infrastructure should be created to prevent fires from spreading. These can be created by clearing vegetation or planting fire-resistant vegetation. There should be regular clearing of areas with dry vegetation to reduce the amount of flammable material available for a fire. Farmers should designate areas for cooking and possibly smoking to prevent fire. Access to water and other fire suppression equipment should be ensured, and farmers should be trained on effective fire suppression techniques. The district fire service should train community members as fire guards to serve as the first point of contact when there is fire outbreak within the project area.
		Polluted Waterbodies	Farm workers and Local communities	Moderate [4]	 Educate farm workers to avoid open defecation. Sediments traps will be designed and constructed within the farm lands to contain contaminated sediments which will later be harvested for producing blocks for building. Potable water tanks or containers could be used on farms to keep water for drinking instead of using empty containers/gallons of fertilizers and agro-chemicals that can pose health risk to farmers.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures
		Sexual Transmitted Diseases	Farm workers and Local communities	Moderate [4]	 Sexual harassment or violence on farms will not be tolerated and community leaders should be made aware of such incidences to ensure that any complaints are addressed in accordance with the law. Undertake sexual health education programs for farm workers and also ensure they desist from irresponsible sexual behaviour during project implementation.
		Security Concerns	Farm workers and local communities	Minor [2]	 Sensitize local community on cultural tolerance and grievance mechanisms at community durbars to prevent confrontations Migrant farm workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. Farm owners should prioritize employing locals into their farms especially the youth who may be unemployed which can ultimately lead to unrest or other social vices.
		Risk of Drowning	Farmers and local community members	Moderate [4]	 The community has proposed that the rain water collected in the burrow pit may be used as their source of water for watering their crops in the dry season. However, dug out or burrowed pits should be fenced to prevent unsuspecting community members from falling and drowning in it. In situations where the burrowed pit will not be in use, it should be reclaimed. There will be pictorial signages mounted close to the pit to warn the community about the danger of drowning.
		Flooding	Farmers, Community members, Flora and Fauna	Major [6]	 Educate farmers and community on early warning signs of flood. Discourage the siting of farms within or close to river beds. Collaborate with spatial planning and disaster management agencies, using disaster maps and systems, to stay away from flood-prone areas. Infrastructure for agricultural establishments should be constructed preferably on high grounds.

AfDB OS#	AfDB OS	Risk/Potential Impact	Receptor(s)	Potential Impact Significance	Proposed Mitigation and Management Measures		
					•	Provide insurance cover for equipment and personnel	
Decom	nissioning Phase						
OS2	Labour conditions, health and safety	Project Site incidents/accidents	All Project workforce, Vulnerable categories of workers, Women	Major [6]	•	Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training.	
OS3	Resource Efficiency and Pollution Prevention and Management	Waste generation and Disposal	Health of project workforce and members of the Local communities within the project area	Moderate [4]	•	Ensure efficiency in the use of materials. Reuse materials such as pieces of wood, and metals. Recycle scrap metal Ensure collection and proper disposal of construction debris Provide adequate waste bins for waste collection and segregation Sensitize workers on waste management Develop SOPs for managing hazardous and non-hazardous waste. Develop and ensure implementation of Pest Management Plan (PMP)	
OS4	Community Health, Safety and Security	Traffic Management	Local communities near the project area of influence	Moderate [4]	•	Avoid transportation of materials and workers during peak hours Train drivers on and ensure adherence to the Highway Code Ensure regular maintenance of vehicles Use flagmen and designated parking areas for safety onsite.	

Table 8-2: Beneficial Impacts of the Project

No.	Beneficial Impact	Details of potential Project Impact
1	Creation of job opportunities	Job opportunities for skilled, semi-skilled and unskilled labour will be created at the construction and operation phases as locals, including women, will be recruited for short-term and long-term jobs.
2	Increased commerce and boost to local economy	Agricultural productivity will increase quantitatively due to increased access to mechanization services by rice farmers.
3	Food Security	Increase in production capacity coupled with availability of storage facilities will make produce available all year round and improve reliance on local agricultural produce and product. This will reduce the importation of agricultural produce across borders and improve food security.
4	Adoption of good agricultural practices	The proposed project will involve the community and the local stakeholders throughout the project cycle equipping them with knowledge and skills in agricultural practices.
5	Technology transfer	Farmers will be exposed to new technologies for geomapping, crop management, pest and disease management, processing, etc. that were otherwise not known to them

9.0 ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN

This section presents the Environmental and Social Management Plan (ESMP), **Table 9-1** that is designed to operationalize the environmental and social commitments presented in this ESIA report. The ESMP presents a set of management, mitigation and monitoring measures to be taken at different stages of the project implementation. It sets out record keeping required to ensure that mitigation measures and monitoring are effective and results duly communicated to stakeholders.

SAL Consult Limited

Ministry of Food and Agriculture, Ghana

Table 9-1: Environmental and Social Management Plan

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
OS1	Environmental and Social Assessment	Poor assessment of environmental and social risks and impacts	Unidentified risks and impacts could prevent or stall project implementation. Selection of unqualified persons for assessment studies	Project proponent (MoFA), environment, community	Major [9]	Detailed and high quality assessment of environmental and social risks Selection of qualified ESIA consultant Environmental permit acquisition	• PIU	358,000/33,966 35,000/3,321	Lender	Project E&S Instrument s (ESIA, RAP, SEP, PMP)	E&S Report Permit	Apr – Sep 2025 31 st Oct 2025
OS5	Involuntary resettlement, land acquisition, population displacement and compensation	Land related disputes	Proposed site is owned by the chief of Tindantua.	Farmers; Community	Moderate [4]	 Acquire signed Voluntary Land Donation (VLD) forms Provide training on completion of VLD forms 		2,000/190 2,500/237	Lender	Signed VLD	Signed VLD	Sep 2025
		Impact on livelihoods (economic displacement)	The project activities could restrict four (4) farmers access to lands that were otherwise used for farming.	s Farmers	Moderate [4]	 Develop a Resettlement Action Plan (RAP)/ Livelihood Restoration Plan Implement the Resettlement Action Plan (RAP) 		80,000/7,590 39,520/3,750	PIU/Lender Lender	RAP Report RAP Implement ation report	RAP Report RAP Implement ation audit	Sep 2025 Qtr 1, 2026
						Build PIU's capacity for RAP implementation	RAP Consultant	20,000/190	PIU/Lender	Training for RAP implement ation team	Training reports	Qtr 1, 2026
OS6	Biodiversity, renewable resources and ecosystem services	Removal of vegetation and displacement of wildlife	The project site is an already disturbed area due to previous human activities such as farming. The floristic analysis conducted indicates that none of the species identified at the site are of conservation concern according to the Forest Reserves of Ghana Information Exhibitor (FROGGIE) data base. Site clearing will not lead to any major destruction of biodiversity of significant importance, only a few trees and destruction of the habitats of some animals.	Flora and Fauna	Minor [2]	Restrict vegetation clearance to the required area only and prohibit hunting of animals which may stray to the project area by providing temporary fences. This must be included in the contractor's bill of quantities and code of Conduct. Train contractor's E&S Officer on ESMP requirements		20,000/1,900	PIU	Installation of Fence Training for E&S officer	Physical inspection Training reports	Before construction Before construction

SAL Consult Limited

Ministry of Food and Agriculture, Ghana

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
OS 2	Labour conditions, health and safety	Project Site incidents/accidents	Project site accidents/incidents and animal/insect threat/bites	All Project workforce, Vulnerable categories of workers, Women	Major [6]	•	Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training	Project Contractor	50,000/4,744	PIU	Records and purchase of PPEs, training on PPE use, house- keeping, emergency response etc.	Review of CESMP OHS audits	Before construction During construction
		Poor labour working conditions	Lack of employment contracts could lead to workers being paid rates below the stipulated national minimum wage or work under poor conditions. Workers could face issues of discrimination, forced labour, child labour, freedom of association and collective bargaining, lack of or ineffective worker grievance redress mechanisms	workforce, Vulnerable categories of workers, Women		•	Adhere to national labour laws as provided in the Labour Act of 2003 (Act 651) and international best practice such as provisions of AfDB ISS (2023) OS 2 on Labour and Working Conditions Specific considerations should include the following: Provide all workers with signed contracts Provide welfare facilities as required. Encourage frequent breaks and job-rotation to reduce impact of the hot weather on workers. Require workers to sign Code of Conduct Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. Provide adequate training for workers on safety, GBV, SEA/SH, child labour/human rights, social norms. Establish an effective worker grievance redress mechanism	Project Contractor	120,000/11,385		Signed contract, welfare facilities, Grievance redress mechanism / records	E&S audits	During construction
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Presence of workers and increase in incidents of rape, defilement, child molestation and GBV.		Major [6]	•	Include the requirements of policies on GBV, SEA/SH, Child Labour and Human Rights in the contractor's Code of Conduct Provide training for workers on required lawful conduct and legal consequences for failure to comply with laws on non-discrimination and GBV	Project Contractor	80,000/7,590	PIU	Clauses on GBV, SEA/SH, Child Labour and Human Rights in the contractor'	Review of contractor' s code of conduct	During construction

SAL Consult Limited

Ministry of Food and Agriculture, Ghana

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
						 Insert clause requiring contractors and consultants to cooperate with law enforcement agencies investigating cases of gender-based violence A minimum requirement of female employment should be indicated in contract documents Contact numbers of representative on the Grievance Redress Committee and GBV Service Providers should be pasted around the project site and within the immediate project zone Discuss issues of Gender Based Violence at daily Toolbox meetings Display on site posters prohibiting sexual exploitation and harassment. 				s Code of Conduct		
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and Contamination	Excavation for foundation of structures could lead to soil erosion and creation of gullies through runoff especially in the rainy season Soil contamination could also occur from inappropriate disposal of waste oil, spilled oil during machinery operation and maintenance as well as fuel storage sites and leaks	Soil	Moderate [4]	 Develop an Erosion Management Plan Implement the Erosion Management Plan Train contractor's E&S Officer on ESMP requirements 		50,000/4,744 100,000/9,488 20,000/1,898	PIU/Lender	Erosion Manage- ment Plan Sediment traps Training on erosion manageme nt	Inspection/ review Inspection Training records	Before construction During construction During construction
		Air Pollution	from vehicle refuelling Emission of fumes and dust from transport of materials especially on untarred routes to project site.	workers and members of the surrounding	Moderate [4]	 Trucks and heavy machinery with a valid emission test pass certificate should only be allowed on the project site. Dust pollution must be reduced by ensuring that drivers do not speed especially on untarred roads. Suppress dust by watering dusty construction areas. Ensure the use of nose mask in dusty environment. 	Project Contractor	60,000/5,693	PIU/ Supervising Engineer	Valid emission test certificate Speed limit signage Wet road surfaces Complaints /grievances	Inspection	During construction

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
		Water Pollution	Sediment and waste oil transport into nearby water bodies. Domestic waste from the construction workers and food vendors providing services to the construction crew.	and pools of water in the	Moderate [4]	 Undertake construction in the dry season Carry out maintenance activities away from water bodies Install sediment traps Educate workers on the importance of waste management. 	Project Contractor	60,000/5,693 10,000/949	PIU/ Supervising Engineer	Sediment traps Toolbox exercises	Inspection Inspection Toolbox records	During construction
		Noise and Vibration	Operation of construction equipment, movement of haulage vehicles and tooting of horns.	workforce and	Moderate [4]	 Ensure construction activities are carried out during the day. Provide and enforce wearing of hearing protection by workers Sensitize workers on effects of noise pollution Ensure the use of well serviced/maintained vehicles and other equipment with acceptable noise emission levels. 	Project Contractor	20,000/1,898	PIU/ Supervising Engineer	Noise emission levels Complaints /grievances	Noise monitoring report Records of complaints /grievances	During construction
		Waste generation and Disposal	Clearance of vegetation at project site, construction debris, pieces of steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog drains and facilitate the outbreak of sanitary related diseases such as cholera.	workforce and members of the Local communities within the	Moderate [4]	 Ensure that contractor develops and implements a detailed Construction Waste Management Plan. Ensure efficiency in the use of materials. Reuse materials such as pieces of wood, and metals. Recycle scrap metal Ensure collection and proper disposal of construction debris Provide adequate waste bins for waste collection and segregation Sensitize workers on waste management Develop SOPs for managing hazardous and non-hazardous waste. 	Project Contractor	100,000/9,488	PIU/ Supervising Engineer	Inventory of waste generated/ Disposed of	Inspection/ review of records/ inventory	During construction
OS4	Community Health, Safety and Security	Traffic Management	Transport of materials and equipment to and from the project site through communities and townships raises traffic/public safety concerns. Broken-down, inappropriately parked or slow-moving haulage/construction trucks could lead to road accidents and traffic congestion especially on busy roads.		Moderate [4]	 Avoid transportation of materials and workers during peak hours Train drivers on and ensure adherence to the Highway Code Ensure regular maintenance of vehicles Use flagmen and designated parking areas for safety onsite. 	Project Contractor	50,000/4,744	PIU/ Supervising Engineer	Records of traffic incident and accidents Community complaints /grievances	Review/ inspection of records	During construction

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
		Fire Outbreak	Fire outbreaks from negligence of workers or the community burning refuse, game hunting and workers not properly extinguishing stubs of cigarette. These fires could spread causing injuries to persons and destruction of property.	Local	Moderate [4]	 Create fire belts to prevent spread of fire into the active working areas. Sensitize workers and community on the dangers of bushfires Store flammable materials away from fire sources Designate cooking and smoking areas onsite. Provide fire-fighting equipment onsite. Train workers on fire fighting and where applicable include community fire volunteers 		50,000/4,744	PIU/ Supervising Engineer	Records of fire incidence Training in fire safety and risk	Review/ inspection of records	During construction
		Visual / Aesthetic Impacts	Presence of construction machinery, material stockpiles, temporary work camps; Vegetation clearance, earthworks (bare ground); Dust plumes.	commuters.	Moderate [4]	 Maintain tidy construction sites (good housekeeping). Minimize area of land clearance beyond essential footprint. Locate temporary facilities at unobtrusive areas to reduce visibility. Promptly rehabilitate disturbed areas post-construction. (grading, seeding). Ensure permanent structures (patios, sheds) use materials/colours that blend reasonably with the surroundings. 	• PIU	20,000/1,898	PIU Lender	Site tidiness. Area cleared. Community feedback (via GRM).	Site Inspections , Photograp hic records	During construction
		Public Health Issues	Pollution of local water bodies (River Daka) will adversely affect the health of users. Sexual relations between workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	Local communities near the project area of influence	Moderate [3]	 Potable water tanks or containers could be used on the project site to keep water for drinking. Sexual harassment or violence on the project site will not be tolerated and project contractor should be made aware of such incidences to ensure that any complaints are addressed in accordance with the law. Undertake sexual health education programs for workers and also ensure they desist from irresponsible sexual behaviour during project implementation. Encourage handwashing after work and if possible provide hand sanitizers to workers. 		60,000/5,693	PIU/ Supervising Engineer	Potable water tanks on site Records of sensitizatio n of workers on GBV/SH Availability of condoms in washrooms Availability of hand washing sinks/basin s and	Physical inspection Review of records Inspection	During construction

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
		Security Concerns	Violent behaviour and confrontations between workers and locals. Workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over illicit sexual affairs, child labour, drunk driving, accidents and destruction of property.	Local communities near the project area of influence	Minor [2]	 Encourage workers to get vaccinated. Provide information, instructions and trainings on STDs, drug abuse etc. to the workers to create awareness. Provide female and male condoms to the community and workers. Sensitize local community on cultural tolerance and grievance mechanisms to prevent confrontations Migrant workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. The contractor should prioritize employing locals especially the youth who may be unemployed which can ultimately lead to unrest or other social vices. 	Project Contractor	30,000/2,846	PIU	community meetings Toolbox exercises Number of locally employed workers	Inspection of community meeting minutes Review of toolbox records Inspection of records of locally employed workers	During construction
		Risk of Drowning	Any borrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for workers especially contract staff who are not familiar with the local terrain. Children who may play around the sites and unsuspecting community members may also be at risk of drowning especially when it rains and the place get flooded.	near the project	Moderate [4]	 Fence dug outs or borrow pits to prevent drowning. Provide warning signage at borrow pit sites. Sensitize community members on risk of drowning 	Project Contractor	100,000/9,488	PIU	Presence of fence and signage Records of drowning incidents/ accidents Records of community sensitizatio n programm es		During construction
	tion Stage							-		1		
OS2	Labour conditions, health and safety	Farm incidents/accidents	Farm accidents/incidents and animal/insect threat/bites		Moderate [4]	 Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and 	District MoFA/ Assembly	300,000/28,463	Regional MoFA	Records of training on PPE use, house- keeping, emergency	Review of ESMP OHS audits	During operation

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
						 investigation, emergency response and training Training and sensitization of farmers on the use of PPE, farm implements and agro-chemicals 				response etc.		
		Poor labour working conditions	Lack of employment contracts could lead to farm workers being paid rates below the stipulated national minimum wage or work under poor conditions. Farm workers could be exposed to discrimination, forced and child labour, restriction of freedom of association and collective bargaining, non-existent or ineffective farm worker grievance redress mechanism.	workforce, Vulnerable categories of	Moderate [4]	 Adhere to national labour laws as provided in the Labour Act of 2003 (Act 651) and international best practice such as provisions of AfDB ISS (2023) OS 2 on Labour and Working Conditions Specific considerations should include the following: Provide all workers with signed contracts Provide welfare facilities as required. Encourage frequent breaks and job-rotation to reduce impact of the hot weather on workers. Require workers to sign Code of Conduct Develop policies against discrimination, forced and child labour, sexual harassment and all forms of abuse including restriction of right to unionize or freedom of speech. Provide adequate training for farm workers on safety, GBV, SEA/SH, child labour/human rights, social norms. Establish an effective grievance redress mechanism for farm workers 	District MoFA / Department of Community Development	200,000/18,975	Regional MoFA	Number of labour related complaints and grievances	Review of the records	
		Sexual Harassment (SH) and Gender Based Violence (GBV)	Presence of migrant farm workers could increase incidents of rape, defilement and GBV.		Moderate [4]	 Provide sensitization and training for farm workers on required lawful conduct, access to GBV service providers and legal consequences for failure to comply with laws on non-discrimination and GBV Farm owners to be encouraged to employ females as farm workers. 	Development	100,000/9,488	Regional MoFA	recorded incidents of GBV/SH cases	records	operation
		Child Labour	Employment and deployment of Children under the working age at the expense of their education and exposure to hazards that endanger their health and wellbeing.	Children	Moderate [4]	 Prohibit the employment of children under age 15 on farms. Ensure children who spend time with their parents on the farm do not do so at the expense of their education and well-being. 	District MoFA/ Department of Community Development	50,000/4,744	Regional MoFA	Number of recorded incidents of child labour cases	Review of records	During operation

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
OS3	Resource Efficiency and Pollution Prevention and Management	Soil erosion and degradation	Abuse of fertilizer use could lead to soil degradation. Leaving farmlands bare especially after harvesting could expose the soil to erosion.	Soil	Moderate [4]	•	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management.	District MoFA	100,000/9,488	Regional MoFA	Training of farmers on soil, water and nutrient management	-	During operation
		Air Pollution	Use of farm machinery, clearing of dry lands and emission of fumes/dust from tricycles or motorcycles conveying farmers and farm produce especially on untarred routes from farms are some of the activities that have the potential of affecting the air quality within the project area. Stubble burning to prepare the field for the next planting season can also affect the air quality within the project area. Baseline air quality data (PM _{2.5} – 10μg/m³, PM ₁₀ – 16μg/m³, NO ₂ – 0.2μg/m³, SO ₂ – 0.1μg/m3) shows that the project area's airshed is not degraded as all parameters are within the emissions thresholds. Hence, emissions from farming activities such as tilling, threshing and transportation of farm produce are not expected to result in significant air quality deterioration.	community members.	Moderate [4]	•	untarred roads transporting farm produce and agric inputs to and from the farm will be strictly controlled to minimize dust generation.	District MoFA	100,000/9,488	Regional	Training of farmers on good farming practices	of training records	
		Water Pollution	Sediment laden with excess fertilizers and other agrochemicals and waste oil transport into nearby water bodies. Pollution of watercourses caused by wastes generated by farm workers as well as runoff from land used for growing rice (containing fertilisers, pesticides and herbicides etc.).	water quality and other water which has gathered as ponds in the	Moderate [4]	•	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management. There will be proper timing in the application of fertilizers/herbicides and other agrochemicals considering the crop's nutrient needs and soil conditions in order to maximize fertilizer uptake and minimize leaching and runoff. Implement Pest Management Plan (PMP)	District MoFA	300,000/28,463	Regional MoFA	Training of farmers on good farming practices	Inspection	During operation

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
						 Provision of on-site sanitation facilities and encourage the farm workers to use it. Educate farm workers to avoid open defecation. Sediments traps will be designed and constructed within the farm lands to contain contaminated sediments which will later be harvested for producing blocks for building. 						
		Noise and Vibration	the rice after cultivating and screaming sounds from farmers or labourers to scare away birds can all generate noise. Tricycles and motorbikes conveying farmers and farm produce to the milling factories or markets could generate some noise including the sounds from tooting horns.	wellbeing of farm workers and members of communities close to the project area		 Scare crows should be encouraged instead of the screaming sounds from farmers or labourers to scare away birds. Use threshing machines with soundproofing devices 	District MoFA	50,000/4,744	Regional MoFA	Sensitizatio n of farmers	MoFA participatio n in community engagemen t meetings	Throughout the operational phase
		Solid waste generation and disposal	Improper disposal of waste, i.e. empty containers of agrochemicals and fertilizers which can serve as breeding grounds for mosquitoes. Threshing will produce rice husk that may pile up to form heaps of waste.	Health of farm workers and the Local community.	Moderate [4]	 Provide education to farmers on the MoFA extension guide on compost production using rice husk, straw, and other organic waste. Provide adequate waste skips to collect empty containers of agrochemicals and fertilizers for disposal by a licenced waste management company. Good housekeeping should be encouraged on farms. Implement Pest Management Plan (PMP) 	District MoFA	75,000/7,116	Regional MoFA	Sensitizatio n of farmers	MoFA participatio n in community engagemen t meetings	Throughout the operational phase
OS4	Community Health Safety and Security	Fire Outbreak	Fire outbreaks from negligence of farm workers and community members, burning refuse, game hunting, cooking and not properly extinguishing stubs of cigarette. These fires could spread to adjoining farms causing injuries to persons and destruction of property.	nearby vegetation, farm workers and	Moderate [4]	 Create fire belts to prevent spread of fire into the active working areas. Sensitize farm workers and community on the dangers of bushfires Store flammable materials away from fire sources Designate cooking and smoking areas on farms. Provide fire-fighting equipment onsite 		100,000/9,488	Regional MoFA	Sensitizatio n of farmers	-	the operational

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
						•	Train farm workers on fire fighting and where applicable include community fire volunteers						
		Traffic Management	Transportation of farmers and farm produce through communities raises traffic/public safety concerns.	Local communities	Minor [2]	•	Drivers should exercise caution when driving through crowded areas such as markets. Installation of speed rumps to check speeding vehicles. Identify safe parking areas off main roads to allow for unloading and long-term parking of vehicles.	MoFA/Assembly	50,000/4,744	PIU/Supervisi ng Engineer	Records of traffic incident and accidents Community complaints /grievances	MoFA and Assembly participatio n in community engagemen t meetings	Throughout the operational phase
		Security Concern	Violent behaviour and confrontations between migrant farm workers and locals. Farm workers who are deemed to be financially sound could be victims of theft and burglary Potential conflict over sexual affairs, child labour, drunk driving, accidents and destruction of property.	Farm workers and Local communities	Minor [2]	•	Sensitize local community on cultural tolerance and grievance mechanisms at community durbars to prevent confrontations Migrant farm workers should be made aware of the community's cultural and traditional values/beliefs so they may not go against them. Farm owners should prioritize employing locals into their farms especially the youth who may be unemployed which can ultimately lead to unrest or other social vices.	MoFA/Assembly	30,000/2,846	PIU/Supervisi ng Engineer	Records of traffic incident and accidents Community complaints /grievances	MoFA and Assembly participatio n in community engagemen t meetings	Throughout the operational phase
		Polluted Waterbodies	Pollution of local water bodies from contaminated sediments and run-off will adversely affect the health of community members.		Moderate [4]	•	Provide education to farmers on the MoFA extension guide on soil, water and nutrient management. Educate farm workers to avoid open defecation.	District MoFA	50,000/4,744	Regional MoFA	Sensitizatio n of farmers	participatio n in community engagemen t meetings	operational phase
		Sexual Transmitted Diseases	Sexual relations between migrant farm workers and locals may bring about increase in sexually transmitted diseases including HIV/AIDs.	and Local	Moderate [4]	•	Undertake sexual health education programs for farm workers to desist from irresponsible sexual behaviour.	District Health	50,000/4,744	Regional MoFA	Sensitizatio n of farmers	n in	-

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance	Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
		Flooding	The project implementation could be adversely affected by events of flood from torrential rainfall in the wet season especially in low-lying areas affecting properties and lives.	Farmers, Local community, Flora and Fauna	Major [6]	 Educate farmers and community on early warning signs of flood. Discourage the siting of farms within or close to river beds. Collaborate with spatial planning and disaster management agencies, using disaster maps and systems, to stay away from flood-prone areas. Infrastructure for agricultural establishments should be constructed preferably on high grounds. Sensitive farmers on the benefits of insurance cover for equipment and personnel. 	MoFA/Assembly/NA DMO	150,000/14,231	Regional MoFA	Sensitizatio n of farmers	Participation in community engagement by MoFA, the Assembly and NADMO.	Throughout the operational phase
		Risk of Drowning	Any burrow or dug-out pits created as a result of excavation of construction materials can accumulate water when it rains. This can pose the risk of drowning for communities in the project area especially children.		Moderate [4]	 Maintenance of dug outs or borrow pits fence to prevent drowning. Provide and replace warning signage at borrow pit sites when necessary. Sensitize community members on risk of drowning 		50,000/4,744	Regional MoFA	Sensitizatio n of community members/f armers	Participatio n in community engagemen t by MoFA.	Throughout the operational phase
Decor	nmissioning Phase											
OS2	Occupational health and safety (OHS) impacts and risks	Project Site incidents/accidents	Project site accidents/incidents and animal/insect threat/bites	workforce, Vulnerable categories of workers, Women		Develop and implement an Occupational, Health and Safety Management Plan that covers at a minimum good housekeeping, provision and use of PPE, incident/accident reporting and investigation, emergency response and training		50,000/4,744	PIU	Records and purchase of PPEs, training on PPE use, housekeepi ng, emergency response etc.		after construction
OS3	Resource Efficiency and Pollution Prevention and Management	Waste generation and Disposal	Clearance of vegetation at project site, construction debris, pieces of steel/metal, packaging materials, plastic pieces, human waste etc. if not disposed properly could clog drains and facilitate the outbreak of sanitary related diseases such as cholera.	workforce and members of the Local communities within the project area		 Ensure efficiency in the use of materials. Reuse materials such as pieces of wood, and metals. Recycle scrap metal Ensure collection and proper disposal of construction debris Provide adequate waste bins for waste collection and segregation Sensitize workers on waste management 		120,000/11,385	PIU	Inventory of waste generated/ Disposed of	records/	Immediately after construction

AfDB No.	AfDB OS Description	Potential Impact/ Issue	Impact description	Receptor(s)	Significance		Proposed Mitigation and Management Measures	Responsibility (implementation/ supervision)	Estimated Cost (GHS/USD)	Monitoring responsibility	Verifiable Monitoring Indicator	Means of Verificatio n	Timetable for Implementat ion
OS4	Community Health and	Traffic	Transport of materials and	Local	Moderate [4]	•	Develop SOPs for managing hazardous and non-hazardous waste. Develop and ensure implementation of Pest Management Plan (PMP)	Project Contractor	50,000/4,744	PIU	Records of	Review/	Immediately
034	Safety	Management	equipment to and from the		Moderate [4]	•	Avoid transportation of materials and workers during peak hours Train drivers on and ensure adherence to the Highway Code Ensure regular maintenance of vehicles Use flagmen and designated parking areas for safety onsite.	Project Contractor	30,000/4,744	PIU	traffic incident and accidents Community complaints /grievances	inspection of records	after construction

9.1 ESMP Implementation

9.1.1 Institutional Arrangement and Responsibilities

The institutional arrangement identifies the relevant institutions and actors involved with the implementation of the ESMP, their roles and responsibilities. The main institutions or actors concerned with the implementation of the Project and the ESMP related activities are provided in **Table 9-2**. The ESMP implementation activities will be under the overall guidance of the PIU.

 Table 9-2:
 Roles and Responsibilities of Key Actors

Key Actors /	Description of Key Roles/Responsibilities	Duration	Reporting
Institutions			
PIU	 Responsible for project implementation in general. Have the overall responsibility to ensure that the project implements the construction phase management and monitoring requirements provided in the ESMP. Responsible for grievance redress procedure and its functioning and effectiveness of other litigation avoidance measures. Oversee sensitization and awareness programmes. Grievance Redress 	Throughout project implementation	Monthly
Ministry of	Project planning and design	Preparatory and	Quarterly
Food and	Payment of compensations to PAPs, if any	construction	
Agriculture	Management of contract award	phases	
	Compliance monitoring		
	Grievance redress		
EPA	Issuing of environmental permit upon review	Throughout	Annually
	and approval of ESIA	project	
	 Adhoc monitoring of the sub project to ensure compliance with conditions of the 	implementation	
	compliance with conditions of the Environmental Permit.		
Mion	Adhoc monitoring of project during the	Throughout	Annually
District	construction phase	project	
Assembly	 Monitoring facilities during the operational 	implementation	
	phase of the project to		
	ensure that it is working properly and help		
	resolve operational phase challenges		
	Grievance Redress		

Key Actors /	Description of Key Roles/Responsibilities	Duration	Reporting
Project Consultant and Safeguards Specialist	 Ensure that project execution meets specified environmental, social, health and safety guidelines contained in the contract documents and ESMP Issue site instructions to Contractors to ensure environmental and social mitigation measures are implemented by contractors Grievance Redress 	Duration of the Preparatory and Construction phases	As required
Works Contractors /Sub Contractors	 Contractors for the civil works will be responsible for construction and installations under the project according to project specifications and designs. Contractors are responsible for reinstatement of all damaged properties. Contractors are responsible for implementation of the construction phase mitigation measures provided in the ESMP Responsible for presentation of monthly monitoring report to the PIU Responsible for remedying defects committed during construction 	Construction phase	Monthly
Grievance Redress Committee	To receive and find solutions to grievances	Preparatory and construction phases	Monthly

9.2 Monitoring and Reporting

At the project implementation stage, monitoring will be done to confirm the effectiveness of impact management, including the degree of success in implementing mitigation measures. During construction works, checks, reviews and inspections will be carried out to assess compliance with permit conditions. Monitoring will be done by the relevant institutions, the PIU, Agric Department, EPA, Mion District Assembly, Fire Service etc. A summary of impacts, mitigation, management and monitoring measures to be implemented is captured in **Table 9-3**.

E&S Monthly monitoring reports will be prepared by the works contractor and submitted to the PIU, EPA and Assembly. The E&S monthly monitoring reports will serve as the basis for EPA's compliance monitoring in line with the permit conditions, and verification of other environmental and social safeguard commitments.

A construction completion report, which is a compilation of outcomes of the monitoring activities, in compliance with EPA's permit conditions and for the records of the District Assembly, will be prepared. The completion report will form the basis for EPA's final monitoring for project completion and

closure. Also, PIU will prepare E&S monthly monitoring reports and share with the lenders to show the extent of compliance with E&S requirements of the EPA and the Bank for the construction period.

9.3 Annual E&S Compliance Audits of the Project and Cost

The Annual Environmental and Social Performance Audit (ESPA) meets AfDB's OSS requirements. The project having a duration of 5 years, 5 audits will be carried out, including one audit per year. These audits will be carried out by an independent consultant who has not carried out any activity under the project. The terms of reference of the Audit as well as each audit report will be submitted to AfDB for review and approval. The PIU will recruit an independent consultant who will be responsible for carrying out annual environmental and social compliance audits of the sub-project.

It should be noted that the annual audit will concern the entire project, therefore the cost as shown below will cover the consideration of the entire project. Also, the cost of an annual audit for both ESIA and RAP is shown in the table below.

Cost of implementing environmental and social compliance audits

	Duration	Materials required for monitoring	No. of audits	Estimated cost of an annual audit (USD)	Total amount (USD)
ESPA	Once a year	Field vehicle	5	10,000	50,000
RAP Completion Audit	Once	Field vehicle	1	7,000	7,000
TOTAL (for 5	years)				57,000

Table 9-3: Environmental and Social Monitoring Plan

No.	Potential Environmental and Social Impacts STRUCTION PHASE	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year (GHS/USD)
1	Project site accidents/incidents	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Tindantua valley	Monthly	PIU Environmental and Social Safeguards Specialists	52,700/5,000
2	Poor labour working conditions	 Availability of copies of signed contracts Human Resource Management Plan/Recruitment Policy Complaints lodged by workers 	Tindantua valley construction site	Quarterly	PIU Environmental and Social Safeguards Specialists	31,620/3,000
3	Soil impacts and sediment transport	 Observable change in turbidity of water in drains or water bodies Observable oil sheen in drain Observation of rills/gullies 	Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental Safeguards Specialist	42,160/4,000
4	Air and Noise Pollution	Number of complaints by community members/workers	Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental Safeguards Specialist	52,700/5,000
5	Waste generation and inefficient management	 Number of mobile toilets and dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site Complaints by workers/community members 	Tindantua valley construction site and Immediate environs	Weekly	PIU Environmental Safeguards Specialist	26,245/2,490

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year (GHS/USD)
6	Traffic accident risks/Public safety concerns	 Grievance records Traffic related incidents/accidents Records of accidents, incidents and near misses. 	Tindantua valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700/5,000
7	Fire outbreaks	 Fire related incidents/accidents Records of fire incidents and near misses. Number of functional fire extinguishers onsite 	Tindantua valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700/5,000
8	Visual / Aesthetic Impacts	Site tidiness.Area cleared.Community feedback (via GRM).	Tindantua valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	5,375 (510)
9	Public health issues	 Number of sensitization campaigns Number of condoms distributed to Contractor's staff in a month Number of STD cases reported to local health facilities involving encounters with Contractor's staff 	Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	47,430/4,500
10	Security and SH/GBV concerns	 Number of conflicts/cases reported to the Grievance Redress Committee/Community Liaison Officer Number of conflicts/cases dealt with by the Grievance Redress Committee 	Tindantua valley construction site and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	36,890/3,500

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year (GHS/USD)
		Number of crimes such as theft, defilement and rape reported, investigated, and concluded by the police involving the Contractor's workers				
Sub T	otal					400,520/38,000
OPER	ATIONAL PHASE					l
1	Farm accidents/incidents	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Tindantua valley Farm	Monthly	District MoFA Extension officers/ Regional MoFA	31,620/3,000
2	Poor labour working conditions	 Availability of copies of signed contracts Complaints lodged by farm hands and other workers 	Tindantua valley Farm	Monthly	District MoFA Extension officers/ Regional MoFA	42,160/4000
3	Soil impacts and sediment transport	 Observable change in turbidity of water in Daka river Observable oil sheen in Daka river Observation of rills/gullies 	Tindantua valley Farm and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	52,700/5,000
4	Air and Noise Pollution	Number of complaints by community members/farmhands	Tindantua valley Farm and community	Monthly	District MoFA Extension officers/ Regional MoFA	31,620/3,000

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year (GHS/USD)
5	Waste generation and inefficient management	 Presence of toilet facilities and number dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site Complaints by farm workers/community members 	Tindantua valley Farm and immediate environs	Weekly	District MoFA Extension officers/ Regional MoFA	52,700/5,000
6	Traffic accident risks/Community safety concerns	 Grievance records Traffic related incidents/accidents Records of all accidents, incidents and near misses. 	Tindantua valley Farm/ community and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	52,700/5,000
7	Fire outbreaks	 Fire related incidents/accidents Records of fire incidents and near misses. Number of functional fire extinguishers onsite 	Tindantua valley Farm and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	31,620/3,000
8	Community health issues	 Number of sensitization campaigns Number of condoms distributed to farm workers or placed at convenient places in a month Prevalence of STD cases reported to local health facilities 	Tindantua valley Farm/ Tindantua community and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	47,430/4,500
9	Security and SH/GBV concerns	Number of conflicts/cases reported to the Grievance Redress Committee/Community Liaison Officer	Tindantua valley Farm/ Tindantua community and immediate environs	Monthly	District MoFA Extension officers/ Regional MoFA	36,890/3,500

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year (GHS/USD)
		 Number of conflicts/cases dealt with by the Grievance Redress Committee Number of crimes such as theft, defilement and rape reported, investigated, and concluded by the police involving workers or patrons 				
10	Risk of Drowning	Number of drowning cases reported and investigated involving unsuspecting community members and animals.	 Dugout (from the previous sand winning site now used as water source) 	Weekly	District MoFA Extension Officers, District Assembly/ Regional MoFA	31,620/3,000
Sub-t	otal					411,060/39,000
DECC	OMMISSIONING PHASE					
1	Project site accidents/incidents	 Records of accidents, incidents and near misses. Records of PPE disbursed Housekeeping 	Tindantua valley	Monthly	PIU Environmental and Social Safeguards Specialists	52,700/5,000
2	Waste generation and inefficient management	 Number of mobile toilets and dustbins provided on site Cleanliness of site/housekeeping Odour Presence of human waste on site Complaints by workers/community members 	Tindantua valley construction site and Immediate environs	Weekly	PIU Environmental Safeguards Specialist	31,620/3,000

No.	Potential Environmental and Social Impacts	Monitoring Indicators/Means of verification	Monitoring Site	Frequency	Responsibility (Implementation/ Monitoring)	Cost Estimate/ Year (GHS/USD)
3	Traffic accident risks/Public safety concerns	 Grievance records Traffic related incidents/accidents Records of accidents, incidents and near misses. 	Tindantua valley and Immediate environs	Monthly	PIU Environmental and Social Safeguards Specialists	52,700/5,000
Sub-total Sub-total						137,020/13,000
TOTAL COST FOR MONITORING						948,600/90,000

9.4 Needs assessment of the implementing institutions

The ESMP outlines mitigation measures, monitoring indicators, and stakeholder engagement protocols to manage potential impacts on land, water, biodiversity, and local communities. MoFA and its extension officers are the project implementers to operationalize the ESMP, given their role in agricultural oversight. This assessment evaluates their readiness and identifies support mechanisms required for successful implementation.

The assessment was conducted through:

- Review of MoFA's operational structure and extension services in the Mion District;
- Consultations with district-level officers and relevant stakeholders;
- Analysis of ESMP requirements and alignment with MoFA's existing mandates; and
- Identification of capacity gaps and resource constraints

9.4.1 Key Institutions

The main institutions to be involved with the implementation of the environmental and social management and monitoring plans include:

- Ministry of Food and Agriculture (MoFA);
- Project Implementation Unit (PIU);
- Environmental Protection Authority (EPA);
- Mion District Assembly;
- CSIR-Water Research Institute;
- CSIR-Soil Research Institute;
- Ghana National Fire Service (GNFS); and
- National Disaster Management Organization (NADMO).

9.4.2 Institutional Roles, Capacity Gaps and Recommendation

The capacity assessment presented in **Table 9-4** provides a holistic picture of institutional roles, their existing capacities, the gaps that may hinder performance, and actionable recommendations to close these gaps.

Table 9-4: Institutional Roles, Capacity Gaps and Recommendations

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
MoFA (District &	Lead	Regional/district	Weak safeguards	Provide intensive
Regional)	implementer;	offices have limited	integration at	training on safeguards
	coordination,	environmental and	local level; and	compliance;
	extension,	social safeguards	limited tools for	Supply digital data
	safeguards	knowledge.	monitoring	collection tools;
	compliance	However, national		Integrate ESMP
		divisional office has		indicators into MoFA
		stronger capacity		M&E systems

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
Project Implementation Unit (PIU)	Safeguards oversight and project management	Adequately staffed with environmental and social safeguards officers	Limited operational linkages with district institutions	Strengthen coordination platforms with MoFA, EPA, and District Assembly; and formalize reporting schedules
EPA (Regional Office)	Regulatory oversight; and participation in joint inspections	Strong technical expertise, but logistics constrained (e.g., transport, field equipment)	Inability to conduct regular field inspections due to lack of resources	Engage EPA to improve support at regional level such as vehicles, field logistics, and budget for regular compliance monitoring
Mion District Assembly	Local governance; grievance redress; community mobilization	Some competence in grievance handling, but limited awareness of safeguards	Weak capacity in grievance redress aligned with ESMP	Provide structured training on grievance mechanisms and safeguards at district/regional levels
CSIR – Water Research Institute	Technical monitoring of water quality	Adequate technical competence and facilities	Underutilized in field implementation	Formalize role in ESMP monitoring with budget and datasharing mandate
CSIR – Soil Research Institute	Technical monitoring of soil quality	Adequate technical competence and facilities	Underutilized in project-specific monitoring	Formalize role in ESMP monitoring with budget and datasharing mandate
GNFS (Regional/District)	Fire education, prevention, and response	Strong institutional mandate, but inadequate fire hydrants, tenders, and trained personnel	Limited firefighting equipment; inadequate training capacity	Engage GNFS to improve fire-fighting equipment resources at the district level; build capacity on prevention and community training methods
NADMO (District Office)	Disaster risk education, preparedness, and response	Active but under- resourced with limited staff and logistics	Staffing and logistical deficits constrain rapid response	Engage district NADMO to recruit additional staff; provide disaster response logistics (vehicles, equipment); and build staff capacity

Institution	Role in ESMP	Capacity	Capacity Gaps	Recommendations
	Implementation	Assessment		
NGOs/CSOs	Community	Active presence but	Weak technical	Provide training in
	engagement and	limited technical	understanding of	safeguards,
	sensitization	expertise on	ESMP safeguards	participatory
		safeguards		monitoring, and
				technical engagement

MoFA should establish formal coordination mechanisms, including joint monitoring schedules and shared reporting platforms to enhance accountability and synergy across agencies.

9.4.3 Capacity Building Approach and Training Needs

Project institutions must fully understand the ESMP objectives, their statutory roles, and how safeguards compliance strengthens outcomes. Current institutional competence varies, with strengths in technical monitoring (e.g. CSIR, PIU) but weaknesses in safeguards integration, resource availability, and disaster/fire response systems (see **Table 9-4**).

The first step in pursuing capacity building has been to identify the specific capacity building needs of the various stakeholders. Capacity building should be viewed as more than training. It is human resource development and includes the process of equipping individuals with the understanding, skills and access to information, knowledge and training that enables them to perform effectively. It also involves organizational development, the elaboration of relevant management structures, processes and procedures, not only within organizations but also the management of relationships between the different organizations and sectors (public, private and community).

The capacity building will mostly be in the form of training workshops. A training workshop on the E&S Safeguards should be organized for the MoFA district and regional officers and the district assembly and should cover the following.

- Inclusion of environmental mitigation measures and penalties in contract documents of contractor and contractor supervision;
- Environmental screening and monitoring;
- Public/community participation techniques and procedures; and
- Grievance redress mechanism.

For each group, training will be provided at different level of expertise in different areas, and would include:

- In-depth training to a level that allows trainees to go on to train others, including environmental and social procedures where relevant; and
- Sensitization or awareness-raising in which the participants are familiarized with the significance
 or relevance of the issues, to the extent that they can identify potential or emergent problems
 and request further assistance as necessary.

9.4.4 Environmental and Social Monitoring Approaches

Environmental Monitoring

Indicator	Current Status	Gap	Recommendation
Soil and water quality tracking	Ad hoc, project- specific	Lack of standardized tools and training	Provide portable testing kits and training on sampling protocols OR Engage the CSIR to carry out the monitoring
Agrochemical use monitoring	Basic advisory role	No formal tracking or reporting	Integrate pesticide use logs into extension visits

Social Safeguards

Indicator	Current Status	Gap	Recommendation
Community engagement	Informal, reactive	No structured grievance or feedback system	Develop community liaison protocols and feedback channels
Gender and vulnerability inclusion	Limited	No disaggregated data or targeted support	Train officers on inclusive engagement and social impact monitoring

9.4.5 Technical and Operational Capacity

Training and Capacity Building

- Environmental Modules: Soil conservation, water management, biodiversity protection
- Social Modules: Stakeholder engagement, grievance redress, labor monitoring
- Technical Skills: GIS mapping, mobile data collection (e.g., KoboToolbox), ESMP reporting formats

Tools and Resources

- Field tablets or smartphones for data capture
- Budget allocation for transport, field visits, and community meetings
- Access to baseline environmental and socio-economic data

9.4.6 Coordination and Accountability

To ensure accountability and adaptive management:

- Develop ESMP indicators aligned with MoFA's monitoring and evaluation (M&E) systems
- Schedule quarterly monitoring visits and biannual inter-agency review meetings
- Establish feedback loops with community representatives for transparency
- Integrate ESMP findings into MoFA's agricultural extension dashboard for mainstreaming into daily operations

Recommendations

MoFA and its extension officers play a pivotal role in safeguarding environmental and social outcomes of the proposed project. To fulfil this role effectively, the following actions are recommended:

• Capacity Building: Deliver targeted training on ESMP components;

- Resource Provision: Equip officers with monitoring tools and digital devices;
- Institutional Coordination: Formalize partnerships with EPA, NADMO, GNFS and local authorities;
- Community Engagement: Establish inclusive and responsive communication channels; and
- Monitoring Systems: Integrate ESMP indicators into MoFA's routine operations.

9.5 Estimated budget to Implement ESMP

The project will require a total of Ghc4,731,480 (US\$448,688) to implement the ESMP as outlined in the table below:

Table 9-5: Estimated Budget to implement ESMP

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
		Cost (USD)	Cost (GHS)
Preconstruction	- E & S assessment and permit acquisition.	37,287	393,000
(Preparatory) Phase	- Training and completion of VLD forms.	427	4,500
	- RAP/LRP Implementation and capacity building for PIU.	13,237	139,520
	Fencing of site to restrict vegetation clearanceTraining of E&S officers on ESMP.	2,841	30,000
- Sub Total		53,792	567,020
Construction Phase	 Development and implementation of an Occupational, Health and safety management plan. 	4,735	50,000
	- Labour force management and training on safety, discrimination, GBV, SEA/SH, child labour/human rights and ethical conduct.	18,939	200,000
	- Erosion management and ESMP training for contractor's E&S team	16,098	170,000
	- Air quality deterioration abatement measures and PPE provision	5,682	60,000
	- Water pollution abatement measures	6,629	70,000
	- Noise abatement measures implementation and PPE provision	1,894	20,000
	- Waste management including hazardous and non-hazardous waste	11,364	120,000
	- Traffic management and road safety training for drivers	4,735	50,000
	 Implementation of fire prevention/fighting measures and training for workers and community 	4,735	50,000
	 Management of grievances including GBV, SEA/SH, child labour/human rights 	5,682	60,000
	- Sensitization of workers and community on cultural tolerance and conflict management	2,841	30,000
	- Management and community sensitization on drowning risks	9,470	100,000
Sub-Total		92,804	980,000
Operation Phase	- Development and implementation of occupational health and safety plan/measures	28,463	300,000

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
		Cost (USD)	Cost (GHS)
	- Sensitization on good labour practices, rights and ethical conduct.	18,975	200,000
	- GBV sensitization for farm owners/workers	9,569	100,000
	- Child labour sensitization for farm owners	4,744	50,000
	- Education on soil, water and nutrient management for farmers.	9,488	100,000
	- Education of farmers on air quality deterioration abatement measures	9,488	100,000
	 Education on soil, water, and nutrient management, waste management, pollution prevention and PMP Implementation 	28,463	300,000
	- Sensitization of farmers on noise abatement measures	4,744	50,000
	 Waste management including provision of skips, collection/disposal and education on composting 	7,116	75,000
	 Fire risk management and sensitization of farmers on fire-fighting techniques. 	9,488	100,000
	- Education of farmers on soil, water and nutrient management.	4,744	50,000
	- Sexual health education programs for farm workers to promote public health	4,744	50,000
	- Flood risk assessment and management	14,231	150,000
	- Sensitization of workers and community on cultural tolerance, and conflict management	2,841	30,000
	- Traffic management and road safety training for drivers	4,744	50,000
	- Management and community sensitization on drowning risks	4,744	50,000
Sub Total		166,508	1,755,000
Decommissioning	- Development and implementation of an Occupational, Health and safety plan.	4,735	50,000
Phase	- Waste management including hazardous and non-hazardous waste	11,364	120,000
	- Traffic management and road safety training for drivers	4,735	50,000
Sub Total		20,834	220,000
Grievance Redress		79,000	832,660
Mechanism (GRM)		2.752	20.522
Resettlement		3,750	39,520
Action Plan			
Implementation Environmental &		35.000	363.533
Social Performance Audit		25,000	263,500
RAP Completion		7,000	73,780
Audit			
Sub Total		114,750	1,209,460

Project Stage	Project Activities	Estimated ESMP	Estimated ESMP
		Cost (USD)	Cost (GHS)
Total		448,688	4,731,480

10.0 DECOMMISSIONING

A Decommissioning and Site Closure Plan (DCP) is required to guard against the remote possibility of abandoning temporary constructed structures. Should such a circumstance arise, the potential would exist for impacts from abandonment of the facility such as aesthetic impacts and potential trespassing and safety concerns. This DCP is being posted to provide a guide on details of the decommissioning activities. The purpose of this conceptual DCP is to describe the general objectives for the post project land use, and the planning processes leading to development of a final DCP.

The specific objectives in managing the decommissioning process will be:

- To ensure that rehabilitation and decommissioning are carried out in a planned sequential manner, consistent with best practice;
- To ensure that agreed post-project land-use outcomes are achieved; and
- To avoid on-going liability.

A Full Decommissioning Report is expected to be prepared in the event of any such activity for approval by the EPA and any other requisite state agencies.

10.1 Pre-Decommissioning Assessment

Prior to any decommissioning, the EPA will be notified and an assessment will be carried out to identify any potential environmental impacts that need to be addressed and mitigated in the decommissioning process.

10.2 Decommissioning Phase Activities

Some of the activities that will be undertaken during the decommissioning phase will mostly be the dismantling and removal of structures and equipment.

10.2.1 Dismantling and Removal of Structures and Equipment

During decommissioning activities, the respective Planning Department and the EPA office shall have access to the site, pursuant to reasonable notice, to inspect the results of complete decommissioning.

The removal of installations, structures, and equipment would include a complete inventory of all hardware and capturing of their final operational status. Disposal of the hardware and documentation would be planned, including any environmental concerns that may dictate disposal method.

All decommissioning and restoration activities will be in accordance with all applicable state and local permits and requirements and will include the following specific activities:

Hardware retirement: All power sources would be disconnected from structures and equipment
before dismantling commences. Cranes and/or other machinery will be used for the disassembly
and removal of structures and associated installations. These will either be transported whole for
reconditioning and reuse or dissembled into salvageable, recyclable, or disposable components;

- Foundation removal: All foundation materials will be removed as per EPA guidelines or requirements. The remaining excavation will be filled with clean sub-grade material, compacted to a density similar to surrounding sub-grade material, and finished with topsoil;
- Monitoring: A monitoring and remediation period of two years immediately following the completion of any decommissioning and restoration activities will be undertaken. If agricultural impacts are identified during this period, follow-up restoration efforts will be implemented; and
- Area restoration: Areas where subsurface components are removed will be graded to match
 adjacent contours, stabilized with an appropriate seed mix, and allowed to re-vegetate naturally.
 All town roads, impacted by Project decommissioning activity, if any, will be restored to original
 condition upon completion of decommissioning.

10.2.2 Solid Waste Management

All solid waste resulting from the decommissioning process will be evacuated by handlers commissioned by the District Solid Waste Department.

10.3 Post-Decommissioning Assessment

Removal of machinery, equipment and all other materials related to the project will be completed within one year of decommissioning. At the end of the decommissioning exercise, the EPA will be invited to carry out a post-decommissioning assessment to establish compliance with all regulatory requirements and issue a certificate to that effect. The Decommissioning and Closure Plan will be finalized and submitted to the relevant authorities for approval at least six months prior to closure of the site.

A report describing the performance of the final DCP in working towards its objectives, based on monitoring results, and the extent to which it has been complied with, will be submitted to the EPA. The report will be provided to documented stakeholders and will otherwise be publicly available on request. Files and documents used to collate information regarding closure commitments, licenses, approvals and other information concerning closure will be catalogued and maintained in accordance with standard practices.

11.0 CONCLUSION

The proposed project will be implemented in accordance with relevant national laws and best international practices provided by the applicable Operational Safeguards of the AfDB Integrated Safeguard System.

Stakeholders have been identified and their suggestions and concerns obtained through the consultation and engagement process have been highlighted in the report and addressed. A Stakeholder Engagement Plan (SEP) has been proposed to ensure continued engagement of all stakeholders and the implementation of a grievance redress mechanism to ensure harmony in the project implementation.

The potential adverse impacts of the project have been identified. Adequate mitigation measures have been proposed to manage the moderate to major adverse impacts. Also, management and monitoring plans have been designed to ensure that the proposed mitigation measures are adequately implemented. The institutional capacities have been assessed and gaps identified with recommendations.

The assessments have shown that the project generally has moderate impacts on the environment and the impacts could be further mitigated with the adoption of good environmental, health and safety practices. A Pest Management Plan (PMP) is required to ensure judicious and safe use of agrochemicals as well as safe disposal of obsolete chemicals and empty containers.

The Chief of the Tindantua community has donated the land for the project. A Resettlement Action Plan has been proposed to mitigate the livelihood impacts on four (4) farmers who will vacate their farm lands for use by the project.

The project holds immense benefit for the Tindantua community, the district and region regarding food security, job creation, growth of MSMEs, etc. The entire country will benefit from improved food security, increased knowledge and adoption of best agricultural practices for rice production, etc.

12.0 BIBLIOGRAPHY

CARE International. (2013) Climate Change Vulnerability and Adaptive Capacity in Northern Ghana. An Adaptation Learning Programme Report. CARE International: Accra.

Ghana Environmental Assessment Regulations, 1999 (L.I. 1652)

Ghana Meteorological Agency Climate data (2015 -2024)

Ghana Statistical Service, 2021. 2020 Population and Housing Census – District Analytical Report for Selected Project Districts.

Government of Ghana/UNICEF, 2013. Northern Region Report: Qualitative Research on Child Protection in Ghana. Government of Ghana/UNICEF: Accra, Ghana.

Government of Ghana, 2021. Medium Term Development Plan for the Mion District Assembly, 2022 – 2025.

Hutchinson, J. and J.M. Dalziel (1954-72). Flora of West Tropical Africa. Crown Agents, London.

Medium Term Development Plan, Mion District, 2021.

Ministry of Food and Agriculture, Department of Agriculture-Mion District, 2024

Murali Krishna Gumma & Paul Pavelic, 2012, Mapping of groundwater potential zones across Ghana using remote sensing, geographic information systems, and spatial modelling, 2012.

Owusu, K (2018) Rainfall Changes in the Savannah Zone of Northern Ghana 1961- 2010. Weather, Vol 73, No. 2

SAL Consult Field data, 2025

Tetteh et al., (2016); Suitability of soils for cereal cropping in Northern Ghana.

The African Development Bank Group's Operational Safeguards Standards (OSS), 2024 (Revised) The 1992 Constitution of Ghana

WKC Group Formula (2015)

Yeboah et al., (2022); Variability of soil physicochemical properties under different land use types in the Guinea savanna zone of northern Ghana

13.0 ANNEXES

Annex 1: Administrative flow chart of environmental assessment procedure

Annex 2: List of environmentally sensitive areas


Annex 3: Sample Code of Conduct

Annex 4: Sample Grievance Form

Annex 5: Details of Stakeholder Engagement

Annex 6: Stakeholder Engagement Attendance Sheets

Annex 1: Administrative flow chart of environmental assessment procedure



Annex 2 List of environmentally sensitive areas

ENVIRONMENTAL ASSESSMENT REGULATIONS, 1999

SCHEDULE 5

(Regulation 30 (2))

ENVIRONMENTALLY SENSITIVE AREAS

- All areas declared by law as national parks, watershed reserves, wildlife reserves and sanctuaries including sacred groves.
- Areas with potential tourist value.
- Areas which constitute the habitat of any endangered or threatened species of indigenous wildlife (tlora and fauna).
- 4. Areas of unique historic, archaeological or scientific interests.
- 5. Areas which are traditionally occupied by cultural communities.
- Areas prone to natural disasters (geological hazards, floods, rainstorms, earthquakes, landslides, volcanic activity etc.)
- 7. Areas prone to bushfires.
- 8. Hilly areas with critical slopes.
- 9. Areas classified as prime agricultural lands.
- 10. Recharge areas of aquifers.
- 11. Water bodies characterized by one or any combination of the following conditions
 - a) water tapped for domestic purposes;
 - b) water within the controlled and/or protected areas;
 - c) water which support wildlife and fishery activities.
- 12. Mangrove areas characterised by one or any combination of the following conditions
 - a) areas with primary pristine and dense growth;
 - b) areas adjoining mouth of major river system;
 - c) areas near or adjacent to traditional fishing grounds;
 - d) areas which act as natural buffers against shore erosion, strong winds or storm floods.

CLETUS AVOKA
Minister Responsible for the Environment

Date of Gazette notification: 26th February, 1999.

Entry into force: 24th June, 1999

105

EIA IN GHANA

Annex 3: Sample Code of Conduct

All the employees of the Contractor and support staff of Supervising Consultant shall adhere to the following Code of Conduct during the execution of the project:

1. Compliance with Applicable Laws, Rules and Regulations

- a. All employees shall perform their duties in accordance with the Labour Act, 2003 and other applicable labour laws in Ghana.
- b. Employees/key experts will enjoy freedom of association and expression as defined in the Constitution of Ghana and expressed in Labour Act, 2003 (Act 651) and other labour laws in Ghana.
- c. The Organization will not condone the activities of employees who achieve results through violation of the law or unethical business dealings. This includes any payments for illegal acts, indirect contributions, rebates, and bribery.
- d. The Organization shall not permit any activity that fails to stand the closest possible public scrutiny.
- e. Employees uncertain about the application or interpretation of any legal requirements should refer the matter to appropriate line supervisor
- f. Workers/employees who falsify their ages will be summarily dismissed as the company does not tolerate child and forced labour.
- g. The company will not tolerate any form of child or forced labour from any subcontractor/employee who practice forced or child labour
- h. Employees are required to report suspected cases of child or forced labour on site to REWARD Environmental and Social Specialist, DOVVSU or District Assembly.

2. Compliance with Applicable Health and Safety Requirements

- a. All employees' have the right and duty to ensure safe working conditions to the extent of exercising control over tools, equipment, machinery and processes and to express their views on working conditions that may affect their safety and health. Subcontractors will do same for their employees
- b. Employees of the Contractor shall be responsible for removing themselves from danger as much as possible whenever they have good reason to believe that there is an imminent and serious danger to their safety or health. They should have the duty so to inform their supervisor immediately.
- c. Employees/key experts will be provided with the appropriate protective gear for the operations or activities and request for same before engaging in any activity associated with the works.
- d. No worker shall be allowed to undertake any work without wearing approved protective clothing/gear.
- e. Workers shall use and take care of personal protective equipment, protective clothing and facilities placed at their disposal and not misuse anything provided for their own protection or the protection of others
- f. First time offenders who are not in the appropriate protective gear will receive a verbal caution, second time offenders will receive a formal written caution, while multiple offenders will receive sanctions ranging from suspensions to dismissal.
- g. Except in an emergency, employees, unless duly authorised, should not interfere with, remove, alter or displace any safety device or other appliance furnished for their protection or the protection of others, or interfere with any method or process adopted with a view to avoiding accidents and injury to health.

- h. Every employee shall take reasonable care for their own safety and health and that of other persons who may be affected by their acts or omissions at work;
- Workers shall report to their immediate supervisor, and Health and Safety Officer, any situation which they believe presents a risk and which they cannot properly deal with themselves;
- j. Damaged or faulty electrical equipment such as power sockets, leads and appliances are removed from service.
- k. Damaged or faulty equipment should be replaced, or repaired by a qualified person as soon as possible.
- I. Power points should be protected by safety-shutters, or all vacant power points be covered by plastic plug protectors.
- m. Electrical appliances and leads should be kept away from water.
- n. All machines and vehicles should be turned off when not in use
- o. All employees shall comply with all the safety and health measures prescribed by the employer. Employees should not operate or interfere with plant and equipment that they have not been duly authorised to operate, maintain or use.
- p. Employees should not sleep or rest in dangerous places such as scaffolds, , garages, or in the vicinity of fires, dangerous or toxic substances, running machines or vehicles and heavy equipment.
- q. Supervisors should not assign employees to undertake activities that the later do not have necessary competence, training or certification or that has not been stated in their contract with the Company.
- r. Employees should not undertake any assigned activity for which you do not have necessary competence, training or certification or that has not been stated in their contract with the Company.
- s. Every employee is encouraged to contribute by integrating environmental sustainability issues as they relate to our industry into our business planning, strategies and decision-making.
- t. Employees shall avail themselves for all OHS, HIV/AIDS Gender Based Violence, Emergency Preparedness Training/Sensitization Programmes organized under the project.
- u. All Company employees should strive to conserve resources and reduce waste through re-use and other energy conservation measures.

3. Use of Illegal Substances

- a. No employee/key expert/sub-contractor shall report to work under the influence of alcohol or any substance considered as illegal under the laws of Ghana including marijuana.
- b. No employee shall smoke, consume alcohol or illegal substances while on duty, including lunches and during overtime meals, or on company property.
- a. Officers and directors <u>may</u> authorize, in advance, the consumption of alcohol for special occasions or for certain business meetings as long as such use is limited and does not violate other legal requirements.
- b. No employee shall under any circumstance engage in any work related to the organization under the influence of Alcohol or illegal substances even if consumption is permitted under the exception described above.
- c. Employees who violate this smoking and alcohol conduct standard may have their contract terminated.

4. Non- Discrimination

- a. Discrimination against any job applicant or employee on the grounds of colour, race, religion, age, nationality, sex, marital or family status, ethnic affiliation, pregnancy, sexual orientation, disability or other reason is prohibited.
- b. In certain cases, however, the requirements of safety regulations relating to specific positions/activities within a construction business will take precedence over clause 4(a).
- c. We do not employ any person below the legal minimum age (18 years) and will require commitments from suppliers and subcontractors to refrain from such practices
- d. Workers are not to undertake any assigned activity for which they do not have necessary competence, training or certification or that has not been stated in their contract with the Company.
- e. Recruitment, job transfer and progression, remuneration and training and award of discretionary bonuses when applicable are determined solely by the application of objective criteria, fair and unprejudiced opinion, personal performance and merit.
- d. Recruitments, transfers, training, maternity leave and standard terms and conditions will be done in accordance within line Ghana Labour laws.
- e. Employees who perceive that they have been discriminated against can seek redress through their supervisor, Environmental, Health and Safety Officer, management and/or the Ministry of Labour and Social Welfare.

5. Interaction with Community

- a. The Company strives to cultivate a local identity in each of its host communities by setting good corporate citizenship standards, while respecting local sensitivities.
- b. The Company will regularly contribute to the economic and social development of communities, and expects all employees to promote human rights and respectful community involvement anywhere it operates.
- c. Employees should comply with the norms, laws, rules and regulations applicable to the host communities except in cases where they are in conflict with that of Ghanaian laws.
- d. In a case where an employee perceives that the laws, rules and regulations of host communities are in conflict with that of the company, employees are to refer such cases to their supervisor, Environment, Health and Safety Officer or manager for further clarification at the Ministry of Labour and Social Security

6. Sexual Harassment

Sexual Harassment would be considered as unwelcome conduct of a sexual nature which makes a person feel offended, humiliated and/or intimidated. It includes situations where a person is asked to engage in sexual activity as a condition of that person's employment, as well as situations which create an environment which is hostile, intimidating or humiliating for the survivor

- a. Sexual harassment is unlawful.
- b. This company does not tolerate sexual harassment in any form.
- c. Every employee has a responsibility to ensure that sexual harassment does not occur.
- d. No employee shall under any circumstance sexually engage another either by the use of words or actions. Some acts that may be considered as sexual include;
 - an unwelcome sexual advance
 - a request for sexual favours
 - unwelcome comments about someone's sex life or physical appearance
 - sexually offensive comments, stories or jokes
 - displaying sexually offensive photos, pinups or calendars, reading matter or objects
 - sexual propositions or continued requests for dates

- physical contact such as touching or fondling, or unnecessary brushing up against someone
 - Indecent assault, defilement or rape (these are criminal offences).
- e. Any employee who believes he or she has been a target/survivor of sexual harassment is encouraged to inform the offending person orally or in writing that such conduct is unwelcome and offensive and must stop or to report the unwelcome conduct as soon as possible to a supervisor, management or the environmental and social officer of GASSLP representative on the Project Grievance Redress Committee or the nearest DOVVSU or Police Station
- f. Reports of sexual harassment will be treated promptly, seriously and confidentially.
- g. Complainants have the right to determine how a complaint will be treated and knowledge of the outcome of investigations.
- h. Anyone found to have sexually harassed another person will be handed over to the Family Support Unit of the Ghana Police Force.
- i. No employee will be treated unfairly as a result of making a complaint of sexual harassment. Immediate disciplinary action will be taken against anyone who victimizes or retaliates against someone who has made a complaint of sexual harassment.
- j. For the purposes of reporting and dealing with sexual harassment and crimes, the Company will provide a hot line to a management level personnel for reporting cases of sexual abuse and harassment.
- k. Rape, defilement and assault cases shall be reported to FSU of the Ghana Police Force by survivor or other employees'

7. Violence or Exploitation

- a. No employee shall bear any weapon on site unless he/she has been authorized and have a legitimate business reason to do so. Even so, this will have to be with the permission of the appropriate supervisor, manager and conformity with the laws of Ghana.
- b. The company is committed to maintaining a safe and secure workplace and working environment. Acts or threats of physical violence, intimidation, harassment or coercion, stalking, sabotage, and similar activities are not tolerated.
- c. Employees who engage in acts or threats of violence, outside of self-defense, shall be dismissed and handed over to the Police Station.
- d. Employees are expected to treat all individuals with respect, tolerance, dignity and without prejudice to create a mutually respectful and positive working environment.

8. Protection of Children

- a. As much as possible, employees' are to avoid bringing any person under 18 to work on the project site) unless with permission from Environment, Health and Safety Officer.
- b. Every employee shall himself be responsible for the safety and wellbeing of any person under age 18 years brought to work by them. *Physical contact with children can be misconstrued both by the recipient and by those who observe it, and should occur only when completely nonsexual and* otherwise appropriate, and never in private.
- c. One-on-one meetings with a child or young person are best held in a public area; in a room where the interaction can be (or is being) observed; or in a room with the door left open, and another employee or supervisor is notified about the meeting.
- d. Avoid any covert or overt sexual behaviors with children on site. This includes seductive speech or gestures as well as physical contact that exploits, abuses, or harasses.
- e. Employees are to provide safe environments for children and youth at all times on site

9. Sanitation Requirement

- a. The company shall provide and maintain sanitary facilities (according to building regulations) for all employees to ensure their total health and safety. All such facilities shall be labelled with inscription in English for the understanding of every employee.
- b. Every employee/key expert shall be responsible for the appropriate use of sanitary facilities including toilets, bathrooms and refuse bins/skip containers where provided.
- c. No employee shall resort to other inappropriate means of defecation or urination (open defecation or indiscriminate disposal of refuse or urination on the company's compound or project site) apart from what has been prescribed by the company.
- d. Any act of indecency with respect to the use of sanitary facilities shall attract punitive actions including suspensions or even dismissals.

10. Avoidance of Conflict of Interest

- a. The Company expects that employees will perform their duties conscientiously, honestly, and in accordance with the best interests of the Organization.
- b. Employees/key experts must not use their positions or the knowledge gained as a result of their positions for private or personal advantage.
- c. Regardless of the circumstances, if employees sense that a course of action they have been pursued, or are presently pursuing, or are contemplating pursuing may make it difficult to perform the work objectively, they should immediately communicate all the facts to their supervisor.
- d. An Employee or a member of his or her immediate family shall not receive improper personal benefits as a result of his or her position in the Company.
- e. Any situation that involves, or may reasonably be expected to involve, a conflict of interest with the Company should be disclosed promptly to supervisors/ managers.

11. Protection and Proper Use of Property

- a. All employees unless otherwise directed are responsible for the proper acquisition, use, maintenance and disposal of company assets (e.g., materials, equipment, tools, real property, information, data, intellectual property and funds) and services. Acquisition of assets should be in compliance with procurement standards of the company.
- b. Any act of theft, carelessness, and waste on the part of an employee shall attract sanctions including the termination of one's work contract.
- c. Every employee shall do their part to protect the company's assets and ensure their efficient use.
- d. Unless otherwise permitted by management, Company guidelines and procedures, the appropriation of Company property by employees for personal use, or for resale is strictly prohibited.
- e. Similarly, you are not permitted to use your authority over other employees to use Company resources for personal benefit.
- f. On termination of and at any other time during your employment when requested you must hand over Company's assets and records stored in whatever format or medium.
- g. The Company strictly prohibits any access, usage or disclosure of employees' personal data without legitimate authorization. Employees should note that the Company reserves the right to retrieve their e-mails transmitted via the Company e-mail accounts and to monitor your use of the Internet.
- h. Every employee shall use company assets only for legal and ethical activities.

12. Report of Violation of Code of Conduct

- a. Employees should promote ethical behavior and encourage other employees to talk to supervisors, managers or other appropriate personnel when in doubt about the best course of action in a particular situation.
- b. In order to protect our organization from unethical or illegal activity, it is your duty and obligation at all times to be watchful of the practices that you see occurring around you, to take reasonable steps to prevent or detect improper conduct, and to report any suspicion of fraudulent, abusive, unethical or illegal activity.
- c. All reports of misconduct or unethical behavior, conflict of interest, or illegal activity are to be handled as confidential and be treated seriously and discreetly.
- d. Employees may report anonymously should that be their preference.
- e. In the event of a grievance being raised to a manager relating to discriminatory behaviour or harassment, the manager must notify Human Resources immediately, irrespective of how trivial the complaint may appear.

13. Non-Retaliation

- a. The company will not tolerate any act of retaliation against anyone who, in good faith, reports known or suspected unethical or illegal misconduct, seeks advice, raises a concern, or provides information in an internal or external investigation or legal proceeding pertaining to the company.
- b. Allegations of retaliation will be investigated, as appropriate.
- c. Acts of retaliation (which may include firing or laying off, demoting, denying overtime or promotion, disciplining, denying benefits, failing to hire or rehire, intimidation or making threats) may lead to disciplinary action against the person responsible for the retaliation, up to and including termination of contract.
- d. Any employee who believes he/she has experienced retaliation, should report to his/her supervisor, manager or the REWARD Environmental and Social Officer.
- e. Any false accusation of retaliation would attract disciplinary actions even to the extent of termination of contract.

Implementation of Code of Conduct

- a. The Environment, Health and Safety Officer of the Contractor will be responsible for implementing and enforcing the Code of Conduct, while monitoring
- b. The following measures will be adopted to implement the Code of Conduct:
 - The Consultant will ensure that all employees/key experts and sub-contractors are given copies of the Code of Conduct for reference.
 - All employees on the assignment will be made to sign the Code of Conduct.

Annex 4: Sample Grievance Form

GRIEVANCE REGISTRATION FORM (FORM A) - For Complainant

Confidentiality Required: Yes No:
Name (Complainant) Optional:
Contact Information (house number/ mobile phone):
Nature of Grievance or Complaint:
Details of Grievance:
Name (Receiver):
Name (Filer):
Relationship of Filer to Complainant (if different from Complainant):

Annex 5: Details of Stakeholder Engagement

Stakeholder/ Institution/ Location	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
	ns. Catagory A					
Government Institutio Ministry of Food and Agriculture – Mion	ns – Category A Prince Namkazoa Yelabeyani Dennis	Management Information System Officer	0243483674	2025-04-14	 Land-Acquisition – The department is aware of land acquisition for the project. District Agriculture Production – Agriculture is the main livelihood of the people in the district and it is suitable for the project. About 61,337 people are into agriculture. Maize, Rice, Soya, groundnut and Yam are the common crops grown in the dis. The farmers do not have generally are engaged in rain-fed agriculture which is making production difficult. Project Implementation - The Department must be well-resourced (finance/logistics) for monitoring/supervision of the project. There is land available in the proposed area and it stool land. Farmers should be supported with farm inputs and machinery for land preparation and crop harvesting to reduce post-harvest losses through farmer service centers. Main agriculture problem in the area is lack of irrigation therefore this should be factored into the project planning. Project Impact – The project is expected to have a positive impact on community members where it is expected to create jobs in the rice value chain thereby reducing rural migration. Recommendations - All relevant stakeholders should be involved in the project. There should be ready markets for the rice that will be produced. The road network in the area should be improved to enhance mobility of people and goods. 	
Environmental Protection Authority (EPA) – Tamale	Abdul karim Jato	Programme Officer	0201224235	2025-04-22	 Compensation - Compensation issues will arise if there are PAPs in the valley. Compensation should be addressed through comprehensive RAP. There must be valuation of properties if any, as well as compensation for any form of displacement. Project Implementation - Environmental permit is required for the project. Biodiversity conservation should be a consideration in the project implementation. If there are RAP issues, it should be handled properly in order not to impoverish persons involved. There will be field visits by the EPA team to monitor environmental compliance during implementation. Farmers should be educated on the use and handling of agro-chemicals. The project has the potential to transform livelihoods of beneficiaries if it is implemented effectively. Recommendations - There should be environmental monitoring during implementation to check results against established baseline conditions. There should be good water management practices. There should be a flood control plan in the valley. EPA Monitoring – the project should include EPA staff in the implementation phase of the project to monitor the compliance of the farmers with environmental standards. 	

Stakeholder/ Institution/ Location	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Lands Commission	Mohammed Alhassan	Assistant Secretary	0242081543	2025-04-14	 Compensation - Land acquisition will warrant some form of compensation to right owners. There must compensation for physical and economic displacement if any. Capturing of PAPs data must be done comprehensively. Project Implementation - The land in the area is owned by stools. Land for this kind of project are normally acquired from the traditional authorities. The project will help to improve livelihoods and food security. Assistance in the farm of farm inputs should be provided to the farmers. The project will lead to effective land utilization. Recommendation - Need more community engagement for on the project for enhanced participation. 	
Water Resource Commission (WRC)	Yussif Abdul -Razak Gunu	Accountant	0249768120	2025-04-15	Concerns/Recommendations: - Farmers should form fire fighter groups. Education on agrochemicals use for farmers There should be timely harvest of crops by farmers. community education on disaster management	
NADMO, Mion (Kpabia)	Iddrisu Alhassan Ganiyu	NADMO director	0242772740	2025-04-22	 Floods – Floods mostly happen once in a year during the rainy season. Drought – Drought is also experienced sometimes Disaster Impact: There have been loss of farmland as a result of floods. This can pose the risk of food insecurity in the area. Sensitization: NADMO sensitizes the communities once a year. Operations: They assess the situation and report for support. Concerns/Recommendations: NADMO appeals to farmers to stop farming along waterways. 	
District Assembly, Mion	Fuseini Karim	Assistant Co- ordinating Director	0243509709	2025-04-25	 Support from the District Assembly – The assembly is willing to provide support to any project that will improve the production of farmers in the community. Compensation - Compensation must be clearly determined before the commencement of the project if that is doing to be undertaken. Compensation should be comprehensive covering land, physical and economic displacement if identified. Project Implementation - The district assembly is delighted to be part of the project. 	

Stakeholder/	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Institution/ Location						
Ghana National Fire	Isaac Ofei Dodoo	Administrative Officer	0249829629	2025-04-14	 The project will improve upon the living condition of the people in the area if implemented well. The main economic activity in the district farming and majority of the population engage in it. Land for farming is acquired from the traditional authorities. Main agricultural challenges in the area are lack of mechanization, and agro-input cost. The area is generally peaceful and there is no existing conflict. Recommendations - The road network needs upgrade to make transportation easy. The farmers should be supported seasonally to maintain high production levels. Preservation of water bodies - The project should put measures in place to preserve 	
Service, Tamale					 existing water bodies as this serves as farm boundaries and also helps to curb bush fires. Training of fire volunteers – Fire volunteers from the farming communities should be trained to provide immediate assistance in the case of fire outbreaks. Soil tests – The project should conduct water logging as well as fertility tests to determine the suitability of soil for maximum crop production. Inadequate logistics – The Fire Service department should be provided with adequate logistics like vehicles to facilitate project monitoring and training of fire volunteers. 	
Private Sector – Catego Commercial Farmer, Mion	Abdulai Karim	Farmer	0598590323	2025-04-16	Farming – Crops like Maize, Rice, Groundnut, and Yam are mostly grown by the commercial farmers on farm lands which are owned or leased. Fertilizer like NPK and Urea are mostly used by farmers. A Farmer can cultivate on about 150 acres of land. Project Implementation - The project should make farm inputs available to farmers that will be involved in the project. Farmer service centres should be instituted to support the farmers with modern equipment. There should be ready market for produce with reasonable pricing regime. Irrigation should be an important project component to ensure dry season farming. Extension services should be provided by qualified professionals. Recommendations - Government support for the project should be timely Farm inputs provision to the farmers is key if production levels are to be increased to make the project a success. Rice milling machines should be provided for processing of harvested rice. Concerns — The project should be devoid of any political interferences.	Galaxy A05s 14:38

Stakeholder/ Institution/ Location	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Small Holder Farmers	Iddrisu Abdul Rahman	Farmer	0558801927	2025-04-16	 Farming Activities – They farm in crops like Soybean, maize, rice, sorghum, yam, cassava and groundnut. They don't indulge in Irrigation farming. They engage in weekly insect monitoring. They use pesticide like Lambda yearly. They decide pest control methods via AEA recommendation. Concerns – Their top 3 needs are tractor service, assistance in getting fertilizer and agrochemicals for their crops. Poor road network need to be addressed. Project Implementation - The project should take into consideration challenges of climate change to incorporate irrigation. Inputs and credit support will be required for the beneficiaries on the project. Drought and pest resistant seed varieties should be provided for production. Ready market for produce is key to encourage more people to get involved. Land preparation support is required before planting. Existing farmers on the proposed project site must be compensated if they are to move out. Recommendations - Gender bias/political influences should be avoided in the project implementation. Farmers should be trained on sustainable farm practices by extension officers. The road in the area should be improved especially during the raining season. 	
Faith Based Organizations (FBO) / Mion (Dabogni)	Abdulai Awabu	(Soglo Mbori Buni group)	0557758314	2025-04-16	 Associations - There are VSLA group like Soglo Mbori Buni thjat offer financial assistance to members. Project Impact – They believe the project can boost the economy of the area by increasing farming activities Concerns/Recommendations – Avoid political bias during project implantation. There should be consideration and much focus on the vulnerable during the project implementation Traditional authorities shouldn't be ignored but should be involved in the project implementation. Inputs should be subsidized for farmers to afford them. Address land reallocation concerns through consultation. They can partner farmers for capacity building. 	

Agro Input Dealers Shani Amin Member Member Member		Contact Person(s) Role	Date	Concerns Raised/ Information Received	Pictures
Agro Input Dealers Shani Amin Member	0597833024	Mion Musah Abdul Rashid Member	2025-04-16	 Rice Variety – Rice variety mostly aggregated are AGRA and Jasmine rice. These are bought from individual farmers. Storage facilities – Aggregators purchase about 30 bags per month and store them in rented rooms. Challenges – Inadequate buyers hence have to end up lowering their price. Poor roads making transportation difficult. No digital platforms to ease business process. Access to finance is very difficult. Storage infrastructure is not enough. Recommendations – They expect the programme to provide fertilizers/agrochemicals to farmers. 	
	0535698730	Shani Amin Member	2025-04-22	 Activities – They sell fertilizers, seeds (maize, soybean), chemicals, tools/equipment. Customers are mostly small holder farmers. March to June is their peak season. They Source their products from local distributors. The bundle inputs on credit to 10% of their customers. Other roles – Aside selling, they offer technical advice/training to farmers. Concerns/Recommendations - They need easier means of connecting to suppliers and accessing credit/financial services. NGO Partnership - They are open to partnering with NGOs and other private organizations. Challenges – They have limited capital, inadequate storage facility for their products. Farmers' inability to sometimes purchase their products due to seemingly high cost. Farmers lacking enough technical knowledge on how to use agro-chemicals. High transport cost Lack own transport making transportation difficult. Opinion - They believe the project is going to have a Positive impact and increase rice production for farmers. They will also need support and training on business management. 	

Stakeholder/ Institution/ Location	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Traditional Elders	Saani Muftawu Mohammed Abdulai Abdul Razak Issahaku, Shani Sherazu Iliasu Issahaku Shei Napari Hamza Ayisha Abukari Adam Abdul Mateen Amadu Mohammed Hardi	Chief Zaachi Zagyuri na Wulan bla Kpana lana Community Member	0555524505, 0244870321, 0539661971, 0549794263, 0542733042, 0547113628, 0543751635, 0547564722, 0555392007	2025-04-22	 History of Town - Town was formed about 400 years ago. Found was called Chief Yidana and he initially came to farm. The natives are Dagombas with a population of 5200 and mostly practiced Islam. Culture - They celebrate the Damba festival which is a festival of fire. There are sacred sites in the area. There are drama and entertainment group for the youth and women. They practice traditional medicine like bone setting due to lack of clinic resources. Land Ownership – All the land are stool lands. Land Use – The land is mainly used for farming and rearing of livestock. Health Challenges – Some of the health challenges experienced include Piles, fever, HBP, Hepatitis B. etc. The nearest health facility is the Dabogni CHP compound. Conflicts – There have been conflict with locals with regards activities of herdsmen. Conflict resolved at palace, infrequent). Compensation - Land documentation to indicate its allocation for the project should be undertaken. Compensation for physical and economic displacement must be clearly determined before the commencement of the project. Project Implementation - The traditional authorities are in support for the project as it will improve incomes and reduce youth unemployment. Enough land owned by the traditional authority available in the area for farming and the chiefs are ready to give out lands for such activities. There should not be discrimination in the selection of beneficiaries. Input and credit support should be extended to the farmers on the project increase production. Irrigation for dry season farming should be provided to make the project more impactful. There is no conflict issue in the area. Rec	

Stakeholder/	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Institution/ Location						
Women's Group	Memuna Soale, Fuseina Asumana Nafisa Osman Nasifa Alhassan Azimpaga Alhassan Abubakari Safura Azaratu Yakubu Mutaru Ayisha Imoro Sanatu Zakaria Sanatu	Chairperson Key stakeholder Treasurer Member Member Member Member Member Member Member Member	0557364663 0595450936 0240601889 0248014801 0537435427 0598134306 0598126606	2025-04-16	 Project Implementation - The project will go a long way to enhance women's and families' livelihood. The project should be made to be successful by providing all necessary assistance to the women who are mostly disadvantaged. The women have interest in been part of the rice production initiative. Input support to the women will be key for their involvement in the project. Land is controlled by men (ownership) in the area. Recommendations - Ready market for produce should they be made available in the district. Processing facilities should be provided to reduce post-harvest challenges. Support for women in this project should be deliberate and targeted. Women role in the Community – They cook, fetch water and clean the house. Though they take part in decision making regarding finance, the men make the final decision. They also engage them in farming activities by growing legumes, groundnut, vegetables, and soybean to sell at the market. Other activities - They engage in shea picking. Some engage in livestock rearing e.g. sheep, goat, cattle, poultry etc. Some also process soy bean for kebab and groundnut for cake, paste or oil. Vulnerable Groups – There are vulnerable persons in the community as well as disabled persons in the community. Health Challenges – They mostly experience health challenges like waist/chest pains, fever. They mostly treat these illnesses with herbs. Women Association – They have formed a women association with about 30 members where they have savings and loans and meet weekly. The association is not formally registered. Cultural Group – The have a cultural group called Tora which is mostly for entertainment. Local groups – Local groups present include: VSLA group, providing financial support to members, farm groups, and youth groups providing ass	

Stakeholder/ Institution/ Location	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Men's group	Saani Muftawu Mohammed Abdulai Abdul Razak Issahaku, Shani Sherazu Iliasu Issahaku Shei Napari Abukari Adam Abdul Mateen Amadu Mohammed Hardi Yakubu Adam	Chief Zaachi Zagyuri na Wulan bla Kpana lana Community Member Community Member Community Member Community Member Community Member	0555524505, 0244870321, 0539661971, 0549794263, 0542733042, 0547113628, 0547564722, 0555392007	2025-04-16	 Activities – Some of the activities the men engage in are Farming (Maize, groundnut, yam, rice, sorghum, soybean), rearing of livestock (e.g. sheep, goat, cattle) for subsistence and charcoal production. Farming - The Planting season which used to be between June to December of the years have been changing due to deforestation. Health Challenges - They mostly experience health challenges like High blood pressure, malaria and chest pains, fever. They mostly treat these illnesses with herbs. Concerns - Their top concerns are road network, access to portable drinking water, farming support and hospital. Project Implementation - The project is good news to the men in the area as it will help improve incomes and livelihoods. Opportunity should be given to all men to decide to be part of the project. Those who are not currently farming in the project valley should also be considered. Water for dry season irrigation should be a part of the project. Farm inputs support should be provided to the beneficiaries. Ready market for produce is key if the project will be sustained. Extension services should be part of the project especially in the use of agrochemicals. Recommendations - Credit for farmers to buy inputs if the inputs will not be supplied. Processing facility should be established to cater for the farmers. The road transportation should be improved to facilitate movement of goods. Farmer service centers should be set up in the district to help farmers especially 	
Youth group	Adam Abdul Somed Abdul Rahim Yakubu Abdul Karim Abass Yakubu Amin Nasifa Alhassan, Azimpaga Alhassan, Abubakari Safura, Azaratu Yakubu,	Member	0540347921, 0533251028, 0542644629, 0240658186, 024801480, 0537435427, 0598134306, 0598126606	2025-04-14	 Project Implementation – The youth in the area enthusiastic about the project and looking forward it its full implementation. The project will help to reduce youth unemployment in the area. The necessary support should be extended to the beneficiaries especially the youth to buy inputs. Ready markets for the rice produce will be required to ensure flow of income. Irrigation is necessary to make the project more effective and sustainable. Recommendations - Extension officers should be attached to the project. Machinery for land preparation and harvesting as well as processing facilities should be part of the project. The roads in the area are not in good shape and should be improved. Community—Healthcare, potable water and Farm machinery, are the three topmost needs of the community. 	

Stakeholder/ Institution/ Location	Contact Person(s)	Role	Contact No.	Date	Concerns Raised/ Information Received	Pictures
Cattle Herde Tindantua	s, Kadri Sulemana	Herdsman	0558376779	2025-04-16	 Origin – The cattle herders are originally from Bimbilla and the family have been herding for about 45 years. They don't have any cattle herders' association Conflict Resolution - They manage crop intrusion by paying affected farmers as compensation for crops destroyed or settling conflicts at chief's palace. They mostly check on their cattle regularly to prevent intrusion when grazing. Herding Activities - They can travel more than 10 km with their cattle to graze mostly setting off in the morning around and there are no specific spots to graze. Their cattle mostly feed on waste/plants in dry season. Most of them own the cattle and also farms as well. They have no association. Concerns - They need clear demarcation of pathways for their cattle to move during grazing so they don't intrude into people's farms. Challenges - Food becomes scarce especially during the dry season and they have to travel far with their cattle for pastures. The cattle herders sometimes thirst and get hungry especially under the scorching sun when they take the cattle out to graze. 	

Annex 6: Stakeholder Engagement Attendance Sheets

lo.	Name	Organization/District/Community	Position	Fhone No.	Email/Sign
· Fus	eini Kainm	Sistinal Assembly	To-ordinaling Vire	dr 0243509709	
+					
-					
-					
+					
-					
				-	
			-		

-	Name	Organization/District/Community	Position	Phone No.	Email / Sign
1	Abdul Karim Jato	EP4	Programme Officer	0201224285	1
+					
-					
+					in the second second
+	- !		37		
t					
t					
T					
T					
L					
L			#		

SAL CONSULT LIMITED STAKEHOLDER MEETING ATTENDANCE SHEET

REWARD

4/2025 Time: 09:30 Pm Venue: Traditional Authority

No.	Name	Organisation/District/Community	Position	Phone Na.	Email / Sign
	Stani Mugteriou	Indantes	Clief	05 52534505	,
-	Mohammed Asdulai	_	Zagchi	0244870321	
	Aldul Razak Issahaku	_	Zagyuri Na	0539661971	
_	Shori Sherazy		Wylan Bla	CTY 9794263	
- 1	Iltary Israhaku			0542783042	
-	shei Mapqui		Community Mense	0547113628	
	Hamza Ajisha	~	Member	2891218720	V.
	Abukan Adam			0547564722	
	Asolul Mateer Amadu			0555392007	
0. 1	Mohammed Hardi		~		
+					
+					
+					
+					
+					
+					
+					
+					
_					

	Posses	SAL CONSULT LIMITED STAKEHO	NDER MEETING ATTE	NDANCE SHEET	
	Date: 22/04/2025	Time: 1125 pm	Vens	ie: Agro Input 1	Jealer
No.	Name	Organization/District/Community	Position	Phone No.	
1.	Sharim Anin	Agro Input borles	Memser	0535698780	
	21			1	

NG.	Name	Organization/District/Community	Position	Phone No.	Email / Sign
1.	Sharim Anin	Agro Input Boules	Memser	0535698730	
-				1	
-					
-					
	14"				
	*				
_					
1					
1					
1					
1					
1					
1					
1			+		
1					
1					
1					
1					

SIL Date: 1610 4 2025			: Cattle Herders	7.1-1-010104
		ty Position	Phone No.	Email / Sign
Kadn Sufemana	Tindontua	Herdman	0558376729	*
				di.
				8
*				
	Name Kadir Sufemana	Name Organization/District/Communication/Dist	Name Organization/District/Community Position Kadin Sufernana Tindantua Herdman	Name Organization/District/Community Position Phone No. Kadin Gufemana Tindantua Herdeman 0158376729

Name	Organization/District/Community	Position	Phone No.	Email / Sign
Sami Negtowy		dies	05555 24105	
Mohammed Abdulai		Zagchi	0244870321	
Asdul Razak Isaghaky		Zagyvin Ka	0539661971	
Shani Sherazu		Wulen Bla		
Cliary Israhory		Kpana Lang		
Shei Mapani Abukan Adam		Community Meade		
Abdul Mateen Amada		<u> </u>	0547564725	
Mohammed Hardi		<u> </u>	0555392007	
Yakubu Adam				
Talency Mercin				

io.		-	Time: 4100 pm	vertue:	Womens' Groun	· · · · · · · · · · · · · · · · · · ·
-	100	eme	Organization/District/Community	Position	Phone No.	Email / Sign
10	Memung &	sorle		Cherrperson	0537364663	
2 .		imana		Key Stakeholder	3EP 0242P20	
3.	1	nan		Tregsurer	004060 1889	
4,		act 1		M-enoSer	0248014801	
5.	Azimpaga A			Member	0537435427	
_		Sagura		Member	0598134306	
_		Yakusu		Member	05981126606	
	Mutaru :	Agrina		Member		
9,		Sanatu		Member		
D.	Jakeng .	Sanahi		Member		
_						
_						
-				- 27		
-						

Name	Organization/District/Community	Position	Phone No.	Emall/Sign
Musah Asdul Rashid	Aggregator	Mende	0597833024	
*				
			1	
		1		11.0

SAL CONSULT LIMITED STAKEHOLDER MEETING ATTENDANCE SHEET

0.	Name	Organization/District/Community	Position	Phone No.	Email / Sign
	Aboulai Awabo	FSO, Mion	Iglo Mari Boni.	0557758314	
+					
T					
1	2(4)				
+	3f				
t					
T					
-					
+					
r			E.		
-					
L					

Title of Project: Date: 1610412025 Time: 10: To an Vense: Fairifer, Mion Name Organization/District/Community Position Finance 10: Email/Sign I. Aschular Karim Mion Farmer Or 18901927 I. Aschular Midn Hahren Mion Farmer Or 18901927

SAL CONSULT LIMITED STAKEHOLDER MEETING ATTENDANCE SHEET

Title of Project:

Date: 15/04/2025

o.	Name		Organization/District/Community	Position	Phone No.	Email / Sign
. Id	disu Alharra	Gariyu	MADMO	Brector	0242772740	
-						
+						
					-	
+						

TIME: 11: 12 2m Venue: Water Resources Commission (DRC)

No.	Name	Organization/District/Community	Position	Phone No.	Email / Sign
1.	Yussif Abdul-Razak Guny	WRC	Accountant	0249768120	
	(36)				
	•				
1					
4					
4					
4					
4					
1					
1			- M		
1					
1					
1					
1					
1					

SAL CONSULT LIMITED STAKEHOLDER MEETING ATTENDANCE SHEET

Name	Organization/Dist	trict/Community	Positio	on	Phone No.	Email / Sign
Mohammed Alhason	Lands	Commission	Asistano	Search	0242081543	
- 1			-			
						-
		-				
			10			

SAL CONSULT LIMITED STAKEHOLDER MEETING ATTENDANCESHEET

lo.	Name	Organization/District/Community		osition	Phone No.	Email / Sign
Prince	Namkazog	MOFA	Matem	officer	0243483674	and a
Yelasey	iani Dennis	MOFA	0			
			9			
	*					

SAL CONSULT LIMITED STAKEHOLDER MEETING ATTENDANCE SHEET Title of Project: Date: 14 104 12025 Time: 12:05 pm Venue: Ghang Habbral Fire Cerrice Tamak. No. Name Organization/District/Community Position Phone No. Email/Sign I Israc Office Dedro GMFS Admin. Officer 0249829629

Vo. Name	Organization/District/Community	Position	Pitone No.	Email / Sign
1. Adam Adul Somed		Chaipasan	0540847921	
. Abdul Rahim Yakubu		Key holder	8201128	
3. Aldul Kain Asass		Member	0142644629	
for Yakubu Amin		Member	0040658186	
· Nasifa Alhaman			004801480	
s. Azimpaga Alhasian			754284250	
1. Abubakan Safura			0598134306	
r. Asarah Yakubu			059812660-6	
			-	
		#11		